



08-16-2022

Powur PBC

2683 Via De La Valle #321G

Subject: Structural Certification for Installation of Residential Solar
re job: George Johnson

52 Lynch Ave, Lillington, NC 27546, USA

Attn.: To Whom It May Concern

Observation of the condition of the existing framing system was performed by an audit team of Powur PBC

After review of the field observation data, structural capacity calculations were performed in accordance with applicable building codes to determine adequacy of the existing roof framing supporting the proposed panel layout. Please see full Structural Calculations report for details regarding calculations performed and limits of scope of work and liability. The design criteria and structural adequacy are summarized below:

Design Criteria:

Code: 2018 NCSBC, IBC 2015, ASCE 7-10, Ult Wind Speed: 118 mph, Ground Snow: 15 psf, Min Snow Roof: 0 psf

ROOF 1: Shingle roofing supported by 2x6 Truss @ 16 in. OC spacing. The roof is sloped at approximately 45 degrees and has a max beam span of 8.0 ft between supports. Roof is adequate to support the imposed loads. Therefore, no structural upgrades are required.

Current Renewables Engineering Inc.
Professional Engineer
info@currentrenewableseng.com

08-16-2022

