



Scott E. Wyssling, PE  
Coleman D. Larsen, SE, PE  
Gregory T. Elvestad, PE

76 North Meadowbrook Drive  
Alpine, UT 84004  
office (201) 874-3483  
swyssling@wysslingconsulting.com

December 1, 2022

Sustainable Energy and Lighting Solutions  
8351 Palmetto Commerce Parkway, Ste. 203  
Ladson, SC 29456

Re: Engineering Services  
Evans Residence  
875 Troy Parker Lane, Dunn, NC  
13.650 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

**A. Site Assessment Information**

1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

**B. Description of Structure:**

**Roof Framing 1:** Assumed 2x6 dimensional lumber at 16" on center.  
**Roof Framing 2:** Assumed 2x6 dimensional lumber at 16" on center.  
**Roof Material 1:** Composite Asphalt Shingles  
**Roof Material 2:** Metal Roof  
**Roof Slope:** 20 degrees  
**Attic Access:** Inaccessible  
**Foundation:** Permanent

**C. Loading Criteria Used**

- **Dead Load**
  - Existing Roofing and framing = 7 psf
  - New Solar Panels and Racking = 3 psf
  - TOTAL = 10 PSF
- **Live Load** = 20 psf (reducible) – 0 psf at locations of solar panels
- **Ground Snow Load** = 15 psf
- **Wind Load** based on ASCE 7-10
  - Ultimate Wind Speed = 115 mph (based on Risk Category II)
  - Exposure Category C

*Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the 2018 NCRC, including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.*


**D. Solar Panel Anchorage**

1.
  - i. The solar panels shall be mounted in accordance with the most recent Roof Tech installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
  - ii. The solar panels shall be mounted in accordance with the most recent S-5! installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
2.
  - i. The maximum allowable withdrawal force for a M5 x 60mm lag screw is 213 lbs per inch of penetration as identified in the National Design Standards (NDS) of timber construction specifications. Based on a minimum penetration depth of 2", the allowable capacity per connection is greater than the design withdrawal force (demand). Considering the variable factors for the existing roof framing and installation tolerances, the connection using two (2) M5 x 60mm lag screw with a minimum of 2" embedment will be adequate and will include a sufficient factor of safety.
  - ii. System will be attached to the metal roofing material utilizing the patented S-5! Connection. Installation of the connections shall be in accordance with the manufacturer's recommendations.
3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 72" on center.
4. Panel supports connections shall be staggered to distribute load to adjacent framing members.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the 2018 NCRC, current industry standards, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

Very truly yours,



Scott E. Wyssling, PE  
North Carolina License No. 46546  
North Carolina COA #P-2308





Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina COA # P-2308

Signed 12/1/2022

# TERRY EVANS - 13.650KW DC, 10.000KW AC

## SITE PLAN



**A1** VICINITY MAP  
PV-1.0 SCALE: NTS

### GENERAL INFORMATION

|                  |           |
|------------------|-----------|
| ELECTRIC CODE    | NEC 2020  |
| FIRE CODE        | NCFC 2018 |
| RESIDENTIAL CODE | NCRC 2018 |
| BUILDING CODE    | NCBC 2018 |
| WIND SPEED       | 115 MPH   |
| SNOW LOAD        | 15 PSF    |

### INDEX

| INDEX NO. | DESCRIPTION         |
|-----------|---------------------|
| PV-1.0    | SITE PLAN           |
| PV-2.0    | GENERAL NOTES       |
| PV-3.0    | MOUNTING DETAILS    |
| PV-3.1    | STRUCTURAL DETAILS  |
| PV-3.2    | STRUCTURAL DETAILS  |
| PV-4.0    | SINGLE LINE DIAGRAM |
| PV-4.1    | SINGLE LINE DIAGRAM |
| PV-5.0    | WARNING PLACARDS    |
| PV-6.0+   | SPEC SHEET(S)       |



Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD



Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina CDA # P-2308

Signed 12/1/2022

### CUSTOMER INFORMATION

NAME & ADDRESS:

TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### SITE PLAN

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE: AS NOTED

PAPER SIZE: 17"x11"

DATE: 11/19/22

REV: B

PV-1.0

**A** SITE PLAN

PV-1.0 SCALE: 1/16"=1'-0"

## GENERAL NOTES

### GENERAL NOTES

1. MODULES ARE LISTED UNDER UL 1703 AND CONFORM TO THE STANDARDS.
2. INVERTERS ARE LISTED UNDER UL 1741 AND CONFORM TO THE STANDARDS.
3. DRAWINGS ARE DIAGRAMMATIC, INDICATING GENERAL ARRANGEMENT OF THE PV SYSTEM AND THE ACTUAL SITE CONDITION MIGHT VARY.
4. WORKING CLEARANCES AROUND THE NEW PV ELECTRICAL EQUIPMENT WILL BE MAINTAINED IN ACCORDANCE WITH NEC 110.26(A)(1).
5. ALL GROUND WIRING CONNECTED TO THE MAIN SERVICE GROUNDING IN MAIN SERVICE PANEL/ SERVICE EQUIPMENT.
6. ALL CONDUCTORS SHALL BE 600V, 75°C STANDARD COPPER UNLESS OTHERWISE NOTED.
7. WHEN REQUIRED, A LADDER SHALL BE IN PLACE FOR INSPECTION IN COMPLIANCE WITH OSHA REGULATIONS.
8. THE SYSTEM WILL NOT BE INTERCONNECTED BY THE CONTRACTOR UNTIL APPROVAL FROM THE LOCAL JURISDICTION AND/OR THE UTILITY.
9. ROOF ACCESS POINT SHALL BE LOCATED IN AREAS THAT DO NOT REQUIRE THE PLACEMENT OF GROUND LADDERS OVER OPENINGS SUCH AS WINDOWS OR DOORS, AND LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION WHERE THE ACCESS POINT DOES NOT CONFLICT WITH OVERHEAD OBSTRUCTIONS SUCH AS TREES, WIRES OR SIGNS.
10. PV ARRAY COMBINER/JUNCTION BOX PROVIDES TRANSITION FROM ARRAY WIRING TO CONDUIT WIRING

### EQUIPMENT LOCATION:

11. ALL EQUIPMENT SHALL MEET MINIMUM SETBACKS AS REQUIRED BY NEC 110.26(A)(1).
12. WIRING SYSTEMS INSTALLED IN DIRECT SUNLIGHT MUST BE RATED FOR EXPECTED OPERATING TEMPERATURE AS SPECIFIED BY NEC 690.31(A),(C) AND NEC TABLES 310.15(B)(2)(A) AND 310.15(B)(3)(C).
13. JUNCTION AND PULL BOXES PERMITTED INSTALLED UNDER PV MODULES ACCORDING TO NEC 690.34.
14. ADDITIONAL AC DISCONNECT(S) SHALL BE PROVIDED WHERE THE INVERTER IS NOT WITHIN SIGHT OF THE AC SERVICING DISCONNECT.
15. ALL EQUIPMENT SHALL BE INSTALLED ACCESSIBLE TO QUALIFIED PERSONNEL ACCORDING TO NEC APPLICABLE CODES.
16. ALL COMPONENTS ARE LISTED FOR THEIR PURPOSE AND RATED FOR OUTDOOR USAGE WHEN APPROPRIATE.

### STRUCTURAL NOTES:

17. RACKING SYSTEM & PV ARRAY WILL BE INSTALLED ACCORDING TO CODE-COMPLIANT INSTALLATION MANUAL. TOP CLAMPS REQUIRE A DESIGNATED SPACE BETWEEN MODULES, AND RAILS MUST ALSO EXTEND A MINIMUM DISTANCE BEYOND EITHER EDGE OF THE ARRAY/SUBARRAY, ACCORDING TO RAIL MANUFACTURER'S INSTRUCTIONS.
18. JUNCTION BOX WILL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. IF ROOF-PENETRATING TYPE, IT SHALL BE FLASHED & SEALED PER LOCAL REQUIREMENTS.
19. ROOFTOP PENETRATIONS FOR PV RACEWAY WILL BE COMPLETED AND SEALED WITH APPROVED CHEMICAL SEALANT PER CODE BY A LICENSED CONTRACTOR.
20. ALL PV RELATED ROOF ATTACHMENTS TO BE SPACED NO GREATER THAN THE SPAN DISTANCE SPECIFIED BY THE RACKING MANUFACTURER.
21. WHEN POSSIBLE, ALL PV RELATED RACKING ATTACHMENTS WILL BE STAGGERED AMONGST THE ROOF FRAMING MEMBERS.

### WIRING & CONDUIT NOTES:

22. ALL CONDUIT AND WIRE WILL BE LISTED AND APPROVED FOR THEIR PURPOSE. CONDUIT AND WIRE SPECIFICATIONS ARE BASED ON MINIMUM CODE REQUIREMENTS AND ARE NOT MEANT TO LIMIT UP-SIZING.
23. CONDUCTORS SIZED ACCORDING TO NEC 690.8, NEC 690.7.
24. DC WIRING LIMITED TO MODULE FOOTPRINT. MICRO INVERTER WIRING SYSTEMS SHALL BE LOCATED AND SECURED UNDER THE ARRAY WITH SUITABLE WIRING CLIPS.
25. AC CONDUCTORS COLORED OR MARKED AS FOLLOWS: PHASE A OR L1- BLACK PHASE B OR L2- RED, OR OTHER CONVENTION IF THREE PHASE PHASE C OR L3- BLUE, YELLOW, ORANGE\*\*, OR OTHER CONVENTION NEUTRAL- WHITE OR GREY IN 4-WIRE DELTA CONNECTED SYSTEMS THE PHASE WITH HIGHER VOLTAGE TO BE MARKED ORANGE [NEC 110.15].

### INTERCONNECTION NOTES:

26. LOAD-SIDE INTERCONNECTION SHALL BE IN ACCORDANCE WITH [NEC 690.64(B)]
27. THE SUM OF THE UTILITY OCPD AND INVERTER CONTINUOUS INPUT MAY NOT EXCEED 120% OF BUSBAR RATING [NEC 705.12(D)(2)(3)].
28. WHEN SUM OF THE PV SOURCES EQUALS >100% OF BUSBAR RATING, PV DEDICATED BACKFFED BREAKERS MUST BE LOCATED OPPOSITE END OF THE BUS FROM THE UTILITY SOURCE OCPD [NEC 705.12(D)(2)(3)].
29. AT MULTIPLE PV OUTPUT COMBINER PANEL, TOTAL RATING OF ALL OVER CURRENT DEVICES SHALL NOT EXCEED AMPACITY OF BUSBAR. HOWEVER, THE COMBINED OVER CURRENT DEVICE MAY BE EXCLUDED ACCORDING TO NEC 705.12(D)(2)(3)(C).
30. FEEDER TAP INTER CONNECTION (LOAD SIDE) ACCORDING TO NEC 705.12(D)(2)(1) SUPPLY SIDE TAP INTERCONNECTION ACCORDING TO NEC 705.12(A) WITH SERVICE ENTRANCE CONDUCTORS IN ACCORDANCE WITH NEC 230.42 BACK FEEDING BREAKER FOR UTILITY-INTERACTIVE INVERTER OUTPUT IS EXEMPT FROM ADDITIONAL FASTENING [NEC 705.12(D)(5)].

### GROUNDING NOTES:

31. GROUNDING SYSTEM COMPONENTS SHALL BE LISTED FOR THEIR PURPOSE, AND GROUNDING DEVICES EXPOSED TO THE ELEMENTS SHALL BE RATED FOR SUCH USE.
32. PV EQUIPMENT SHALL BE GROUNDED ACCORDING TO NEC 690.43 AND MINIMUM NEC 250.122.
33. METAL PARTS OF MODULE FRAMES, MODULE RACKING, AND ENCLOSURES CONSIDERED GROUNDED IN ACCORD WITH 250.134 AND 250.136(A).
34. EQUIPMENT GROUNDING CONDUCTORS SHALL BE SIZED ACCORDING TO NEC 690.45 AND MICRO INVERTER MANUFACTURER'S INSTRUCTIONS.
35. EACH MODULE WILL BE GROUNDED USING WEEB GROUNDING CLIPS AS SHOWN IN MANUFACTURER DOCUMENTATION AND APPROVED BY THE AHJ. IF WEEBS ARE NOT USED, MODULE GROUNDING LUGS MUST BE INSTALLED AT THE SPECIFIED GROUNDING LUG HOLES PER THE MANUFACTURERS' INSTALLATION REQUIREMENTS.
36. THE GROUNDING CONNECTION TO A MODULE SHALL BE ARRANGED SUCH THAT THE REMOVAL OF A MODULE DOES NOT INTERRUPT A GROUNDING CONDUCTOR TO ANOTHER MODULE.
37. GROUNDING AND BONDING CONDUCTORS, IF INSULATED, SHALL BE COLORED GREEN OR MARKED GREEN IF #4 AWG OR LARGER [NEC 250.119]
38. THE GROUNDING ELECTRODE SYSTEM COMPLIES WITH NEC 690.47 AND NEC 250.50 THROUGH 250.106. IF EXISTING SYSTEM IS INACCESSIBLE, OR INADEQUATE, A GROUNDING ELECTRODE SYSTEM PROVIDED ACCORDING TO NEC 250, NEC 690.47 AND AHJ.
39. GROUND-FAULT DETECTION SHALL COMPLY WITH NEC 690.5 IN GENERAL AND NEC 690.5(A)(1) SPECIFICALLY.
40. DISCONNECTION AND OVER-CURRENT PROTECTION NOTES:
41. DISCONNECTING SWITCHES SHALL BE WIRED SUCH THAT WHEN THE SWITCH IS OPENED THE CONDUCTORS REMAINING ENERGIZED ARE CONNECTED TO THE TERMINALS MARKED "LINE SIDE" (TYPICALLY THE UPPER TERMINALS).
42. DISCONNECTS TO BE ACCESSIBLE TO QUALIFIED UTILITY PERSONNEL, BE LOCKABLE, AND BE A VISIBLE-BREAK SWITCH
43. RAPID SHUTDOWN OF ENERGIZED CONDUCTORS BEYOND 10 FT OF PV ARRAY OR 5 FT INSIDE A BUILDING WITHIN 10 SECONDS. CONTROLLED CONDUCTORS ≤30V AND ≤240VA [NEC 690.12]. LOCATION OF LABEL ACCORDING TO AHJ.
44. ALL OCPD RATINGS AND TYPES SPECIFIED ACCORDING TO NEC 690.8, 690.9 AND 240.
45. MICRO INVERTER BRANCHES CONNECTED TO A SINGLE BREAKER OR GROUPED FUSES IN ACCORDANCE WITH NEC 110.3(B). 2.6.7 IF REQUIRED BY AHJ, SYSTEM WILL INCLUDE ARC-FAULT CIRCUIT PROTECTION ACCORDING TO NEC 690.11 AND UL1699B.



## SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

## ENGINEER OF RECORD



Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina CDA # P-2308

Signed 12/1/2022

## CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

## GENERAL NOTES

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE: AS NOTED PAPER SIZE: 17"x11"

DATE: 11/19/22 REV: B PV-2.0





Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

**SYSTEM INFORMATION**

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

**ENGINEER OF RECORD**



Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina COA # P-2308

Signed 12/1/2022

**CUSTOMER INFORMATION**

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

**MOUNTING DETAILS**

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED

PAPER SIZE:17"x11"

DATE:11/19/22

REV:B

PV-3.0

**MODULES DATA**

TRINA SOLAR TSM-390 DE09.05 390W

MODULE DIMS 69.06"x43.15"x1.18"

LAG SCREWS 5/16"x3.5":2.5"MIN EMBEDMENT

**FIRE SETBACK**

MINIMUM FIRE ACCESS PATHWAYS PER CFC 2019  
RIDGE TO ARRAY: 1'-6"  
EAVE TO ARRAY : 3'-0"  
HIP/VALLEY W/ ADJACENT ARRAY: 1'-6"  
EACH SIDE HIP/VALLEY W/O ADJACENT ARRAY: 0'-0"


**NOTE:** INSTALLER TO VERIFY RAFTER SIZE, SPACING AND SLOPED SPANS, AND NOTIFY ANY DISCREPANCIES BEFORE PROCEEDING.

**AERIAL VIEW**




**SITE INFORMATION**

| SR.NO | AZIMUTH | PITCH | NO. OF MODULES | ARRAY AREA (SQ. FT.) | ROOF TYPE           | ATTACHMENT           | ROOF EXPOSURE | FRAME TYPE | FRAME SIZE | FRAME SPACING | MAX RAIL SPAN | OVER HANG |
|-------|---------|-------|----------------|----------------------|---------------------|----------------------|---------------|------------|------------|---------------|---------------|-----------|
| MP-01 | 162°    | 20°   | 26             | 537.94               | COMPOSITION SHINGLE | ROOF TECH/RT-MINI II | ATTIC         | RAFTERS    | 2 X 6      | 1'-4"         | 4'-0"         | 2'-0"     |
| MP-02 | 72°     | 20°   | 9              | 186.21               | METAL               | S-5! CORRUBRACKET    | ATTIC         | RAFTERS    | 2 X 6      | 1'-4"         | 4'-0"         | 2'-0"     |



2X6 RAFTERS  
@ 1'-4" SPACING  
ALUMINIUM RAILS  
ARRAY MP-01



ARRAY MP-02

**B MOUNTING DETAILS**

PV-3.0 SCALE: 1/16"=1'-0"





Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD



Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina COA # P-2308

Signed 12/1/2022

### CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### STRUCTURAL DETAILS

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX


SCALE:AS NOTED

PAPER SIZE:17"x11"


DATE:11/19/22

REV:B

PV-3.1



1 RAIL AND 'L-FOOT' ORIENTATION  
SCALE: N.T.S.



2 RAIL AND 'L-FOOT' ORIENTATION  
SCALE: N.T.S.



Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD



Wyssling Consulting, PLLC  
76 N Meadowbrook Drive Alpine UT 84004  
North Carolina CDA # P-2308

Signed 12/1/2022

### CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### STRUCTURAL DETAILS

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX



SCALE:AS NOTED

PAPER SIZE:17"x11"

DATE:11/19/22

REV:B


PV-3.2






Ø .28 4X  
[Ø 7mm]

M8x1.25 THREADED HOLE

M10x1.5 THREADED HOLE



FACTORY APPLIED  
BUTYL SEALANT  
DIM: 3/4" X 1/8"



### S-5! CORRUBRACKET



**SINGLE LINE DIAGRAM: DC SYSTEM SIZE - 13.650KW DC, 10.000KW AC**



Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

**SYSTEM INFORMATION**

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

**ENGINEER OF RECORD**

**CUSTOMER INFORMATION**

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

**SINGLE LINE DIAGRAM**

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX


SCALE:AS NOTED

PAPER SIZE:17"x11"

DATE:11/19/22

REV:B

PV-4.0





**SINGLE LINE DIAGRAM: DC SYSTEM SIZE - 13.650kW DC, 10.000kW AC**



**SYSTEM INFORMATION**

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

**ENGINEER OF RECORD**

**CUSTOMER INFORMATION**

NAME & ADDRESS:

TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

**SINGLE LINE DIAGRAM**

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED PAPER SIZE:17"x11"

DATE:11/19/22 REV:B PV-4.1

| MODULE SPECIFICATION      |                                     |
|---------------------------|-------------------------------------|
| MODEL                     | TRINA SOLAR<br>TSM-390 DE09.05 390W |
| MODULE POWER @ STC        | 390W                                |
| OPEN CIRCUIT VOLTAGE:Voc  | 40.8V                               |
| MAX POWER VOLTAGE:Vmp     | 33.8V                               |
| SHORT CIRCUIT VOLTAGE:Isc | 12.14A                              |
| MAX POWER CURRENT:Imp     | 11.54A                              |

| INVERTER-1 SPECIFICATIONS |                                    |
|---------------------------|------------------------------------|
| MODEL                     | SOLAREEDGE SE10000H-US<br>INVERTER |
| POWER RATING              | 10000W                             |
| MAX OUTPUT CURRENT        | 42A                                |
| CEC WEIGHTED EFFICIENCY   | 99.2%                              |
| MAX INPUT CURRENT         | 27A                                |
| MAX DC VOLTAGE            | 480V                               |

**CONDUIT SCHEDULE**

| TAG ID | CONDUIT SIZE     | CONDUCTOR                        | NEUTRAL               | GROUND                 |
|--------|------------------|----------------------------------|-----------------------|------------------------|
| 1      | NONE             | (2) PV WIRE<br>12AWG THHN/THWN-2 | NONE                  | (1) 4 AWG BARE COPPER  |
| 2      | 3/4"EMT OR EQUIV | (6) 10AWG THHN/THWN-2            | NONE                  | (1) 10 AWG THHN/THWN-2 |
| 3      | 3/4"EMT OR EQUIV | (2) 6 AWG THHN/THWN-2            | (1) 6 AWG THHN/THWN-2 | (1) 6 AWG THHN/THWN-2  |

**ELECTRICAL CALCULATION**

AC WIRE CALCULATIONS:- MATERIAL:COPPER & TEMPERATURE RATING:75°C

| TAG ID | REQUIRED CONDUCTOR AMPACITY |   |   |   |    |   |      |   | CORRECTED AMPACITY CALCULATION |    |   |      |   |     | TERMINAL RATING CHECK |        |        | DERATED CONDUCTOR AMPACITY CHECK |     |        |   |        |
|--------|-----------------------------|---|---|---|----|---|------|---|--------------------------------|----|---|------|---|-----|-----------------------|--------|--------|----------------------------------|-----|--------|---|--------|
|        | 1                           | 2 | 3 | 4 | 5  | 6 | 7    | 8 | 1                              | 2  | 3 | 4    | 5 | 6   | 7                     | 8      | 1      | 2                                | 3   | 1      | 2 | 3      |
| 1      | 15                          | X | 1 | = | 15 | X | 1.25 | = | 18.75A                         | 25 | X | 0.91 | X | 1   | =                     | 22.75A | 18.75A | <                                | 20A | 18.75A | < | 22.75A |
| 2      | 15                          | X | 1 | = | 15 | X | 1.25 | = | 18.75A                         | 35 | X | 0.91 | X | 0.8 | =                     | 25.48A | 18.75A | <                                | 20A | 18.75A | < | 25.48A |
| 3      | 42                          | X | 1 | = | 42 | X | 1.25 | = | 52.50A                         | 65 | X | 0.91 | X | 1   | =                     | 59.15A | 52.50A | <=                               | 60A | 52.50A | < | 59.15A |

**ELECTRICAL NOTES:**

1. MAXIMUM DC/AC VOLTAGE DROP SHALL BE NO MORE THAN 2%.
2. BREAKER/FUSE SIZES CONFORMS TO NEC 240.6 CODE SECTION.
3. AC GROUNDING ELECTRODE CONDUCTOR SIZED PER NEC 250.66.
4. AMBIENT TEMPERATURE CORRECTION FACTOR IS BASED ON NEC 690.31(A).
5. AMBIENT TEMPERATURE ADJUSTMENT FACTOR IS BASED ON NEC 310.15(B)(2)(C) AND 310.15(B)(2)(B)
6. AC SYSTEM VOLTAGE CORRECTION IS PER NEC 690.7(A)
7. CONDUCTORS ARE SIZED PER WIRE AMPACITY TABLE NEC 310.15(B)(16).
8. CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC 310.10(D).
9. CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE IN WET LOCATIONS PER NEC 310.10(C).

**WARNING PLACARDS**



**SYSTEM INFORMATION**

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

**ENGINEER OF RECORD**

**CUSTOMER INFORMATION**

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

**WARNING PLACARDS**

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED PAPER SIZE:17"x11"

DATE:11/19/22 REV:B PV-5.0

**WARNING**

**ELECTRIC SHOCK HAZARD**  
THE DC CONDUCTORS OF THIS PHOTOVOLTAIC SYSTEM ARE UNGROUNDED AND MAY BE ENERGIZED

LABEL LOCATION  
DC DISCONNECT,INVERTER  
[PER CODE: NEC 690.41]  
[To be used when inverter is ungrounded]

**WARNING**

**ELECTRIC SHOCK HAZARD**  
DO NOT TOUCH TERMINALS  
TERMINALS ON BOTH LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

DC VOLTAGE IS ALWAYS PRESENT WHEN SOLAR MODULES ARE EXPOSED TO SUNLIGHT

LABEL LOCATION  
AC DISCONNECT,POINT OF INTERCONNECTION  
[PER CODE: NEC 690.13(B)]

**WARNING**

**ELECTRIC SHOCK HAZARD**  
DO NOT TOUCH TERMINALS  
TERMINALS ON BOTH LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

LABEL LOCATION  
AC DISCONNECT,POINT OF INTERCONNECTION  
[PER CODE: NEC 690.13(B)]

**WARNING-Electric Shock Hazard**  
**No User Serviceable Parts inside**  
**Contact authorized service provide for assistance**

LABEL LOCATION  
INVERTER, JUNCTION BOXES(ROOF),  
AC DISCONNECT  
[PER CODE: NEC 690.13]

**WARNING:PHOTOVOLTAIC POWER SOURCE**

LABEL LOCATION  
CONDUIT, COMBINER BOX  
[PER CODE: NEC690.31(G)(3)]

**WARNING**  
**DUAL POWER SOURCE SECOND SOURCE IS PHOTOVOLTAIC SYSTEM**

LABEL LOCATION  
POINT OF INTERCONNECTION  
[PER CODE: NEC705.12(D)(4)]

**PHOTOVOLTAIC SYSTEM DC DISCONNECT**  
MAX VOLTAGE 480 VDC  
MAX CIRCUIT CURRENT 42 ADC  
MAX RATED OUTPUT CURRENT OF THE CHARGE CONTROLLER OR DC TO DC CONVERTER (IF INSTALLED) ADC

LABEL LOCATION  
DC DISCONNECT SWITCH, INVERTER  
[PER. CODE:NEC 690.53]

**PHOTOVOLTAIC SYSTEM AC DISCONNECT SWITCH**

RATED AC OPERATING CURRENT **42.00** AMPS AC  
AC NOMINAL OPERATING VOLTAGE **240** VAC

LABEL LOCATION  
AC DISCONNECT , POINT OF INTERCONNECTION  
[PER CODE: NEC 690.54]

**WARNING**  
**INVERTER OUTPUT CONNECTION DO NOT RELOCATE THIS OVER-CURRENT DEVICE**

LABEL LOCATION  
POINT OF INTERCONNECTION  
(PER CODE: NEC 705.12(2)(b))  
[ Not Required if Panel board is rated not less than sum of ampere ratings of all overcurrent devices supplying it]

**CAUTION: SOLAR CIRCUIT**

LABEL LOCATION  
MARKINGS PLACED ON ALL INTERIOR AND EXTERIOR DC CONDUIT, RACEWAYS, ENCLOSURES AND CABLE ASSEMBLES AT LEAST EVERY 10 FT, AT TURNS AND ABOVE/BELOW PENETRATIONS AND ALL COMBINER/JUNCTION BOXES.  
(PER CODE: NEC1204.5)

**SOLAR DISCONNECT**

LABEL LOCATION  
DISCONNECT, POINT OF INTERCONNECTION  
[PER CODE: NEC 690.13(B)]

**CAUTION: SOLAR ELECTRIC SYSTEM CONNECTED**


LABEL LOCATION  
WEATHER RESISTANT MATERIAL, DURABLE ADHESIVE, UL969 AS STANDARD TO WEATHER RATING (UL LISTING OF MARKINGS NOT REQUIRED), MIN 3/8" LETTER HEIGHT ARIAL OR SIMILAR FONT NON-BOLD,PLACED WITHIN THE MAIN SERVICE DISCONNECT,PLACED ON THE OUTSIDE OF THE COVER WHEN DISCONNECT IS OPERATED WITH THE SERVICE PANEL CLOSED.  
(PWER CODE: NEC690.15 ,690.13(B))

**RAPID SHUTDOWN SWITCH FOR SOLAR SYSTEM**

LABEL LOCATION  
INVERTER,POINT OF INTERCONNECTION  
[PER CODE: NEC 690.56(C)(3)]

**SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN**


**TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY**




LABEL LOCATION  
AC DISCONNECT, DC DISCONNECT, POINT OF INTERCONNECTION  
(PER CODE: NEC690.56(C)(1)(A))

ALL PLACARDS SHALL BE OF WEATHER PROOF CONSTRUCTION, BACKGROUND ON ALL PLACARDS SHALL BE RED WITH WHITE LETTERING U.O.N. PLACARD SHALL BE MOUNTED DIRECTLY ON THE EXISTING UTILITY ELECTRICAL SERVICE.FASTENERS APPROVED BY THE LOCAL JURISDICTION

NOTE:ALL SIGNAGE CANNOT BE HAND WRITTEN NEC 110.21

**WARNING**   
**POWER TO THIS BUILDING IS ALSO SUPPLIED FROM THE FOLLOWING SOURCES WITH DISCONNECTS LOCATED AS SHOWN**



875 TROY PARKER LN, DUNN, NC 28334

# Vertex S


BACKSHEET MONOCRYSTALLINE MODULE

PRODUCT: TSM-DE09.05  
POWER RANGE: 380-400 W

**400 W+**  
MAXIMUM POWER OUTPUT

**0/+5 W**  
POSITIVE POWER TOLERANCE

**20.8 %**  
MAXIMUM EFFICIENCY




- Outstanding Visual Appearance**
  - Designed with aesthetics in mind
  - Ultra-thin, virtually invisible busbars
  - Excellent cell color control by machine selection
- Small in size, big on power**
  - Generates up to 400 W, 20.8 % module efficiency with high density interconnect technology
  - Multi-busbar technology for better light trapping, lower series resistance, improved current collection and enhanced reliability
  - Excellent low light performance (IAM) with cell process and module material optimization
- Universal solution for residential and C&I rooftops**
  - Designed for compatibility with existing mainstream inverters, optimizers and mounting systems
  - Perfect size and low weight for easy handling. Optimized transportation cost
  - Reduces installation cost with higher power bin and efficiency
  - Flexible installation solutions for system deployment
- High Reliability**
  - 6,000 Pa snow load (test load)
  - 4,000 Pa wind load (test load)

## Extended Vertex S Warranty

**2 %**  
1<sup>st</sup> year max. degradation

**0.55 %**  
Max. annual degradation from year 2 to 25

**15 Years**  
Product Workmanship Warranty




## Comprehensive Product and System Certificates

IEC61215/IEC61730/IEC61701/IEC62716  
ISO 9001: Quality Management System  
ISO 14001: Environmental Management System  
ISO14064: Greenhouse Gases Emissions Verification  
ISO45001: Occupational Health and Safety Management System




# Vertex S


## DIMENSIONS OF PV MODULE (mm)



## I-V CURVES OF PV MODULE (390W)



## P-V CURVES OF PV MODULE (390W)



| ELECTRICAL DATA (STC)                      | TSM-380 DE09.05 | TSM-385 DE09.05 | TSM-390 DE09.05 | TSM-395 DE09.05 | TSM-400 DE09.05 |
|--|-----------------|-----------------|-----------------|-----------------|-----------------|
| Peak Power Watts-P <sub>max</sub> (Wp)*    | 380             | 385             | 390             | 395             | 400             |
| Power Tolerance-P <sub>max</sub> (W)       | 0/+5            | 0/+5            | 0/+5            | 0/+5            | 0/+5            |
| Maximum Power Voltage-V <sub>MPP</sub> (V) | 33.4            | 33.6            | 33.8            | 34.0            | 34.2            |
| Maximum Power Current-I <sub>MPP</sub> (A) | 11.38           | 11.46           | 11.54           | 11.62           | 11.70           |
| Open Circuit Voltage-V <sub>oc</sub> (V)   | 40.4            | 40.5            | 40.8            | 41.0            | 41.2            |
| Short Circuit Current-I <sub>sc</sub> (A)  | 12.00           | 12.07           | 12.14           | 12.21           | 12.28           |
| Module Efficiency η <sub>m</sub> (%)       | 19.8            | 20.0            | 20.3            | 20.5            | 20.8            |

STC: Irradiance 1000 W/m², Cell Temperature 25°C, Air Mass AM1.5 \*Measuring tolerance: ±3%

| ELECTRICAL DATA (NOCT)                     | TSM-380 DE09.05 | TSM-385 DE09.05 | TSM-390 DE09.05 | TSM-395 DE09.05 | TSM-400 DE09.05 |
|--|-----------------|-----------------|-----------------|-----------------|-----------------|
| Maximum Power-P <sub>max</sub> (Wp)        | 286             | 290             | 294             | 298             | 302             |
| Maximum Power Voltage-V <sub>MPP</sub> (V) | 31.4            | 31.6            | 31.8            | 31.9            | 32.1            |
| Maximum Power Current-I <sub>MPP</sub> (A) | 9.12            | 9.18            | 9.24            | 9.32            | 9.38            |
| Open Circuit Voltage-V <sub>oc</sub> (V)   | 38.0            | 38.2            | 38.4            | 38.6            | 38.8            |
| Short Circuit Current-I <sub>sc</sub> (A)  | 9.67            | 9.73            | 9.78            | 9.84            | 9.90            |

NOCT: Irradiance at 800 W/m², Ambient Temperature 20°C, Wind Speed 1 m/s.

| MECHANICAL DATA      |   |
|----------------------|---|
| Solar Cells          | Monocrystalline   |
| No. of cells         | 120 cells   |
| Module Dimensions    | 1754×1096×30 mm   |
| Weight               | 21.0 kg   |
| Glass                | 3.2 mm, High Transmission, AR Coated Heat Strengthened Glass                              |
| Encapsulant material | EVA/POE   |
| Backsheet            | Black-White   |
| Frame                | 30 mm Anodized Aluminium Alloy  |
| J-Box                | IP 68 rated   |
| Cables               | Photovoltaic Technology Cable 4.0 mm²<br>Landscape: 1100/1100 mm<br>Portrait: 280/280 mm* |
| Connector            | TS4/MC4 EV02*   |

\*Special order only

| TEMPERATURE RATINGS                         | MAXIMUM RATINGS |
|---|-----------------|
| NOCT (Nominal Operating Cell Temperature)   | 43 °C (±2 K)    |
| Temperature Coefficient of P <sub>max</sub> | -0.34 %/K       |
| Temperature Coefficient of V <sub>oc</sub>  | -0.25 %/K       |
| Temperature Coefficient of I <sub>sc</sub>  | 0.04 %/K        |
| Operational Temperature                     | -40 to +85 °C   |
| Maximum System Voltage                      | 1500 V DC (IEC) |
| Max Series Fuse Rating                      | 20 A            |

| WARRANTY                             | PACKAGING CONFIGURATION              |
|--------------------------------------|--------------------------------------|
| 15 Year product workmanship warranty | Modules per box 36 pieces            |
| 25 Year power warranty               | Modules per 40' container 936 pieces |
| 2% First year degradation            |                                      |
| 0.55% Annual power degradation       |                                      |

(Please refer to the applicable limited warranty for details)



CAUTION: READ SAFETY AND INSTALLATION INSTRUCTIONS BEFORE USING THE PRODUCT.  
© 2021 Trina Solar Limited, All rights reserved, Specifications included in this datasheet are subject to change without notice. Version number: TSM\_EN\_2021\_C

www.trinasolar.com



Sustainable Energy & Lighting Solutions  
Your future is brighter with us!

## SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

## ENGINEER OF RECORD

## CUSTOMER INFORMATION

NAME & ADDRESS:

TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

## MODULE SPECSHEET

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED

PAPER SIZE:17"x11"

DATE:11/19/22

REV:B

PV-6.0



# Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US



12-25  
YEAR  
WARRANTY

INVERTERS

## Optimized installation with HD-Wave technology

- Specifically designed to work with power optimizers
- Record-breaking 99% weighted efficiency
- Quick and easy inverter commissioning directly from a smartphone using the SolarEdge SetApp
- Fixed voltage inverter for longer strings
- Integrated arc fault protection and rapid shutdown for NEC 2014, NEC 2017 and NEC 2020 per article 690.11 and 690.12
- UL1741 SA certified, for CPUC Rule 21 grid compliance
- Small, lightweight, and easy to install both outdoors or indoors
- Built-in module-level monitoring
- Optional: Faster installations with built-in consumption metering (1% accuracy) and production revenue grade metering (0.5% accuracy, ANSI C12.20)

[solaredge.com](http://solaredge.com)



## Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US

| MODEL NUMBER  | SE3000H-US                      | SE3800H-US                 | SE5000H-US | SE6000H-US                 | SE7600H-US | SE10000H-US              | SE11400H-US                  |     |
|---|---------------------------------|----------------------------|------------|----------------------------|------------|--------------------------|------------------------------|-----|
| APPLICABLE TO INVERTERS WITH PART NUMBER                                  | SEXXXXH-XXXXXBXX4               |                            |            |                            |            |                          |                              |     |
| <b>OUTPUT</b>   |                                 |                            |            |                            |            |                          |                              |     |
| Rated AC Power Output   | 3000                            | 3800 @ 240V<br>3300 @ 208V | 5000       | 6000 @ 240V<br>5000 @ 208V | 7600       | 10000                    | 11400 @ 240V<br>10000 @ 208V | VA  |
| Maximum AC Power Output   | 3000                            | 3800 @ 240V<br>3300 @ 208V | 5000       | 6000 @ 240V<br>5000 @ 208V | 7600       | 10000                    | 11400 @ 240V<br>10000 @ 208V | VA  |
| AC Output Voltage Min.-Nom.-Max. (211 - 240 - 264)                        | ✓                               | ✓                          | ✓          | ✓                          | ✓          | ✓                        | ✓                            | Vac |
| AC Output Voltage Min.-Nom.-Max. (183 - 208 - 229)                        | -                               | ✓                          | -          | ✓                          | -          | -                        | ✓                            | Vac |
| AC Frequency (Nominal)  | 59.3 - 60 - 60.5 <sup>(1)</sup> |                            |            |                            |            |                          |                              | Hz  |
| Maximum Continuous Output Current @240V                                   | 12.5                            | 16                         | 21         | 25                         | 32         | 42                       | 47.5                         | A   |
| Maximum Continuous Output Current @208V                                   | -                               | 16                         | -          | 24                         | -          | -                        | 48.5                         | A   |
| Power Factor  | 1, Adjustable - 0.85 to 0.85    |                            |            |                            |            |                          |                              |     |
| GFDI Threshold  | 1                               |                            |            |                            |            |                          |                              | A   |
| Utility Monitoring, Islanding Protection, Country Configurable Thresholds | Yes                             |                            |            |                            |            |                          |                              |     |
| <b>INPUT</b>  |                                 |                            |            |                            |            |                          |                              |     |
| Maximum DC Power @240V  | 4650                            | 5900                       | 7750       | 9300                       | 11800      | 15500                    | 17650                        | W   |
| Maximum DC Power @208V  | -                               | 5100                       | -          | 7750                       | -          | -                        | 15500                        | W   |
| Transformer-less, Ungrounded  | Yes                             |                            |            |                            |            |                          |                              |     |
| Maximum Input Voltage   | 480                             |                            |            |                            |            |                          |                              | Vdc |
| Nominal DC Input Voltage  | 380                             |                            |            | 400                        |            |                          |                              | Vdc |
| Maximum Input Current @240V <sup>(2)</sup>                                | 8.5                             | 10.5                       | 13.5       | 16.5                       | 20         | 27                       | 30.5                         | Adc |
| Maximum Input Current @208V <sup>(2)</sup>                                | -                               | 9                          | -          | 13.5                       | -          | -                        | 27                           | Adc |
| Max. Input Short Circuit Current  | 45                              |                            |            |                            |            |                          |                              | Adc |
| Reverse-Polarity Protection   | Yes                             |                            |            |                            |            |                          |                              |     |
| Ground-Fault Isolation Detection  | 600ka Sensitivity               |                            |            |                            |            |                          |                              |     |
| Maximum Inverter Efficiency   | 99                              | 99.2                       |            |                            |            |                          |                              | %   |
| CEC Weighted Efficiency   | 99                              |                            |            |                            |            | 99 @ 240V<br>98.5 @ 208V | %                            |     |
| Nighttime Power Consumption   | < 2.5                           |                            |            |                            |            |                          |                              | W   |

(1) For other regional settings please contact SolarEdge support  
(2) A higher current source may be used; the inverter will limit its input current to the values stated



### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD

### CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### INVERTER SPECSHEET

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED PAPER SIZE:17"x11"

DATE:11/19/22 REV:B PV-6.1



# Power Optimizer

For North America

P370 / P400 / P401 / P485 / P505



POWER OPTIMIZER

## PV power optimization at the module-level

- Specifically designed to work with SolarEdge inverters
- Up to 25% more energy
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch losses, from manufacturing tolerance to partial shading
- Flexible system design for maximum space utilization
- Fast installation with a single bolt
- Next generation maintenance with module-level monitoring
- Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)
- Module-level voltage shutdown for installer and firefighter safety

solaredge.com



## Power Optimizer

For North America

P370 / P400 / P401 / P485 / P505

| Optimizer model (typical module compatibility)  | P370 (for higher-power 60 and 72-cell modules) | P400 (for 72 & 96-cell modules)  | P401 (for high power 60 and 72 cell modules) | P485 (for high-voltage modules)                      | P505 (for higher current modules) |         |
|---|--|----------------------------------|--|--|-----------------------------------|---------|
| <b>INPUT</b>  |  |                                  |  |  |                                   |         |
| Rated Input DC Power <sup>(1)</sup>   | 370  | 400                              |  | 485  | 505                               | W       |
| Absolute Maximum Input Voltage (Voc at lowest temperature)  | 60   | 80                               | 60   | 125 <sup>(2)</sup>                                   | 83 <sup>(2)</sup>                 | Vdc     |
| MPPT Operating Range  | 8 - 60   | 8 - 80                           | 8-60   | 12.5 - 105   | 12.5 - 83                         | Vdc     |
| Maximum Short Circuit Current (Isc)   | 11   | 10.1                             | 11.75  | 11   | 14                                | Adc     |
| Maximum DC Input Current  | 13.75  | 12.5                             | 14.65  | 12.5   | 17.5                              |         |
| Maximum Efficiency  |  |                                  |  | 99.5   |                                   | %       |
| Weighted Efficiency   |  |                                  |  | 98.8   |                                   | %       |
| Oversvoltage Category   |  |                                  |  | II   |                                   |         |
| <b>OUTPUT DURING OPERATION (POWER OPTIMIZER CONNECTED TO OPERATING SOLAREEDGE INVERTER)</b>                     |  |                                  |  |  |                                   |         |
| Maximum Output Current  |  |                                  |  | 15   |                                   | Adc     |
| Maximum Output Voltage  |  |                                  |  | 60   | 80                                | Vdc     |
| <b>OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM SOLAREEDGE INVERTER OR SOLAREEDGE INVERTER OFF)</b> |  |                                  |  |  |                                   |         |
| Safety Output Voltage per Power Optimizer   |  |                                  |  | 1 ± 0.1  |                                   | Vdc     |
| <b>STANDARD COMPLIANCE</b>  |  |                                  |  |  |                                   |         |
| EMC   |  |                                  |  | FCC Part 15 Class B, IEC61000-6-2, IEC61000-6-3      |                                   |         |
| Safety  |  |                                  |  | IEC62109-1 (class II safety), UL1741, NEC/PVRSS      |                                   |         |
| Material  |  |                                  |  | UL94 V-0, UV Resistant                               |                                   |         |
| RoHS  |  |                                  |  | Yes  |                                   |         |
| <b>INSTALLATION SPECIFICATIONS</b>  |  |                                  |  |  |                                   |         |
| Maximum Allowed System Voltage  |  |                                  |  | 1000   |                                   | Vdc     |
| Compatible inverters  |  |                                  |  | All SolarEdge Single Phase and Three Phase inverters |                                   |         |
| Dimensions (W x L x H)  | 129 x 153 x 27.5 / 5.1 x 6 x 1.1               | 129 x 153 x 33.5 / 5.1 x 6 x 1.3 | 129 x 153 x 29.5 / 5.1 x 6 x 1.16            | 129 x 159 x 49.5 / 5.1 x 6.3 x 1.9                   | 129 x 162 x 59 / 5.1 x 6.4 x 2.3  | mm / in |
| Weight (including cables)   | 630 / 1.4                                      | 750 / 1.7                        | 655 / 1.5                                    | 845 / 1.9  | 1064 / 2.3                        | gr / lb |
| Input Connector   |  |                                  |  | MC4 <sup>(3)</sup>                                   | MC4 <sup>(3)</sup>                |         |
| Input Wire Length   |  |                                  |  | 0.16 / 0.5   |                                   | m / ft  |
| Output Wire Type / Connector  |  |                                  |  | Double Insulated / MC4                               |                                   |         |
| Output Wire Length  |  |                                  |  | 1.2 / 3.9  |                                   | m / ft  |
| Operating Temperature Range <sup>(4)</sup>  |  |                                  |  | -40 to +85 / -40 to +185                             |                                   | °C / °F |
| Protection Rating   |  |                                  |  | IP68 / Type6B  |                                   |         |
| Relative Humidity   |  |                                  |  | 0 - 100  |                                   | %       |

(1) Rated power of the module at STC will not exceed the optimizer "Rated Input DC Power". Modules with up to +5% power tolerance are allowed  
 (2) NEC 2017 requires max input voltage be not more than 80V  
 (3) For other connector types please contact SolarEdge  
 (4) Longer inputs wire lengths are available for use. For 0.9m input wire length order P401-xxxLxxx  
 (5) For ambient temperature above +85°C / +185°F power de-rating is applied. Refer to Power Optimizers Temperature De-Rating Technical Note for more details: <https://www.solaredge.com/sites/default/files/se-temperature-de-rating-note-na.pdf>

| PV System Design Using a SolarEdge Inverter <sup>(6)(7)</sup> | Single Phase HD-Wave                                   | Single phase        | Three Phase for 208V grid | Three Phase for 277/480V grid |   |
|---|--|---------------------|---------------------------|-------------------------------|---|
| Minimum String Length (Power Optimizers)                      | P370, P400, P401                                       | 8                   | 10                        | 18                            |   |
|   | P485, P505   | 6                   | 8                         | 14                            |   |
| Maximum String Length (Power Optimizers)                      |  | 25                  | 25                        | 50                            |   |
| Maximum Power per String                                      | 5700 <sup>(8)</sup> (6000 with SE7600-US - SE11400-US) | 5250 <sup>(9)</sup> | 6000 <sup>(9)</sup>       | 12750 <sup>(10)</sup>         | W |
| Parallel Strings of Different Lengths or Orientations         |  |                     |                           | Yes                           |   |

(6) For detailed string sizing information refer to: [http://www.solaredge.com/sites/default/files/string\\_sizing\\_na.pdf](http://www.solaredge.com/sites/default/files/string_sizing_na.pdf)  
 (7) It is not allowed to mix P485/P505 with P370/P400/P401 in one string  
 (8) A string with more than 30 optimizers does not meet NEC rapid shutdown requirements; safety voltage will be above the 30V requirement  
 (9) For 208V grid: it is allowed to install up to 6,500W per string when the maximum power difference between each string is 1,000W  
 (10) For 277/480V grid: it is allowed to install up to 15,000W per string when the maximum power difference between each string is 2,000W

© SolarEdge Technologies Ltd. All rights reserved. SOLAREEDGE, the SolarEdge logo, OPTIMIZED BY SOLAREEDGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: 12/1/2022-NA. Subject to change without notice.



## SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
 AC SYSTEM SIZE : 10000W

MODULES:  
 (35) TRINA SOLAR TSM-390 DE09.05 390W  
 INVERTER:  
 (1) SOLAREEDGE SE10000H-US  
 OPTIMIZER  
 (35) SOLAREEDGE P405

## ENGINEER OF RECORD

## CUSTOMER INFORMATION

NAME & ADDRESS:  
 TERRY EVANS  
 875 TROY PARKER LN,  
 DUNN, NC 28334  
 35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

## OPTIMIZER SPECSHEET

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
 SOLAROFIX

SCALE:AS NOTED PAPER SIZE:17"x11"

DATE:11/19/22 REV:B PV-6.2

### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD

### CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### RACKING SPECSHEET

PROJECT NUMBER:


DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED PAPER SIZE:17"x11"

DATE:11/19/22 REV:B PV-6.3

# RT-MINI II

A Self-flashing PV Mount Featuring Roof Tech's AlphaSeal™ Technology




RT-MINI II is suitable for all systems with a conventional L-Foot.


- ✓ Less Aluminum
- ✓ More Efficient Design
- ✓ Additional Mounting Options
- ✓ Metal, EPDM, TPO, & Asphalt Roofs



1/4" x 1" Carriage Bolt EMT Accessory



RT Serrated Hex Flange Bolt/Nut: 5/16-18 x 1"



Installation Manual



ICC ESR 3575



**Roof Tech**  
The Standard for Waterproof Flexible Flashing Since 1994  
www.roof-tech.us info@roof-tech.us



# RT-MINI II


Flexible Flashing Certified by the International Code Council (ICC)

### Components




Optional Items:  
5 x 60mm Mounting Screw (RT2-04-SD5-60) : 100 ea./Bag  
5/16 X 25MM Flange Bolt & Nut (RT2-04-FBN25) : 100 ea./Bag  
RT-Butyl (RT2-04-MNBUTYL) : 10 ea./Box


### Dimensions in (mm)




### Deck Installation Rafter Installation



### Offset Rafter Installation



### Offset Rafter Attachment Options



RT-Butyl is Roof Tech's flexible flashing used in one million residential PV systems for the last 27 years. It is the first PV mounting system with Flexible Flashing certified by the ICC. Engineered to withstand wind speeds up to 180 mph and ground snow up to 90 psf.


Engineered to ASTM D 1761  
(Standard Test Methods for Mechanical Fasteners in Wood)

ICC ESR-3575 ASTM2140 Testing



TAS 100 A on metal and asphalt roof.  
P.E. Stamped Letters available at [www.roof-tech.us/support](http://www.roof-tech.us/support)

### Metal Flashing Retrofit Flexible Flashing



## Roof Tech Inc.

www.roof-tech.us info@roof-tech.us  
10620 Trenea Street, Suite 230, San Diego, CA 92131  
858.935.6064

January 2022



The right way to attach almost anything to metal roofs!

# S-5!<sup>®</sup>

## The Right Way!

### CorruBracket™


CorruBracket™ can be used to mount almost anything to corrugated metal roofing and is compatible with 7/8" and 3/4" corrugated roofing. No messy sealants to apply! No chance for leaks! The CorruBracket comes with factory-applied butyl sealant already in the base, and the S-5!<sup>®</sup> patented reservoir conceals the sealant, preventing UV degradation.

Installation is simple! CorruBracket is mounted directly into the supporting structure of the roof, i.e. roof decking, wood or steel purlins, or trusses. No surface preparation is necessary; simply wipe away excess oils and debris, peel the release paper, align, and apply. Secure through the pre-punched holes using the appropriate screws for the supporting structure.

CorruBracket is so strong, it will even support heavy-duty applications like snow retention. For corrugated profiles, the CorruBracket is the perfect match for our ColorGard<sup>®</sup> snow retention system. CorruBracket is economical and facilitates quick and easy installation.



CorruBracket™



S-5!<sup>®</sup> CorruBracket™ is the right way to attach almost anything to 7/8" and 3/4" corrugated roofing, including PV via DirectAttached™ or rail methods.

888-825-3432 | www.S-5.com

# S-5!<sup>®</sup>


## The Right Way!

CorruBracket™ is extremely versatile. It can be used for almost any attachment need on 7/8" and 3/4" corrugated metal roofing. No messy sealants to apply. The factory-applied butyl sealant waterproofs and makes installation a snap!


Each CorruBracket™ comes with factory-applied butyl sealant in the base. CorruBracket is compatible with most common metal roofing materials. For design assistance, ask your distributor, or use our web-based calculator at [www.S-5.com](http://www.S-5.com) for job-specific system engineering and design of your next snow retention project. Also, please visit our website for more information including CAD details, metallurgical compatibilities and specifications.

The CorruBracket has been tested for load-to-failure results on wood decking, and metal and wood purlins. The independent lab test data found at [www.S-5.com](http://www.S-5.com) can be used for load-critical designs and applications. S-5!<sup>®</sup> holding strength is unmatched in the industry.

### Example Profile




### CorruBracket™




Please note: All measurements are rounded to the second decimal place. Contact your distributor for information about hardware requirements.

### Example Applications

S-5-PV Kit (DirectAttached™ or Rail)



ColorGard<sup>®</sup>



#### S-5!<sup>®</sup> Warning! Please use this product responsibly!

Products are protected by multiple U.S. and foreign patents. For published data regarding holding strength, bolt torque, patents and trademarks visit the S-5! website at [www.S-5.com](http://www.S-5.com).

Copyright 2013, Metal Roof Innovations, Ltd. S-5! products are patent protected. S-5! aggressively protects its patents, trademarks, and copyrights. Version 120517.

Distributed by



### SYSTEM INFORMATION

DC SYSTEM SIZE : 13650W  
AC SYSTEM SIZE : 10000W

MODULES:  
(35) TRINA SOLAR TSM-390 DE09.05 390W  
INVERTER:  
(1) SOLAREEDGE SE10000H-US  
OPTIMIZER  
(35) SOLAREEDGE P405

### ENGINEER OF RECORD

### CUSTOMER INFORMATION

NAME & ADDRESS:  
TERRY EVANS  
875 TROY PARKER LN,  
DUNN, NC 28334  
35°34'37.6"N 78°59'62.2"W

AHJ: HARNETT COUNTY

UTILITY: DUKE ENERGY PROGRESS

### RACKING SPECSHEET

PROJECT NUMBER:

DESIGNER/CHECKED BY:  
SOLAROFIX

SCALE:AS NOTED

PAPER SIZE:17"x11"

DATE:11/19/22

REV:B

PV-6.4