

SCOPE OF WORK

TO INSTALL A SOLAR PHOTOVOLTAIC (PV) SYSTEM AT THE TRAVASSO RESIDENCE, LOCATED AT 820 CHRISTIAN LIGHT ROAD, FUQUAY-VARINA, NORTH CAROLINA. THE POWER GENERATED BY THE PV SYSTEM WILL BE INTERCONNECTED WITH THE UTILITY GRID THROUGH THE EXISTING ELECTRICAL SERVICE EQUIPMENT. THE PV SYSTEM DOES NOT INCLUDE STORAGE BATTERIES.

SYSTEM RATING

10.400 kW DC STC
9.984 kW AC

EQUIPMENT SUMMARY


(26) SPR-U-400-BLK-W-DC (WAAREE WSMD-400) PV MODULES
(26) ENPHASE IQ7HS-66-M-US [240V] PV INVERTERS
(129) (12 X 10.75') LINEAR FEET SUNPOWER INVISIMOUNT

SHEET INDEX


PV-0 COVER
PV-1 SITE MAP AND PV LAYOUT
PV-1A RACKING PLAN
PV-2 STRING MAP AND MONITORING LAYOUT
PV-3 ELECTRICAL DIAGRAM
PV-4 EQ WALL & MOUNTING DETAIL
PV-5 SYSTEM LABELING DETAIL
PV-6 SITE DIRECTORY PLACARD
PV-7 SAFETY PLAN

GOVERNING CODES

2017 NATIONAL ELECTRIC CODE
2018 NORTH CAROLINA STATE BUILDING CODE
UNDERWRITERS LABORATORIES (UL) STANDARDS
OSHA 29 CFR 1910.269



PROJECT LOCATION



VICINITY MAP

Digitally signed by: Ermocrates E. Castillo
Date: 2023.04.07



DESIGN BY:
FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR

**FREEDOM™
SOLAR POWER**

FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH CAROLINA, 27526
(919) 897-3260

SHEET NAME

COVER

SHEET SIZE

ANSI B
11" x 17"

SHEET NUMBER

PV-0

LEAD ID: 109840

CONSTRUCTION SUMMARY

- (26) (SPR-U-400-BLK-W-DC (WAAREE WSMD-400)) SOLAR MODULES, 10.400 kW DC STC
MODULE DIMENSIONS = 40.9" X 75.7" X 1.38"
- (26) ENPHASE IQ7HS-66-M-US [240V] PV INVERTERS
COMBINED INVERTER OUTPUT = 9.984 kW AC.
- (129) (12 X 10.75') LINEAR FEET SUNPOWER INVISIMOUNT
- (60) QUICKBOLT QB2 ROOF ATTACHMENTS
- (01) SUNPOWER MONITORING

SITE DETAILS

ROOF TYPE: ASPHALT SHINGLE
 ARRAY #1 - TILT = 26°, AZIMUTH = 209°
 ARRAY #2 - TILT = 16°, AZIMUTH = 209°

NOTE: PE STAMPS REQUIRED IF
 -WEIGHT OF ARRAY IS >3PSF
 -MORE THAN 1-LAYER OF SHINGLE
 -ROOF TYPE IS OTHER THAN COMP SHINGLES
 -WIND SPEED IS GREATER THAN 140 MPH

FALL PROTECTION REQUIRED

PV ARRAY #2
(12) MODULES

PV ARRAY #1
(14) MODULES

GROUNDING ELECTRODE
MAIN DISTRIBUTION PANEL
(INSIDE GARAGE WALL)

DUKE ENERGY
REVENUE METER
#331 373 146
SOLAR LOAD CENTER
MONITORING
PV AC DISCONNECT
-VISIBLE
-LOCKABLE
-LABELED
"KNIFE BLADE DISCONNECT"
(OUTSIDE GARAGE WALL)

CONSTRUCTION NOTES

- 1.) ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 2.) ALL OUTDOOR EQUIPMENT SHALL BE RAIN-TIGHT WITH MINIMUM NEMA 3R RATING.
- 3.) ALL LOCATIONS ARE APPROXIMATE AND REQUIRE FIELD VERIFICATION.



Digitally signed by: Ermocrates E. Castillo, Date: 2023.04.07

DESIGN BY:
FREEDOM SOLAR LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|---------------|------------|-----|
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



FREEDOM SOLAR POWER

FREEDOM SOLAR LLC
 4801 FREIDRICH LN, STE 100
 AUSTIN, TX 78744
 TECL # 28621
 TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
 820 CHRISTIAN LIGHT ROAD
 FUQUAY-VARINA, NORTH CAROLINA, 27526
 (919) 897-3260

SHEET NAME


SITE MAP & PV LAYOUT

SHEET SIZE

ANSI B
11" x 17"

SHEET NUMBER

PV-1



Digitally signed by: E. Castillo
Date: 2023.04.07

DESIGN BY:
FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



**FREEDOM[™]
SOLAR POWER**

FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH CAROLINA, 27526
(919) 897-3260

SHEET NAME


RACKING PLAN

SHEET SIZE

ANSI B
11" x 17"




SHEET NUMBER

PV-1A



CONSTRUCTION NOTES

- 1.) ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 2.) ALL OUTDOOR EQUIPMENT SHALL BE RAIN-TIGHT WITH MINIMUM NEMA 3R RATING.
- 3.) ALL LOCATIONS ARE APPROXIMATE AND REQUIRE FIELD VERIFICATION.



Digitally signed by: Ermocrates E. Castillo
Date: 2023.04.07

DESIGN BY:
FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



**FREEDOM[™]
SOLAR POWER**

FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH CAROLINA, 27526
(919) 897-3260

SHEET NAME

STRING MAP & MONITORING LAYOUT

SHEET SIZE


ANSI B
11" x 17"

SHEET NUMBER

PV-2

SUNPOWER SUPERVISOR S/N _____

SOLAR ARRAY - 10.400 kW DC STC, 9.984 kW AC STC (26) SUNPOWER SPR-U-400-BLK-W-DC (WAAREE WSMD-400W) MODULES



ELECTRICAL NOTES

- 1.) ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL, AND LABELED FOR ITS APPLICATION.
- 2.) ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600 V AND 90°C WET ENVIRONMENT UNLESS OTHERWISE NOTED.
- 3.) IN CASE WIRING, CONDUIT AND RACEWAYS ARE MOUNTED ON ROOFTOPS, THEY SHALL BE ROUTED DIRECTLY TO, AND LOCATED AS CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP OR VALLEY, NO LESS THAN 7/8" ABOVE THE ROOF SURFACE.
- 4.) WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- 5.) DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- 6.) WHERE SIZES OF JUNCTION BOXES, RACEWAYS AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY. SPECIFIED CONDUIT SIZES ARE MINIMUM REQUIREMENTS AND LARGER DIAMETER SHALL BE PERMITTED.
- 7.) ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- 8.) MAXIMUM MOUNTING HEIGHT FROM GRADE TO CENTER OF METER SOCKET SHALL BE 72" FOR RESIDENTIAL SINGLE PHASE METER SOCKETS 0-320 AMPS. MINIMUM MOUNTING HEIGHT IS 30" FROM FOR AUSTIN ENERGY, AND 48" FOR ALL OTHER JURISDICTIONS
- 9.) MINIMUM HORIZONTAL CLEARANCE FROM GAS REGULATOR TO ANY ELECTRICAL ENCLOSURE IS 36", EXCEPT AUSTIN ENERGY WHICH REQUIRES 48" CLEARANCE FROM GAS TO METER SOCKET
- 10.) PV DISCONNECT SHALL BE VISIBLE, LOCKABLE AND LABELED AND THE DOOR CANNOT BE OPENED WHEN HANDLE IS IN ON POSITION
- 11.) BY DEFAULT THE MONITORING DEVICE IS SHOWN CONNECTED TO A 20-AMP BREAKER IN THE SOLAR LOAD CENTER. ALTERNATIVELY, THE MONITORING DEVICE MAY BE CONNECTED TO A 20 AMP BREAKER AT THE MAIN DISTRIBUTION PANEL.
- 12.) ALL EQUIPMENT TERMINATIONS SHALL BE RATED FOR 75 DEGREES OR GREATER
- 13.) ALL CT WIRES SHALL BE CONSIDERED CLASS 1 PER NEC ARTICLE 725, AND BE MARKED AS RATED FOR 600V. PER 725.48(A) CLASS 1 CIRCUITS SHALL BE PERMITTED TO OCCUPY THE SAME RACEWAY AS OTHER CIRCUITS PROVIDED ALL CONDUCTORS ARE INSULATED FOR THE MAXIMUM VOLTAGE OF ANY CONDUCTOR IN THE RACEWAY.
- 14.) AWG #10 COPPER CONDUCTORS ARE SPECIFIED AS THE DEFAULT WIRE REQUIRE FROM THE PV ARRAY TO THE SOLAR LOAD CENTER, HOWEVER, AWG #12 COPPER CONDUCTORS MAY BE UTILIZED IF BOTH OF THE FOLLOWING CONDITIONS ARE MET: THE LENGTH OF THE CONDUCTOR IS LESS THAN 75 FT AND THERE ARE LESS THAN 8 CURRENT-CARRYING CONDUCTORS WITHIN THE RACEWAY.

| CALCULATIONS FOR CURRENT CARRYING CONDUCTORS | CALCULATIONS FOR OVERCURRENT DEVICES |
|--|---|
| INVERTER OUTPUT WIRE AMPACITY CALCULATION [NEC 690.8(A)(3)]: 1.60A PER INVERTER (ENPHASE IQ7HS-66-M-US [240V]) MAXIMUM INVERTER BRANCH CURRENT = (10)(1.60A) = 16.0A CONTINUOUS USE: #12 WIRE 75°C DERATED AMPACITY = (0.80)(25.0A) = 20.0A 20.0A > 16.0A CONDITIONS OF USE: #12 WIRE 90°C DERATED AMPACITY = (0.91)(0.80)(30.0A) = 21.8A 21.8A > 16.0A | INVERTER BRANCH AC CURRENT CALCULATION [NEC 690.8(A)(3)]: 1.60A PER INVERTER (ENPHASE IQ7HS-66-M-US [240V]) MAXIMUM BRANCH INVERTER CURRENT = (10)(1.60A) = 16.0A MINIMUM OCPD = (16.0A)(1.25) = 20.0A USE 2P-20A BREAKERS IN SOLAR LOAD CENTER FOR INVERTER BRANCH OCPD |
| SOLAR LOAD CENTER OUTPUT WIRE AMPACITY CALCULATION [NEC 690.8(A)(3)]: 1.60A PER INVERTER (ENPHASE IQ7HS-66-M-US [240V]) COMBINED CURRENT = (26)(1.60A) = 41.6A CONTINUOUS USE: #6 WIRE 75°C DERATED AMPACITY = (0.80)(65A) = 52.0A 52.0A > 41.6A CONDITIONS OF USE: #6 WIRE 90°C DERATED AMPACITY = (0.91)(75A) = 68.3A 68.3A > 41.6A | SYSTEM AC CURRENT CALCULATION [NEC 690.8(A)(3)]: 1.60A PER INVERTER (ENPHASE IQ7HS-66-M-US [240V]) COMBINED CURRENT = (26)(1.60A) = 41.6A MINIMUM OCPD = (41.6A)(1.25) = 52.0A USE 2P-60A BREAKER IN MDP FOR SYSTEM OCPD |

DESIGN BY:
FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR

**FREEDOM[™]
SOLAR POWER**

FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH
CAROLINA, 27526
(919) 897-3260

SHEET NAME

**ELECTRICAL
DIAGRAM**

SHEET SIZE

**ANSI B
11" x 17"**

SHEET NUMBER

PV-3

MAIN DISTRIBUTION PANEL
-POINT OF INTERCONNECTION
- INSIDE GARAGE WALL

PV AC DISCONNECT
-KNIFE BLADE DISCONNECT

DUKE ENERGY
REVENUE METER

MONITORING

SOLAR LOAD CENTER
-OUTSIDE GARAGE WALL

FROM PV ARRAY

DESIGN BY:
FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



**FREEDOMSM
SOLAR POWER**

FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH
CAROLINA, 27526
(919) 897-3260

EQUIPMENT ELEVATION
NTS

1

SEE (3/PV4 - EQ
WALL) FOR
ENLARGED
VIEW


QUICKBOLT QB2 ROOF
ATTACHMENT AT @72" O.C

(E) SHINGLE ROOF

2"X6" TRUSSES 24"O.C

MOUNTING METHOD
NTS

2



MOUNTING DETAIL
NTS

3

SHEET NAME
EQ.WALL &
MOUNTING DETAIL

SHEET SIZE
ANSI B
11" x 17"

SHEET NUMBER
PV-4

NOTE: NOT ALL LABELS MAY BE APPLICABLE

SIGNAGE REQUIREMENTS

- > RED BACKGROUND
- > WHITE LETTERING
- > MIN. 3/8" LETTER HEIGHT
- > ALL CAPITAL LETTERS
- > ARIAL OR SIMILAR FONT
- > REFLECTIVE, WEATHER RESISTANT MATERIAL, UL 969

PV SYSTEM DISCONNECT

WARNING
ELECTRIC SHOCK HAZARD.
DO NOT TOUCH TERMINALS.
TERMINALS ON THE LINE AND
LOAD SIDES MAY BE
ENERGIZED IN THE OPEN
POSITION.

WARNING: PHOTOVOLTAIC
POWER SOURCE

WARNING
POWER SOURCE OUTPUT
CONNECTION. DO NOT
RELOCATE THIS
OVERCURRENT DEVICE

REQ'D BY: NEC 690.13(B)
 APPLY TO:
 PV DISCONNECT

A

REQ'D BY: NEC 690.13(B)
 APPLY TO:
 PV DISCONNECT

B

REQ'D BY: NEC 690.31(G)(3)
 APPLY TO:
 RACEWAYS, CABLE TRAYS,
 OTHER WIRING METHODS, AND
 ENCLOSURES THAN CONTAIN
 PV SYSTEM DC CONDUCTORS

C

REQ'D BY: NEC 705.12(B)(2)(3)(b)
 APPLY TO:
 DISTRIBUTION EQUIPMENT
 ADJACENT TO BACK-FED BREAKER

D

2" ADDRESS NUMBERS

REVENUE METER

MONITORING

RAPID SHUTDOWN SWITCH
FOR SOLAR PV SYSTEM

REQ' BY: AHJ
 APPLY TO:
 REVENUE METER SOCKET
 (IF APPLICABLE)

E

REQ'D BY: AHJ
 APPLY TO:
 REVENUE METER SOCKET
 (IF APPLICABLE)

F


REQ'D BY: FREEDOM SOLAR
 APPLY TO:
 MONITORING DEVICE ENCLOSURE

G

REQ'D BY: NEC 690.56(C)(2)
 APPLY TO:
 PV DISCONNECT

H

PHOTOVOLTAIC SYSTEM
AC DISCONNECT
OPERATING CURRENT: 41.6A
OPERATING VOLTAGE: 240 VAC



CAUTION
 POWER TO THIS BUILDING IS ALSO SUPPLIED FROM THE
 FOLLOWING SOURCES WITH DISCONNECTS AS SHOWN:

UTILITY SUPPLY & CUSTOMER
 SERVICE PANEL

PV AC DISCONNECT

RAPID SHUTDOWN SWITCH

FRONT

REQ'D BY: 705.10
 APPLY TO:
 MAIN DISTRIBUTION PANEL
 (*ONLY REQUIRED IF PV SYSTEM
 DISCONNECT IS NOT GROUPED
 WITH MAIN SERVICE DISCONNECT)
**SEE SHEET PV-6 FOR SITE
 SPECIFIC LABELS**

K

REQ'D BY: 690.56(1)(a)
 APPLY TO:
 PV DISCONNECT

I

REQ'D BY: NEC 690.56(C)(1)(a)
 UTILITY AC DISCONNECT

J

DESIGN BY:
 FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



FREEDOM
SOLAR POWER

FREEDOM SOLAR LLC
 4801 FREDRICH LN, STE 100
 AUSTIN, TX 78744
 TECL # 28621
 TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
 820 CHRISTIAN LIGHT ROAD
 FUQUAY-VARINA, NORTH
 CAROLINA, 27526
 (919) 897-3260

SHEET NAME

**SYSTEM
 LABELING
 DETAIL**

SHEET SIZE

**ANSI B
 11" x 17"**

SHEET NUMBER

PV-5

DESIGN BY:
FREEDOM SOLAR LLC

REVISIONS

| DESCRIPTION | DATE | REV |
|---------------|------------|-----|
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR



**FREEDOMTM
SOLAR POWER**
FREEDOM SOLAR LLC
4801 FREIDRICH LN, STE 100
AUSTIN, TX 78744
TECL # 28621
TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
820 CHRISTIAN LIGHT ROAD
FUQUAY-VARINA, NORTH
CAROLINA, 27526
(919) 897-3260

SHEET NAME

SITE
DIRECTORY
PLACARD

SHEET SIZE

ANSI B
11" x 17"


SHEET NUMBER

PV-6

CAUTION:

MULTIPLE SOURCES OF POWER

LOCATION OF EACH POWER SOURCE
DISCONNECTING MEANS SHOWN BELOW




QUESTIONS, CALL:
800-504-2337
www.freedomsolarpower.com


820 CHRISTIAN LIGHT ROAD
PROJECT ID:109840

USE THE SAFETY SYMBOL KEY TO DRAW IN THE CONTROLLED ACCESS ZONE (CAZ), LADDER PLACEMENT, METER LOCATION, FALL PROTECTION ANCHOR POINT, AND ANY OTHER HAZARD.

HARD HAT IS REQUIRED AT ALL TIMES IN CAZ



SAFETY SYMBOL KEY

- CAZ
- L** LADDER
- M** METER
- ==== POWER LINES
- R** RESTRAINT ANCHOR
- A** ARREST ANCHOR

Digitally signed by: Ermocra S E Castillo
 Date: 2023.04.07

DESIGN BY:
 FREEDOM SOLAR LLC

| REVISIONS | | |
|---------------|------------|-----|
| DESCRIPTION | DATE | REV |
| DESIGN PACKET | 04/04/2023 | |
| | | |
| | | |
| | | |
| | | |
| | | |

CONTRACTOR

FREEDOM SOLAR POWER
 FREEDOM SOLAR LLC
 4801 FREIDRICH LN, STE 100
 AUSTIN, TX 78744
 TECL # 28621
 TBPE FIRM # F-17690

PROJECT NAME

MARIA TRAVASSO
 820 CHRISTIAN LIGHT ROAD
 FUQUAY-VARINA, NORTH CAROLINA, 27526
 (919) 897-3260

SHEET NAME

SAFETY PLAN

SHEET SIZE

**ANSI B
 11" x 17"**

SHEET NUMBER

PV-7

CONDUCT SAFETY MEETING WITH ALL CREW MEMBERS ON SITE AT THE BEGINNING OF EACH JOB. USE SIGN IN SHEET BELOW.

1. _____
2. _____
3. _____
4. _____
5. _____

GUEST SIGN IN

1. _____
2. _____
3. _____

COMPETENT PERSON: _____ JOB START DATE: _____

ARKA SERIES

WSMDi-395 to WSMDi-415



One with the Sun



One with the Sun



Highest reliability & enhanced crack tolerant 9BB module



Better performance under all climatic conditions



Split junction box




Reduced power losses up to 1/4 times




PID resistant with long term reliability




Sustain heavy wind & snow loads (2400 pa & 5400 pa)




M6 Mono PERC cells




I-V VARIATION WITH IRRADIANCE



I-V VARIATION WITH TEMPERATURE



The Graphs are for reference purpose only. Please consult Waaree technical team for further clarifications.



INTERNATIONAL & NATIONAL CERTIFICATIONS

IEC 61215 | IEC 61730 | UL61730
IEC TS 62804-1



ISO 9001:2015 | ISO 14001:2015 | ISO 45001:2018
Independent assessment of factories by BLACK & VEATCH

ARKA SERIES

WSMDi-395 to WSMDi-415

ELECTRICAL CHARACTERISTICS

| Models | Pmax (W) | | Vmp (V) | | Imp (A) | | Isc (A) | | Voc (V) | | Module Eff. (%) |
|----------|----------|-------|---------|-------|---------|------|---------|------|---------|-------|-----------------|
| | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | |
| WSMD-395 | 395 | 296.8 | 37.77 | 34.70 | 10.47 | 8.55 | 11.24 | 9.08 | 45.00 | 42.10 | 19.78 |
| WSMD-400 | 400 | 300.6 | 38.00 | 34.90 | 10.54 | 8.62 | 11.32 | 9.14 | 45.22 | 42.30 | 20.03 |
| WSMD-405 | 405 | 304.4 | 38.22 | 35.10 | 10.61 | 8.68 | 11.40 | 9.21 | 45.44 | 42.50 | 20.28 |
| WSMD-410 | 410 | 308.2 | 38.44 | 35.30 | 10.68 | 8.74 | 11.48 | 9.27 | 45.66 | 42.70 | 20.53 |
| WSMD-415 | 415 | 312.1 | 38.66 | 35.40 | 10.75 | 8.81 | 11.57 | 9.34 | 45.88 | 42.90 | 20.78 |


*Standard Test Conditions (STC) - 1000 W/m2 irradiance, Air Mass 1.5 and 25°C cell temperature. Nominal Operating Cell Temperature (NOCT) - 800 W/m2 irradiance, Air Mass 1.5, Ambient temperature 20°C and Wind speed 1 m/s. Average power reduction of 4.5% at 200 W/m2 as per IEC 60904-1. Measuring Uncertainty ± 3%.

| | | | |
|----------------|--------|--------------------|------|
| System Voltage | 1500 V | Series Fuse Rating | 22 A |
|----------------|--------|--------------------|------|

MECHANICAL CHARACTERISTICS

| | |
|--|---|
| Length x Width x Thickness (L x W x T) | 1924 mm (L) x 1038 mm (W) x 35 mm (T) |
| Weight | 22 kgs |
| Solar Cells per Module (Units) / Arrangement | 132 cells / (11x6 11x6) |
| Solar Cell Type & Size | Mono PERC, 83 x 166 mm |
| Front Glass | 3.2 mm Low Iron and Tempered glass with ARC coating |
| Encapsulate | PID Free & UV Resistant |
| Junction Box (Protection degree/ Material) | IP68 / Weatherproof PPO |
| Cable & Connector (Protection degree / Type) | IP68 rated / Staubli MC4 Connector |
| Cable cross - section & Length | 4 mm ² & 1200mm |
| Frame | Anodized Aluminium Alloy, Anodization thickness ≥ 15 micron |

DESIGN SPECIFICATIONS



THERMAL CHARACTERISTICS

| | |
|--|----------|
| Temperature coefficient of Current (Isc), α (%/°C) | 0.055 |
| Temperature coefficient of Voltage (Voc), β (%/°C) | -0.285 |
| Temperature coefficient of Power (Pm), γ (%/°C) | -0.365 |
| NOCT (°C) | 43 ± 2 |
| Operating temperature range (°C) | -40 to 8 |

Waaree Energies Ltd. is amongst the top Solar Energy Companies and has the country's largest Solar PV Module manufacturing capacity of 5 GW. In addition, it is committed to provide top notch EPC services, project development, rooftop solutions, solar water pumps and also in an Independent Power Producer. Waaree has its presence in over 325+ locations nationally and 68 countries globally.

*If you need specific product certificates, and if module installations are to deviate from our guidance specified in our installation manual, please contact your local Waaree sales and technical representatives.

12 Years Product Warranty • 27 Years Power Output Warranty

- The electrical data given here is for reference purpose only.
- Please confirm your exact requirements with the sales representative while placing your order.
- Refer installation Manual instructions & Waaree warranty statement for terms & conditions.
- Waaree Reserves the right to change the specifications without prior notice.z

Enphase IQ7HS Microinverter

The high-powered smart grid-ready **Enphase IQ7HS Microinverter™** with integrated MC4 connectors dramatically simplify the installation process while achieving the highest system efficiency.

The IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power-on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.



Easy to Install

- Lightweight and simple
- Faster installation with improved, lighter two-wire cabling
- Built-in rapid shutdown compliant (NEC 2014, 2017 & 2020)

Efficient and Reliable

- Optimized for high powered 66-cell* modules
- Highest CEC efficiency of 97.0%
- More than a million hours of testing
- Class II double-insulated enclosure
- UL listed

Smart Grid Ready

- Complies with advanced grid support, voltage and frequency ride-through requirements
- Remotely updates to respond to changing grid requirements
- Configurable for varying grid profiles
- Meets CA Rule 21 (UL 1741-SA)

* The IQ7HS is required to support 66-cell modules.

Enphase IQ7HS Microinverter

| INPUT DATA (DC) | IQ7HS-66-M-US | |
|--|---|--|
| Commonly used module pairings ¹ | 320 W - 460 W + | |
| Module compatibility | 66-cell PV modules | |
| Maximum input DC voltage | 59 V | |
| Peak power tracking voltage | 38 V - 43 V | |
| Operating range | 20 V - 59 V | |
| Min/Max start voltage | 30 V / 59 V | |
| Max DC short circuit current (module Isc) | 15 A | |
| Overvoltage class DC port | II | |
| DC port backfeed current | 0 A | |
| PV array configuration | 1 x 1 ungrounded array; No additional DC side protection required; AC side protection requires max 20A per branch circuit | |

| OUTPUT DATA (AC) | @240 VAC | @208 VAC |
|--|------------------------------|------------------------------|
| Peak output power | 384 VA | 369 VA |
| Maximum continuous output power | 384 VA | 369 VA |
| Nominal (L-L) voltage/range ² | 240 V / 211-264 V | 208 V / 183-229 V |
| Maximum continuous output current | 1.60 A (240V) | 1.77 A (208V) |
| Nominal frequency | 60 Hz | 60 Hz |
| Extended frequency range | 47 to 68 Hz | 47 to 68 Hz |
| AC short circuit fault current over 3 cycles | 4.82 A | 4.82 A |
| Maximum units per 20 A (L-L) branch circuit ³ | 10 | 9 |
| Overvoltage class AC port | III | III |
| AC port backfeed current | 18 mA | 18 mA |
| Power factor setting | 1.0 | 1.0 |
| Power factor (adjustable) | 0.85 leading ...0.85 lagging | 0.85 leading ...0.85 lagging |

| EFFICIENCY | @240 V | @208 V |
|-------------------------|--------|--------|
| CEC weighted efficiency | 97.0 % | 96.5 % |

| MECHANICAL DATA | |
|---|---|
| Ambient temperature range | -40°C to +60°C |
| Relative humidity range | 4% to 100% (condensing) |
| Connector type | Staubli made MC4 |
| Dimensions (WxHxD) | 212 mm x 175 mm x 30.2 mm (without bracket) |
| Weight | 1.08 kg (2.38 lbs) |
| Cooling | Natural convection - No fans |
| Approved for wet locations | Yes |
| Pollution degree | PD3 |
| Enclosure | Class II, corrosion resistant polymeric enclosure |
| Environmental category / UV exposure rating | NEMA type 6 / outdoor |
| Altitude | 2000m |

| FEATURES | |
|---------------------|--|
| Communication | Power Line Communication (PLC) |
| Disconnecting means | The AC and DC connectors have been evaluated and approved by UL for use as the load-break disconnect means required by NEC 690 and C22.1-2018 Rule 64-220. |
| Compliance | CA Rule 21 (UL 1741-SA), HECO v1.1 UL 62109-1, UL1741/IEEE1547, FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 This product is UL Listed as PV Rapid Shut Down Equipment and conforms with NEC-2014, NEC-2017 section 690.12, NEC 2020 and C22.1-2015 Rule 64-218 Rapid Shutdown of PV Systems, for AC and DC conductors, when installed according to manufacturer's instructions. |

1. No enforced DC/AC ratio. See the compatibility calculator at <https://enphase.com/en-us/support/module-compatibility>.
 2. Nominal voltage range can be extended beyond nominal if required by the utility.
 3. Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

To learn more about Enphase offerings, visit enphase.com






SunPower® EnergyLink™ | Residential and Commercial PVS6

Improve Support, Reduce Maintenance Costs

An intuitive monitoring website enables you to:

- See a visual map of customer sites
- Remotely manage hundreds of sites
- Receive elective system reports
- Locate system issues and remotely diagnose
- Diagnose issues online
- Drill down for the status of individual devices



Add Value for Customers

With the SunPower Monitoring System customers can:

- See what their solar system produces each day, month, or year
- Optimize their solar investment and save on energy expenses
- See their energy use and estimated bill savings
- See their solar system's performance using the SunPower monitoring website or mobile app



SunPower EnergyLink—Plug-and-Play Installation

This complete solution for residential and commercial monitoring and control includes the SunPower® PV Supervisor 6 (PVS6) which improves the installation process, overall system reliability, and customer experience.

- Compact footprint for improved aesthetics
- Robust cloud connectivity and comprehensive local connectivity
- Flexible configuration of devices during installation
- Consumption metering
- Revenue-grade production metering (pending)
- Web-based commissioning
- Remote diagnostics of PVS6 and inverters
- Durable UL Type 3R enclosure reduces maintenance costs
- Easy integration with SunPower eBOS



Robust Cloud Connectivity


Multiple options to maintain optimal connectivity:

- Hardwired Ethernet
- Wi-Fi
- Cellular backup



SunPower® EnergyLink™ | Residential and Commercial PVS6


SunPower Monitoring Websites



PVS6



SunPower AC Modules



Multiple communication options include Ethernet, Wi-Fi, and cellular.

| Site Requirements | |
|--|---|
| Number of SunPower AC modules supported per PVS6 | 85 |
| Internet access | High-speed internet access via accessible router or switch |
| Power | <ul style="list-style-type: none"> • 100–240 VAC (L–N), 50 or 60 Hz • 208 VAC (L–L in 3-phase), 60 Hz |

| Operating Conditions | |
|----------------------|----------------------------------|
| Temperature | –22°F to +140°F (–30°C to +60°C) |
| Humidity (maximum) | 95%, non-condensing |

| Mechanical | |
|------------------|--|
| Weight | 5.5 lbs (2.5 kg) |
| Dimensions | 11.8 × 8.0 × 4.2 in. (30.5 × 20.5 × 10.8 cm) |
| Enclosure rating | UL50E Type 3R |

| Communication | |
|---------------------|--|
| RS-485 | Inverters and meters |
| Integrated Metering | <ul style="list-style-type: none"> • One channel of revenue-grade production metering • Two channels of consumption metering |
| Ethernet | 1 LAN (or optional WAN) port |
| PLC | PLC for SunPower AC modules |
| Wi-Fi | 802.11b/g/n 2.4 GHz and 5 GHz |
| Cellular | LTE Cat-M1/3G UMTS |
| ZigBee | IEEE 802.15.4 MAC, 2.4GHz ISM band |
| Data Storage | 60 days |
| Upgrades | Automatic firmware upgrades |

| Web and Mobile Device Support | |
|-------------------------------|--|
| Customer site | monitor.us.sunpower.com |
| Partner site | pvsmgmt.us.sunpower.com |
| Browsers | Firefox, Safari, and Chrome |
| Mobile devices | iPhone®, iPad®, and Android™ |
| Customer app | <ol style="list-style-type: none"> 1. Create account online at: monitor.us.sunpower.com. 2. On a mobile device, download the SunPower Monitoring app from Apple App Store™ or Google Play™ store. 3. Sign in using account email and password. |

| Warranty and Certifications | |
|-----------------------------|---|
| Warranty | 10-year Limited Warranty |
| Certifications | UL, cUL, CE, UL 61010-1 and -2, FCC Part 15 (Class B) |



© 2019 SunPower Corporation. All rights reserved. SUNPOWER, SUNPOWER logo, and ENERGYLINK are trademarks or registered trademarks of SunPower Corporation. iPhone and iPad are registered trademarks of Apple Inc. Android and Google Play are trademarks of Google Inc. All other trademarks are the property of their respective owners. Specifications included in this datasheet are subject to change without notice.

530536 RevC





SunPower® InvisiMount™ | Residential Mounting System

Simple and Fast Installation

- Integrated module-to-rail grounding
- Pre-assembled mid and end clamps
- Levitating mid clamp for easy placement
- Mid clamp width facilitates consistent, even module spacing
- UL 2703 Listed integrated grounding

Flexible Design


- Addresses nearly all sloped residential roofs
- Design in landscape and portrait with up to 8' rail span
- Pre-drilled rails and rail splice
- Rails enable easy obstacle management

Customer-Preferred Aesthetics

- #1 module and #1 mounting aesthetics
- Best-in-class system aesthetics
- Premium, low-profile design
- Black anodized components
- Hidden mid clamps and capped, flush end clamps

Part of Superior System

- Built for use with SunPower DC and AC modules
- Best-in-class system reliability and aesthetics
- Optional rooftop transition flashing, rail-mounted J-box, and wire management rail clips
- Combine with SunPower modules and SunPower EnergyLink® monitoring app



Elegant Simplicity

SunPower® InvisiMount™ is a SunPower-designed rail-based mounting system. The InvisiMount system addresses residential sloped roofs and combines faster installation time, design flexibility, and superior aesthetics. The InvisiMount product was specifically envisioned and engineered to pair with SunPower modules. The resulting system-level approach amplifies the aesthetic and installation benefits—for homeowners and for installers.

sunpower.com



SunPower® InvisiMount™ | Residential Mounting System

InvisiMount Components



| InvisiMount Component Details | | |
|-------------------------------|--|-------------------|
| Mid clamp | Black oxide stainless steel 300 series | 63 g (2.2 oz) |
| End clamp | Black anodized aluminum 6000 series | 110 g (3.88 oz) |
| Rail | Black anodized aluminum 6000 series | 830 g/m (9 oz/ft) |
| Rail splice | Aluminum alloy 6000 series | 830 g/m (9 oz/ft) |
| Rail bolt | M10-1.5 x 25 mm; custom T-head SS304 | 18 g (0.63 oz) |
| Rail nut | M10-1.5; DIN 6923 SS304 | nominal |
| Ground lug assembly | SS304; A2-70 bolt; tin-plated copper lug | 106.5 g (3.75 oz) |
| Row-to-row grounding clip | SS 301 with SS 304 M6 bolts | 75 g (2.6 oz) |
| Row-to-row spacer | Black POM-grade plastic | 5 g (0.18 oz) |

| InvisiMount Operating Conditions | |
|----------------------------------|---|
| Temperature | -40° C to 90° C (-40° F to 194° F) |
| Max. Load (LRFD) | <ul style="list-style-type: none"> • 3000 Pa uplift • 6000 Pa downforce |

| Roof Attachment Hardware Supported by Design Tool | |
|---|--|
| Application | <ul style="list-style-type: none"> • Composition Shingle Rafter Attachment • Composition Shingle Roof Decking Attachment • Curved and Flat Tile Roof Attachment • Universal interface for other roof attachments |

| InvisiMount Component LRFD Capacities ² | | |
|--|------------------|------------|
| Mid clamp | Uplift | 664 lbf |
| | Shear | 540 lbf |
| End clamp | Uplift | 899 lbf |
| | Shear | 220 lbf |
| Rail | Moment: upward | 548 lbf-ft |
| | Moment: downward | 580 lbf-ft |
| Rail splice | Moment: upward | 548 lbf-ft |
| | Moment: downward | 580 lbf-ft |
| L-foot | Uplift | 1000 lbf |
| | Shear | 390 lbf |

| InvisiMount Warranties And Certifications | |
|---|--|
| Warranties | <ul style="list-style-type: none"> • 25-year product warranty • 5-year finish warranty |
| Certifications | <ul style="list-style-type: none"> • UL 2703 Listed • Class A Fire Rated |



| Roof Attachment Hardware Warranties | |
|---|--|
| Refer to roof attachment hardware manufacturer's documentation. | |

¹ Module frame that is compatible with the InvisiMount system required for hardware interoperability.
² SunPower recommends that all Equinox™, InvisiMount™, and AC module systems always be designed using the InvisiMount Span Tables #524734. If a designer decides to instead use the component capacities listed in this document to design a system, note that the capacities shown are Load and Resistance Factor Design (LRFD) design loads, and are NOT to be used for Allowable Stress Design (ASD) calculations; and that a licensed Professional Engineer (PE) must then stamp all calculations. If you have any questions please contact SunPower Technical Support at 1-855-977-7867.

© 2018 SunPower Corporation. All Rights Reserved. SUNPOWER, the SUNPOWER logo, EQUINOX, and INVISIMOUNT are trademarks or registered trademarks of SunPower Corporation. All other trademarks are the property of their respective owners. Specifications included in this datasheet are subject to change without notice.

SPEC SHEET

| Part # | Box Quantity |
|--------|--|
| 17660 | 4" QB2 (25) |
| 17662 | 3" Microflashing® (25); 4" QB2 (25); L-Foot (25) |



Eaton general duty cartridge fuse safety switch

DG222NRB

UPC:782113144221

Dimensions:

- **Height:** 14.37 IN
- **Length:** 7.35 IN
- **Width:** 8.4 IN

Weight:10 LB

Notes:Maximum hp ratings apply only when dual element fuses are used. 3-Phase hp rating shown is a grounded B phase rating, UL listed.

Warranties:

- Eaton Selling Policy 25-000, one (1) year from the date of installation of the Product or eighteen (18) months from the date of shipment of the Product, whichever occurs first.

Specifications:

- **Type:** General duty, cartridge fused
- **Amperage Rating:** 60A
- **Enclosure:** NEMA 3R
- **Enclosure Material:** Painted galvanized steel
- **Fuse Class Provision:** Class H fuses
- **Fuse Configuration:** Fusible with neutral
- **Number Of Poles:** Two-pole
- **Number Of Wires:** Three-wire
- **Product Category:** General duty safety switch
- **Voltage Rating:** 240V

Supporting documents:

- [Eatons Volume 2-Commercial Distribution](#)
- [Eaton Specification Sheet - DG222NRB](#)

Certifications:

- UL Listed

Product compliance: No Data



Eaton general duty non-fusible safety switch

DG222URB

UPC:782113144238

Dimensions:

- **Height:** 14.38 IN
- **Length:** 7.38 IN
- **Width:** 8.69 IN

Weight:9 LB

Notes:WARNING! Switch is not approved for service entrance unless a neutral kit is installed.

Warranties:

- Eaton Selling Policy 25-000, one (1) year from the date of installation of the Product or eighteen (18) months from the date of shipment of the Product, whichever occurs first.

Specifications:

- **Type:** Non-fusible, single-throw
- **Amperage Rating:** 60A
- **Enclosure:** NEMA 3R, Rainproof
- **Enclosure Material:** Painted galvanized steel
- **Fuse Configuration:** Non-fusible
- **Number Of Poles:** Two-pole
- **Number Of Wires:** Two-wire
- **Product Category:** General duty safety switch
- **Voltage Rating:** 240V

Supporting documents:

- [Eatons Volume 2-Commercial Distribution](#)
- [Eaton Specification Sheet - DG222URB](#)

Certifications:

- UL Listed

Product compliance: No Data



Eaton CH main lug loadcenter

CH8L125RP

UPC:782114190548

Dimensions:

- **Height:** 3.69 IN
- **Length:** 13 IN
- **Width:** 11 IN

Weight:12 LB

Notes:Ground bar kits priced separately. Suitable for use as service equipment when not more than two service disconnecting mains are provided or when not used as a lighting and appliance panelboard.

Warranties:

- Limited lifetime

Specifications:

- **Special Features:** Cover included
- **Type:** Main lug only
- **Amperage Rating:** 125A
- **Box Size:** 7r
- **Bus Material:** Copper
- **Enclosure:** NEMA 3R
- **Enclosure Material:** Metallic
- **Feed Type:** Overhead
- **Main Circuit Breaker:** CH
- **Number Of Circuits:** 8
- **Number Of Wires:** Three-wire
- **Phase:** Single-phase
- **Voltage Rating:** 120/240V, 208Y/120, 240V
- **Wire Size:** #6-1/0 AWG

Supporting documents:

- [Type CH Circuit Breakers and Loadcenters](#)
- [Loadcenters and Circuit Breakers](#)
- [Eatons Volume 1-Residential and Light Commercial](#)



Eaton CH main lug loadcenter

CH12L125R

UPC:782113097381

Dimensions:

- **Height:** 5.19 IN
- **Length:** 16.75 IN
- **Width:** 14.31 IN

Weight:15.8 LB

Notes:Suitable for use as service equipment when not more than six service disconnecting mains are provided or when not used as a lighting and appliance panelboard. Rainproof panels are furnished with hub closure plates. For rainproof hubs.

Warranties:

- Limited lifetime







Specifications:

- **Special Features:** Cover included
- **Type:** Main lug only
- **Amperage Rating:** 125A
- **Box Size:** B
- **Bus Material:** Copper
- **Enclosure:** NEMA 3R
- **Enclosure Material:** Metallic
- **Feed Type:** Overhead
- **Main Circuit Breaker:** CH
- **Number Of Circuits:** 12
- **Number Of Wires:** Three-wire
- **Phase:** Single-phase
- **Voltage Rating:** 120/240V
- **Wire Size:** #6-2/0 AWG


Supporting documents:

- [Dimensional Drawing - CH 3/4 LOADCENTER, MAIN LUG ONLY, OUTDOOR NEMA 3R, 120/240 VAC, 1 PH](#)





UL Listed
 Marine Listed
 UL File # E205935 (QCUP)
 UL Control # 92CM
 Material is Rigid PVC
 132 cu in Volume (2163 cu cm)
 Screws are Zinc Plated Steel
 Gasket is neoprene



| | | |
|--|---------------|---------|
| CANTEX INC. Fort Worth, TEXAS | | |
| Junction Box 6 x 6 x 4 | | |
| Drawn By: O.M. | Date: 6/19/17 | 5133710 |

1.4 Listings, Compatibility, and Classification

The SunPower InvisiMount Residential Mounting System is UL 2703 Listed. The InvisiMount Listing **includes** the following modules, which have been tested for grounding and mechanical load with the InvisiMount system.

For Classic InvisiMount certification information, refer to UL at their site <https://www.ul.com> or the at the UL portal <https://www.ul.com/resources/apps/myul-client-portal> and view *File E314938* and *File E466981*. For Universal InvisiMount certification information, refer to Intertek at [https://ramuk.intertekconnect.com/WebClients/ITS/DLP/products.nsf/\\$\\$Search?OpenForm](https://ramuk.intertekconnect.com/WebClients/ITS/DLP/products.nsf/$$Search?OpenForm) and view *Control Number 5024883*.

| SunPower DC Modules | SunPower AC Modules | |
|--|---|--|
| <ul style="list-style-type: none"> • SPR-A400-BLK-DC • SPR-A400-DC • SPR-A410-DC • SPR-E19-320 • SPR-E20-327 • SPR-X21-335-BLK • SPR-X21-350-BLK • SPR-X21-345 • SPR-X22-360 • SPR-X22-370 | <ul style="list-style-type: none"> • SPR-A400-BLK-G-AC • SPR-A390-G-AC • SPR-A400-G-AC • SPR-A410-G-AC • SPR-A415-G-AC • SPR-A425-G-AC • SPR-M415-BLK-H-AC • SPR-M425-BLK-H-AC • SPR-M420-H-AC • SPR-M435-H-AC • SPR-M440-H-AC | <ul style="list-style-type: none"> • SPR-X22-370-E-AC • SPR-X22-360-E-AC • SPR-X21-350-BLK-E-AC • SPR-X21-335-BLK-E-AC • SPR-X20-327-BLK-E-AC • SPR-X21-345-E-AC • SPR-X21-335-E-AC • SPR-X20-327-E-AC • SPR-E20-327-E-AC • SPR-E19-320-E-AC |

With Universal InvisiMount:

| Manufacturer | Module Model / Series |
|--------------|---|
| SunPower | <ul style="list-style-type: none"> • SPR-Axxx-COM (may be followed by -BLK), where xxx can be 380–460. • SPR-Axxx-yyy-MLSD, where xxx can be 350–460 and where yyy can be -COM and/or -300 V. |
| Aptos | <ul style="list-style-type: none"> • DNA-120-MF26-xxxW, where xxx is wattage. • DNA-108-BF10-xxxW, where xxx is wattage. • DNA-120-BF26-xxxW where xxx is 350–370. |
| Hanwha | <ul style="list-style-type: none"> • Q.PEAK DUO BLK ML-G10.a+ xxx, where xxx can be 370–425. |


| | |
|----------------|--|
| REC | <ul style="list-style-type: none"> • RECxxxNP2, where xxx can be 350–380. • RECxxxNP2 Black, where xxx can be 350–380. • RECxxxTP4, where xxx can be 350–380. • RECxxxTP4 Black, where xxx can be 350–380. • RECxxxAA, where xxx can be 340–385. • RECxxxAA Black, where xxx can be 340–385. • RECxxxAA Pure, where xxx can be 380–415. |
| Trina | <ul style="list-style-type: none"> • TSM-xxxDE06X.05(II), where xxx can be 355–380. |
| Jinko | <ul style="list-style-type: none"> • JKMxxxM-6RL3-B, where xxx can be 365–400. |
| Canadian Solar | <ul style="list-style-type: none"> • Canadian Solar: CS3NxxxMS where xxx is 380–405. |
| Waaree | <ul style="list-style-type: none"> • WSMDi-xxx where xxx is 395–415. |

System Design Load Rating: 10 PSF downward, 5 PSF upward, 5 PSF lateral. Actual system structural capacity is defined by the *InvisiMount Span Tables 524734*.

Grounding from the module to the rail is accomplished through the clamps. See Section 1.5 for more information. The Listing also includes the following components, which have been evaluated for both mounting and bonding in accordance with UL 2703:


- End clamp
- Mid clamp
- Rail
- Splice and splice screw
- Ground lug assembly
- L-foot
- Row-to-row (R2R) grounding clip
- Row-to-row (R2R) grounding jumper
- Row-to-row (R2R) spacer
- Rail-mounted grounding junction box (RMJ)

SunPower Universal InvisiMount™ Ground Path and Compliance



| | Bonding Components | Compliance | |
|---|--|-------------------------------------|------|
| | | NEC | UL |
| 1 | Grounding Electrode to Service Panel | 690.47(A) 690.47(D) | n/a |
| 2 | Service Panel to Ground Wire | 690.43(C) | 1741 |
| 3 | Ground Wire to Ground Lug to Rail | 690.43(C) | 2703 |
| 4 | Module Frame | n/a | 1703 |
| 5 | Rail to Mid Clamp to Module Frame | 690.43(A) 690.43(C) 690.43(D) | 2703 |
| 6 | End Clamp to Rail* *Note that end clamp does not bond module to rail; mid clamp bonds module to rail. | 690.43(A) 690.43(C) 690.43(D) | 2703 |
| 7 | Rail to Splice | 690.43(A) 690.43(C) 690.43(D) | 2703 |

SunPower Universal InvisiMount™ with Grounding Jumper Ground Path and Compliance



| | Bonding Components | Compliance | |
|---|--|-------------------------------------|------|
| | | NEC | UL |
| 1 | Grounding Electrode to Service Panel | 690.47(A) 690.47(D) | n/a |
| 2 | Service Panel to Ground Wire | 690.43(C) | 1741 |
| 3 | Ground Wire to Ground Lug to Rail | 690.43(C) | 2703 |
| 4 | Module Frame to Module Frame | 690.43(C) | 2703 |
| 5 | Module Frame | n/a | 1703 |
| 6 | Rail to Mid Clamp to Module Frame | 690.43(A) 690.43(C) 690.43(D) | 2703 |
| 7 | End Clamp to Rail* *Note that end clamp does not bond module to rail; mid clamp bonds module to rail. | 690.43(A) 690.43(C) 690.43(D) | 2703 |
| 8 | Rail to Splice | 690.43(A) 690.43(C) 690.43(D) | 2703 |

July 29, 2022

To whom it may concern,

This letter confirms and attests that:

SPWR-A5 is equivalent to Enphase Models:

IQ7HS-66-ACM-US, 369 VA, 208Vac Grid Support Utility Interactive Inverter
IQ7HS-66-E-ACM-US, 369 VA, 208Vac Grid Support Utility Interactive Inverter
IQ7HS-66-M-US, 369 VA, 208Vac Grid Support Utility Interactive Inverter
IQ7HS-66-ACM-US, 384 VA, 240Vac Grid Support Utility Interactive Inverter
IQ7HS-66-E-ACM-US, 384 VA, 240Vac Grid Support Utility Interactive Inverter
IQ7HS-66-M-US, 384 VA, 240Vac Grid Support Utility Interactive Inverter

Regards,



Aranjit Sangha
Senior Staff Engineer
Enphase Energy Inc.
1420 North McDowell Blvd.
Petaluma, CA 94954
v: (707) 763-4784 x7098
asangha@enphaseenergy.com