



PALMETTO

+1 843-720-1844

997 MORRISON DR SUITE #200,
CHARLESTON, SC 29403, USA

Need on-site installation support?

Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com


David C. Hernandez Digitally signed by David C. Hernandez
Date: 2023.05.16 06:25:28 -04:00



RESIDENTIAL SOLAR PHOTOVOLTAIC SYSTEM

355 HUNTING WOOD DR ANGIER, NC 27501

4.050 kW DC-STC / 3.800 kW AC
15/MAY/23




EXACTUS ENERGY
NEW AGE ENGINEERING

+1 833 392 2887
208-888 DUPONT STREET
TORONTO, ON

SHEET INDEX

| |
|---|
| C1 - COVER PAGE |
| N1 - GENERAL NOTES |
| G1 - SITE PLAN |
| G2 - PANEL LAYOUT |
| G3 - MOUNTING DETAIL |
| E1 - LINE DIAGRAM |
| E2 - WARNING LABELS |
| E3 - PLACARD |
| A1 - PANEL SPECIFICATIONS |
| A2 - RACKING SPECIFICATIONS |
| A3 - BONDING AND GROUNDING SPECIFICATIONS |
| A4 - MOUNTING SPECIFICATIONS |
| A5 - INVERTER SPECIFICATIONS |
| A6 - OPTIMIZER SPECIFICATIONS |



SYSTEM SPECIFICATIONS

SYSTEM SIZE: 4.050 kW
MODULE: VSUN 405-108BMH 405W
NUMBER OF PANELS: 10
INVERTER: SE3800H-US (240V)
OPTIMIZER: S440
RACKING SYSTEM: IRONRIDGE XR-10-168M



AHJ: HARNETT COUNTY, NC
UTILITY: DUKE ENERGY PROGRESS (DEP) (NC)
GOVERNING CODE:
2018 NORTH CAROLINA STATE BUILDING CODE
IBC 2018
2018 NC FIRE PREVENTION CODE
NEC 2017

C1 - COVER PAGE

GENERAL NOTES:

THE INSTALLATION OF PV SYSTEM SHALL BE IN ACCORDANCE WITH THE MOST RECENT NATIONAL ELECTRICAL AND BUILDING CODES AND STANDARDS, AS AMENDED BY JURISDICTION

- PV SYSTEMS SHALL BE PERMITTED TO SUPPLY A BUILDING OR OTHER STRUCTURE IN ADDITION TO ANY OTHER ELECTRICAL SUPPLY SYSTEM(S) [NEC 690.4(A)]
- THE INSTALLATION OF EQUIPMENT AND ALL ASSOCIATED WIRING AND INTERCONNECTION SHALL BE PERFORMED ONLY BY QUALIFIED PERSONS [NEC 690.4(C)]
- EXISTING PLUMBING VENTS, SKYLIGHTS, EXHAUST OUTLETS, VENTILATIONS INTAKE AIR OPENINGS SHALL NOT BE COVERED BY THE SOLAR PHOTOVOLTAIC SYSTEM
- INVERTERS, MOTOR GENERATORS, PHOTOVOLTAIC MODULES, PHOTOVOLTAIC PANELS, AC PHOTOVOLTAIC MODULES, SOURCE-CIRCUIT COMBINERS, AND CHARGE CONTROLLERS INTENDED FOR USE IN PV SYSTEMS SHALL BE LISTED OR FIELD LABELED FOR THE PV APPLICATION [NEC 690.4(B)]
- ALL OUTDOOR EQUIPMENT SHALL BE NEMA 3R RATED (OR BETTER), INCLUDING ALL ROOF MOUNTED TRANSITION BOXES AND SWITCHES.
- ALL EQUIPMENT SHALL BE PROPERLY GROUNDED AND BONDED IN ACCORDANCE WITH NEC ARTICLE 250.
- SYSTEM GROUNDING SHALL BE IN ACCORDANCE WITH NEC 690.41
- FOR PV MODULES, EQUIPMENT GROUNDING CONDUCTORS SMALLER THAN 6AWG SHALL COMPLY WITH NEC 250.12(C) [NEC 690.46]
- ALL PV SYSTEM DC CIRCUIT AND INVERTER OUTPUT CONDUCTORS AND EQUIPMENT SHALL BE PROTECTED AGAINST OVERCURRENT UNLESS STATED OTHERWISE IN NEC 690.9(A)
- OVERCURRENT DEVICES USED IN PV SYSTEM DC CIRCUITS SHALL BE LISTED FOR USE IN PV SYSTEMS [NEC 690.9(B)]
- PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION IN ACCORDANCE WITH NEC 690.12
- DISCONNECTING MEANS SHALL BE LOCATED IN A VISIBLE, READILY ACCESSIBLE LOCATION OR A MAXIMUM OF 10 FEET AWAY FROM THE SYSTEM [NEC 690.13(A)]
- ALL WIRING METHODS SHALL BE IN ACCORDANCE WITH NEC 690.31
- CONNECTORS SHALL REQUIRE A TOOL TO OPEN AND BE MARKED "DO NOT DISCONNECT UNDER LOAD" OR "NOT FOR CURRENT INTERRUPTING". [NEC 690.33(E)]
- ALL GROUNDED CONDUCTORS SHALL BE PROPERLY COLOR IDENTIFIED AS WHITE. [NEC 200.6]
- PV SYSTEM CONNECTED ON THE LOAD SIDE OF THE SERVICE DISCONNECTING MEANS OF THE OTHER SOURCE(S) AT ANY DISTRIBUTION EQUIPMENT ON THE PREMISES SHALL MEET THE FOLLOWING [NEC 705.12(B)]:
 1. EACH SOURCE CONNECTION SHALL BE MADE AT A DEDICATED CIRCUIT BREAKER OF FUSIBLE DISCONNECTING MEANS. [NEC 705.12(B)(1)]
 2. 125 PERCENT OF THE POWER SOURCE OUTPUT CIRCUIT CURRENT SHALL BE USED IN AMPACITY CALCULATIONS. [NEC 705.12(B)(2)]
 3. EQUIPMENT CONTAINING OVERCURRENT DEVICES IN CIRCUITS SUPPLYING POWER TO A BUS BAR OR CONDUCTOR SHALL BE MARKED TO INDICATE THE PRESENCE OF ALL SOURCES. [NEC 705.12(B)(3)]
 4. CIRCUIT BREAKER, IF BACK FED, SHALL BE SUITABLE FOR SUCH OPERATION [NEC 705.12(B)(4)]

- WHEN A BACKFED BREAKER IS THE METHOD OF UTILITY INTERCONNECTION, THE BREAKER SHALL BE INSTALLED AT THE OPPOSITE END OF THE BUS BAR OF THE MAIN BREAKER.
- TO REDUCE FIRE HAZARDS, DC PV SYSTEMS WILL BE EQUIPPED WITH A GROUND FAULT PROTECTION SYSTEM IN ACCORDANCE WITH NEC 690.41(B)
- WHERE GROUND-FAULT PROTECTION IS USED, THE OUTPUT OF AN INTERACTIVE SYSTEM SHALL BE CONNECTED TO THE SUPPLY SIDE OF THE GROUND FAULT PROTECTION [NEC 705.32]
- ALL PLAQUES AND SIGNAGE REQUIRED BY THE LATEST EDITION OF NATIONAL ELECTRICAL CODE. LABEL SHALL BE METALLIC OR PLASTIC, ENGRAVED OR MACHINE PRINTED IN A CONTRASTING COLOR TO THE PLAQUE. PLAQUE SHALL BE UV RESISTANT IF EXPOSED TO SUNLIGHT
- ALL THE NEC REQUIRED WARNING SIGNS, MARKINGS, AND LABELS SHALL BE POSTED ON EQUIPMENT AND DISCONNECTS PRIOR TO ANY INSPECTIONS TO BE PERFORMED BY THE BUILDING DEPARTMENT.
- CONNECTORS SHALL BE OF LATCHING OR LOCKING TYPE. CONNECTORS THAT ARE READILY ACCESSIBLE AND OPERATING AT OVER 30 VOLTS SHALL REQUIRE TOOL TO OPEN AND MARKED "DO NOT DISCONNECT UNDER LOAD" OR "NOT FOR CURRENT INTERRUPTING". [NEC 690.33(C) & (E)(2)]
- FLEXIBLE, FINE-STRANDED CABLES SHALL BE TERMINATED ONLY WITH TERMINALS, LUGS, DEVICES, OR CONNECTORS IN ACCORDANCE WITH NEC 110.14
- WORK CLEARANCES AROUND ELECTRICAL EQUIPMENT WILL BE MAINTAINED PER NEC 110.26(A)(1), 110.26(A)(2) AND 110.26(A)(3)
- ALL EXTERIOR CONDUITS, FITTINGS AND BOXES SHALL BE RAIN-TIGHT AND APPROVED FOR USE IN WET LOCATIONS PER NEC 314.15.
- ROOFTOP MOUNTED PHOTOVOLTAIC PANELS AND MODULES SHALL BE TESTED, LISTED & IDENTIFIED IN ACCORDANCE WITH UL1703
- EACH MODULE TO BE GROUNDED USING THE SUPPLIED CONNECTION POINT PER MANUFACTURER'S REQUIREMENTS. ALL SOLAR MODULES, EQUIPMENT, AND METALLIC COMPONENTS ARE TO BE BONDED. IF THE EXISTING GROUNDING ELECTRODE SYSTEM CAN NOT BE VERIFIED OR IS ONLY METALLIC WATER PIPING, IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSTALL A SUPPLEMENTAL GROUNDING ELECTRODE.
- DC CONDUCTORS SHALL BE RUN IN EMT AND SHALL BE LABELED "CAUTION DC CIRCUIT" OR EQUIV. EVERY 5 FT
- CONFIRM LINE SIDE VOLTAGE AT ELECTRIC UTILITY SERVICE PRIOR TO CONNECTING INVERTER. VERIFY SERVICE VOLTAGE IS WITHIN INVERTER VOLTAGE OPERATIONAL RANGE.
- SERVING UTILITY TO BE NOTIFIED BEFORE ACTIVATION OF PV SYSTEM.
- ELECTRICAL CONTRACTOR TO PROVIDE CONDUIT EXPANSION JOINTS AND ANCHOR CONDUIT RUNS AS REQUIRED PER NEC.
- THE HOMEOWNER IS RESPONSIBLE FOR ENSURING ALL EQUIPMENT OUTSIDE THE SCOPE OF WORK IS NEC COMPLIANT.




PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC


AUTHOR: EE
DATE: 15/MAY/23
REV: -

N1 - GENERAL NOTES
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com





SCALE: 1"=40'



SCALE: 1"=8'

NOTES:

- SCALE AS SHOWN
- ALL DIMENSIONS IN FEET UNLESS OTHERWISE STATED

SAFETY PLAN:

- INSTALLERS SHALL DRAW IN DESIGNATED SAFETY AREA AROUND HOME
- INSTALLERS SHALL UPDATE NAME, ADDRESS, AND PHONE NUMBER OF NEAREST URGENT CARE FACILITY RELATIVE TO THE SITE BEFORE STARTING WORK

NEAREST URGENT CARE FACILITY

NAME:
ADDRESS:
PHONE NUMBER:



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -

G1 - SITE PLAN
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com





SITE INFORMATION


| ARRAY | AZIMUTH | PITCH | NO. OF PANELS | ARRAY AREA (SQ. FT.) | ROOF TYPE | ATTACHMENT | FRAME SIZE & FRAME TYPE | FRAME SPACING | MAX ATTACHMENT SPAN | OVERHANG |
|--------|---------|-------|---------------|----------------------|-----------|---------------------|--------------------------------|---------------|---------------------|----------|
| ROOF 1 | 178° | 27° | 10 | 210.23 | SHINGLE | QUICK MOUNT L-MOUNT | 2" X 4" PRE FABRICATED TRUSSES | 2'-0" | 4'-0" | 1'-4" |

PANELS DATA


| | |
|--|-----------------------|
| PANEL TYPE | VSUN 405-108BMH 405 W |
| NO. OF PANELS | 10 |
| PANEL SIZE | 67.80" X 44.65" |
| PANEL WEIGHT (LBS) | 47.18 |
| PANEL AREA (FT ²) | 21.02 |
| UNIT WEIGHT OF AREA (LBS/FT ²) | 2.24 |

LEGEND

- M METER
- PVC VENT
- ⊗ METAL VENT
- VENT BOX
- STRUCTURAL DELIMITER
- SERVICE MAST
- SATELLITE
- △ ANTENNA
- SNOW GUARD
- DOWNSPOUT
- MOUNT
- RAIL
- TOP CHORD
- CHIMNEY



MOUNTING PATTERN SAMPLE



ALL HARDWARE, INCLUDING MOUNTING AND RACKING, TO BE INSTALLED PER MANUFACTURER SPECIFICATIONS.

SCALE: 1"=6'

TOTAL ROOF AREA: 1481.93 FT²
 TOTAL ARRAY AREA: 210.23 FT²
 TOTAL ARRAY PERCENT COVERAGE: 14.19%

MODULE WATTAGE: 405 W
 NUMBER OF PANELS: 10
 SYSTEM SIZE: 4.050 kW

NOTES:
 - SOLAR PANEL LAYOUT SUBJECT TO CHANGE ACCORDING TO EXISTING CONDITIONS
 - SCALE AS SHOWN
 - ALL DIMENSIONS IN FEET UNLESS OTHERWISE STATED




PALMETTO
 PHONE: +1 843-720-1844
 WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
 MUNICIPALITY: ANGIER, NC
 ZIP CODE: 27501
 CLIENT: JENNIFER LEE
 4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
 DATE: 15/MAY/23
 REV: -

G2 - PANEL LAYOUT
Need on-site installation support?
 Palmetto Installation Hotline
 Call or Text: 1-843-258-5389
 InstallHotline@Palmetto.com



SCALE: NTS

PANEL TYPE: VSUN 405-108BMH 405W
 PANEL SIZE: 67.80" X 44.65"
 RACKING TYPE: IRONRIDGE XR-10-168M
 MOUNT TYPE: QUICK MOUNT L-MOUNT
 SOLAR SYSTEM DEAD LOAD: 3.0 PSF

NOTES:

- SCALE AS SHOWN
- ALL DIMENSIONS IN FEET UNLESS OTHERWISE STATED



PALMETTO
 PHONE: +1 843-720-1844
 WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
 MUNICIPALITY: ANGIER, NC
 ZIP CODE: 27501
 CLIENT: JENNIFER LEE
 4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
 DATE: 15/MAY/23
 REV: -

G3 - MOUNTING DETAIL
Need on-site installation support?
 Palmetto Installation Hotline
 Call or Text: 1-843-258-5389
 InstallHotline@Palmetto.com



UTILITY METER NUMBER: 322529049

NABCEP PV PROFESSIONAL LICENSE: PV-102415-012615


ELECTRICAL CONTRACTOR LICENSE: U.32289

NOTE:

4.0500kW DC SYSTEM SIZE (STC)
 MODULES: 10 X 405W = 4.050kW DC (STC)

INVERTER: 1X SOLAREEDGE SE3800H-US INVERTER
 = 3.800kW AC SYSTEM

(10) VSUN 405-108BMH 405W PANELS
 (10) SOLAREEDGE S440 OPTIMIZER
 (1) SOLAREEDGE SE3800H-US INVERTER



(E) UTILITY METER
 240/120 V, 1Ø, 3W, 200A

(E) EXTERNAL MAIN SERVICE PANEL
 240/120 V 1Ø, 3W, 200A

MAX PV ALLOWED CALC.:
 (MSP RATING X 120%) - MCB RATING =
 MAX PV ALLOWED

200A X 1.2 - 200A = 40A
 40A ALLOWED >= 20.00A (PV OUTPUT X 125%)

SOLAR BREAKER LOCATED AT THE
 FURTHEST END OF BUS BAR FROM
 THE MAIN BREAKER OR FEEDER UNIT

(E) GROUNDING
 ELECTRODE

AC CONDUCTOR SCHEDULE

| ID | From | To | Phase | AC Voltage | Circuit Current | 80% or 100% Rated OCPD? | Circuit Current x 125% | OCPD (If Present) | Material | Conductor Type | # of CCCs | Fill Factor | Ambient Temp. | Temp. Factor | Conductor Size | Ampacity @ 75°C | Max Ampacity | Derated Ampacity | # of Neutrals | Neutral Size | Ground | Ground Material | Ground Type | Ground Size | Conduit Type | Conduit Size |
|----|----------------------|---------------|-------|------------|-----------------|-------------------------|------------------------|-------------------|----------|----------------|-----------|-------------|---------------|--------------|----------------|-----------------|--------------|------------------|---------------|--------------|--------|-----------------|-------------|-------------|--------------|--------------|
| 1 | SolarEdge Inverter 1 | AC Disconnect | 1Ø | 240 (V) | 16.0 (A) | 80% | 20.0 (A) | 20 (A) | CU | THWN-2 | 2 | 1.00 | 32.9 (°C) | 0.96 | 10 AWG | 35 (A) | 40 (A) | 38.4 (A) | 1 | 10 AWG | EGC | CU | THWN-2 | 10 AWG | EMT | 0.75 (in.) |
| 2 | AC Disconnect | POI | 1Ø | 240 (V) | 16.0 (A) | 80% | 20.0 (A) | 20 (A) | CU | THWN-2 | 2 | 1.00 | 32.9 (°C) | 0.96 | 10 AWG | 35 (A) | 40 (A) | 38.4 (A) | 1 | 10 AWG | EGC | CU | THWN-2 | 10 AWG | EMT | 0.75 (in.) |

SOLAREEDGE DC CONDUCTOR SCHEDULE

(A) FREE AIR
 *TEMPERATURE FACTOR IS BASED ON 2% DRY BULB HIGH TEMPERATURE OF 32.9°C WITH A 0°C TEMPERATURE ADDER THEREFORE RACEWAYS MUST BE AT LEAST 0.875 INCHES ABOVE ROOF AS PER NEC 310.15(B)(3)(C)

| Number of Strings | Conductor Material | Conductor Type | Conductor Size | Base Ampacity @ 90°C | *Temperature Factor | Fill Factor | Derated Ampacity | Circuit Current | Min. OCPD (If Required) | EGC Material | EGC Type | EGC Size | Conduit |
|-------------------|--------------------|----------------|----------------|----------------------|---------------------|-------------|------------------|-----------------|-------------------------|--------------|----------|----------|----------------|
| No Limit | CU | PV Wire | 10 AWG | 40A | 0.96 | 1.00 | 38.40A | 15.00A | 20A | CU | BARE | 6 AWG | N/A - Free Air |

(B) IN CONDUIT
 *TEMPERATURE FACTOR IS BASED ON 2% DRY BULB HIGH TEMPERATURE OF 32.9°C WITH A 0°C TEMPERATURE ADDER THEREFORE RACEWAYS MUST BE AT LEAST 0.875 INCHES ABOVE ROOF AS PER NEC 310.15(B)(3)(C)
 **CALCULATIONS ARE BASED ON THE LARGEST CIRCUIT CURRENT (WORST CASE SCENARIO).
 ***TABLE ASSUMES ONE EGC PER CONDUIT. MINIMUM ONE EGC IS REQUIRED PER INVERTER PER CONDUIT.

| Number of Strings | Conductor Material | Conductor Type | Conductor Size | Base Ampacity @ 90°C | *Temperature Factor | Fill Factor | Derated Ampacity | **Circuit Current | Min. OCPD (If Required) | EGC Material | EGC Type | EGC Size | Min. EMT Size |
|-------------------|--------------------|----------------|----------------|----------------------|---------------------|-------------|------------------|-------------------|-------------------------|--------------|----------|----------|---------------|
| 1 | CU | THWN-2 | 10 AWG | 40A | 0.96 | 1.00 | 38.40A | 15.00A | 20A | CU | THWN-2 | 10 AWG | 0.50 in. |

PALMETTO
 PHONE: +1 843-720-1844
 WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
 MUNICIPALITY: ANGIER, NC
 ZIP CODE: 27501
 CLIENT: JENNIFER LEE
 4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
 DATE: 15/MAY/23
 REV: -

E1 - LINE DIAGRAM
 Need on-site installation support?
 Palmetto Installation Hotline
 Call or Text: 1-843-258-5389
 InstallHotline@Palmetto.com

WARNING

ELECTRIC SHOCK HAZARD
TERMINALS ON BOTH THE LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

CODE REF: [NEC 690.13(B)]
LOCATION: PLACE ON **ALL** DISCONNECTING MEANS WHERE ENERGIZED IN AN OPEN POSITION

WARNING

TURN OFF PHOTOVOLTAIC AC DISCONNECT PRIOR TO WORKING INSIDE PANEL

CODE REF: [NEC 110.27(C) & OSHA 1910.14(f)(7)]
LOCATION: PLACE ON **ALL** COMBINER BOX/ENCLOSURES, MAIN SERVICE DISCONNECT, BREAKER PANEL & PULL BOXES

WARNING

THIS EQUIPMENT FED BY MULTIPLE SOURCES

TOTAL RATING OF ALL OVERCURRENT DEVICES EXCLUDING MAIN POWER SUPPLY SHALL NOT EXCEED AMPACITY OF BUSBAR

CODE REF: [NEC 705.12(B)(2)(3)(c)]
LOCATION: PLACE THIS LABEL AT P.O.C. TO SERVICE DISTRIBUTION EQUIPMENT (I.E. MAIN PANEL OR SUB-PANEL) IF APPLICABLE

WARNING

THE DISCONNECTION OF THE GROUNDED CONDUCTOR(S) MAY RESULT IN OVERVOLTAGE ON THE EQUIPMENT

CODE REF: [NEC 690.31(I)]
LOCATION: PLACE ON **ALL** DISCONNECTING MEANS WHERE ENERGIZED IN AN OPEN POSITION

WARNING

DUAL POWER SOURCE
SECOND SOURCE IS PHOTOVOLTAIC SYSTEM

CODE REF: [NEC 705.12(B)(3) & 690.59]
LOCATION: PLACE LABEL ON ALL EQUIPMENT CONTAINING OVERCURRENT DEVICES IN CIRCUITS SUPPLYING POWER TO A BUSBAR OR CONDUCTORS SUPPLIED FROM MULTIPLE SOURCES

WARNING

POWER SOURCE OUTPUT CONNECTION
DO NOT RELOCATE THIS OVERCURRENT DEVICE

CODE REF: [NEC 705.12(B)(2)(3)(b)]
LOCATION: PLACE LABEL ON ALL EQUIPMENT CONTAINING OVERCURRENT DEVICES IN CIRCUITS SUPPLYING POWER TO A BUSBAR OR CONDUCTORS SUPPLIED FROM MULTIPLE SOURCES

CAUTION

PHOTOVOLTAIC SYSTEM CIRCUIT IS BACKFED


CODE REF: [NEC 705.12(B)(4) & 690.59]
LOCATION: PLACE LABEL ON ALL EQUIPMENT CONTAINING OVERCURRENT DEVICES IN CIRCUITS SUPPLYING POWER TO A BUSBAR OR CONDUCTORS SUPPLIED FROM MULTIPLE SOURCES

RAPID SHUTDOWN SWITCH FOR SOLAR PV SYSTEM

CODE REF: [NEC 690.56(C)(3)]
LOCATION: PLACE NO MORE THAN 1m (3FT) FROM SWITCH

SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY.



CODE REF: [NEC 690.56(C)]
LOCATION: PLACE AT MAIN SERVICE PANEL

WARNING: PHOTOVOLTAIC POWER SOURCE

CODE REF: [NEC 690.31 (G)(3) & 690.31 (G)(4)]
LOCATION: PLACE ON ALL JUNCTION BOXES. EXPOSED RACEWAYS EVERY 10'

MAXIMUM VOLTAGE 480 V
MAXIMUM CIRCUIT CURRENT 10.5 A
MAX RATED OUTPUT CURRENT OF DC-TO-DC CONVERTER (IF INSTALLED) 15 A

CODE REF: [NEC 690.53]
LOCATION: PLACE AT INVERTER 1

DO NOT DISCONNECT UNDER LOAD

CODE REF: [NEC 690.15(C) & 690.33(E)(2)]
LOCATION: PLACE ON **ALL** DISCONNECTING MEANS WHERE ENERGIZED IN AN OPEN POSITION

PHOTOVOLTAIC AC DISCONNECT

RATED AC OUTPUT CURRENT 16A
NOMINAL OPERATING AC VOLTAGE 240V

CODE REF: [NEC 690.54]
LOCATION: PLACE AT P.O.C. TO SERVICE DISTRIBUTION EQUIPMENT / AC DISCONNECT / PULL BOXES

PHOTOVOLTAIC

AC DISCONNECT

CODE REF: [NEC 690.13(B)]
LOCATION: PLACE AT P.O.C. TO SERVICE DISTRIBUTION EQUIPMENT / AC DISCONNECT / PULL BOXES

PHOTOVOLTAIC

DC DISCONNECT

CODE REF: [NEC 690.13(B)]
LOCATION: PLACE ON DC DISCONNECT

NOTES:

- ALL LABELING USED OUTDOORS MUST BE ENGRAVED METAL, UV STABILIZED ENGRAVED PLASTIC OR OF A MATERIAL SUFFICIENTLY DURABLE TO WITHSTAND THE ENVIRONMENT INVOLVED. VALUES HAND WRITTEN OR IN WRITTEN IN MARKER ARE NOT ACCEPTABLE PER NEC 2017.
- LABELS USED INDOORS MAY BE MADE OF DURABLE VINYL OR PAPER
- DO NOT COVER ANY EXISTING MANUFACTURER APPLIED LABELS WITH INSTALLATION SPECIFIC LABELS
- LABEL COLORS CHOSEN PER NFPA 70 2017 DIRECTION THAT ANSI Z535-2011 BE USED
- REQUIREMENTS COMPLY WITH NEC 2017
- ADDITIONALLY, IT IS HIGHLY RECOMMENDED THAT THE INSTALLER ATTACH A LABEL WITH THE COMPANY NAME AND CONTACT INFORMATION AT THE INVERTER
- ALL WARNING SIGNS OR LABELS SHALL COMPLY WITH NEC 110.21(B)

FORMAT

- WHITE LETTERING ON A RED BACKGROUND
- MINIMUM 3/8 INCHES LETTER HEIGHT
- ALL LETTERS SHALL BE CAPITALIZED
- ARIAL OR SIMILAR FONT (NON-BOLD)

MATERIAL

REFLECTIVE, WEATHER RESISTANT MATERIAL SUITABLE FOR THE ENVIRONMENT (USE UL-969 AS STANDARD FOR WEATHER RATING). DURABLE ADHESIVE MATERIALS



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC


AUTHOR: EE
DATE: 15/MAY/23
REV: -

E2 - WARNING LABELS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com



CAUTION: MULTIPLE SOURCES OF POWER

POWER TO THIS SERVICE IS ALSO SUPPLIED FROM THE FOLLOWING SOURCES WITH DISCONNECTS LOCATED AS SHOWN



[NEC 705.10 & NEC 706.11] CUSTOMER SERVICE PANEL, PV/AC DISCONNECT AND RAPID SHUTDOWN DEVICE



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -

E3 - PLACARD
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com




VSUN405-108BMH

405W
Highest power output


20.74%
Module efficiency

25years
Material & Workmanship warranty

30years
Linear power output warranty



VSUN405-108BMH VSUN400-108BMH
VSUN395-108BMH VSUN390-108BMH



- MBB technology with Circular Ribbon
- Higher output power
- Half-cell Technology
- Positive tolerance offer

- Micro Gap
- Up to 30% extra power generation yield from the back side
- Certified for salt/ammonia corrosion resistance
- Load certificates: wind to 2400Pa and snow to 5400Pa
- Lower LCOE

VSUN, a BNEF Tier-1 PV module manufacturer invested by Fuji Solar, has been committed to providing greener, cleaner and more intelligent renewable energy solutions. VSUN is dedicated to bringing reliable, customized and high-efficient products into various markets and customers worldwide



Engineered in Japan
www.vsun-solar.com

Electrical Characteristics at Standard Test Conditions(STC)

| Module Type | VSUN405-108BMH | VSUN400-108BMH | VSUN395-108BMH | VSUN390-108BMH |
|----------------------------------|----------------|----------------|----------------|----------------|
| Maximum Power - Pmax (W) | 405 | 400 | 395 | 390 |
| Open Circuit Voltage - Voc (V) | 37.36 | 37.2 | 37.03 | 36.84 |
| Short Circuit Current - Isc (A) | 13.78 | 13.68 | 13.59 | 13.5 |
| Maximum Power Voltage - Vmpp (V) | 31.36 | 31.17 | 31 | 30.82 |
| Maximum Power Current - Imp (A) | 12.92 | 12.84 | 12.75 | 12.66 |
| Module Efficiency | 20.74% | 20.48% | 20.23% | 19.97% |

Standard Test Conditions (STC): irradiance 1,000 W/m²; AM 1.5; module temperature 25°C. Pmax Sorting: 0-5W. Measuring Tolerance: ±3%.
Remark: Electrical data do not refer to a single module and they are not part of the offer. They only serve for comparison among different module types.

Electrical Characteristics with different rear side power gain(reference to 400 front)

| Pmax (W) | Voc (V) | Isc (A) | Vmpp (V) | Imp (A) | Pmax gain |
|----------|---------|---------|----------|---------|-----------|
| 420 | 37.1 | 14.36 | 31.17 | 13.48 | 5% |
| 440 | 37.1 | 15.05 | 31.17 | 14.12 | 10% |
| 479 | 37.2 | 16.42 | 31.12 | 15.41 | 20% |
| 499 | 37.2 | 17.10 | 31.12 | 16.05 | 25% |

Temperature Characteristics

| | |
|---------------------------------|------------|
| NOCT | 45°C(±2°C) |
| Voltage Temperature Coefficient | -0.27%/°C |
| Current Temperature Coefficient | +0.048%/°C |
| Power Temperature Coefficient | -0.32%/°C |

Maximum Ratings

| | |
|----------------------------|---------|
| Maximum System Voltage [V] | 1500 |
| Series Fuse Rating [A] | 30 |
| Bifaciality | 70%±10% |

Material Characteristics

| | |
|--------------------|--|
| Dimensions | 1722×1134×30mm (L×W×H) |
| Weight | 21.4kg |
| Frame | Black anodized aluminum profile |
| Front Glass | White toughened safety glass, 3.2 mm |
| Cell Encapsulation | EVA (Ethylene-Vinyl-Acetate) or POE |
| Back Sheet | Transparent black-mesh backsheet |
| Cells | 12×9 pieces monocrystalline solar cells series strings |
| Junction Box | IP68, 3 diodes |
| Cable&Connector | Portrait: 500 mm (cable length can be customized, 1×4 mm ² , compatible with MC4) |


Packaging

| | |
|-------------------|------------------|
| Dimensions(L×W×H) | 1760×1125×1253mm |
| Container 20' | 216 |
| Container 40' | 468 |
| Container 40'HC | 936 |


System Design

| | |
|----------------------|---|
| Temperature Range | -40 °C to + 85 °C |
| Withstanding Hail | Maximum diameter of 25 mm with impact speed of 23 m/s |
| Maximum Surface Load | 5,400 Pa |
| Application class | class A |

Dimensions



IV-Curves



Certificate of Compliance

Certificate: 80098025 Master Contract: 265697
Project: 80156103 Date Issued: 2023-02-07
Issued to: VIETNAM SUNERGY JOINT STOCK COMPANY
Lot III-Dong Vang Area, Dinh Tram Industrial Zone,
Hoang Ninh Commune, Viet Yen District, 230000 Bac Giang Province,
VIETNAM

The products listed below are eligible to bear the CSA Mark shown with adjacent indicators 'C' and 'US' for Canada and US or with adjacent indicator 'US' for US only or without either indicator for Canada only



Issued by: Qiang (Sean) Jiang
Qiang (Sean) Jiang

PRODUCTS

CLASS 5311 10 - POWER SUPPLIES - Photovoltaic Modules and Panels
CLASS 5311 90 - POWER SUPPLIES - Photovoltaic Modules and Panels - Certified to U.S. Standards
Photovoltaic modules with Fire Performance (USA) Type 29, maximum system voltage of 1500 V dc, model series: VSUNxxx-144BMH-DG (xxx=510-580, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 29, maximum system voltage of 1500 V dc, model series: VSUNxxx-132BMH-DG (xxx=475-520, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 29, maximum system voltage of 1500 V dc, model series: VSUNxxx-120BMH-DG (xxx=430-470, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 29, maximum system voltage of 1500 V dc, model series: VSUNxxx-108BMH-DG (xxx=390-410, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 1, maximum system voltage of 1500 V dc, model series: VSUNxxx-144BMH (xxx=510-580, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 1, maximum system voltage of 1500 V dc, model series: VSUNxxx-132BMH (xxx=475-520, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 1, maximum system voltage of 1500 V dc, model series: VSUNxxx-120BMH (xxx=430-470, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 1, maximum system voltage of 1500 V dc, model series: VSUNxxx-108BMH (xxx=390-410, in steps of 5), Fuse rating 30A.
Photovoltaic modules with Fire Performance (USA) Type 1, maximum system voltage of 1500 V dc, model series: VSUNxxx-144MH-BB (xxx=510-580, in steps of 5), Fuse rating 30A.



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC



AUTHOR: EE
DATE: 15/MAY/23
REV: -

A1 - PANEL SPECIFICATIONS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com





XR10 Rail

| Rail Section Properties | |
|----------------------------|-----------------------|
| Property | Value |
| Total Cross-Sectional Area | 0.363 in ² |
| Section Modulus (X-axis) | 0.136 in ³ |
| Moment of Inertia (X-axis) | 0.124 in ⁴ |
| Moment of Inertia (Y-axis) | 0.032 in ⁴ |
| Torsional Constant | 0.076 in ³ |
| Polar Moment of Inertia | 0.033 in ⁴ |


| Clear Part Number | Black Part Number | Description / Length | Material | Weight |
|-------------------|-------------------|---------------------------|----------------------|-----------|
| XR-10-132A | XR-10-132B | XR10, Rail 132" (11 Feet) | 6000-Series Aluminum | 4.67 lbs. |
| XR-10-168A | XR-10-168B | XR10, Rail 168" (14 Feet) | | 5.95 lbs. |
| XR-10-204A | XR-10-204B | XR10, Rail 204" (17 Feet) | | 7.22 lbs. |


v1.0

UL Certification

The IronRidge Flush Mount, Tilt Mount, and Ground Mount Systems have been listed to UL 2703 by Intertek Group plc.

UL 2703 is the standard for evaluating solar mounting systems. It ensures these devices will maintain strong electrical and mechanical connections over an extended period of time in extreme outdoor environments.

 [Go to IronRidge.com/UFO](http://IronRidge.com/UFO)



PALMETTO
 PHONE: +1 843-720-1844
 WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
 MUNICIPALITY: ANGIER, NC
 ZIP CODE: 27501
 CLIENT: JENNIFER LEE
 4.050 KW DC-STC / 3.800 KW AC


AUTHOR: EE
 DATE: 15/MAY/23
 REV: -

A2 - RACKING SPECIFICATIONS
Need on-site installation support?
 Palmetto Installation Hotline
 Call or Text: 1-843-258-5389
 InstallHotline@Palmetto.com

Simplified Grounding for Every Application

The UFO family of components eliminates the need for separate grounding hardware by bonding solar modules directly to IronRidge XR Rails. All system types that feature the UFO family—Flush Mount, Tilt Mount and Ground Mount—are fully listed to the UL 2703 standard.

UFO hardware forms secure electrical bonds with both the module and the rail, resulting in many parallel grounding paths throughout the system. This leads to safer and more reliable installations.



Universal Fastening Object (UFO)
The UFO securely bonds solar modules to XR Rails. It comes assembled and lubricated, and can fit a wide range of module heights.



Stopper Sleeve
The Stopper Sleeve snaps onto the UFO, converting it into a bonded end clamp.



BOSS™ Splice
Bonded Structural Splice connects rails with built-in bonding teeth. No tools or hardware needed.




Grounding Lug
A single Grounding Lug connects an entire row of PV modules to the grounding conductor.



Bonded Attachments
The bonding bolt attaches and bonds the L-foot to the rail. It is installed with the same socket as the rest of the system.

System Diagram



○ UFO ◐ Stopper Sleeve ● Grounding Lug ◻ BOSS™ Splice ≡ Ground Wire

Approved Enphase microinverters can provide equipment grounding of IronRidge systems, eliminating the need for grounding lugs and field installed equipment ground conductors (EGC). A minimum of two microinverters mounted to the same rail and connected to the same Engage cable is required. Refer to installation manuals for additional details.

UL Certification

The IronRidge Flush Mount, Tilt Mount, and Ground Mount Systems have been listed to UL 2703 by Intertek Group plc.

UL 2703 is the standard for evaluating solar mounting systems. It ensures these devices will maintain strong electrical and mechanical connections over an extended period of time in extreme outdoor environments.

Go to IronRidge.com/UFO

Cross-System Compatibility

| Feature | Flush Mount | Tilt Mount | Ground Mount |
|--|--|------------|--------------|
| XR Rails | ✓ | ✓ | XR1000 Only |
| UFO/Stopper | ✓ | ✓ | ✓ |
| BOSS™ Splice | ✓ | ✓ | N/A |
| Grounding Lugs | 1 per Row | 1 per Row | 1 per Array |
| Microinverters & Power Optimizers | Compatible with most MLPE manufacturers. Refer to system installation manual. | | |
| Fire Rating | Class A | Class A | N/A |
| Modules | Tested or Evaluated with over 400 Framed Modules. Refer to installation manuals for a detailed list. | | |

VSUN

VSUN modules with 30, 35 and 40 mm frames

VSUNxxx-YYz-aa

Where "YY" can be 60, 72, 108, 120, or 144; "z" can be M, P, MH, PH, or **BMH**; and "aa" can be blank, BB, BW, or DG



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -


A3 - BONDING AND GROUNDING SPECIFICATIONS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com



L-Mount® Installation Instructions

Installation Tools Required: tape measure, roofing bar, chalk line, stud finder, caulking gun, sealant compatible with roofing materials, drill with 7/32" or 1/8" bit, drill or impact gun with 1/2" socket.

WARNING: Quick Mount® products are NOT designed for and should NOT be used to anchor fall protection equipment.



| ITEM NO | DESCRIPTION |
|---------|--|
| 1 | LAG SCREW, HEX HEAD 5/16"x4", 1/2" HEAD |
| 2 | WASHER, SEALING, EPDM BONDED SS |
| 3 | L-FOOT, 2"x3.3" |
| 4 | FLAHING, ROUNDED CORNERS |
| 5 | STRUCTURAL SCREW, T-30 HEX WASHER HEAD, 5/16"x4.5" |

L-MOUNT®

SIZE **A** DO NOT SCALE DRAWING

WGT: 0.7565 lbs SHEET 1 OF 1

© 2022 QuickMount All rights reserved. Visit www.Ironridge.com or call 1-800-227-9523 for more information.


L-Mount MAN Rev 1.12



1 Locate, choose, and mark centers of rafters to be mounted. Select the courses of shingles where mounts will be placed.



2 Carefully lift composition roof shingle with roofing bar, just above placement of mount. Remove nails as required and backfill holes with approved sealant. See "Proper Flashing Placement" on next page.



3 Insert flashing between 1st and 2nd course. Slide up so top edge of flashing is at least 3/4" higher than the butt-edge of the 3rd course and lower flashing edge is above the butt-edge of 1st course. Mark center for drilling.




4 If attaching with lag bolt use a 1/4" bit (Lag). Use a 3/8" bit (ST) for attaching with the structural screw. Drill pilot hole into roof and rafter, taking care to drill square to the roof. Do not use mount as a drill guide. Drill a 2" deep hole into rafter.



5 Clean off any sawdust, and fill hole with sealant compatible with roofing materials.



6 Place L-foot onto elevated flute and rotate L-foot to desired orientation.



7 Prepare lag bolt or structural screw with sealing washer. Using a 1/2-inch socket on an impact gun, drive prepared lag bolt through L-foot until L-foot can no longer easily rotate. **DO NOT over-torque.** NOTE: Structural screw can be driven with T-30 hex head bit.



8 You are now ready for the rack of your choice. Follow all the directions of the rack manufacturer as well as the module manufacturer. NOTE: Make sure top of L-Foot makes solid contact with racking.

All roofing manufacturers' written instructions must also be followed by anyone modifying a roof system. Consult the roof manufacturer's specs and instructions prior to working on the roof.

© 2022 QuickMount All rights reserved. Visit www.Ironridge.com or call 1-800-227-9523 for more information.

L-Mount MAN Rev 1.12

PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -

A4 - MOUNTING SPECIFICATIONS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com

Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US



INVERTERS

Optimized installation with HD-Wave technology

- Specifically designed to work with power optimizers
- Record-breaking 99% weighted efficiency
- Quick and easy inverter commissioning directly from a smartphone using the SolarEdge SetApp
- Fixed voltage inverter for longer strings
- Integrated arc fault protection and rapid shutdown for NEC 2014, NEC 2017 and NEC 2020 per article 690.11 and 690.12
- UL1741 SA certified, for CPUC Rule 21 grid compliance
- Small, lightweight, and easy to install both outdoors or indoors
- Built-in module-level monitoring
- Optional: Faster installations with built-in consumption metering (1% accuracy) and production revenue grade metering (0.5% accuracy, ANSI C12.20)

solaredge.com



Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US

| MODEL NUMBER | SE3000H-US | SE3800H-US | SE5000H-US | SE6000H-US | SE7600H-US | SE10000H-US | SE11400H-US | | |
|---|---|----------------------------|------------------|----------------------------|-------------------------------------|--------------------------|------------------------------|---------|---------|
| APPLICABLE TO INVERTERS WITH PART NUMBER | | | SEXXXXH-XXXXBXX4 | | | | | | |
| OUTPUT | | | | | | | | | |
| Rated AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA | |
| Maximum AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA | |
| AC Output Voltage Min.-Nom.-Max. (211 - 240 - 264) | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | Vac | |
| AC Output Voltage Min.-Nom.-Max. (183 - 208 - 229) | - | ✓ | - | ✓ | - | - | ✓ | Vac | |
| AC Frequency (Nominal) | 59.3 - 60 - 60.5 ¹⁾ | | | | | | | Hz | |
| Maximum Continuous Output Current @240V | 12.5 | 16 | 21 | 25 | 32 | 42 | 47.5 | A | |
| Maximum Continuous Output Current @208V | - | 16 | - | 24 | - | - | 48.5 | A | |
| Power Factor | 1, Adjustable - 0.85 to 0.85 | | | | | | | | |
| GFDI Threshold | 1 | | | | | | | A | |
| Utility Monitoring, Islanding Protection, Country Configurable Thresholds | Yes | | | | | | | | |
| INPUT | | | | | | | | | |
| Maximum DC Power @240V | 4650 | 5900 | 7750 | 9300 | 11800 | 15500 | 17650 | W | |
| Maximum DC Power @208V | - | 5100 | - | 7750 | - | - | 15500 | W | |
| Transformer-less, Ungrounded | Yes | | | | | | | | |
| Maximum Input Voltage | 480 | | | | | | | Vdc | |
| Nominal DC Input Voltage | 380 | | | | | | | Vdc | |
| Maximum Input Current @240V ²⁾ | 8.5 | 10.5 | 13.5 | 16.5 | 20 | 27 | 30.5 | Adc | |
| Maximum Input Current @208V ²⁾ | - | 9 | - | 13.5 | - | - | 27 | Adc | |
| Max. Input Short Circuit Current | 45 | | | | | | | Adc | |
| Reverse-Polarity Protection | Yes | | | | | | | | |
| Ground-Fault Isolation Detection | 600ku Sensitivity | | | | | | | | |
| Maximum Inverter Efficiency | 99 | | 99.2 | | | | | % | |
| CEC Weighted Efficiency | 99 | | | | | 99 @ 240V 98.5 @ 208V | | % | |
| Nighttime Power Consumption | < 2.5 | | | | | | | W | |
| ADDITIONAL FEATURES | | | | | | | | | |
| Supported Communication Interfaces | RS485, Ethernet, ZigBee (optional), Cellular (optional) | | | | | | | | |
| Revenue Grade Metering, ANSI C12.20 Consumption metering | Optional ³⁾ | | | | | | | | |
| Inverter Commissioning | With the SetApp mobile application using Built-in Wi-Fi Access Point for Local Connection | | | | | | | | |
| Rapid Shutdown - NEC 2014, NEC 2017 and NEC 2020, 690.12 | Automatic Rapid Shutdown upon AC Grid Disconnect | | | | | | | | |
| STANDARD COMPLIANCE | | | | | | | | | |
| Safety | UL1741, UL1741 SA, UL1699B, CSA C22.2, Canadian AFCI according to T.I.L. M-07 | | | | | | | | |
| Grid Connection Standards | IEEE1547, Rule 21, Rule 14 (H) | | | | | | | | |
| Emissions | FCC Part 15 Class B | | | | | | | | |
| INSTALLATION SPECIFICATIONS | | | | | | | | | |
| AC Output Conduit Size / AWG Range | 1" Maximum / 14-6 AWG | | | | 1" Maximum / 14-4 AWG | | | | |
| DC Input Conduit Size / # of Strings / AWG Range | 1" Maximum / 1-2 strings / 14-6 AWG | | | | 1" Maximum / 1-3 strings / 14-6 AWG | | | | |
| Dimensions with Safety Switch (HxWxD) | 17.7 x 14.6 x 6.8 / 450 x 370 x 174 | | | | 21.3 x 14.6 x 7.3 / 540 x 370 x 185 | | | | in / mm |
| Weight with Safety Switch | 22 / 10 | 25.1 / 11.4 | 26.2 / 11.9 | 38.8 / 17.6 | | | | lb / kg | |
| Noise | < 25 | | | | < 50 | | | | dBA |
| Cooling | Natural Convection | | | | | | | | |
| Operating Temperature Range | -40 to +140 / -40 to +60 ⁴⁾ | | | | | | | °F / °C | |
| Protection Rating | NEMA 4X (Inverter with Safety Switch) | | | | | | | | |

³⁾ Inverter with Revenue Grade Meter P/N: SExxxxH-US000BNC4; Inverter with Revenue Grade Production and Consumption Meter P/N: SExxxxH-US000BNH4. For consumption metering, current transformers should be ordered separately: SEACT0750-200NA-20 or SEACT0750-400NA-20. 20 units per box.
⁴⁾ Full power up to at least 50°C / 122°F; for power de-rating information refer to: <https://www.solaredge.com/sites/default/files/se-temperature-derating-note-napdf>



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -

A5 - INVERTER SPECIFICATIONS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com



Power Optimizer For North America

S440, S500



POWER OPTIMIZER

PV power optimization at the module level

- Specifically designed to work with SolarEdge residential inverters
- Detected abnormal PV connector behavior, preventing potential safety issues*
- Module-level voltage shutdown for installer and firefighter safety
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch loss, from manufacturing tolerance to partial shading
- Faster installations with simplified cable management and easy assembly using a single bolt
- Flexible system design for maximum space utilization
- Compatible with bifacial PV modules
- Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)

* Expected availability in 2022

solaredge.com




Power Optimizer For North America S440, S500

| | S440 | S500 | Unit |
|---|------|---|---------|
| INPUT | | | |
| Rated Input DC Power ⁽¹⁾ | 440 | 500 | W |
| Absolute Maximum Input Voltage (Voc) | | 60 | Vdc |
| MPPT Operating Range | | 8 - 60 | Vdc |
| Maximum Short Circuit Current (Isc) of Connected PV Module | 14.5 | 15 | Adc |
| Maximum Efficiency | | 99.5 | % |
| Weighted Efficiency | | 98.6 | % |
| Overtoltage Category | | II | |
| OUTPUT DURING OPERATION | | | |
| Maximum Output Current | | 15 | Adc |
| Maximum Output Voltage | | 60 | Vdc |
| OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM INVERTER OR INVERTER OFF) | | | |
| Safety Output Voltage per Power Optimizer | | 1+/-0.1 | Vdc |
| STANDARD COMPLIANCE | | | |
| Photovoltaic Rapid Shutdown System | | NEC 2014, 2017 & 2020 | |
| EMC | | FCC Part 15 Class B, IEC61000-6-2, IEC61000-6-3 | |
| Safety | | IEC62109-1 (class II safety), UL1741 | |
| Material | | UL94 V-0, UV Resistant | |
| RoHS | | Yes | |
| Fire Safety | | VDE-AR-E 2100-712:2013-05 | |
| INSTALLATION SPECIFICATIONS | | | |
| Maximum Allowed System Voltage | | 1000 | Vdc |
| Dimensions (W x L x H) | | 129 x 153 x 30 / 5.07 x 6.02 x 1.18 | mm / in |
| Weight (including cables) | | 655 / 1.5 | gr / lb |
| Input Connector | | MC4 ⁽²⁾ | |
| Input Wire Length | | 0.1 / 0.32 | m / ft |
| Output Connector | | MC4 | |
| Output Wire Length | | (+) 2.3, (-) 0.10 / (+) 7.54, (-) 0.32 | m / ft |
| Operating Temperature Range ⁽³⁾ | | -40 to +85 | °C |
| Protection Rating | | IP68 / NEMA6P | |
| Relative Humidity | | 0 - 100 | % |

(1) Rated power of the module at STC will not exceed the power optimizer Rated Input DC Power. Modules with up to +5% power tolerance are allowed
 (2) For other connector types please contact SolarEdge
 (3) For ambient temperature above +70°C / +158°F power de-rating is applied. Refer to Power Optimizers Temperature De-Rating Technical Note for more details

| PV System Design Using a SolarEdge Inverter | Single Phase HD-Wave | Three Phase for 208V Grid | Three Phase for 277/480V Grid | |
|---|--------------------------------------|---|-------------------------------|---|
| Minimum String Length (Power Optimizers) | S440, S500 8 | 10 | 18 | |
| Maximum String Length (Power Optimizers) | 25 | | 50 ⁽⁴⁾ | |
| Maximum Nominal Power per String | 5700 (6000 with SE7600-US-SE11400-U) | 6000 | 12750 | W |
| Maximum Allowed Connected Power per String ⁽⁵⁾ (Permitted only when the difference in connected power between strings is 1000W or less) | Refer to Footnote 5 | One string 7200 Two strings or more 7800 | 15000 | W |
| Parallel Strings of Different Lengths or Orientations | | Yes | | |

(4) A string with more than 30 optimizers does not meet NEC rapid shutdown requirements; safety voltage will be above the 30V requirement
 (5) If the inverters rated AC power ≤ maximum nominal power per string, then the maximum power per string will be able to reach up to the inverters maximum input DC power. Refer to: <https://www.solaredge.com/sites/default/files/se-power-optimizer-single-string-design-application-note.pdf>
 (6) It is not allowed to mix S-series and P-series Power Optimizers in new installations



© SolarEdge Technologies, Inc. All rights reserved. SOLAREEDGE, the SolarEdge logo, OPTIMIZED BY SOLAREEDGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: July 12, 2022 DS-000018-NA. Subject to change without notice.



PALMETTO
PHONE: +1 843-720-1844
WWW.PALMETTO.COM

PROJECT: 355 HUNTING WOOD DR
MUNICIPALITY: ANGIER, NC
ZIP CODE: 27501
CLIENT: JENNIFER LEE
4.050 KW DC-STC / 3.800 KW AC

AUTHOR: EE
DATE: 15/MAY/23
REV: -

A6 - OPTIMIZER SPECIFICATIONS
Need on-site installation support?
Palmetto Installation Hotline
Call or Text: 1-843-258-5389
InstallHotline@Palmetto.com

