

September 06, 2023

Contractor Name: Top Tier Solar Solutions Contractor Address: 1530 Center Park Dr #2911, Charlotte, NC 28217

Subject: Proposed Solar Panel Installation Elizabeth Moore Residence, 2474 Docs Rd, Spring Lake, NC DC System Size: 4.740 kW PV Letters Job #004-2415

To Whom it May Concern,

I have reviewed information, provided by you or your office, related to the proposed solar panel installation at the abovereferenced address. The purpose of the review was to determine if the existing roof is structurally adequate for the proposed installation. Based on my review and analysis of the given information, and in accordance with governing building codes, it is my professional opinion that the existing structure is permitted to remain unaltered for the proposed solar installation.

Design Parameter Summary

Governing Building Code: 2018 North Carolina Residential Code Risk Category: II Wind Exposure: B Design Wind Speed: 120 mph Ground Snow Load: 15 psf

Roof Information Roofing Material: Corrugated Metal Roof Slope: 22 degrees

Roof Connection Details

S-5! ProteaBracket to existing member at 45 O.C. along rails per manufacture specs. Stagger attachments to avoid overloading any individual rafter.

Engineering Analysis

The proposed installation - including weight of panels, racking, mounts, and inverters where applicable - will be approximately 3 psf. In the areas where panels are installed, roof live loads will not be present. The reduction of roof live load is adequate to fully or partially compensate for the addition of the panel installation. Because the member forces in the area of the solar panels are not increased by more than 5%, and so per provisions in the adopted building codes, the structure need not be altered for gravity loading.

The proposed installation will be 6" max. above the roof surface (flush mounted) and parallel to the roof surface. Therefore, any increase in wind loading on the building structure from the solar panel installation is expected to be negligible. Wind is the governing lateral load case. Because the increase in lateral loading is not increased by more than 10%, per provisions in the adopted building codes, the structure need not be altered for lateral loading.

Wind uplift on the panels has been calculated in accordance with the relevant provisions of ASCE 7-10. This loading has been used to verify the adequacy of the connection specified above. Connection locations should be in accordance with design drawings.

IronRidge XR10 rails will support the modules and will fasten to the roof structure with S-5! ProteaBracket at a maximum spacing of 45" along the rail with a maximum rail cantilever of 18". The max attachment spacing, rail span and cantilever is valid in all roof zones (1, 2, and 3).

Conclusion


The roof structure need not be altered for either gravity loading (including snow) or lateral loading (including wind). Therefore, the existing structure is permitted to remain unaltered. Connections to the roof must be made per the "Roof Connection Details" section above. Copies of all relevant calculations are enclosed.

Limitations and Disclaimers

The opinion expressed in this letter is made in reliance on the following assumptions: the existing structure is in good condition; the existing structure is free from defects in design or workmanship; and the existing structure was code-compliant at the time of its design and construction. These assumptions have not been independently verified, and we have relied on representations made by your office with respect to the foregoing. The undersigned has not inspected the structure for defects, although we have reviewed the information provided by your office, including pictures where applicable.

Electrical design is excluded from this analysis. Solar panels must be installed per manufacturer specifications. Structural design and analysis of the adequacy of solar panels, racks, mounts, and other components is performed by each component's respective manufacturer; the undersigned makes no statement of opinion regarding such components. This letter and the opinions expressed herein are rendered solely for the benefit of the permitting authority (city or county building department) and your office, and may not be utilized or relied on by any other party.

If you have any questions or concerns, please contact me at (208)-994-1680, or email me directly at Trevor@pvletters.com.




9/6/23



This calculation justifies the additional solar load by comparing existing to proposed gravity loads in the location of the solar panels.

in the location of the solar parens.			
	Without Solar	With Solar	
Dead Load			
Corrugated Metal	3	3	psf
1/2" Plywood	1	1	psf
Framing	2	2	psf
Insulation			psf
1/2" Gypsum Ceiling			psf
M,E, & Misc			psf
Solar Panel	0	3	psf
Total Dead Load	6	9	psf
Snow Load			
Ground Snow Load, P_g	15		psf
Exposure Factor, C _e	0.9		
Thermal Factor, C _t	1.1		
Importance Factor, I _s	1		
Flat Roof Snow Load	10		Eqn. 7.3-1 or jurisdiction min.
Slope	22		degrees
Unobstructed Slippery Surface?	Yes	Yes	
Slope Factor, C _s	0.80	0.80	
Sloped Roof Snow Load	8.3	8.3	psf
Live Load			
Roof Live Load	20	0	psf
Load Combination			
D + Lr	26.0	9.0	psf
D + S	14.3	17.3	psf
Max. Load	26.0	17.3	psf
% of original		67%	
Result	Recause the total f	orces are decre	ased ner the relevant code





Because the total forces are decreased, per the relevant code provisions stated in the body of the letter, the existing roof structure is permitted to remain unaltered.



This calculation justifies the connection of the solar panels to existing roof members, by showing the connection capacity is equal to or greater than the uplift force demands.

Connection Demand

Spacing perpendicular to rail (1/2 panel length)	38	in
Roof Angle	22	degrees
Roof Layout	Gable	
Wind Speed	120	mph
Exposure Coefficient, K _z	0.67	
Topographic Factor, K _{zt}	1.00	
Directionality Factor, K _d	0.85	
Elevation Factor, K _e	1.00	
Velocity Pressure, q _z	20.8	psf


Zones	<u>: 1</u>	<u>2</u>	_
$GC_{p}(max)$	1.00	2.20	
Exposed Panels? ($\gamma_E = 1.5$)	No	No	
Spacing parallel to rail, in	45	45	
Effective Wind Area on each connection, ft ²	11.7	11.7	
Pressure Equalization Factor, γ_a	0.77	0.77	
Uplift Force	16.0	35.3	psf
Max. Uplift Force / Connection (0.6 WL)	112.9	248.3	lbs
Solar Dead Load (0.6 DL)	21.1	21.1	lbs
Max. Uplift Force (0.6 WL - 0.6 DL)	91.7	227.2	lbs

Connection Capacity

Connection Type	ProteaBracket	
Ultimate Capacity	817	lbs
Factor of Safety	2.50	
Qty. of Connectors	1	_
Total Capacity	326.8	lbs

Compare ASD Factored Demand to Capacity

Demand



227.2	lbs
326.8	lbs

Capacity exceeds demands. Therefore, connection passes.

9/6/23