


VICINITY MAP



PROPERTY MAP



ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |

PROJECT INFORMATION

PV1.1

SCOPE OF WORK

(24) REC405AA PURE
(1) SOLAREEDGE SE7600H-US
ROOF MOUNT: FLASHKIT PRO
MOUNTING RAILS: UNIRAC SM LIGHT RAIL

SITE CONDITION

ASCE 7-10 WIND SPEED - 118 MPH
EXPOSURE CATEGORY - B
RISK CATEGORY - II
SNOW LOAD - 10 LBS/SQFT

SHEET INDEX

PV1.1 - 1.2 PROJECT INFORMATION
PV2.1 SITE INFORMATION
PV3.1 STRUCTURAL INFORMATION
PV4.1 - 4.2 ELECTRICAL INFORMATION
PV5.1 - 5.5 LABELS, DETAILS & SPECS

INTERCONNECTIONS TYPE

SUPPLY SIDE TAP





CODE REFERENCES

2017 NATIONAL ELECTRIC CODE
2018 NORTH CAROLINA FIRE CODE
2018 NORTH CAROLINA BUILDING CODE
2018 NORTH CAROLINA RESIDENTIAL CODE

UTILITY COMPANY

SOUTH RIVER EMC

LEGEND

-  DISCONNECT SWITCH
-  FUSE
-  CIRCUIT BREAKER
-  EQUIP. GROUND



AURORA SOLAR SHADE ANALYSIS

GONZALEZ CRUZ, KIDDIAN MICHELLE
 1651 RAYNOR MCLAMB RD
 LINDEN, NC 28356
 9.720 KW DC STC
 7.600 KW AC

MODULES:

(24) REC405AA PURE

INVERTERS:


(1) SOLAREEDGE SE7600H-US

POWER OPTIMIZERS:

(24) S440

THE SYSTEM HAS A FIRST YEAR ANNUAL ENERGY PRODUCTION OF: 12,907 KWH/YEAR

THIS PRODUCTION IS AN ESTIMATE PREPARED USING AURORA SOLAR SHADE ANALYSIS SOFTWARE. ALL SOLAR SYSTEMS EXPERIENCE PERFORMANCE DEGRADATION OVER THEIR LIFETIME. THIS IS USUALLY APPROXIMATELY 1% PER YEAR, BUT VARIES BASED ON EQUIPMENT USED AND ENVIRONMENTAL CONDITIONS.



ENGINEER:



MODEL ENERGY
 300 FAYETTEVILLE ST.
 #1430
 RALEIGH, NC 27602
 919-274-9905
 MODELENERGY.COM
 P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
 7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian Michelle
 1651 Raynor McLamb Rd
 Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:





| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |

PROJECT INFORMATION

PV1.2

FRONT OF
RESIDENCE



NOTE: PROVIDE ADDITIONAL JUNCTION BOXES AS REQUIRED TO COMBINE MODULES ON DIFFERENT ARRAYS INTO A SINGLE STRING

1 SITE PLAN
SCALE: 3/16" = 1' -0"

NFPA-1/FFPC SECTION 11.12.2.2.2 REQUIRED 3 FEET ACCESS, PATHWAYS, AND SETBACKS. DO NOT PLACE ANY PV MODULES IN THIS SPACE.

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM

P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT

7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle

1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:




| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |
| | |
| | |
| | |
| | |


| | |
|--|--|
| | |
| | |
| | |
| | |
| | |

SITE INFORMATION


PV2.1



3 FASTENER DETAIL
SCALE: NTS



2 ROOF "B" PLANAR VIEW
SCALE: 1/8" = 1'-0"



1 ROOF "A" PLANAR VIEW
SCALE: 1/8" = 1'-0"

| ARRAY "B" SUMMARY | |
|-------------------|----------|
| # MODULES | 4 |
| # ROOF MOUNTS | 9 |
| RAIL LENGTH | 56 FT. |
| ARRAY AREA | 80 SQFT. |
| ARRAY WEIGHT | 207 LBS. |
| AZIMUTH @ SN | 293° |
| TILT ANGLE | 19° |

| ARRAY "A" SUMMARY | |
|-------------------|-----------|
| # MODULES | 20 |
| # ROOF MOUNTS | 52 |
| RAIL LENGTH | 141 FT. |
| ARRAY AREA | 398 SQFT. |
| ARRAY WEIGHT | 969 LBS. |
| AZIMUTH @ SN | 113° |
| TILT ANGLE | 19° |

| MOUNTING RAILS | |
|----------------|---------------|
| MAKE | UNIRAC |
| MODEL | SM LIGHT RAIL |
| MATERIAL | ALUMINUM |
| WEIGHT | 0.49 LBS/SQFT |
| SPACING | 34" |

| ROOF ZONES (PORTRAIT): | | |
|------------------------|----------------------------------|-----|
| ALL ZONES | MAX. RAIL OVERHANG = | 16" |
| □ ZONE 1 | MAX. FASTENER SPAN ZONE 1 = | 48" |
| ▨ ZONE 2 | MAX. FASTENER SPAN ZONE 2 = | 24" |
| ▩ ZONE 3 | DO NOT INSTALL MODULES IN ZONE 3 | N/A |

| ROOF ZONES (LANDSCAPE): | | |
|-------------------------|-----------------------------|-----|
| ALL ZONES | MAX. RAIL OVERHANG = | 16" |
| □ ZONE 1 | MAX. FASTENER SPAN ZONE 1 = | 72" |
| ▨ ZONE 2 | MAX. FASTENER SPAN ZONE 2 = | 48" |
| ▩ ZONE 3 | MAX. FASTENER SPAN ZONE 3 = | 24" |

| ROOF "A" & "B" LOADING | |
|------------------------|----------------|
| GROUND SNOW LOAD: | 10 LBS./SQFT. |
| LIVE LOAD: | 20 LBS./SQFT. |
| DEAD LOAD: | |
| ROOFING | 3.9 LBS./SQFT. |
| PV ARRAY | 2.5 LBS./SQFT. |
| STRUCTURAL | 1.1 LBS./SQFT. |
| TOTAL | 7.5 LBS./SQFT. |
| WIND LOAD: | |
| UPLIFT ZONE 1 | -23.0 LBS/SQFT |
| UPLIFT ZONE 2 | -38.0 LBS/SQFT |
| UPLIFT ZONE 3 | -57.1 LBS/SQFT |
| DOWNWARD | 13.6 LBS/SQFT |
| FASTENER LOAD: | |
| UPLIFT ZONE 1 | -275 LBS |
| UPLIFT ZONE 2 | -227 LBS |
| UPLIFT ZONE 3 | N/A |
| DOWNWARD | 163 LBS |

STATEMENT OF STRUCTURAL COMPLIANCE

THE EXISTING ROOF STRUCTURE HAS BEEN DESIGNED TO SUPPORT THE ADDITIONAL LOADS OF THE PURPOSED PV SYSTEM. IN ADDITION, THE RACKING AND FASTENING SYSTEM SHALL BE CAPABLE OF SECURING THE SYSTEM TO THE STRUCTURE UNDER DESIGN CONDITIONS WHEN INSTALLED PROPERLY AND IN ACCORDANCE WITH THE RACKING AND FASTENING ARRANGEMENT DETAILED WITHIN THESE DRAWINGS.

SIGNED: _____
 NAME: ANDREW W. KING, PE
 TITLE: PROFESSIONAL ENGINEER

| ROOF MOUNT & FASTENER | |
|-----------------------|----------------------|
| ROOF MOUNT: | |
| MAKE | UNIRAC |
| MODEL | FLASHKIT PRO |
| MATERIAL | ALUMINUM |
| FASTENER | |
| MAKE | GENERIC |
| MODEL | LAG BOLT |
| MATERIAL | SS LAG W/EPDM WASHER |
| SIZE | 5/16" x 4" |
| GENERAL | |
| WEIGHT | 1 LBS |
| FASTENERS PER MOUNT | 1 PER MOUNT |
| MAX. PULL-OUT FORCE | 800 LBS. |
| SAFETY FACTOR | 2 |
| DESIGN PULL-OUT FORCE | 400 LBS. |

- LAG BOLT EMBEDDED WITH 2.5" OF THREAD IN WOOD RAFTER OR TRUSSES MEMBER

| ROOF SUMMARY | |
|--------------|------------------|
| STRUCTURE: | |
| TYPE | RAFTER |
| MATERIAL | SOUTHERN PINE #2 |
| SIZE | 2" X 6" |
| SPACING | 24" |
| EFF. SPAN | |
| ROOF "A" | 12'-10" |
| ROOF "B" | 12'-10" |
| PITCH | |
| ROOF "A" | 4/12 |
| ROOF "B" | 4/12 |
| DENSITY | 30 LBS./CU.FT. |
| DECKING: | |
| TYPE | OSB |
| MATERIAL | WOOD COMPOSITE |
| THICKNESS | 7/16 |
| WEIGHT | 1.6 LBS./SQFT. |
| ROOFING: | |
| TYPE | ARCH SHINGLE |
| MATERIAL | ASPHALT |
| WEIGHT | 2.3 LBS./SQFT. |

| PV MODULES | |
|------------|---------------------|
| MAKE | REC |
| MODEL | REC405AA PURE BLACK |
| WIDTH | 40.0" |
| LENGTH | 71.7" |
| THICKNESS | 1.2" |
| WEIGHT | 45 LBS |

ENGINEER:

MODEL ENERGY
 300 FAYETTEVILLE ST. #1430
 RALEIGH, NC 27602
 919-274-9905
 MODELENERGY.COM P-1194

JOB TITLE:
NEW SOLAR PV SYSTEM
 9.720 kW DC INPUT
 7.600 kW AC EXPORT
 Gonzalez Cruz, Kiddian Michelle
 1651 Raynor McLamb Rd
 Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:

| ISSUED FOR: | DATE: |
|-------------|-----------|
| PERMIT | 9/11/2023 |
| | |
| | |
| | |
| | |

STRUCTURAL INFORMATION
PV3.1

| PV MODULES | |
|--------------------------------|---------------------|
| MAKE | REC |
| MODEL | REC405AA PURE BLACK |
| TECHNOLOGY | MONO-CRYST. |
| NOM. POWER (P _{nom}) | 405 WATTS |
| NOM. VOLT. (V _{mp}) | 37.39 VOLTS |
| O.C. VOLT. (V _{oc}) | 45.34 VOLTS |
| MAX. SYS. VOLT. | 1000 V (UL) |
| TEMP. COEF. (V _t) | -0.27 %/°C |
| NOM. CURR. (I _{mp}) | 10.83 AMPS |
| S.C. CURR. (I _{sc}) | 11.17 AMPS |
| MAX. SERIES FUSE | 20 AMPS |

| MODULE OPTIMIZER | |
|-------------------|---------------|
| MAKE | SOLAREEDGE |
| MODEL | S440 |
| DC INPUT: | |
| RATED POWER | 440 WATTS |
| VOLT. RANGE | 8-60 |
| MAX. SCC | 14.5 AMPS |
| DC OUTPUT: | |
| MAX. CURRENT | 15 AMPS |
| MAX. VOLT. | 60 VOLTS |
| MAX. SYSTEM VOLT. | 1000 VOLTS |
| MIN. STRING | 8 OPTIMIZERS |
| MAX. STRING | 25 OPTIMIZERS |
| MAX. POWER | 5700 WATTS |

| JUNCTION BOX | |
|--------------|-----------|
| MAKE | SOLADECK |
| MODEL | 0783-3R |
| PRO. RATING | NEMA 3R |
| VOLT. RATING | 600 VOLTS |
| AMP RATING | 120 AMPS |
| UL LISTING | UL 50 |

NOTES:

- PROVIDE ADDITIONAL JUNCTION BOXES AS REQUIRED TO COMBINE MODULES ON DIFFERENT ARRAYS INTO A SINGLE STRING

| CONDUCTOR SCHEDULE | | | | | | | | | | | | | |
|--------------------|-----------------------------|--------|----------|------------|----------------------|--------|----------|------------|-----------------|------|------------|----------|----------|
| TAG | CURRENT CARRYING CONDUCTORS | | | | GROUNDING CONDUCTORS | | | | CONDUIT/RACEWAY | | | NOTES | |
| | QTY. | SIZE | MATERIAL | INSULATION | QTY. | SIZE | MATERIAL | INSULATION | QTY. | SIZE | MATERIAL | | LOCATION |
| C1 | 4 | 10 AWG | COPPER | PV WIRE | 1 | 6 AWG | COPPER | BARE WIRE | - | - | - | FREE AIR | 1 |
| C2 | 4 | 10 AWG | COPPER | THWN-2 | 1 | 10 AWG | COPPER | THWN-2 | 1 | 1/2" | FMC/EMT/MC | EXT/INT | 2,4 |
| C3 | 3 | 8 AWG | COPPER | THWN | 1 | 10 AWG | COPPER | THWN | 1 | 3/4" | NOTE 5 | EXTERIOR | 2,4,5 |
| C4 | 3 | 6 AWG | COPPER | THWN | - | - | - | - | 1 | 3/4" | NOTE 5 | EXT | 2,4,5,6 |
| XC | - | - | - | - | - | - | - | - | - | - | - | - | 3 |

NOTES:

- MANUFACTURER PROVIDED, UL LISTED WIRING HARNESS FOR USE ON EXPOSED ROOFS
- CONDUIT SIZE SHOWN IS CODE MINIMUM. LARGER SIZES ARE ALLOWED
- EXISTING CONDUCTORS, FIELD VERIFY
- EQUIPMENT TERMINAL RATING SHALL BE A MINIMUM OF 75°C AT BOTH END OF CONDUCTOR
- PVC, EMT, ROMEX, LFNMC & FMC ARE ACCEPTABLE WHEN USED IN ACCORDANCE WITH ARTICLES 330, 334, 348, 350, 352, 356, & 358 OF THE 2017 NEC
- SERVICE CONDUCTORS SHALL NOT TRAVEL MORE THAN 5' INSIDE OF THE BUILDING AND MORE THAN 10' IN TOTAL.

| DC/AC INVERTER | |
|-----------------|-------------|
| MAKE | SOLAREEDGE |
| MODEL | SE7600H-US |
| TECHNOLOGY | TRANS-LESS |
| DC INPUT: | |
| MAX. POWER | 11800 WATTS |
| MAX. VOLT. | 480 VOLTS |
| NOM. VOLT. | 400 VOLTS |
| MAX. CURRENT | 20 AMPS |
| MAX. SCC | 45 AMPS |
| STRINGS INPUTS | 2 STRINGS |
| AC OUTPUT: | |
| RATED POWER | 7600 WATTS |
| MAX. POWER | 7600 WATTS |
| NOM. VOLT. | 240 VOLTS |
| MAX. CURR. | 32 AMPS |
| GFP (Y/N) | YES |
| RPP (Y/N) | YES |
| GFCI (Y/N) | YES |
| AFCI (Y/N) | YES |
| DC DISC. (Y/N) | YES |
| RAPID SHUTDOWN | AUTOMATIC |
| FUSE RATING | 15 AMPS |
| PROTECT. RATING | NEMA 4X |

| AC DISCONNECT | |
|----------------|-----------|
| MAKE | GENERIC |
| MODEL | N/A |
| ENCL. RATING | NEMA 3R |
| VOLT. RATING | 240 VOLTS |
| AMP RATING | 60 AMPS |
| UL LIST. (Y/N) | YES |
| FUSED (Y/N) | YES |
| FUSE RATING | 40 AMPS |


NOTES:

- LOAD-BREAK RATED
- VISIBLE OPEN
- LOCKABLE IN OPEN POSITION
- INSTALL ADJACENT TO METER
- DISCONNECT TO BE READILY ACCESSIBLE TO UTILITY COMPANY PERSONNEL AT ALL TIMES
- SERVICE RATED
- PROVIDE NEUTRAL/GROUND BONDING JUMPER

| MD PANEL (EXISTING) | |
|---------------------|-----------|
| MAKE | N/A |
| MODEL | N/A |
| ENCL. RATING | NEMA 3R |
| VOLT. RATING | 240 VOLTS |
| BUS RATING | 150 AMPS |
| UL LIST. (Y/N) | YES |
| MAIN BREAKER (Y/N) | YES |
| BREAKER RATING | 150 AMPS |


NOTES:

- BACK-FEED SOLAR OUTPUT VIA SUPPLY SIDE TAP INSIDE OF MD PANEL



1 PV SYSTEM ELECTRICAL WIRING SCHEMATIC
SCALE: NTS

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



ISSUED FOR: PERMIT
DATE: 9/11/2023


ELECTRICAL INFORMATION

PV4.1

EQUIPMENT LABELS

SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY



NEC 690.56 (C)(1)(a)
PLACE WITHIN 3FT OF SERVICE DISCONNECTING MEANS TO WHICH THE PV SYSTEMS ARE CONNECTED AND SHALL INDICATE THE LOCATIONS OF RAPID SHUTDOWN SWITCHES

PV SYSTEM DISCONNECT

NEC 690.13 (B)
PLACE ON PV SYSTEM DISCONNECTING MEANS.

⚠ WARNING

DUAL POWER SUPPLY

SOURCES: UTILITY GRID AND PV SOLAR ELECTRIC SYSTEM

NEC 705.12 (B)(3)
PLACE ON ALL EQUIPMENT THAT IS SUPPLIED BY BOTH POWER SOURCES

⚠ WARNING

ELECTRIC SHOCK HAZARD
TERMINALS ON THE LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

NEC 690.13 (B)
PLACE ON PV SYSTEM DISCONNECTING MEANS.

⚠ WARNING

POWER SOURCE OUTPUT CONNECTION
DO NOT RELOCATE THIS OVERCURRENT DEVICE

NEC 705.12 (B)(2)(3)(b)
PLACE ADJACENT TO BACK-FED BREAKER

WARNING: PHOTOVOLTAIC POWER SOURCE

NEC 690.31 (G)(3)&(4)
PLACE ON ALL JUNCTION BOXES, EXPOSED RACEWAYS, AND OTHER WIRING METHODS EVERY 10' AND ON EVERY SECTION SEPARATED BY ENCLOSURES, WALLS, PARTITIONS, CEILINGS, OR FLOORS.

⚠ WARNING

FED BY MULTIPLE POWER SOURCES

TOTAL RATING OF ALL OVERCURRENT DEVICES EXCLUDING UTILITY OVERCURRENT DEVICE SHALL NOT EXCEED AMPACITY OF BUSBAR

NEC 705.12 (B)(2)(3)(c)
PLACE ADJACENT TO BACK-FED BREAKER

DIRECT CURRENT PHOTOVOLTAIC POWER SOURCE

MAXIMUM VOLTAGE 600 VDC
MAX CIR. CURRENT 30 AMPS

NEC 690.53
PLACE ON ALL DC DISCONNECTING MEANS

PHOTOVOLTAIC POWER SOURCE

OPERATING AC VOLT. 240 VAC
MAXIMUM OPERATING AC OUTPUT CURRENT 32 AMPS

NEC 690.54
PLACE ON INTERCONNECTION DISCONNECTING MEANS

EQUIPMENT LABEL NOTES

1. LABELS SHOWN ARE 1/2 THEIR ACTUAL REQUIRED SIZE.
2. LABEL MATERIAL SHALL BE SUITABLE FOR THE EQUIPMENT ENVIRONMENT.
3. CONDUIT SHALL BE MARKED WITH REQUIRED LABEL EVERY 10 FEET.


RAPID SHUTDOWN SWITCH FOR SOLAR PV SYSTEM

NEC 690.56 (C)(3)
PLACE ON RAPID SHUTDOWN SWITCH OR EQUIPMENT WITH INTEGRATED RAPID SHUTDOWN *REFLECTIVE*

CONSTRUCTION NOTES

1. ALL WORK AND EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST NATIONAL, STATE, AND LOCAL CODES AND ORDINANCES
2. FOLLOW MANUFACTURER'S INSTALLATION INSTRUCTIONS, BEST PRACTICES, AND SPECIFICATIONS
3. WIRES SHALL BE RATED AND LABELED "SUNLIGHT RESISTANT" WHERE EXPOSED TO AMBIENT CONDITIONS
4. THE PHOTOVOLTAIC SYSTEM SHALL NOT EXCEED 600 VOLTS OR 800 AMPS
5. EACH ELECTRICAL APPLIANCE SHALL BE PROVIDED WITH A NAMEPLATE GIVING THE IDENTIFYING NAME AND THE RATING IN VOLTS AND AMPERES, OR VOLTS AND WATTS. IF THE APPLIANCE IS TO BE USED ON A SPECIFIC FREQUENCY OR FREQUENCIES, IT SHALL BE SO MARKED. WHERE MOTOR OVERLOAD PROTECTION EXTERNAL TO THE APPLIANCES IS REQUIRED, THE APPLIANCE SHALL BE SO MARKED
6. WHERE APPLICABLE, GROUNDING ELECTRODE CONDUCTOR TO BE CONTINUOUS. GROUNDING CRIMPS TO BE IRREVERSIBLE
7. IN ONE- AND TWO-FAMILY DWELLINGS, LIVE PARTS IN PHOTOVOLTAIC SOURCE CIRCUITS AND PHOTOVOLTAIC OUTPUT CIRCUITS OVER 150 VOLTS TO GROUND, SHALL ONLY BE ACCESSIBLE TO QUALIFIED PERSONS WHILE ENERGIZED.
8. PHOTOVOLTAIC SYSTEMS SHALL BE PERMANENTLY MARKED AT VARIOUS EQUIPMENT LOCATIONS TO IDENTIFY THAT A PHOTOVOLTAIC SYSTEM IS INSTALLED AND THAT VARIOUS DANGERS ARE PRESENT.
9. EACH PHOTOVOLTAIC SYSTEM DISCONNECTING MEANS SHALL BE PERMANENTLY MARKED TO IDENTIFY IT AS A PHOTOVOLTAIC SYSTEM DISCONNECT
10. WHERE ALL TERMINALS OF A DISCONNECTING MEANS MAY BE ENERGIZED IN THE OPEN POSITION, A WARNING SIGN SHALL BE MOUNTED ON OR ADJACENT TO THE DISCONNECT
11. A PERMANENT LABEL FOR THE DIRECT-CURRENT PHOTOVOLTAIC POWER SOURCE SHALL BE PROVIDED BY THE INSTALLED AT THE DC DISCONNECT MEANS
12. A PERMANENT PLAQUE OR DIRECTORY, DENOTING ALL ELECTRIC POWER SOURCES SERVING THE PREMISES, SHALL BE INSTALLED AT EACH SERVICE EQUIPMENT LOCATION AND AT LOCATIONS OF ALL POWER PRODUCTION SOURCES.
13. A PERMANENT PLAQUE OR DIRECTORY SHALL BE PROVIDED DENOTING THE LOCATIONS OF THE SERVICE DISCONNECT MEANS AND THE PHOTOVOLTAIC SYSTEM DISCONNECT MEANS IF THEY ARE NOT LOCATED AT THE SAME LOCATION.
14. ALL MODULE GROUND CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH NEC SECTION 690.4 (C)

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |
| | |
| | |
| | |
| | |
| | |

ELECTRICAL
INFORMATION


PV4.2

SOLAR'S MOST TRUSTED



REC ALPHA PURE BLACK SERIES > PRODUCT SPECIFICATIONS

PRODUCT SPECIFICATIONS



GENERAL DATA

| | | | |
|---------------|--|-------------|---|
| Cell type: | 132 half-cut REC heterojunction cells with lead-free, gapless technology 6 strings of 22 cells in series | Connectors: | Stäubli MC4 PV-KBT4/KST4; 12AWG (4mm ²) in accordance with IEC 62852 IP68 only when connected |
| Glass: | 0.13 in (3.2 mm) solar glass with anti-reflection surface treatment | Cable: | 12AWG (4mm ²) PV wire, 43+47 in (11+1.2 m) accordance with EN50618 |
| Backsheet: | Highly resistant polymer (black) | Dimensions: | 71.7 x 40 x 1.2 in (1821 x 1016 x 30 mm) |
| Frame: | Anodized aluminum (black) | Weight: | 45 lbs (20.5 kg) |
| Junction box: | 3-part, 3 bypass diodes, IP67 rated in accordance with IEC 62790 | Origin: | Made in Singapore |

ELECTRICAL DATA

| | Product Code*: RECxxxAA Pure Black | | | | |
|--|------------------------------------|-------|-------|-------|-------|
| Power Output - P _{MAX} (Wp) | 385 | 390 | 395 | 400 | 405 |
| Watt Class Sorting - (W) | 0/+5 | 0/+5 | 0/+5 | 0/+5 | 0/+5 |
| Nominal Power Voltage - V _{MPP} (V) | 41.2 | 41.5 | 41.8 | 42.1 | 42.4 |
| Nominal Power Current - I _{MPP} (A) | 9.35 | 9.40 | 9.45 | 9.51 | 9.56 |
| Open Circuit Voltage - V _{OC} (V) | 48.5 | 48.6 | 48.7 | 48.8 | 48.9 |
| Short Circuit Current - I _{SC} (A) | 9.99 | 10.03 | 10.07 | 10.10 | 10.14 |
| Power Density (W/sq ft) | 19.3 | 19.6 | 19.8 | 20.1 | 20.3 |
| Panel Efficiency (%) | 20.8 | 21.1 | 21.3 | 21.6 | 21.9 |
| Power Output - P _{MAX} (Wp) | 293 | 297 | 301 | 305 | 309 |
| Nominal Power Voltage - V _{MPP} (V) | 38.8 | 39.1 | 39.4 | 39.7 | 40.0 |
| Nominal Power Current - I _{MPP} (A) | 7.55 | 7.59 | 7.63 | 7.68 | 7.72 |
| Open Circuit Voltage - V _{OC} (V) | 45.7 | 45.8 | 45.9 | 46.0 | 46.1 |
| Short Circuit Current - I _{SC} (A) | 8.07 | 8.10 | 8.13 | 8.16 | 8.19 |

Values at standard test conditions (STC: air mass AM1.5, irradiance 1075 W/sq ft (1000 W/m²), temperature 77°F (25°C), based on a production spread with a tolerance of P_{MAX}, V_{OC} & I_{SC} ±3% within one watt class. Nominal module operating temperature (NMOT: air mass AM1.5, irradiance 800 W/m², temperature 68°F (20°C), windspeed 3.3 ft/s (1 m/s). *Where xxx indicates the nominal power class (P_{MAX}) at STC above.

CERTIFICATIONS

IEC 61215:2016, IEC 61730:2016, UL 61730 (Pending)
ISO 14001:2004, ISO 9001:2015, OHSAS 18001:2007, IEC 62941



WARRANTY

| | Standard | REC ProTrust |
|--|----------|------------------|
| Installed by an REC Certified Solar Professional | No | Yes |
| System Size | All | <25 kW 25-500 kW |
| Product Warranty (yrs) | 20 | 25 |
| Power Warranty (yrs) | 25 | 25 |
| Labor Warranty (yrs) | 0 | 25 |
| Power in Year 1 | 98% | 98% |
| Annual Degradation | 0.25% | 0.25% |
| Power in Year 25 | 92% | 92% |

See warranty documents for details. Conditions apply

MAXIMUM RATINGS

| | |
|----------------------------|--------------------------------|
| Operational temperature: | -40 ... +185°F (-40 ... +85°C) |
| Maximum system voltage: | 1000 V |
| Maximum test load (front): | +7000 Pa (146 lbs/sq ft)* |
| Maximum test load (rear): | -4000 Pa (83.5 lbs/sq ft)* |
| Max series fuse rating: | 25 A |
| Max reverse current: | 25 A |

*See installation manual for mounting instructions. Design load = Test load / 1.5 (safety factor)


TEMPERATURE RATINGS*

| | |
|---|-------------|
| Nominal Module Operating Temperature: | 44°C (±2°C) |
| Temperature coefficient of P _{MAX} : | -0.26 %/°C |
| Temperature coefficient of V _{OC} : | -0.24 %/°C |
| Temperature coefficient of I _{SC} : | 0.04 %/°C |

*The temperature coefficients stated are linear values

LOW LIGHT BEHAVIOUR

Typical low irradiance performance of module at STC:



Specifications subject to change without notice.

Ref: PM-DS-12-01-Rev-A_03.21

ENGINEER:

MODEL ENERGY
300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:
NEW SOLAR PV SYSTEM
9.720 kW DC INPUT
7.600 kW AC EXPORT
Gonzalez Cruz, Kiddian Michelle
1651 Raynor McLamb Rd
Linden, NC 28356


© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:

| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |
| | |
| | |
| | |
| | |
| | |
| | |

LABELS, DETAILS & SPECS
PV5.1

REC ALPHA[®] PURE BLACK SERIES
PRODUCT SPECIFICATIONS



400WP
20.1 W/FT²



Founded in 1996, REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power. As Solar's Most Trusted, REC is committed to high quality, innovation, and a low carbon footprint in the solar materials and solar panels it manufactures. Headquartered in Norway with operational headquarters in Singapore, REC also has regional hubs in North America, Europe, and Asia-Pacific.



Power Optimizer For Residential Installations

S440, S500



POWER OPTIMIZER

Enabling PV power optimization at the module level

- Specifically designed to work with SolarEdge residential inverters
- Detects abnormal PV connector behavior, preventing potential safety issues*
- Module-level voltage shutdown for installer and firefighter safety
- Superior efficiency (99.5%)
- Mitigates all types of module mismatch loss, from manufacturing tolerance to partial shading
- Faster installations with simplified cable management and easy assembly using a single bolt
- Flexible system design for maximum space utilization
- Compatible with bifacial PV modules

* Functionality subject to inverter model and firmware version

solaredge.com




Power Optimizer For Residential Installations S440, S500

| | S440 | S500 | UNIT |
|---|--|--------------------|---------|
| Rated Input DC Power ⁽¹⁾ | 440 | 500 | W |
| Absolute Maximum Input Voltage (Voc) | | 60 | Vdc |
| MPPT Operating Range | | 8 - 60 | Vdc |
| Maximum Short Circuit Current (Isc) of Connected PV Module | 14.5 | 15 | Adc |
| Maximum Efficiency | | 99.5 | % |
| Weighted Efficiency | | 98.6 | % |
| Overtoltage Category | | II | |
| OUTPUT DURING OPERATION | | | |
| Maximum Output Current | | 15 | Adc |
| Maximum Output Voltage | | 60 | Vdc |
| OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM INVERTER OR INVERTER OFF) | | | |
| Safety Output Voltage per Power Optimizer | | 1 | Vdc |
| STANDARD COMPLIANCE | | | |
| EMC | FCC Part 15 Class B, IEC61000-6-2, IEC61000-6-3, CISPR11, EN-55011 | | |
| Safety | IEC62109-1 (class II safety), UL1741 | | |
| Material | UL94 V-0, UV Resistant | | |
| RoHS | Yes | | |
| Fire Safety | VDE-AR-E 2100-712:2013-05 | | |
| INSTALLATION SPECIFICATIONS | | | |
| Maximum Allowed System Voltage | | 1000 | Vdc |
| Dimensions (W x L x H) | | 129 x 155 x 30 | mm |
| Weight (including cables) | | 655 / 1.5 | gr / lb |
| Input Connector | | MC4 ⁽²⁾ | |
| Input Wire Length | | 0.1 | m |
| Output Connector | | MC4 | |
| Output Wire Length | | (+) 2.3, (-) 0.10 | m |
| Operating Temperature Range ⁽³⁾ | | -40 to +85 | °C |
| Protection Rating | | IP68 / NEMA6P | |
| Relative Humidity | | 0 - 100 | % |

(1) Rated power of the module at STC will not exceed the Power Optimizer Rated Input DC Power. Modules with up to +5% power tolerance are allowed
 (2) For other connector types please contact SolarEdge
 (3) For ambient temperature above +70°C / +158°F power de-rating is applied. Refer to Power Optimizers Temperature De-Rating Technical Note for more details

| PV System Design Using a SolarEdge Inverter | | Single Phase HD-Wave | Three Phase | Three Phase for 277/480V Grid | |
|---|------------|----------------------|----------------------|-------------------------------|---|
| Minimum String Length (Power Optimizers) | S440, S500 | 8 | 16 | 18 | |
| Maximum String Length (Power Optimizers) | | 25 | 50 | | |
| Maximum Nominal Power per String ⁽⁴⁾ | | 5700 | 11250 ⁽⁵⁾ | 12750 ⁽⁶⁾ | W |
| Parallel Strings of Different Lengths or Orientations | | | Yes | | |

(4) If the inverters rated AC power ≤ maximum nominal power per string, then the maximum power per string will be able to reach up to the inverters maximum input DC power Refer to: <https://www.solaredge.com/sites/default/files/se-power-optimizer-single-string-design-application-note.pdf>
 (5) For the 230/400V grid: It is allowed to install up to 13,500W per string when the maximum power difference between each string is 2,000W
 (6) For the 277/480V grid: It is allowed to install up to 15,000W per string when the maximum power difference between each string is 2,000W
 (7) It is not allowed to mix S-series and P-series Power Optimizers in new installations



© SolarEdge Technologies, Inc. All rights reserved. SOLAREEDGE, the SolarEdge logo, OPTIMIZED BY SOLAREEDGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: 12/2021 DS-00091-12-ENG. Subject to change without notice.

CE RoHS

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



ISSUED FOR: PERMIT
DATE: 9/11/2023

EQUIPMENT
SPEC SHEETS

PV5.2

Single Phase Inverter with HD-Wave Technology

for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US



12-25
YEAR
WARRANTY

INVERTERS

Optimized installation with HD-Wave technology

- Specifically designed to work with power optimizers
- Record-breaking efficiency
- Fixed voltage inverter for longer strings
- Integrated arc fault protection and rapid shutdown for NEC 2014 and 2017, per article 690.11 and 690.12
- UL1741 SA certified, for CPUC Rule 21 grid compliance
- Extremely small
- Built-in module-level monitoring
- Outdoor and indoor installation
- Optional: Revenue grade data, ANSI C12.20 Class 0.5 (0.5% accuracy)

solaredge.com



Single Phase Inverter with HD-Wave Technology for North America

SE3000H-US / SE3800H-US / SE5000H-US / SE6000H-US / SE7600H-US / SE10000H-US / SE11400H-US

| | SE3000H-US | SE3800H-US | SE5000H-US | SE6000H-US | SE7600H-US | SE10000H-US | SE11400H-US | | |
|---|---|----------------------------|-------------|----------------------------|-------------------------------------|--------------------------|------------------------------|---------|---------|
| OUTPUT | | | | | | | | | |
| Rated AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA | |
| Maximum AC Power Output | 3000 | 3800 @ 240V 3300 @ 208V | 5000 | 6000 @ 240V 5000 @ 208V | 7600 | 10000 | 11400 @ 240V 10000 @ 208V | VA | |
| AC Output Voltage Min.-Nom.-Max. (211 - 240 - 264) | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | Vac | |
| AC Output Voltage Min.-Nom.-Max. (183 - 208 - 229) | - | ✓ | - | ✓ | - | - | ✓ | Vac | |
| AC Frequency (Nominal) | 59.3 - 60 - 60.5 ¹⁾ | | | | | | | Hz | |
| Maximum Continuous Output Current @240V | 12.5 | 16 | 21 | 25 | 32 | 42 | 47.5 | A | |
| Maximum Continuous Output Current @208V | - | 16 | - | 24 | - | - | 48.5 | A | |
| GFDI Threshold | 1 | | | | | | | A | |
| Utility Monitoring, Islanding Protection, Country Configurable Thresholds | Yes | | | | | | | | |
| INPUT | | | | | | | | | |
| Maximum DC Power @240V | 4650 | 5900 | 7750 | 9300 | 11800 | 15500 | 17650 | W | |
| Maximum DC Power @208V | - | 5100 | - | 7750 | - | - | 15500 | W | |
| Transformer-less, Ungrounded | Yes | | | | | | | | |
| Maximum Input Voltage | 480 | | | | | | | Vdc | |
| Nominal DC Input Voltage | 380 | | | 400 | | | | Vdc | |
| Maximum Input Current @240V ²⁾ | 8.5 | 10.5 | 13.5 | 16.5 | 20 | 27 | 30.5 | Adc | |
| Maximum Input Current @208V ²⁾ | - | 9 | - | 13.5 | - | - | 27 | Adc | |
| Max. Input Short Circuit Current | 45 | | | | | | | Adc | |
| Reverse-Polarity Protection | Yes | | | | | | | | |
| Ground-Fault Isolation Detection | 600ka Sensitivity | | | | | | | | |
| Maximum Inverter Efficiency | 99 | 99.2 | | | | | | % | |
| CEC Weighted Efficiency | 99 | | | | | 99 @ 240V 98.5 @ 208V | | % | |
| Nighttime Power Consumption | < 2.5 | | | | | | | W | |
| ADDITIONAL FEATURES | | | | | | | | | |
| Supported Communication Interfaces | RS485, Ethernet, ZigBee (optional), Cellular (optional) | | | | | | | | |
| Revenue Grade Data, ANSI C12.20 | Optional ³⁾ | | | | | | | | |
| Rapid Shutdown - NEC 2014 and 2017 690.12 | Automatic Rapid Shutdown upon AC Grid Disconnect | | | | | | | | |
| STANDARD COMPLIANCE | | | | | | | | | |
| Safety | UL1741, UL1741 SA, UL1699B, CSA C22.2, Canadian AFCI according to T.I.L. M-07 | | | | | | | | |
| Grid Connection Standards | IEEE1547, Rule 21, Rule 14 (HI) | | | | | | | | |
| Emissions | FCC Part 15 Class B | | | | | | | | |
| INSTALLATION SPECIFICATIONS | | | | | | | | | |
| AC Output Conduit Size / AWG Range | 1" Maximum / 14-6 AWG | | | | 1" Maximum /14-4 AWG | | | | |
| DC Input Conduit Size / # of Strings / AWG Range | 1" Maximum / 1-2 strings / 14-6 AWG | | | | 1" Maximum / 1-3 strings / 14-6 AWG | | | | |
| Dimensions with Safety Switch (HxWxD) | 17.7 x 14.6 x 6.8 / 450 x 370 x 174 | | | | 21.3 x 14.6 x 7.3 / 540 x 370 x 185 | | | | in / mm |
| Weight with Safety Switch | 22 / 10 | 25.1 / 11.4 | 26.2 / 11.9 | 38.8 / 17.6 | | | | lb / kg | |
| Noise | < 25 | | | | <50 | | | | dBA |
| Cooling | Natural Convection | | | | | | | | |
| Operating Temperature Range | -13 to +140 / -25 to +60 ⁴⁾ (-40°F / -40°C option) ⁵⁾ | | | | | | | °F / °C | |
| Protection Rating | NEMA 4X (Inverter with Safety Switch) | | | | | | | | |

¹⁾ For other regional settings please contact SolarEdge support
²⁾ A higher current source may be used; the inverter will limit its input current to the values stated
³⁾ Revenue grade inverter P/N: SExxxxH-US000NNC2
⁴⁾ For power de-rating information refer to: <https://www.solaredge.com/sites/default/files/se-temperature-derating-note-na.pdf>
⁵⁾ -40 version P/N: SExxxxH-US000NNU4

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



ISSUED FOR: PERMIT DATE: 9/11/2023

| | |
|--|--|
| | |
| | |
| | |
| | |
| | |

EQUIPMENT SPEC SHEETS

PV5.3

FLASHKIT PRO



FLASHKIT PRO is the complete attachment solution for composition shingle roofs. Featuring Unirac's patented **SHED & SEAL** technology, a weather proof system which provides the ultimate protection against roof leaks. Kitted in 10 packs for maximum convenience, flashings and hardware are available in Mill or Dark finishes. With **FLASHKIT pro**, you have everything you need for a quick, professional installation.



TRUSTED WATER SEAL FLASHINGS
FEATURING SHED & SEAL TECHNOLOGY



YOUR COMPLETE SOLUTION
Flashings, lags, continuous slot L-Feet and hardware



CONVENIENT 10 PACKS
Packaged for speed and ease of handling

THE COMPLETE ROOF ATTACHMENT SOLUTION

FOR QUESTIONS OR CUSTOMER SERVICE VISIT UNIRAC.COM OR CALL (505) 248-2702

FLASHKIT PRO

INSTALLATION GUIDE



FLASHKIT PRO IS THE COMPLETE FLASHING AND ATTACHMENT SOLUTION FOR COMPOSITION ROOFS.



INSTALL **FLASHKIT PRO** FLASHING



INSTALL L-FOOT



ATTACH L-FOOT TO RAIL

PRE-INSTALL

- Locate roof rafters and snap chalk lines to mark the installation point for each roof attachment.
- Drill a 7/32" pilot hole at each roof attachment. Fill each pilot hole with sealant.

STEP 1 INSTALL FLASHKIT PRO FLASHING

- Add a U-shaped bead of roof sealant to the underside of the flashing with the open side of the U pointing down the roof slope. Slide the aluminum flashing underneath the row of shingles directly up slope from the pilot hole as shown. Align the indicator marks on the lower end of the flashing with the chalk lines on the roof to center the raised hole in the flashing over the pilot hole in the roof. When installed correctly, the flashing will extend under the two courses of shingles above the pilot hole.

STEP 2 INSTALL L-FOOT

- Fasten L-foot and Flashing into place by passing the included lag bolt and pre-installed stainless steel-backed EPDM washer through the L-foot EPDM grommet, and the raised hole in the flashing, into the pilot hole in the roof rafter.

- Drive the lag bolt down until the L-foot is held firmly in place. It is normal for the EPDM on the underside of the stainless steel backed EPDM washer to compress and expand beyond the outside edge of the steel washer when the proper torque is applied.

TIP:

- Use caution to avoid over-torquing the lag bolt if using an impact driver.
- Repeat Steps 1 and 2 at each roof attachment point.

STEP 3 ATTACH L-FOOT TO RAIL

- Insert the included 3/8"-16 T-bolts into the lower slot on the Rail (sold separately), spacing the bolts to match the spacing between the roof attachments.
- Position the Rail against the L-Foot and insert the threaded end of the T-Bolt through the continuous slot in the L-Foot. Apply anti-seize to bolt threads to prevent galling of the T-bolt and included 3/8" serrated flange nut. Place the 3/8" flange nut on the T-bolt and finger tighten. Repeat STEP 3 until all L-Feet are secured to the Rail with a T-bolt. Adjust the level and height of the Rail and torque each bolt to 30ft-lbs.

FASTER INSTALLATION. 25-YEAR WARRANTY.

FOR QUESTIONS OR CUSTOMER SERVICE VISIT UNIRAC.COM OR CALL (505) 248-2702

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT
7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle
1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:




| | |
|-------------|-----------|
| ISSUED FOR: | DATE: |
| PERMIT | 9/11/2023 |

| |
|--|
| |
| |
| |
| |
| |
| |
| |
| |


EQUIPMENT
SPEC SHEETS

PV5.4







1/4" BOLT LOCATION

3/8" BOLT LOCATION




BONDING SPLICE BAR



#12 X 3/4" SELF DRILLING SS SCREWS INCLUDED


TYPICAL SPLICE BAR DETAIL



TYPICAL EXPANSION JOINT DETAIL

NOTE THAT ONLY 2 SCREWS ARE USED AT AN EXPANSION JOINT. THE SPLICE BAR DOES NOT BOND ACROSS AN EXPANSION JOINT.

ENGINEER:



MODEL ENERGY

300 FAYETTEVILLE ST.
#1430
RALEIGH, NC 27602
919-274-9905
MODELENERGY.COM
P-1194

JOB TITLE:

NEW SOLAR PV SYSTEM

9.720 kW DC INPUT

7.600 kW AC EXPORT

Gonzalez Cruz, Kiddian
Michelle

1651 Raynor McLamb Rd
Linden, NC 28356

© 2023 MODEL ENERGY, PLLC EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF MODEL ENERGY, PLLC.

CLIENT:



ISSUED FOR:

DATE:

PERMIT

9/11/2023

UNIRAC
1411 BROADWAY BLVD NE
ALBUQUERQUE, NM 87102 USA
WWW.UNIRAC.COM

PRODUCT LINE: SOLARMOUNT
DRAWING TYPE: PART DETAIL
DESCRIPTION: LIGHT RAIL
REVISION DATE: APRIL 2016

DRAWING NOT TO SCALE
ALL DIMENSIONS ARE NOMINAL

PRODUCT PROTECTED BY ONE
OR MORE US PATENTS

LEGAL NOTICE

SM-P02

SHEET

UNIRAC
1411 BROADWAY BLVD NE
ALBUQUERQUE, NM 87102 USA
WWW.UNIRAC.COM

PRODUCT LINE: SOLARMOUNT
DRAWING TYPE: PART & ASSEMBLY
DESCRIPTION: BONDING SPLICE BAR
REVISION DATE: APRIL 2016

DRAWING NOT TO SCALE
ALL DIMENSIONS ARE NOMINAL

PRODUCT PROTECTED BY ONE OR MORE
US PATENTS

LEGAL NOTICE

SM-A01

SHEET

EQUIPMENT
SPEC SHEETS

PV5.5

Customer: Gonzalez Cruz, Kiddian Michelle
Installer: SmartSun
Subject: PV System Structural Compliance
Date: 9/11/2023



To whom it may concern:

Model Energy, PLLC has reviewed the installation details of the proposed PV system that is to be installed by SmartSun at 1651 Raynor McLamb Rd, Linden, NC 28356. The conditions of the existing structure have been reviewed and validated by Model Energy, PLLC. The existing roof structure has been designed to support the additional loads of the proposed PV system. In addition, the racking and fastening system shall be capable of securing the system to the structure under design conditions when installed properly and in accordance with the racking and fastening arrangement detailed within the accompanying permit set. The installation design is compliant with current 2018 North Carolina state and national building codes.

Thank you,

Andrew King, PE

