

PHOTOVOLTAIC GROUND MOUNT SYSTEM

40 MODULES-GROUND MOUNTED - 19.200 kW DC, 23.000 kW AC

2184 WIRE RD, BUNNLEVEL, NC 28323



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

PROJECT DATA

PROJECT ADDRESS: 2184 WIRE RD, BUNNLEVEL, NC 28323

OWNER: TRAVIS BASS

DESIGNER: ESR

SCOPE: 19.200 KW DC GROUND MOUNT SOLAR PV SYSTEM WITH 40 HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W PV MODULES WITH 01 SOL-ARK 15K-LV INVERTER 01 SOL-ARK 8K-P INVERTER

AUTHORITIES HAVING JURISDICTION: BUILDING: HARNETT COUNTY ZONING: HARNETT COUNTY UTILITY: DUKE ENERGY PROGRESS

SHEET INDEX

PV-1	COVER SHEET
PV-2	PLOT PLAN WITH GROUND PLAN
PV-3	GROUND PLAN & MODULES
PV-4	ELECTRICAL PLAN
PV-5	RACKING DETAILS
PV-6	ELECTRICAL LINE DIAGRAM
PV-7	WIRING CALCULATIONS
PV-8	LABELS
PV-9	PLACARD
PV-10+	EQUIPMENT SPECIFICATIONS

SIGNATURE



GENERAL NOTES

- ALL COMPONENTS ARE UL LISTED AND CEC CERTIFIED, WHERE WARRANTED.
- THE SOLAR PV SYSTEM WILL BE INSTALLED IN ACCORDANCE WITH ARTICLE 690 OF THE NEC 2017.
- THE UTILITY INTERCONNECTION APPLICATION MUST BE APPROVED AND PV SYSTEM INSPECTED PRIOR TO PARALLEL OPERATION.
- ALL CONDUCTORS OF A CIRCUIT, INCLUDING THE EGC, MUST BE INSTALLED IN THE SAME RACEWAY, OR CABLE, OR OTHERWISE RUN WITH THE PV ARRAY CIRCUIT CONDUCTORS WHEN THEY LEAVE THE VICINITY OF THE PV ARRAY.
- WHERE METALLIC CONDUIT CONTAINING DC CONDUCTORS IS USED INSIDE THE BUILDING, IT SHALL BE IDENTIFIED AS "CAUTION: SOLAR CIRCUIT" EVERY 10FT.
- HEIGHT OF THE AC DISCONNECT SHALL NOT EXCEED 6'-7" PER NEC CODE 240.24.
- A GROUNDING ELECTRODE SYSTEM IN ACCORDANCE WITH CEC 690.47 AND 250.50 THROUGH 60 AND 250-166 SHALL BE PROVIDED. PER NEC GROUNDING ELECTRODE SYSTEM OF EXISTING BUILDING MAY BE USED AND BONDED TO THE SERVICE ENTRANCE. IF EXISTING SYSTEM IS INACCESSIBLE OR INADEQUATE A SUPPLEMENTAL GROUNDING ELECTRODE WILL BE USED AT THE INVERTER LOCATION CONSISTING OF A UL LISTED 8 FT. GROUND ROD WITH ACORN CLAMP. GROUNDING ELECTRODE CONDUCTORS SHALL BE NO LESS THAN #8 AWG AND NO LARGER THAN #6 AWG COPPER AND BONDED TO THE EXISTING GROUNDING ELECTRODE TO PROVIDE FOR A COMPLETE SYSTEM.
- PHOTOVOLTAIC MODULES ARE TO BE CONSIDERED NON-COMBUSTIBLE.
- PHOTOVOLTAIC INSTALLATION WILL NOT OBSTRUCT ANY PLUMBING, MECHANICAL, OR BUILDING ROOF VENTS.
- ALL WIRING MUST BE PROPERLY SUPPORTED BY DEVICES OR MECHANICAL MEANS DESIGNED AND LISTED FOR SUCH USE. WIRING MUST BE PERMANENTLY AND COMPLETELY HELD OFF THE ROOF SURFACE.
- ALL SINAGE TO BE PLACED IN ACCORDANCE WITH THE LOCAL BUILDING CODE. IF EXPOSED TO SUNLIGHT, IT SHALL BE UV RESISTANT. ALL PLAQUES AND SINAGE WILL BE INSTALLED AS REQUIRED BY THE NEC AND AHJ.
- INVERTER(S) USED IN UNGROUNDED SYSTEM SHALL BE UL 1741 LISTED.
- THE INSTALLATION OF EQUIPMENT AND ALL ASSOCIATED WIRING AND INTERCONNECTION SHALL BE PERFORMED ONLY BY QUALIFIED PERSONS [NEC 690.4(C)]
- ALL OUTDOOR EQUIPMENT SHALL BE NEMA 3R RATED (OR BETTER), INCLUDING ALL ROOF MOUNTED TRANSITION BOXES AND SWITCHES.
- ALL EQUIPMENT SHALL BE PROPERLY GROUNDED AND BONDED IN ACCORDANCE WITH NEC ARTICLE 250.
- SYSTEM GROUNDING SHALL BE IN ACCORDANCE WITH NEC 690.41.
- PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION IN ACCORDANCE WITH NEC 690.12
- DISCONNECTING MEANS SHALL BE LOCATED IN A VISIBLE, READILY ACCESSIBLE LOCATION WITHIN THE PV SYSTEM EQUIPMENT OR A MAXIMUM OF 10 FEET AWAY FROM THE SYSTEM [NEC 690.13(A)]
- ALL WIRING METHODS SHALL BE IN ACCORDANCE WITH NEC 690.31
- WORK CLEARANCES AROUND ELECTRICAL EQUIPMENT WILL BE MAINTAINED PER NEC 110.26(A)(1), 110.26(A)(2) AND 110.26(A)(3).
- ROOFTOP MOUNTED PHOTOVOLTAIC PANELS AND MODULES SHALL BE TESTED, LISTED & IDENTIFIED IN ACCORDANCE WITH UL1703
- ELECTRICAL CONTRACTOR TO PROVIDE CONDUIT EXPANSION JOINTS AND ANCHOR CONDUIT RUNS AS REQUIRED PER NEC.

VICINITY MAP




HOUSE PHOTO



CODE REFERENCES

2018 NORTH CAROLINA BUILDING CODE
2018 NORTH CAROLINA RESIDENTIAL CODE
2018 NORTH CAROLINA FIRE CODE
2017 NATIONAL ELECTRICAL CODE

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

TRAVIS BASS
RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
COVER SHEET

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-1

PROJECT DESCRIPTION:



40 X HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MONO MODULES
 GROUND MOUNTED SOLAR PHOTOVOLTAIC MODULES
 DC SYSTEM SIZE: 19.200 kW DC
 AC SYSTEM SIZE: 23.000 kW AC

EQUIPMENT SUMMARY

40 HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MONO MODULES
 01 SOL-ARK 15K-LV INVERTER
 01 SOL-ARK 8K-K INVERTER

GROUND MOUNT ARRAY AREA #1:- 995.60 SQ FT.


NOTE: VISIBLE, LOCKABLE, LABELED AC DISCONNECT
 LOCATED WITHIN 10' OF UTILITY METER



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS,
 GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

**TRAVIS BASS
 RESIDENCE**

2184 WIRE RD,
 BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
**PLOT PLAN WITH
 GROUND PLAN**

SHEET SIZE
**ANSI B
 11" X 17"**

SHEET NUMBER
PV-2




1 | PLOT PLAN WITH GROUND PLAN

PV-2

SCALE: 1/64" = 1'-0"

MODULE TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULES = 40 MODULES
 MODULE TYPE = HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MONO MODULES
 MODULE WEIGHT = 64.2 LBS / 29.1KG.
 MODULE DIMENSIONS = 87.2" x 41.1" = 24.89 SF



LEGEND


ACD	- AC DISCONNECT
INV	- INVERTER
UM	- UTILITY METER
SUB	- SUBPANEL
MSP	- MAIN SERVICE PANEL
JB	- JUNCTION BOX
---	- CONDUIT
---	- TRENCH



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

TRAVIS BASS RESIDENCE
 2184 WIRE RD,
 BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
GROUND PLAN & MODULES


SHEET SIZE
**ANSI B
 11" X 17"**

SHEET NUMBER
PV-3

1 GROUND PLAN & MODULES

PV-3 SCALE: 1/16" = 1'-0"

STRING LEGENDS	
	STRING #1/INV#1
	STRING #2/INV#1
	STRING #3/INV#1
	STRING #4/INV#1
	STRING #5/INV#1
	STRING #1/INV#2
	STRING #2/INV#2



Bill of Materials		
Part	Spares	Total Qty
K10423-063 Ground Screw, 63"		20
A21165-060 HSS 2.375" OD Front Pipe		10
A21165-120 HSS 2.375" OD Rear Pipe		10
A21168-112 2.875" OD E/W Pipe Beam, 112"		16
A50164-066 HSS E/W Tube Brace		2
A50164-092 HSS N/S Tube Brace		10
A20444-174-ML SMR300 Rail, 174"		20
K10343-005 2.5" Pipe U-Clamp Kit		40
K10341-002 2.5" Pipe T-Cap Kit		20
K10219-001 2" Pipe Clamp Kit		22
K10222-001 2.5" Pipe Clamp Kit		2
K10342-001 2.5" Pipe Splice Kit		14
K10417-003 Mid Clamp, SMR Pop-on		60
K10418-003 End Clamp, SMR Pop-On		40
K10469-001 SMR Grounding Lug		1
A20445-001 Rail End Cap, SMR300		40


BILL OF MATERIALS	
EQUIPMENT DESCRIPTION	QTY
SOLAR PV MODULES: HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MODULE	40
INVERTER: SOL-ARK 15K-LV INVERTER	40
INVERTER: SOL-ARK 8K-P INVERTER	01
JUNCTION BOXES: 6"X6"X4" UL LISTED, STEEL WATER TIGHT NEMA TYPE 3R, UL LISTED	2
AC DISCONNECT: FUSED AC DISCONNECT, 200A FUSED, (2) 125A FUSES 240V NEMA 3R, UL LISTED	1



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS


TRAVIS BASS
RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
ELECTRICAL PLAN

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-4



REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

**TRAVIS BASS
RESIDENCE**
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY

ESR

SHEET NAME


RACKING DETAILS

SHEET SIZE

**ANSI B
11" X 17"**


SHEET NUMBER

PV-5



1 | **ARRAY DETAILS (TOP VIEW)**
PV-5 | SCALE: N.T.S


GROUND ARRAY #1
(40) HANWHA SOLAR: Q CELLS
Q.PEAK DUO XL-G10.3/BFG 480W
MONO MODULES



2 | **ARRAY DETAILS (SIDE VIEW)**
PV-5 | SCALE: N.T.S

DC SYSTEM SIZE: 19,200 kW DC
AC SYSTEM SIZE: 23,000 kW AC

(40) HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MONO MODULES
(01) SOL-ARK 15K-LV INVERTER
01 SOL-ARK 8K-P INVERTER
(05) STRINGS OF 06 MODULES AND
(02) STRINGS OF 05 MODULES ARE CONNECTED IN SERIES



INTERCONNECTION NOTES:

1. INTERCONNECTION SIZING, LIMITATIONS AND COMPLIANCE DETERMINED IN ACCORDANCE WITH [NEC 705.12], AND [NEC 690.59].
2. GROUND FAULT PROTECTION IN ACCORDANCE WITH [NEC 215.9], [NEC 230.95].
3. ALL EQUIPMENT TO BE RATED FOR BACKFEEDING.
4. PV BREAKER TO BE POSITIONED AT THE OPPOSITE END OF THE BUSBAR RELATIVE TO THE MAIN BREAKER.

DISCONNECT NOTES:

1. DISCONNECTING SWITCHES SHALL BE WIRED SUCH THAT WHEN THE SWITCH IS OPENED THE CONDUCTORS REMAINING LIVE ARE CONNECTED TO THE TERMINALS MARKED "LINE SIDE" (TYPICALLY THE UPPER TERMINALS)
2. AC DISCONNECT MUST BE ACCESSIBLE TO QUALIFIED UTILITY PERSONNEL, BE LOCKABLE, AND BE A VISIBLE-BREAK SWITCH
3. DISCONNECT MEANS AND THEIR LOCATION SHALL BE IN ACCORDANCE WITH [NEC 225.31] AND [NEC 225.32].

GROUNDING & GENERAL NOTES:

1. PV GROUNDING ELECTRODE SYSTEM NEEDS TO BE INSTALLED IN ACCORDANCE WITH [NEC 690.43]
2. PV INVERTER IS UNGROUNDED, TRANSFORMER-LESS TYPE.
3. DC GEC AND AC EGC TO REMAIN UNSPLICED, OR SPLICED TO EXISTING ELECTRODE
4. ANY EXISTING WIRING INVOLVED WITH PV SYSTEM CONNECTION THAT IS FOUND TO BE INADEQUATE PER CODE SHALL BE CORRECTED PRIOR TO FINAL INSPECTION.
5. JUNCTION BOX QUANTITIES, AND PLACEMENT SUBJECT TO CHANGE IN THE FIELD - JUNCTION BOX DEPICTED ON ELECTRICAL DIAGRAM REPRESENT WIRE TYPE TRANSITIONS.
6. AC DISCONNECT NOTED IN EQUIPMENT SCHEDULE OPTIONAL IF OTHER AC DISCONNECTING MEANS IS LOCATED WITHIN 10' OF SERVICE DISCONNECT.
7. RACEWAYS AND CABLES EXPOSED TO SUNLIGHT ON ROOFTOPS SHOULD BE INSTALLED MORE THAN 7/8" ABOVE THE ROOF USING CONDUIT SUPPORTS.

RACKING NOTE:

1. BOND EVERY OTHER RAIL WITH #6 BARE COPPER



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

PROJECT NAME & ADDRESS

TRAVIS BASS RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY

ESR

SHEET NAME

ELECTRICAL LINE DIAGRAM

SHEET SIZE

**ANSI B
11" X 17"**

SHEET NUMBER

PV-6

QTY	CONDUCTOR INFORMATION	CONDUIT TYPE	CONDUIT SIZE
1 (14)	#10AWG - PV WIRE/USE-2	N/A	N/A
(1)	#6AWG - BARE COPPER IN FREE AIR		
1 (14)	#8AWG - CU, THWN-2	PVC BURIAL (MIN 18" DEPTH)	1-1/4"
1 (1)	#10AWG - CU, THWN-2 GND		
2 (10)	#8AWG - CU, THWN-2	EMT, LFMC OR PVC	1-1/4"
1 (1)	#10AWG - CU, THWN-2 GND		
2 (4)	#10AWG - CU, THWN-2		
1 (1)	#10AWG - CU, THWN-2 GND	EMT, LFMC OR PVC	3/4"
1 (2)	#4AWG - CU, THWN-2		
1 (1)	#4AWG - CU, THWN-2 N	EMT, LFMC OR PVC	1"
1 (1)	#8AWG - CU, THWN-2 GND		
1 (2)	#8AWG - CU, THWN-2		
1 (1)	#8AWG - CU, THWN-2 N	EMT, LFMC OR PVC	3/4"
1 (1)	#10AWG - CU, THWN-2 GND		
1 (2)	#1AWG - CU, THWN-2		
1 (1)	#1AWG - CU, THWN-2 N	EMT, LFMC OR PVC	1-1/4"
1 (1)	#6AWG - CU, THWN-2 GND		
1 (2)	#1AWG - CU, THWN-2		
1 (1)	#1AWG - CU, THWN-2 N	EMT, LFMC OR PVC	1-1/4"

NOTE: CONDUIT TO BE UL LISTED FOR WET LOCATIONS AND UV PROTECTED

SOLAR MODULE SPECIFICATIONS	
MANUFACTURER / MODEL #	HANWHA SOLAR: Q CELLS Q.PEAK DUO XL-G10.3/BFG 480W MODULE
VMP	45.33V
IMP	10.59A
VOC	53.39V
ISC	11.12A
TEMP. COEFF. VOC	-0.27%/°C
MODULE DIMENSION	87.2"L x 41.1"W x 1.38"D (In Inch)

INVERTER #1 SPECIFICATIONS	
MANUFACTURER / MODEL #	SOL-ARK 15K-LV INVERTER
NOMINAL AC POWER	15.000 kW
NOMINAL OUTPUT VOLTAGE	240 VAC
NOMINAL OUTPUT CURRENT	62.5A

AMBIENT TEMPERATURE SPECS	
RECORD LOW TEMP	-9°
AMBIENT TEMP (HIGH TEMP 2%)	38°
MODULE TEMPERATURE COEFFICIENT OF Voc	-0.27%/°C
PERCENT OF VALUES	NUMBER OF CURRENT CARRYING CONDUCTORS IN EMT
.80	4-6
.70	7-9
.50	10-20

INVERTER #2 SPECIFICATIONS	
MANUFACTURER / MODEL #	SOL-ARK 8K-P INVERTER
NOMINAL AC POWER	8.000 kW
NOMINAL OUTPUT VOLTAGE	240 VAC
NOMINAL OUTPUT CURRENT	33.3A

DC FEEDER CALCULATIONS																					
CIRCUIT ORIGIN	CIRCUIT DESTINATION	VOLTAGE (V)	FULL LOAD AMPS "FLA" (A)	FLA*1.56 (A)	OC PD SIZE (A)	GROUND SIZE	CONDUCTOR SIZE	75°C AMPACITY (A)	AMPACITY CHECK #1	AMBIENT TEMP. (°C)	TOTAL CC CONDUCTORS IN RACEWAY	90°C AMPACITY (A)	DERATION FACTOR FOR AMBIENT TEMPERATURE NEC 310.15(B)(2)(a)	DERATION FACTOR FOR CONDUCTORS PER RACEWAY NEC 310.15(B)(3)(a)	90°C AMPACITY DERATED (A)	AMPACITY CHECK #2	FEEDER LENGTH (FEET)	CONDUCTOR RESISTANCE (OHM/KFT)	VOLTAGE DROP AT FLA (%)	CONDUIT SIZE	CONDUIT FILL (%)
STRING 1/INV#1	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 2/INV#1	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 3/INV#1	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 4/INV#1	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 5/INV#1	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 1/INV#2	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
STRING 2/INV#2	JUNCTION BOX 1	500	11.12	17.35	20	BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2	40	0.91	1	36.4	PASS	5	1.24	0.028	N/A	#N/A
JUNCTION BOX 1	JUNCTION BOX 2	500	11.12	17.35	20	CU #10 AWG	CU #8 AWG	50	PASS	38	14	55	0.91	0.5	25.025	PASS	94	0.778	0.325	1 1/4" EMT	35.66176
JUNCTION BOX 2	INVERTER 1	500	11.12	17.35	20	CU #10 AWG	CU #8 AWG	50	PASS	38	10	55	0.91	0.5	25.025	PASS	28	0.778	0.097	1 1/4" EMT	25.87567
JUNCTION BOX 2	INVERTER 2	500	11.12	17.35	20	CU #10 AWG	CU #10 AWG	35	PASS	38	4	40	0.91	0.8	29.12	PASS	28	1.24	0.154	3/4" EMT	19.79362

String 1/Inv#1 Voltage Drop	0.450
String 2/Inv#1 Voltage Drop	0.450
String 3/Inv#1 Voltage Drop	0.450
String 4/Inv#1 Voltage Drop	0.450
String 5/Inv#1 Voltage Drop	0.450
String 1/Inv#2 Voltage Drop	0.507
String 2/Inv#2 Voltage Drop	0.507

AC FEEDER CALCULATIONS																						
CIRCUIT ORIGIN	CIRCUIT DESTINATION	VOLTAGE (V)	FULL LOAD AMPS "FLA" (A)	FLA*1.25 (A)	OC PD SIZE (A)	NEUTRAL SIZE	GROUND SIZE	CONDUCTOR SIZE	75°C AMPACITY (A)	AMPACITY CHECK #1	AMBIENT TEMP. (°C)	TOTAL CC CONDUCTORS IN RACEWAY	90°C AMPACITY (A)	DERATION FACTOR FOR AMBIENT TEMPERATURE NEC 310.15(B)(2)(a)	DERATION FACTOR FOR CONDUCTORS PER RACEWAY NEC 310.15(B)(3)(a)	90°C AMPACITY DERATED (A)	AMPACITY CHECK #2	FEEDER LENGTH (FEET)	CONDUCTOR RESISTANCE (OHM/KFT)	VOLTAGE DROP AT FLA (%)	CONDUIT SIZE	CONDUIT FILL (%)
INVERTER 1	COMBINER PANEL	240	62.5	78.125	80	CU #4 AWG	CU #8 AWG	CU #4 AWG	85	PASS	38	2	95	0.91	1	86.45	PASS	5	0.308	0.080	1" EMT	32.8472
INVERTER 2	COMBINER PANEL	240	33.3	41.625	50	CU #8 AWG	CU #10 AWG	CU #8 AWG	50	PASS	38	2	55	0.91	1	50.05	PASS	5	0.778	0.108	3/4" EMT	24.5591
COMBINER PANEL	AC DISCONNECT	240	95.8	119.75	125	CU #1 AWG	CU #6 AWG	CU #1 AWG	130	PASS	38	2	145	0.91	1	131.95	PASS	5	0.154	0.061	1 1/4" EMT	34.7126
AC DISCONNECT	POI	240	95.8	119.75	125	CU #1 AWG	N/A	CU #1 AWG	130	PASS	38	2	145	0.91	1	131.95	PASS	5	0.154	0.061	1 1/4" EMT	31.3235

CUMULATIVE VOLTAGE DROP INV #1	0.20
CUMULATIVE VOLTAGE DROP INV #2	0.23

ELECTRICAL NOTES

- ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL, AND LABELED FOR ITS APPLICATION.
- ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600 V AND 90 DEGREE C WET ENVIRONMENT.
- WIRING, CONDUIT, AND RACEWAYS MOUNTED ON GROUND TOPS SHALL BE ROUTED DIRECTLY TO, AND LOCATED AS CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP, OR VALLEY.
- WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- WHERE SIZES OF JUNCTION BOX, RACEWAYS, AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
- ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
- MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR ILSKO GBL-4DBT LAY-IN LUG.
- TEMPERATURE RATINGS OF ALL CONDUCTORS, TERMINATIONS, BREAKERS, OR OTHER DEVICES ASSOCIATED WITH THE SOLAR PV SYSTEM SHALL BE RATED FOR AT LEAST 75 DEGREE C.



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

PROJECT NAME & ADDRESS

TRAVIS BASS
RESIDENCE

2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
WIRING CALCULATIONS

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-7

PHOTOVOLTAIC POWER SOURCE

EVERY 10' ON CONDUIT & ENCLOSURES

LABEL- 1:
LABEL LOCATION:
EMT/CONDUIT RACEWAY
SOLADECK / JUNCTION BOX
CODE REF: NEC 690.31 (D)(2)

WARNING

ELECTRIC SHOCK HAZARD

TERMINALS ON THE LINE AND LOAD SIDES MAY
BE ENERGIZED IN THE OPEN POSITION

LABEL- 2:
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.13(B)

WARNING

DUAL POWER SUPPLY

SOURCE: UTILITY GRID AND
PV SOLAR ELECTRIC SYSTEM

LABEL- 3:
LABEL LOCATION:
MAIN SERVICE PANEL
CODE REF: NEC 705.12(C) & NEC 690.59

SOLAR PV BREAKER:

BREAKER IS BACKFED
DO NOT RELOCATE

LABEL-4:
LABEL LOCATION:
MAIN SERVICE PANEL
CODE REF: NEC 705.12(C) & NEC 690.59


WARNING

POWER SOURCE OUTPUT
CONNECTION. DO NOT
RELOCATE THIS
OVERCURRENT DEVICE

LABEL- 5:
LABEL LOCATION:
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
SUBPANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 705.12(B)(3)(2)

SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN
SWITCH TO THE
"OFF" POSITION TO
SHUT DOWN PV SYSTEM
AND REDUCE
SHOCK HAZARD
IN THE ARRAY



LABEL- 6:
LABEL LOCATION:
AC DISCONNECT
CODE REF: [NEC 690.56(C)(1)(A)]

RAPID SHUTDOWN SWITCH FOR SOLAR PV SYSTEM

LABEL- 7:
LABEL LOCATION:
AC DISCONNECT
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 690.56(C)(2)

DC DISCONNECT

LABEL- 8:
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.13(B)

AC DISCONNECT PHOTOVOLTAIC SYSTEM POWER SOURCE

NOMINAL OPERATING AC VOLATGE **240 V**
RATED AC OUTPUT CURRENT **95.8 A**

LABEL- 9:
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.54

FOR INV #1

INVERTER AC DISCONNECT

NOMINAL OPERATING AC VOLATGE **240 V**
RATED AC OUTPUT CURRENT **62.50 A**

LABEL- 10:
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.54

FOR INV #2

INVERTER AC DISCONNECT

NOMINAL OPERATING AC VOLATGE **240 V**
RATED AC OUTPUT CURRENT **33.3 A**

LABEL- 11:
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.54

FOR INV #1 & #2

MAXIMUM VOLTAGE **500 V**

MAXIMUM CIRCUIT CURRENT **18 A**

MAXIMUM RATED OUTPUT
CURRENT OF THE CHARGE
CONTROLLER OR DC-TO-DC
CONVERTER (IF INSTALLED)

LABEL- 12:
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.53



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS,
GA 30606, UNITED STATES

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

PROJECT NAME & ADDRESS

TRAVIS BASS
RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY

ESR

SHEET NAME

LABELS


SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-8

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

**TRAVIS BASS
RESIDENCE**

2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR


SHEET NAME
PLACARD

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-9

CAUTION

POWER TO THIS BUILDING IS ALSO SUPPLIED FROM MULTIPLE SOURCES OF POWER WITH SAFETY DISCONNECTS AS SHOWN:



2184 WIRE RD, BUNNLEVEL, NC 28323

DIRECTORY

PERMANENT PLAQUE OR DIRECTORY PROVIDING THE LOCATION OF THE SERVICE DISCONNECTING MEANS AND THE PHOTOVOLTAIC SYSTEM.

(ALL PLAQUES AND SIGNAGE WILL BE INSTALLED AS OUTLINED WITHIN:
NEC 690.56(B)&(C), [NEC 705.10])
[NEC 690.56(C)(1)(A)]

LABELING NOTES:

1. LABELS CALLED OUT ACCORDING TO ALL COMMON CONFIGURATIONS. ELECTRICIAN TO DETERMINE EXACT REQUIREMENTS IN THE FIELD PER CURRENT NEC AND LOCAL CODES AND MAKE APPROPRIATE ADJUSTMENTS.
2. LABELING REQUIREMENTS BASED ON THE 2017 NATIONAL ELECTRIC CODE, OSHA STANDARD 19010.145, ANSI Z535.
3. MATERIAL BASED ON THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
4. LABELS TO BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED [NEC 110.21]
5. LABELS TO BE A MINIMUM LETTER HEIGHT OF 3/8", WHITE ON RED BACKGROUND; REFLECTIVE, AND PERMANENTLY AFFIXED [NEC 690.56(C)(1)(A)].

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

PROJECT NAME & ADDRESS

**TRAVIS BASS
RESIDENCE**

**2184 WIRE RD,
BUNNLEVEL, NC 28323**

DRAWN BY

ESR

**SHEET NAME
EQUIPMENT
SPECIFICATION**

SHEET SIZE

**ANSI B
11" X 17"**

SHEET NUMBER

PV-10



**Q.PEAK DUO XL-G10.3 / BFG
470-485**

**BIFACIAL DOUBLE GLASS MODULE
WITH EXCELLENT RELIABILITY
AND ADDITIONAL YIELD**



BIFACIAL ENERGY YIELD GAIN OF UP TO 20%

Bifacial Q.ANTUM solar cells with zero gap cell layout make efficient use of light shining on the module rear-side for radically improved LCOE.



LOW ELECTRICITY GENERATION COSTS

Q.ANTUM DUO Z combines cutting edge cell separation and innovative wiring with Q.ANTUM Technology for higher yield per surface area, lower BOS costs, higher power classes, and an efficiency rate of up to 21.2%.



INNOVATIVE ALL-WEATHER TECHNOLOGY

Optimal yields, whatever the weather with excellent low-light and temperature behavior.



ENDURING HIGH PERFORMANCE

Long-term yield security with Anti LID and Anti PID Technology¹, Hot-Spot Protect and Traceable Quality Tra.QTM.



FRAME FOR VERSATILE MOUNTING OPTIONS

High-tech aluminum alloy frame protects from damage, enables use of a wide range of mounting structures and is certified regarding IEC for high snow (5400Pa) and wind loads (2400Pa).



A RELIABLE INVESTMENT

Double glass module design enables extended lifetime with 12-year product warranty and improved 30-year performance warranty².

¹ APT test conditions according to IEC / TS 62804-1:2015 method B (-1500 V, 168h) including post treatment according to IEC 61215-1-1 Ed. 2.0 (CD)
² See data sheet on rear for further information.

THE IDEAL SOLUTION FOR:




Engineered in Germany



MECHANICAL SPECIFICATION

Format	87.2 in × 41.1 in × 1.38 in (including frame) (2216 mm × 1045 mm × 35 mm)
Weight	64.2 lbs (29.1 kg)
Front Cover	0.08 in (2.0 mm) thermally pre-stressed glass with anti-reflection technology
Back Cover	0.08 in (2.0 mm) semi-tempered glass
Frame	Anodized aluminum
Cell	6 × 26 monocrystalline Q.ANTUM solar half cells
Junction Box	2.09-3.98 in × 1.26-2.36 in × 0.59-0.71 in (53-101 mm × 32-60 mm × 15-18 mm), IP67, with bypass diodes
Cable	4 mm ² Solar cable; (+) ≥ 27.6 in (700 mm), (-) ≥ 13.8 in (350 mm)
Connector	Stäubli MC4-Evo2, Hanwha Q CELLS HQC4, IP68



ELECTRICAL CHARACTERISTICS

POWER CLASS		470	475	480	485	
MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC* AND BSTC* (POWER TOLERANCE +5 W / -0 W)						
Minimum	Power at MPP ¹	P _{MPP} [W]	470	475	480	485
	Short Circuit Current ¹	I _{SC} [A]	11.04	11.08	11.12	11.16
	Open Circuit Voltage ¹	V _{OC} [V]	52.91	53.10	53.34	53.58
	Current at MPP	I _{MPP} [A]	10.51	10.55	10.59	10.63
	Voltage at MPP	V _{MPP} [V]	44.73	45.03	45.33	45.63
	Efficiency ¹	η [%]	≥ 20.3	≥ 20.5	≥ 20.7	≥ 20.9

Bifaciality of P_{MPP} and I_{SC}: 70% ± 5% • Bifaciality given for rear side irradiation on top of STC (front side) • According to IEC 60904-1-2


* Measurement tolerances P_{MPP} ± 3%, I_{SC}, V_{OC} ± 5% at STC; 1000 W/m²; * at BSTC: 1000 W/m²; φ = 135 W/m²; φ = 70% ± 5%; 25 ± 2 °C, AM 1.5 according to IEC 60904-3

MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT²

Minimum	Power at MPP	P _{MPP} [W]	353.8	357.6	361.4	365.1
	Short Circuit Current	I _{SC} [A]	8.89	8.92	8.96	8.99
	Open Circuit Voltage	V _{OC} [V]	50.04	50.27	50.49	50.72
	Current at MPP	I _{MPP} [A]	8.27	8.30	8.34	8.37
Voltage at MPP		V _{MPP} [V]	42.77	43.06	43.35	43.63

² 800 W/m², NMOT, spectrum AM 1.5


Q CELLS PERFORMANCE WARRANTY



At least 98% of nominal power during first year. Thereafter max. 0.45% degradation per year. At least 93.95% of nominal power up to 10 years. At least 84.95% of nominal power up to 30 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Q CELLS sales organisation of your respective country.

PERFORMANCE AT LOW IRRADIANCE



Typical module performance under low irradiance conditions in comparison to STC conditions (25 °C, 1000 W/m²)

TEMPERATURE COEFFICIENTS

Temperature Coefficient of I _{SC}	α [%/K]	+0.04	Temperature Coefficient of V _{OC}	β [%/K]	-0.27
Temperature Coefficient of P _{MPP}	γ [%/K]	-0.34	Nominal Module Operating Temperature	NMOT [°F]	108 ± 5.4 (42 ± 3 °C)

PROPERTIES FOR SYSTEM DESIGN

Maximum System Voltage V _{MYS}	[V]	1500	PV module classification	Class II
Maximum Series Fuse Rating	[A DC]	20	Fire Rating based on ANSI / UL 61730	TYPE 29 ⁴
Max. Design Load, Push / Pull ³	[lbs/ft ²]	75 (3600 Pa) / 33 (1600 Pa)	Permitted Module Temperature on Continuous Duty	-40 °F up to +185 °F (-40 °C up to +85 °C)
Max. Test Load, Push / Pull ³	[lbs/ft ²]	113 (5400 Pa) / 50 (2400 Pa)		

³ See Installation Manual

⁴ New Type is similar to Type 3 but with metallic frame

QUALIFICATIONS AND CERTIFICATES

UL 61730, CE-compliant, IEC 61215:2016, IEC 61730:2016, U.S. Patent No. 9,893,215 (solar cells), Certification in process.



Note: Installation instructions must be followed. See the installation and operating manual or contact our technical service department for further information on approved installation and use of this product.

Hanwha Q CELLS America Inc.
400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 748 59 96 | EMAIL inquiry@us.q-cells.com | WEB www.q-cells.us

Specifications subject to technical changes © Q CELLS © PEAK DUO XL-G10.3 / BFG 470-485 2023-01_Rw01_NA



**LIMITLESS
15K-LV
Spec Sheet**



Solar Input Power 17000W

Max Allowed PV Power	17000W
Max PV Power Delivered to Battery & AC Outputs	15000W
Max DC Voltage (Voc)	500V @ 18A, 450V @ 20A
MPPT Voltage Range	150-425V
Starting Voltage	125V
Number of MPPT	3
Max Solar Strings Per MPPT	2
Max DC Current per MPPT (Self Limiting)	26A
Max AC Coupled Input (Micro/String Inverters)	19200W

AC Output Power 15kW On-Grid & Off-Grid

Connections	120/240/208V Split Phase
Continuous AC Power from PV	15000W 62.5A-L (240V)
Continuous AC Power from Batteries	12000W 50A-L (240V)
Surge AC Power 10sec	24,000W L-L (240V)
Surge AC Power 100ms	TBD
Parallel Stacking	Yes - 12 Max
Frequency	60/50Hz
Continuous AC Power with Grid or Generator	48000W 200A L-L (240V) 24000W 200A L-N (120V)
CEC Efficiency	96.5% (Peak 97.5%)
Idle Consumption Typical—No Load	90W
Sell Back Power Modes	Limited to Household/Fully Grid-Tied
Design (DC to AC)	Transformerless DC
Response Time (Grid-Tied to Off-Grid)	4ms
Power Factor	+/- 0.9 - 1.0

Battery (optional) Output Power 12000W

Type	Lead-Acid or Li-Ion
Nominal DC Input	48V
Capacity	50 — 9900Ah
Voltage Range	43.0 — 63.0V
Continuous Battery Charging Output	275A
Charging Curve	3-Stage w/ Equalization
Grid to Batt Charging Efficiency	96.0%
External Temperature Sensor	Included
Current Shunt for Accurate % SOC	Integrated
External Gen Start Based on Voltage or %SOC	Integrated
Communication to Lithium Battery	CanBus & RS485

General

Dimensions (H x W x D)	31.8" x 18.3" x 10.9"
Weight	101 lbs
Enclosure	IP65 / NEMA 3R
Ambient Temperature	-40~60°C, >45°C Derating
Installation Style	Wall-Mounted
Wi-Fi & LAN Communication	Included
Standard Warranty (verified by HALT Testing)	10 Years


Protections & Certifications

Electronics Certified Safety by SGS Labs to NEC & UL Specs - NEC 690.4B & NEC 705.4/6	Yes
Grid Sell Back — UL1741-2010/2018, IEE-E1547a-2003/2014, FCC 15 Class B, UL1741SA, CA Rule 21, HECO Rule 14H	Yes
PV DC Disconnect Switch — NEC 240.15	Integrated
Ground Fault Detection — NEC 690.5	Integrated
PV Rapid Shutdown Control — NEC 690.12	Integrated
PV Arc Fault Detection — NEC 690.11	Integrated
PV Input Lightning Protection	Integrated
PV String Input Reverse Polarity Protection	Integrated
AC Output Breakers - 63A	Integrated
250A Battery Breaker / Disconnect	Integrated
Surge Protection	DC Type II / AC Type II



SOUTHEAST ENERGY SOLUTIONS
855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS
**TRAVIS BASS
RESIDENCE**
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
**EQUIPMENT
SPECIFICATION**

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-11



**Sol-Ark
8K-P
Spec Sheet**



Solar Input Power 9000W	
Max Allowed PV Power	5500W + 5500W = 11000W
Max PV Power Delivered to Battery & AC Outputs	8000W
Max DC Voltage (Voc)	500V @ 18A, 450V @ 20A
MPPT Voltage Range	150-425V
Starting Voltage	125V
Number of MPPT	2
Max Solar Strings Per MPPT	2
Max DC Current per MPPT (Self Limiting)	20A
Max AC Coupled Input (Micro/String Inverters)	9600W

AC Output Power 8kW On-Grid & Off-Grid	
Connections	120/240/208V Split Phase
Continuous AC Power to Grid (On-Grid)	8000W 33.3A-L (240V)
Continuous AC Power to Load (Off-Grid)	8000W 33.3A-L (240V)
Surge AC Power 10sec (Load)	16,000VA L-L (240V)
Surge AC Power 100ms (Load)	25,000VA L-L(240V)
Parallel Stacking	No
Frequency	60/50Hz
Continuous AC Power with Grid or Generator (Pass-through Power)	15120W 63A L-L (240V) 7560W 63A L-N (120V)
CEC Efficiency	96.5% (Peak 97.5%)
Idle Consumption Typical—No Load	60W
Sell Back Power Modes	Limited to Household/Fully Grid-Tied
Design (DC to AC)	Transformerless DC
Response Time (Grid-Tied to Off-Grid)	4ms
Power Factor	+/- 0.9 - 1.0

Battery (optional) Output Power 8000W	
Type	Lead-Acid or Li-Ion
Nominal DC Input	48V
Capacity	50 — 9900Ah
Voltage Range	43.0 — 63.0V
Continuous Battery Charging Output	185A
Charging Curve	3-Stage w/ Equalization
Grid to Batt Charging Efficiency	96.0%
External Temperature Sensor	Included
Current Shunt for Accurate % SOC	Integrated
External Gen Start Based on Voltage or %SOC	Integrated
Communication to Lithium Battery	CanBus & RS485


General	
Dimensions (H x W x D)	30.0" x 18.3" x
Weight	78 lbs
Enclosure	NEMA 3R
Ambient Temperature	-25-55°C, >45°C
Installation Style	Wall-Mounted
Wi-Fi & LAN Communication	Included
Standard Warranty (verified by HALT Testing)	5 Years

Protections & Certifications	
Electronics Certified Safety by SGS Labs to NEC & UL Specs - NEC 690.4B & NEC 705.4/6	Yes
Grid Sell Back — UL1741-2010/2018, IEE-E1547a-2003/2014, FCC 15 Class B, UL1741SA,	Yes
PV DC Disconnect Switch — NEC 240.15	Integrated
Ground Fault Detection — NEC 690.5	Integrated
PV Rapid Shutdown Control — NEC 690.12	Integrated
PV Arc Fault Detection — NEC 690.11	Integrated
PV Input Lightning Protection	Integrated
PV String Input Reverse Polarity Protection	Integrated
AC Output Breakers - 63A	Integrated
250A Battery Breaker / Disconnect	Integrated
Surge Protection	DC Type II / AC Type II



SOUTHEAST ENERGY SOLUTIONS
855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS
TRAVIS BASS RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
EQUIPMENT SPECIFICATION

SHEET SIZE
ANSI B 11" X 17"

SHEET NUMBER
PV-12



GO BIG ON TURF

SunTurf™ Ground Mount System



SunModo offers the next generation Ground Mount System with SunTurf™. The streamlined design combines the strength of Helio Rails with steel pipes to create the perfect ground mount solution.

SunTurf™ is ideal for solar installers looking for a durable and cost-effective system that can accommodate a wide variety of soil conditions.

The SunTurf™ Ground Mount Advantage

- ✓ Easily scalable from kilowatts to multimegawatts PV Arrays.
- ✓ Foundation design solution for every soil condition.
- ✓ Online configuration tool available to streamline design process.
- ✓ Components optimized for strength, durability and fast installation.
- ✓ UL 2703 Listed by Intertek.

Key Features of SunTurf™ Ground Mount System

SunTurf™ Ground Mount System easily integrate Helio Rails with Schedule 40 steel pipes. No drilling is required to attach the aluminum rails to the horizontal pipe. Optional bracing can provide additional structural rigidity for sites with high snow or wind load conditions. Anchor any ground mount installation using one of our fountain types including helical piles, precast ballasts and concrete piers.




Augers and Ground Screws

Our augers are suitable for use in weak to moderate strength soils and areas with a high-water table. Our ground screws are ideal for use in hard packed earth or soils with large amounts of cobbles and gravel.



Ground Screw



Earth Auger

Technical Data

Application	Ground Mount
Material	High grade aluminum, galvanized steel and 304 stainless steel hardware
Module Orientation	Portrait and Landscape
Tilt Angle	Range between 10 to 50 degrees
Foundation Types	Post in concrete, helical earth auger, ground screw anchor and ballast
Structural Integrity	Stamped engineering letters available
Certificate	UL2703 listed by ETL
Warranty	25 years

SunModo, Corp. Vancouver, WA., USA • www.sunmodo.com • 360.844.0048 • info@sunmodo.com



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS, GA 30606, UNITED STATES

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

PROJECT NAME & ADDRESS

TRAVIS BASS
RESIDENCE
2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY

ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-13







Sub Array #1 Layout

NOTES: UNLESS OTHERWISE SPECIFIED

1. THIS DRAWING IS NOT FOR CONSTRUCTION UNTIL ENGINEERING HAS REVIEWED AND STAMPED THIS DOCUMENT.
2. DIMENSIONS SHOWN ARE INCHES.
3. THE SELF-BONDING SYSTEM AND SINGLE GROUND LUG IS FOR USE WITH PV MODULES THAT HAVE A MAXIMUM SERIES FUSE RATING OF 30A.
4. MATERIALS ARE AS SPECIFIED OR EQUIVALENT:
HARDWARE: 304 STAINLESS STEEL
FABRICATED EXTRUDED PARTS: 6005-T5 ALUMINUM ALLOY
FABRICATED DIE CAST PARTS: ANSI/AA A380 ALUMINUM ALLOY
STEEL PIPE: SCHEDULE 40 GALVANIZED
ALUMINUM PIPE: SCHEDULE 10 ANODIZED
5. THE MAXIMUM PERMISSIBLE LENGTH OF ANY STRUCTURE SHALL BE 200 FT. FOR SYSTEMS USING A SHARED RAIL CONFIGURATION, A THERMAL BREAK IS REQUIRED IN THE RAIL EVERY 40 FT. PER THE DRAWING DETAILS.
6. 4LX10-25DEG-STR-GSM-AGM-BGM-PGM
7. APPROVED RAIL PROFILES VARY BASED ON ENGINEERING REQUIREMENTS. CONFIRM SELECTION WITH STRUCTURAL ENGINEER. SEE BOM IN BOTTOM RIGHT CORNER.
8. K10224-XXX END CLAMP KIT OR K10299-XXX ADJ. END CLAMP KIT.
9. FOUNDATION TYPES:
GSM = GROUND SCREW GROUND MOUNT
AGM = HELICAL AUGER GROUND MOUNT
PGM = POST-IN-CONCRETE GROUND MOUNT
BSM = BALLAST GROUND MOUNT

10. 1 OF 1 ARRAY TYPES
11. 1 ARRAYS TOTAL

PACKET A7	
Model Code	ASCE 7-10
Exposure Category	C
Wind Speed	110
Ground Snow Load	10
Tilt	25



ITEM	PART NUMBER	DESCRIPTION	QTY
17	K10343-005	2.5" Pipe U-Clamp Kit	40
16	K10342-001	2.5" Pipe Splice Kit	14
15	K10341-002	2.5" Pipe T-Cap Kit	20
14	K10222-001	2.5" Pipe Clamp Kit	2
13	K10219-001	2" Pipe Clamp Kit	22
12	K10417-003	Mid Clamp, SMR Pop-on	60
11	K10469-001	SMR Grounding Lug	1
10	A50164-066	HSS E/W Tube Brace	2
9	A50164-092	HSS N/S Tube Brace	10
8	A21168-112	2.875" OD E/W Pipe Beam, 112"	16
7	A21165-060	HSS 2.375" OD Front Pipe	10
6	A21165-120	HSS 2.375" OD Rear Pipe	10
5	A20380-001	2.5" PIPE END CAP (OPTIONAL)	4
4		Panel 2,215 x1,044 x35.0mm	40
3	A20444-174-ML	SMR300 Rail, 174"	20
2	A20445-001	Rail End Cap, SMR300	40
1	K10418-003	End Clamp, SMR Pop-On	40

SunModo Corp.
14800 NE 65TH STREET, VANCOUVER WA 98682

TITLE: TRAVIS BASS
DRAWING NUMBER: 493E29
SCALE: N.T.S. SHEET 1 of 4

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	

PROJECT NAME & ADDRESS

TRAVIS BASS RESIDENCE

2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
EQUIPMENT SPECIFICATION

SHEET SIZE
ANSI B 11" X 17"

SHEET NUMBER
PV-14

THIS DRAWING IS CONFIDENTIAL PROPERTY OF SUNMODO AND ITS CONTENTS MAY NOT BE DISCLOSED WITHOUT THE PRIOR WRITTEN CONSENT OF SUNMODO CORP.


Sub Array #1 Spans



SOUTHEAST ENERGY SOLUTIONS

855 SUNSET DR #8, ATHENS,
GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS	
<p>TRAVIS BASS RESIDENCE</p>	<p>2184 WIRE RD, BUNNLEVEL, NC 28323</p>

DRAWN BY	ESR
----------	------------

SHEET NAME	EQUIPMENT SPECIFICATION
------------	------------------------------------


SHEET SIZE	ANSI B 11" X 17"
------------	-----------------------------

SHEET NUMBER	PV-15
--------------	--------------

NOTES:

- 1. DIMENSIONS LABELED AS MAX ARE MAXIMUM ALLOWABLE AND MAY RESULT IN END POSTS BEING OUTSIDE ARRAY EDGES. MAXIMUM DIMENSIONS MAY BE REDUCED IF DESIRED.


RAIL SPACING
LANDSCAPE: PER MODULE MANUFACTURER



SunModo Corp.	
TITLE	TRAVIS BASS
D	DRAWING NUMBER 493E29
SCALE	N.T.S. SHEET 2 of 4 REV

Sub Array #1 Foundation Part 1

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



PROJECT NAME & ADDRESS

TRAVIS BASS RESIDENCE

2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY

ESR

SHEET NAME


EQUIPMENT SPECIFICATION

SHEET SIZE

**ANSI B
11" X 17"**

SHEET NUMBER

PV-16




Grounding



SOUTHEAST ENERGY SOLUTIONS


855 SUNSET DR #8, ATHENS,
GA 30606, UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	10/27/2023	



- Pipe Connection
- ▬ Pipe
- ▬ Mid Clamp
- ▬ Fault Current Path
- ▬ Rail
- ▭ Solar Panel
- ⊠ Rail Splice
- Ground Lug

Note: All SunTurf metal structural components (Horizontal and Vertical Pipe, Pipe Splices, Post Caps, Pipe Clamps, Braces, Rail and Rail Splices) are electrically bonded together by design during the assembly of the racking.



PROJECT NAME & ADDRESS

**TRAVIS BASS
RESIDENCE**

2184 WIRE RD,
BUNNLEVEL, NC 28323

DRAWN BY
ESR

SHEET NAME
**EQUIPMENT
SPECIFICATION**

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-17