

# **Standard Document**

Quote: PR71633 Date Issued: 01/08/2024

Regional Foundations Solutions 721 E. Gannon Ave Zebulon, NC 27597

F (919) 269-6788

Prepared for:

Kristie McLean hairmonkey255@gmail.com M (919) 669-8495 L (919) 390-9431

Job Location: 255 Old Mill Road Fuquay Varina, NC 27526 Prepared by:

Traver Jackson
Design Specialist
W (919) 437-9613
M (919) 437-9613



# **Project Overview**

| Proposal Summary  |   |
|---|---|
| Total Investment  | <b>\$21,088.49</b> (\$2,108.85)   |
| Total Contract Price  | \$18,979.64   |
|   | \$5,693.89  |
| Deposit Paid  | \$5,700.00  |
| Amount Due Upon Installation  | \$13,279.64   |
| Customer Consent  |   |
| Customer's request or approval. Completing th or delays beyond our control. This Proposal is b  | d corresponding price adjustment (if necessary) will be made only at the e work in this Proposal at the time scheduled is contingent upon accidents ased primarily on the Customer's description of the problem. Engineering h as SFA Engineering and StoneWall Engineering. This Proposal may be hin 20 days.  1/8/2024  |
| Company Signature   | Date  |
| sheet(s), and the attached Limited Warranty, (twindow that Regional has to remedy any service bio-hazards cleaned and remediated that Region plumbing/sewage leaks, and any other hazards are authorized to do the work as specified in the | and agree to the contents of this Proposal, the attached Job Detail ogether, the "Contract"). I am/ we are aware of and agree to the 60 day e issues that are covered under the attached Limited Warranty. I will have anal may discover in the affected work area. This includes at my cost. I will provide documentation from a restoration company. You be Contract. However, field adjustments may be made if deemed vital by will make the payment to crew the day project is completed. |
| May & MoSean  | 1/8/2024  |

**Customer Signature** 

Date

# My Project

| Qty      | Product Name  |              |
|----------|---|--------------|
| Baseme   | ent: Keep Whole Basement Dry  |              |
| 1        | Permit Fee,   |              |
|          | Obtain proper building permit.  |              |
| 1        | Fuel Surcharge, Surcharge   |              |
| 147      | CleanSpace Wall System  |              |
|          | Install CleanSpace Wall System on walls as shown on drawing. Wall System is mechanically fastened to the walls.   |              |
| 165      | SafeDrain, Basement Waterproofing   |              |
|          | Install multi flow drain below the slab of concrete and backfilled with stone. Water diffuser on top of stand re-cement floor   | tone         |
| 1        | Pump: Triple Safe ,   |              |
|          | Install a triple safe pump system, which includes 1/3 hp pump, 1/2 hp pump, ultra sump battery back up canister, waterwatch alarm, clean stand and two 15' discharge lines. | o, twin      |
| 1        | Electrical Circuit 20amp circuit, Electric  |              |
|          | Install 1 electric circuit and 2 outlets with GFI protection.   |              |
| 65       | Exterior Discharge Line ,   |              |
|          | Extend exterior discharge line as indicated on proposal.  |              |
| 6        | Interior PVC Discharge Extension ,  |              |
|          | Install 1.5 inch pvc plumbing from sump pump to location of the discharge line.   |              |
| Total Ir | nvestment   | \$21,088.49  |
| Same D   | Day Savings   | (\$2,108.85) |
| Total C  | Contract Price  | \$18,979.64  |

# **Product Specifications**

#### Permit Fee,

Obtain proper building permit.

### CleanSpace Wall System

Install CleanSpace Wall System on walls as shown on drawing. Wall System is mechanically fastened to the walls.

#### SafeDrain, Basement Waterproofing

Install multi flow drain below the slab of concrete and backfilled with stone. Water diffuser on top of stone and re-cement floor

### Pump: Triple Safe,

Install a triple safe pump system, which includes 1/3 hp pump, 1/2 hp pump, ultra sump battery back up, twin canister, waterwatch alarm, clean stand and two 15' discharge lines.

## **Electrical Circuit 20amp circuit, Electric**

Install 1 electric circuit and 2 outlets with GFI protection.


### Exterior Discharge Line,

Extend exterior discharge line as indicated on proposal.

## Interior PVC Discharge Extension,

Install 1.5 inch pvc plumbing from sump pump to location of the discharge line.

# **Drawing**



Front

## **Job Details**

#### **Contractor Will**

- 1. Permit Project.
- 2. Remove and replace excavated soils. Customer is responsible for final landscaping (pavers, plants, re-seeding, mulch, retaining walls, etc)
- 3. Remove and replace concrete as necessary in the workplace.
- 4. Contact utility locator service

#### **Customer Will**

- 1. Move items at least 10 feet away from the work area.
- 2. Remove finished walls, cabinets/shelving, and or flooring.
- 3. Make Regional aware of any open permits on the property work is being performed.
- **4.** Mark any private lines that may be hidden underground, and assumes all liability if damage should occur to such lines.
- 5. Make payment of remaining balance to foreman of crew the same day installation is complete.