



Scott E. Wyssling, PE
Coleman D. Larsen, SE, PE
Gregory T. Elvestad, PE

76 North Meadowbrook Drive
Alpine, UT 84004
office (201) 874-3483
swyssling@wysslingconsulting.com

February 27, 2024
Revised April 2, 2024

BYLD Better
1213 W Moorehead Street Suite 500
Charlotte, NC 28208

Re: Engineering Services
Camber Residence
56 Countess Court, Cameron, NC
7.800 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

A. Site Assessment Information

1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

B. Description of Structure:

Roof Framing: Prefabricated wood trusses at 24" on center. All truss members are constructed of 2x4 dimensional lumber.
Roof Material: Composite Asphalt Shingles
Roof Slope: 29 degrees
Attic Access: Accessible
Foundation: Permanent

C. Loading Criteria Used

- **Dead Load**
 - Existing Roofing and framing = 7 psf
 - New Solar Panels and Racking = 3 psf
 - TOTAL = 10 PSF
- **Live Load** = 20 psf (reducible) – 0 psf at locations of solar panels
- **Ground Snow Load** = 10 psf
- **Wind Load** based on ASCE 7-10
 - Ultimate Wind Speed = 116 mph (based on Risk Category II)
 - Exposure Category C

Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the 2018 North Carolina Residential Code, including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.


D. Solar Panel Anchorage

1. The solar panels shall be mounted in accordance with the most recent Ironridge installation manual. If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
2. The maximum allowable withdrawal force for a #14 lag bolt is 229 lbs per inch of penetration as identified in the National Design Standards (NDS) of timber construction specifications. Based on a minimum penetration depth of 2", the allowable capacity per connection is greater than the design withdrawal force (demand). Considering the variable factors for the existing roof framing and installation tolerances, the connection using two #14 diameter lag bolt with a minimum of 2" embedment will be adequate and will include a sufficient factor of safety.
3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 48" on center.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the 2018 North Carolina Residential Code, current industry standards, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

Very truly yours,



Scott E. Wyssling, PE
North Carolina License No. 46546
North Carolina COA P-2308



Wyssling Consulting, PLLC
76 N Meadowbrook Drive Alpine UT 84004
North Carolina COA # P-2308

Signed 4/2/2024

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

NEW PV ROOFTOP SYSTEM DESIGN

20 MODULES - 7.800 KW DC & 5.800 KW AC SYSTEM SIZE

MOSELLE CAMBER RESIDENCE - 56 COUNTESS COURT, CAMERON, NORTH CAROLINA 28326

DESIGN ENGINEER



76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004
wyssling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE 500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

COVER SHEET

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES



Signed 4/02/2024


SCOTT E. WYSSLING, P.E.
NORTH CAROLINA LICENSE NO.
46546

DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP

AERIAL MAP



VICINITY MAP



SHEET INDEX

PV-1	COVER SHEET
PV-2	SITE PLAN
PV-3	MOUNTING PLAN
S-1	STRUCTURAL DETAILS
E-1	ELECTRICAL DIAGRAM
E-1.1	ONE LINE ELECTRICAL DIAGRAM
E-2	EQUIPMENT INFORMATION
E-3	PV LABELS
PV-4	SITE PHOTOS
SPECS 1-5	MANUFACTURER'S SPECS

SCOPE OF WORK

INSTALL 7.800 KW DC ROOF MOUNTED PV SYSTEM UTILIZING
(20) TRINASOLAR TSM-390DE09.07
(10) NEP BDM 600-X
(1) AC COMBINER PANEL
(1) 60A FUSED UTILITY AC DISCONNECT
IRONRIDGE AIRE RACKING WITH
IRONRIDGE - HUG MOUNTS
EXISTING 200 A BUSBAR WITH 200 A MAIN BREAKER
INTERCONNECTION METHOD: LINE SIDE TAP
ROOF TYPE: COMP SHINGLE
NUMBER OF STORIES: 2

CONTRACTOR

BYLD BETTER
1213 W MOOREHEAD STREET SUITE 500
CHARLOTTE, NC 28208

CODE REFERENCE

AHJ: CAMERON

2020 NATIONAL ELECTRIC CODE (NEC)
2018 NORTH CAROLINA BUILDING CODE
2018 NORTH CAROLINA RESIDENTIAL CODE (2015 INTERNATIONAL RESIDENTIAL CODE)

DESIGN CRITERIA

ASCE 7-10 WIND SPEED: 116 MPH
EXPOSURE CATEGORY C
GROUND SNOW LOAD: 10 PSF

GENERAL NOTES

- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND REVIEW ALL MANUFACTURER INSTALLATION DOCUMENTS PRIOR TO INITIATING CONSTRUCTION.
- ALL COMPONENTS SHALL BE NEW AND LISTED BY A RECOGNIZED ELECTRICAL TESTING LABORATORY AND LISTED FOR THEIR SPECIFIC APPLICATION.
- OUTDOOR EQUIPMENT SHALL BE NEMA 3R RATED OR BETTER.
- ACCESS TO ELECTRICAL COMPONENTS OVER 150 VOLTS TO GROUND SHALL BE RESTRICTED TO QUALIFIED PERSONNEL.
- CONTRACTOR SHALL OBTAIN ELECTRICAL PERMITS PRIOR TO INSTALLATION AND SHALL COORDINATE ALL INSPECTIONS, TESTING COMMISSIONING, AND ACCEPTANCE WITH THE CLIENT, UTILITY CO. AND CITY INSPECTORS AS NEEDED.
- EACH MODULE TO BE GROUNDED USING THE SUPPLIED CONNECTION POINT PER THE MANUFACTURER'S REQUIREMENTS. ALL PV MODULES, EQUIPMENT, AND METALLIC COMPONENTS ARE TO BE BONDED. IF THE EXISTING GROUNDING ELECTRODE SYSTEM CANNOT BE VERIFIED OR IS ONLY METALLIC WATER PIPING, IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSTALL A SUPPLEMENTAL GROUNDING ELECTRODE.
- DC CONDUCTORS SHALL BE RUN IN EMT AND/OR MC (METAL CLAD CABLE) AND SHALL BE LABELED. ALL DC CONDUCTORS RUN INSIDE OF THE STRUCTURE SHALL BE INSTALLED A MINIMUM OF 18" BELOW THE ROOF DECK.
- EXPOSED NON-CURRENT CARRYING METAL PARTS OF ELECTRICAL EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH APPLICABLE NEC.
- CONFIRM LINE SIDE VOLTAGE AT THE ELECTRIC UTILITY SERVICE PRIOR TO CONNECTING INVERTER. VERIFY SERVICE VOLTAGE IS WITHIN INVERTER VOLTAGE OPERATIONAL RANGE.
- ELECTRICAL CONTRACTOR TO PROVIDE CONDUIT EXPANSION JOINTS AND ANCHOR CONDUIT RUNS AS REQUIRED PER CODE.
- ALL WIRING MUST BE PROPERLY SUPPORTED BY DEVICES OR MECHANICAL MEANS DESIGNED AND LISTED FOR SUCH USE, AND FOR ROOF-MOUNTED SYSTEMS, WIRING MUST BE PERMANENTLY AND COMPLETELY HELD OFF OF THE ROOF SURFACE.
- ALL ROOF PENETRATIONS MUST BE SEALED OR FLASHED.
- EQUIPMENT MAY BE SUBSTITUTED FOR SIMILAR EQUIPMENT BASED ON AVAILABILITY. SUBSTITUTED EQUIPMENT SHALL COMPLY WITH DESIGN CRITERIA.
- REMOVAL OF AN INTERACTIVE INVERTER OR OTHER EQUIPMENT SHALL NOT DISCONNECT THE BONDING CONNECTION BETWEEN THE GROUNDING ELECTRODE CONDUCTOR AND THE PHOTOVOLTAIC SOURCE AND/OR OUTPUT CIRCUIT GROUNDED CONDUCTORS.
- WHENEVER A DISCREPANCY IN THE QUALITY OF EQUIPMENT ARISES ON THE DRAWING OR SPECIFICATIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND INSTALLING ALL MATERIAL AND SERVICES REQUIRED BY THE STRICTEST CONDITIONS NOTED ON THE DRAWINGS OR IN THE SPECIFICATIONS TO ENSURE COMPLETE COMPLIANCE AND LONGEVITY OF THE OPERABLE SYSTEM REQUIRED BY THE ENGINEERS.

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

PV-1

SITE PLAN LEGEND

UTILITY METER	
MAIN SERVICE PANEL	
GAS METER	
AC DISCONNECT	
DC DISCONNECT	
AC COMBINER PANEL	
INVERTER	
IQ SYSTEM CONTROLLER	
BACKUP INTERFACE	
BATTERY	
PRODUCTION METER	
SUBPANEL	
JUNCTION BOX	
FIRE PATHWAY	
SATELLITE DISH	
PROPERTY LINE	
ATTIC RUN CONDUIT	
EXTERNAL CONDUIT	
CHIMNEY	
ROOF OBSTRUCTION (TYP.)	
ROOF VENT (TYP.)	

UTILITY: CENTRAL EMC

MODULE SPEC AND ROOF INFO:

PV MODULE TYPE - TRINASOLAR TSM-390DE09.07 (390W)
 WEIGHT OF INDIVIDUAL PANEL - 46.30 LBS
 INDIVIDUAL SOLAR PANEL AREA - 20.69 SQ FT
 ROOF AREA - 2122.79 SQ FT

ROOF COVERAGE - 19.5%

EQUIPMENT LIST:

- (N) (20) TRINASOLAR TSM-390DE09.07
- (N) (10) NEP BDM 600-X
- (N) (1) AC COMBINER PANEL
- (N) (1) 60A FUSED UTILITY AC DISCONNECT
- IRONRIDGE AIRE RACKING WITH IRONRIDGE - HUG MOUNTS

SITE PLAN NOTES:

1. VERIFY ALL OBSTRUCTIONS AND DIMENSIONS IN THE FIELD.
2. PROVIDE RAIL SPLICES AS REQUIRED BY MANUFACTURER'S GUIDELINES.
3. NO SIGNIFICANT SHADING WILL RESULT FROM EXISTING ROOF OBSTRUCTIONS.
4. PV MODULES CANNOT BE INSTALLED OVER OR BLOCK ATTIC, PLUMBING, FURNACE OR WATER HEATER VENTS
5. AC DISCONNECT SHALL BE VISIBLE-OPEN TYPE, LOCKABLE AND READILY ACCESSIBLE. TO BE WITHIN 10' OF THE UTILITY METER
6. 3/4" OR GREATER CONDUIT RUN (7/8" ABOVE ROOF SURFACE)
7. ROOF ACCESS POINTS SHALL BE LOCATED IN AREAS THAT DO NOT REQUIRE THE PLACEMENT OF GROUND LADDERS OVER OPENINGS SUCH AS WINDOWS OR DOORS, AND LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION IN LOCATIONS WHERE THE ACCESS POINT DOES NOT CONFLICT WITH OVERHEAD OBSTRUCTIONS SUCH AS TREE LIMBS, WIRES OR SIGNS.

INVERTER	
MANUFACTURER/ MODEL	NEP BDM 600-X
MAX AC OUTPUT	2.42 A
AC OUTPUT VOLTAGE	240 V
MAX DC INPUT VOLTAGE	60 V
MAX INPUT CURRENT	18 x 2 A
WEIGHTED CEC EFFICIENCY	95.50%
INVERTER WATTAGE	580 W

DESIGN ENGINEER

**76 N. MEADOWBROOK DRIVE
 ALPINE, UTAH 84004**
 swysling@wysslingconsulting.com
 (201) 874-3483
 NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT

 BYLD BETTER
 1213 W MOOREHEAD STREET SUITE
 500
 CHARLOTTE, NC 28208

CAMBER, MOSELLE
 56 COUNTESS COURT
 CAMERON, NC 28326
 7.800 KW DC 5.800 KW AC

REVISIONS		
NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

SITE PLAN

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES





Signed 4/02/2024

SCOTT E. WYSSLING, P.E.
 NORTH CAROLINA LICENSE NO.
 46546

DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP

PV-2



ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

MOUNTING PLAN LEGEND

UTILITY METER	
MAIN SERVICE PANEL	
GAS METER	
AC DISCONNECT	
DC DISCONNECT	
AC COMBINER PANEL	
INVERTER	
IQ SYSTEM CONTROLLER	
BACKUP INTERFACE	
BATTERY	
PRODUCTION METER	
SUBPANEL	
JUNCTION BOX	
SATELLITE DISH	
PROPERTY LINE	
ATTIC RUN CONDUIT	
EXTERNAL CONDUIT	
RAIL	
MOUNT	
ROOF FRAMING	
CHIMNEY	
ROOF OBSTRUCTION (TYP.)	
ROOF VENT (TYP.)	

CANTILEVER NOTES:

1. CANTILEVER (OVERHANG) LENGTHS CAN BE UP TO 33% OF THE SPAN LENGTH.
2. THE CANTILEVER IS DEFINED AS THE DISTANCE FROM THE CENTER OF THE MOUNT TO THE EDGE OF THE RAIL.

MOUNTING PLAN NOTES:

1. VERIFY ALL OBSTRUCTIONS AND DIMENSIONS IN THE FIELD.
2. PROVIDE RAIL SPLICES AS REQUIRED BY MANUFACTURER'S GUIDELINES.
3. NO SIGNIFICANT SHADING WILL RESULT FROM EXISTING ROOF OBSTRUCTIONS.
4. PV MODULES CANNOT BE INSTALLED OVER OR BLOCK ATTIC, PLUMBING, FURNACE OR WATER HEATER VENTS
5. ACTUAL ROOF CONDITIONS AND ROOF FRAMING (OR SEAM) LOCATIONS MAY VARY. INSTALL PER MANUFACTURER(S) INSTALLATION GUIDELINES AND ENGINEERED SPANS FOR ATTACHMENTS


MOUNT QUANTITY:

1. (62) IRONRIDGE - HUG ATTACHMENTS
DISTRIBUTED LOAD - (ARRAY) WEIGHT/AREA = 2.24 lbs/ ft²
TOTAL WEIGHT OF SYSTEM - 926 lbs

	TILT	AZIMUTH	# OF MODULES	ROOF FRAMING	FRAMING SPACING	ROOF TYPE	MAX MOUNT SPACING	MOUNT TYPE
ROOF SECTION 1	29°	213°	20	2X4 - TRUSSES	24"	COMP SHINGLE	48"	IRONRIDGE - HUG

COUNTESS COURT

FRONT OF HOME



SCALE: 3/32" = 1'-0"

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

MOUNTING PLAN

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES




Signed 4/02/2024

SCOTT E. WYSSLING, P.E.
NORTH CAROLINA LICENSE NO.
46546


DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP

PV-3




GENERAL ROOF MOUNT DETAIL

NTS




ROOF MOUNT PLAN VIEW DETAIL

NTS



ROOF MOUNT CROSS SECTION DETAIL

NTS



ROOF MOUNT

NTS

MOUNT INSTALLATION NOTES

1. CONTRACTOR IS TO FOLLOW THE PLAN FOR INSTALLING ROOF MOUNTS.
2. IF THE CONTRACTOR IDENTIFIES THE ROOF FRAMING IS DIFFERENT FROM WHAT IS IDENTIFIED ON THIS PLAN, CONTRACTOR SHALL NOTIFY THE ENGINEER BEFORE PROCEEDING WITH INSTALLATION.
3. CONTRACTOR IS TO LOCATE THE ROOF FRAMING BY UTILIZING A HAMMER.
4. WHEN THE ROOF FRAMING IS LOCATED, CONTRACTOR IS TO DRILL A PILOT HOLE TO CONFIRM CENTER OF ROOF FRAMING. IF THE ROOF FRAMING IS MISSED, AND A NEW PILOT HOLE IS TO BE DRILLED, CONTRACTOR TO UTILIZE SILICON/CAULK TO SEAL THE ORIGINAL PILOT HOLE.
5. DIRECT TO DECK MOUNTS ARE ONLY TO BE USED WITH APPROVED DESIGN BY THE ENGINEER. DIRECT TO DECK MOUNT INSTALLATION IS NOT A SUBSTITUTION FOR LAG SCREWS INTO ROOF FRAMING.
6. CONTRACTOR TO FOLLOW MANUFACTURERS SPECIFICATIONS FOR INSTALLATION AND REQUIRED SCREWS.

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**

swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

**STRUCTURAL
DETAILS**

THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES



Signed 4/02/2024

SCOTT E. WYSSLING, P.E.
NORTH CAROLINA LICENSE NO.
46546

DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP


S-1

CONDUCTOR SCHEDULE

TAG ID	CONDUCTORS				GROUND		CONDUIT
	WIRES IN CONDUIT	WIRE AWG	TYPE, MATERIAL	AMPACITY	SIZE	TYPE, MATERIAL	
1	3	#10 AWG	AC CABLE	30	#6 AWG	BARE, CU	
2	5	#10 AWG	THWN-2, CU	30	#10 AWG	THHW, CU	3/4" CONDUIT
3	4	#8 AWG	THWN-2, CU	50	#10 AWG	THHW, CU	3/4" CONDUIT
4	4	#6 AWG	THWN-2, CU	65	#10 AWG	THHW, CU	3/4" CONDUIT

EQUIPMENT LIST:

- (N) (20) TRINASOLAR TSM-390DE09.07
- (N) (10) NEP BDM 600-X
- (N) (1) AC COMBINER PANEL
- (N) (1) 60A FUSED UTILITY AC DISCONNECT
- IRONRIDGE AIRE RACKING WITH IRONRIDGE - HUG MOUNTS



GENERAL NOTES

1. AC DISCONNECT SHALL BE VISIBLE-OPEN TYPE, LOCKABLE AND READILY ACCESSIBLE. TO BE WITHIN 10' OF THE UTILITY METER
2. 3/4" OR GREATER CONDUIT RUN (7/8" ABOVE ROOF SURFACE
3. GAS METER LOCATED IN PROXIMITY OF THE PV INSTALLATION, LOAD CENTER, AND/OR DISCONNECTS. DISCONNECTS SHALL BE LOCATED IN COMPLIANCE WITH UTILITY AND THE AHJ (AUTHORITY HAVING JURISDICTION).
4. PER NEC REQUIREMENTS GROUNDING CONDUCTORS SMALLER THAN #6 AWG SHALL BE PROTECTED IN A CONDUIT, RACEWAY, OR ARMORED PROTECTIVE SHEATHING (NEC 250.64).
5. THE WORKING CLEARANCES AROUND THE EXISTING ELECTRICAL EQUIPMENT AS WELL AS THE NEW ELECTRICAL EQUIPMENT WILL BE MAINTAINED IN ACCORDANCE WITH NEC 110.26.
6. ANY CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT. (NEC 300.6 C1, 310.8 D).
7. ROOM FOR EQUIPMENT WITHIN 5 FEET FROM MSP.

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swyssl@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

**ELECTRICAL
DIAGRAM**

DATE: 4/2/2024
DRAWN BY: PRT
REVIEWED BY: SCP


E-1

CONDUCTOR SCHEDULE

TAG ID	CONDUCTORS				GROUND		CONDUIT
	WIRES IN CONDUIT	WIRE AWG	TYPE, MATERIAL	AMPACITY	SIZE	TYPE, MATERIAL	
1	3	#10 AWG	AC CABLE	30	#6 AWG	BARE, CU	
2	5	#10 AWG	THWN-2, CU	30	#10 AWG	THHW, CU	3/4" CONDUIT
3	4	#8 AWG	THWN-2, CU	50	#10 AWG	THHW, CU	3/4" CONDUIT

EQUIPMENT LIST:

- (N) (20) TRINASOLAR TSM-390DE09.07
- (N) (10) NEP BDM 600-X
- (N) (1) AC COMBINER PANEL
- (N) (1) 60A FUSED UTILITY AC DISCONNECT
- IRONRIDGE AIRE RACKING WITH IRONRIDGE - HUG MOUNTS
- MODULE WATTAGE: 390W



GENERAL NOTES

1. AC DISCONNECT SHALL BE VISIBLE-OPEN TYPE, LOCKABLE AND READILY ACCESSIBLE. TO BE WITHIN 10' OF THE UTILITY METER
2. 3/4" OR GREATER CONDUIT RUN (7/8" ABOVE ROOF SURFACE
3. GAS METER LOCATED IN PROXIMITY OF THE PV INSTALLATION, LOAD CENTER, AND/OR DISCONNECTS. DISCONNECTS SHALL BE LOCATED IN COMPLIANCE WITH UTILITY AND THE AHJ (AUTHORITY HAVING JURISDICTION).
4. PER NEC REQUIREMENTS GROUNDING CONDUCTORS SMALLER THAN #6 AWG SHALL BE PROTECTED IN A CONDUIT, RACEWAY, OR ARMORED PROTECTIVE SHEATHING (NEC 250.64).
5. THE WORKING CLEARANCES AROUND THE EXISTING ELECTRICAL EQUIPMENT AS WELL AS THE NEW ELECTRICAL EQUIPMENT WILL BE MAINTAINED IN ACCORDANCE WITH NEC 110.26.
6. ANY CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT. (NEC 300.6 C1, 310.8 D).
7. ROOM FOR EQUIPMENT WITHIN 5 FEET FROM MSP.

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swyssling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

**ONE LINE ELECTRICAL
DIAGRAM**

DATE: 4/2/2024
DRAWN BY: PRT
REVIEWED BY: SCP

E-1.1

INTERCONNECTION CALCULATIONS

ITEM	UNIT	PANEL
BUS RATING	AMPS	200A
MAIN OCPD	AMPS	200A
ALLOWED PV PER NEC	AMPS	40A

CONDUCTOR CALCULATIONS

TAG 1 (SEE E-1)	TAG 2 (SEE E-1)	TAG 3 (SEE E-1)
UNDER MODULES, NOT IN CONDUIT	#10 AWG MAX CURRENT = 30A	#8 AWG MAX CURRENT = 50A
#10 AWG MAX CURRENT = 30A		
NEP BDM 600-X MAX CIRCUIT CURRENT	NEP BDM 600-X MAX CIRCUIT CURRENT	NEP BDM 600-X MAX CIRCUIT CURRENT
12.1 A FOR CIRCUIT 1	12.1 A FOR CIRCUIT 1	24.2 A * 1.25 A = 30.25
12.1 A FOR CIRCUIT 2	12.1 A FOR CIRCUIT 2	RECOMMENDED OCPD = 35

EQUIPMENT INFORMATION

MODULE	
MANUFACTURER/ MODEL	TRINASOLAR TSM-390DE09.07
P _{MAX}	390 W
V _{OC}	40.8 V
V _M P	33.8 V
I _M P	11.54 A
I _{SC}	12.14 A
TEMPERATURE COEFFICIENT OF P _{MAX}	-0.34 %/°C
TEMPERATURE COEFFICIENT OF V _{OC}	-0.25 %/°C

INVERTER	
MANUFACTURER/ MODEL	NEP BDM 600-X
MAX AC OUTPUT	2.42 A
AC OUTPUT VOLTAGE	240 V
MAX DC INPUT VOLTAGE	60 V
MAX INPUT CURRENT	18 x 2 A
WEIGHTED CEC EFFICIENCY	95.50%
INVERTER WATTAGE	580 W

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

EQUIPMENT INFORMATION

DATE: 4/2/2024
DRAWN BY: PRT
REVIEWED BY: SCP

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

E-2

PHOTOVOLTAIC AC DISCONNECT
 MAXIMUM AC OPERATING CURRENT: 24.2
 NOMINAL OPERATING AC VOLTAGE: 240

AT POINT OF INTERCONNECTION,
 MARKED AT DISCONNECTING MEANS
 [NEC 690.54]

WARNING DUAL POWER SOURCE
 SECOND SOURCE IS PHOTOVOLTAIC SYSTEM

AT POINT OF INTERCONNECTION.
 [NEC 705.12(C), 690.59]

MAIN PHOTOVOLTAIC SYSTEM DISCONNECT

EACH PV SYSTEM DISCONNECTING MEANS SHALL PLAINLY INDICATE WHETHER IN THE OPEN (OFF) OR CLOSED (ON) POSITION AND BE PERMANENTLY MARKED [NEC. 690.13(B)]

PHOTOVOLTAIC DC DISCONNECT

AT EACH DC DISCONNECTING MEANS [NEC 690.13(B)]

PHOTOVOLTAIC AC DISCONNECT

AT EACH AC DISCONNECTING MEANS [NEC 690.13(B)]

WARNING: PHOTOVOLTAIC POWER SOURCE

AT EXPOSED RACEWAYS, CABLE TRAYS, AND OTHER WIRING METHODS; SPACED AT MAXIMUM 10FT SECTION OR WHERE SEPARATED BY ENCLOSURES, WALLS, PARTITIONS, CEILINGS, OR FLOORS [NEC 690.31(D)(2)]

WARNING ELECTRICAL SHOCK HAZARD
 DO NOT TOUCH TERMINALS
 TERMINALS ON BOTH LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION

AT BUILDING OR STRUCTURE MAIN DISCONNECTING MEANS. [NEC 690.12(E), NEC 690.13(B)]

WARNING PHOTOVOLTAIC SYSTEM COMBINER PANEL DO NOT ADD LOADS

AT AC COMBINER PANEL. NEC 690.13(B)


WARNING
 THE EQUIPMENT FED BY MULTIPLE SOURCES. TOTAL RATING OF ALL OVERCURRENT DEVICES, EXCLUDING MAIN SUPPLY OVERCURRENT DEVICE, SHALL NOT EXCEED AMPACITY OF BUSBAR

PERMANENT WARNING LABELS SHALL BE APPLIED TO DISTRIBUTION EQUIPMENT

WARNING
 INVERTER OUTPUT CONNECTION. DO NOT RELOCATE THIS OVERCURRENT DEVICE

A PERMANENT WARNING LABEL SHALL BE APPLIED TO THE DISTRIBUTION EQUIPMENT ADJACENT TO THE BACK-FED BREAKER FROM THE INVERTER. [NEC 705.12(B)(3)(2)]

SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN
 TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUTDOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN ARRAY




FOR PV SYSTEMS THAT SHUT DOWN THE ARRAY AND CONDUCTORS LEAVING THE ARRAY: THE TITLE "SOLAR PV SYSTEM IS EQUIPPED WITH RAPID SHUTDOWN" SHALL UTILIZE CAPITALIZED CHARACTERS WITH A MINIMUM HEIGHT OF 3/8 IN. IN BLACK ON YELLOW BACKGROUND, AND THE REMAINING CHARACTERS SHALL BE CAPITALIZED WITH A MINIMUM HEIGHT OF 3/16 IN. IN BLACK ON WHITE BACKGROUND. [NEC 690.56(C)(1)(A)]

RAPID SHUTDOWN SWITCH FOR SOLAR PV

A RAPID SHUTDOWN SWITCH SHALL HAVE A LABEL LOCATED ON OR NO MORE THAN 3 FT FROM THE SWITCH THAT INCLUDES THIS WORDING. THE LABEL SHALL BE REFLECTIVE, WITH ALL LETTERS CAPITALIZED AND HAVING A MINIMUM HEIGHT OF 3/8 IN., IN WHITE ON RED BACKGROUND. [NEC 690.56(C)(2)]

CAUTION
 MULTIPLE SOURCES OF POWER



56 COUNTRESS COURT, CAMERON, NORTH CAROLINA 28326

LABEL LOCATION: MSP CODE REF: NEC 2020 - 705.10

DESIGN ENGINEER
WYSSLING CONSULTING
 COURTESY. EXPERIENCE WITH SMALL BUSINESS VALUE
76 N. MEADOWBROOK DRIVE ALPINE, UTAH 84004
 swyssl@wysslingconsulting.com
 (201) 874-3483
 NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT
BYLD BETTER
 BYLD BETTER
 1213 W MOOREHEAD STREET SUITE 500
 CHARLOTTE, NC 28208

CAMBER, MOSELLE
 56 COUNTRESS COURT
 CAMERON, NC 28326
 7.800 KW DC 5.800 KW AC

REVISIONS		
NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		


PV LABELS

DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP

E-3

LABELING NOTES:

1. LABELING REQUIREMENTS BASED ON THE 2020 NATIONAL ELECTRIC CODE, OSHA STANDARD 19010.145, ANSI Z535.
2. MATERIAL BASED ON THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
3. LABELS TO BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED [NEC 110.21]
4. LABELS TO BE A MINIMUM LETTER HEIGHT OF 3/8", WHITE ON RED BACKGROUND; REFLECTIVE, AND PERMANENTLY AFFIXED [IFC 605.11.1.1]



DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**

swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

SITE PHOTOS

DATE: 4/2/2024

DRAWN BY: PRT

REVIEWED BY: SCP

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA 

PV-4

Vertex S

BACKSHEET MONOCRYSTALLINE MODULE

Mono Multi Solutions

PRODUCT: TSM-DE09C.07
PRODUCT RANGE: 380-405W


405W
MAXIMUM POWER OUTPUT

0~+5W
POSITIVE POWER TOLERANCE

21.1%
MAXIMUM EFFICIENCY


- High value**
 - More productivity from same roof size.
 - Outstanding visual appearance.
 - Leading 210mm cell technology.
- Small in size, big on power**
 - Small format module allow greater energy generation in limited space.
 - Up to 405W, 21.1% module efficiency with high density interconnect technology.
 - Multi-busbar technology for better light trapping effect, lower series resistance and improved current.
 - Reduce installation cost with higher power bin and efficiency.
 - Boost performance in warm weather with lower temperature coefficient (-0.34%) and operating temperature.
- Universal solution for residential and C&I rooftops**
 - Designed for compatibility with existing mainstream optimizers, inverters and mounting systems.
 - Perfect size and low weight makes handling and transportation easier and more cost-effective.
 - Diverse installation solutions for flexibility in system deployment
- High Reliability**
 - 25 year product warranty.
 - 25 year performance warranty with lowest degradation.
 - Minimized micro-cracks with innovative non-destructive cutting technology.
 - Ensured PID resistance through cell process and module material control.
 - Mechanical performance up to +6000 Pa and -4000 Pa negative load

Trina Solar's Backsheet Performance Warranty




Vertex S BACKSHEET MONOCRYSTALLINE MODULE


DIMENSIONS OF PV MODULE(mm)



I-V CURVES OF PV MODULE(400W)



P-V CURVES OF PV MODULE(400W)



ELECTRICAL DATA (STC)

Peak Power Watts-P _{max} (Wp)*	380	385	390	395	400	405
Power Tolerance-P _{max} (W)	0 ~ +5					
Maximum Power Voltage-V _{MPP} (V)	33.4	33.6	33.8	34.0	34.2	34.4
Maximum Power Current-I _{MPP} (A)	11.38	11.46	11.54	11.62	11.70	11.77
Open Circuit Voltage-V _{oc} (V)	40.4	40.6	40.8	41.0	41.2	41.4
Short Circuit Current-I _{sc} (A)	12.00	12.07	12.14	12.21	12.28	12.34
Module Efficiency η _m (%)	19.8	20.0	20.3	20.5	20.8	21.1

STC: Irradiance 1000W/m², Cell Temperature 25°C, Air Mass AM1.5, *Measuring tolerance: ±3%

Electrical characteristics with different power bin (reference to 10% Irradiance ratio)

Total Equivalent power-P _{max} (Wp)	407	412	417	423	428	433
Maximum Power Voltage-V _{MPP} (V)	33.4	33.6	33.8	34.0	34.2	34.4
Maximum Power Current-I _{MPP} (A)	12.19	12.26	12.34	12.44	12.51	12.59
Open Circuit Voltage-V _{oc} (V)	40.4	40.6	40.8	41.0	41.2	41.4
Short Circuit Current-I _{sc} (A)	12.92	13.00	13.08	13.20	13.25	13.36
Irradiance ratio (rear/front)	10%					

Power Bifaciality: 70±5%

ELECTRICAL DATA (NOCT)

Maximum Power-P _{max} (Wp)	286	290	294	298	302	305
Maximum Power Voltage-V _{MPP} (V)	31.4	31.6	31.8	31.9	32.1	32.4
Maximum Power Current-I _{MPP} (A)	9.12	9.18	9.24	9.32	9.38	9.42
Open Circuit Voltage-V _{oc} (V)	38.0	38.2	38.4	38.6	38.8	38.9
Short Circuit Current-I _{sc} (A)	9.67	9.73	9.78	9.84	9.90	9.94

NOCT: Irradiance at 800W/m², Ambient Temperature 20°C, Wind Speed 1m/s.

MECHANICAL DATA

Solar Cells	Monocrystalline
No. of cells	120 cells
Module Dimensions	1754×1096×30 mm (69.06×43.15×1.18 inches)
Weight	21.0 kg (46.3 lb)
Glass	3.2 mm (0.13 inches), High Transmission, AR Coated Heat Strengthened Glass
Encapsulant material	EVA/POE
Backsheet	Transparent backsheet
Frame	30mm(1.18 inches) Anodized Aluminium Alloy
J-Box	IP 68 rated
Cables	Photovoltaic Technology Cable 4.0mm² (0.006 inches²), Portrait: 350/280 mm (13.78/11.02 inches), Landscape: N 1100 mm / P 1100 mm (43.31/43.31 inches)
Connector	MC4 EV02 / TS4*

*Please refer to regional datasheet for specified connector.

TEMPERATURE RATINGS

NOCT (Nominal Operating Cell Temperature)	43°C (±2°C)
Temperature Coefficient of P _{max}	-0.34%/°C
Temperature Coefficient of V _{oc}	-0.25%/°C
Temperature Coefficient of I _{sc}	0.04%/°C

MAXIMUM RATINGS

Operational Temperature	-40~+85°C
Maximum System Voltage	1500V DC (IEC)
	1500V DC (UL)
Max Series Fuse Rating	25A


WARRANTY

25 year Product Workmanship Warranty
25 year Power Warranty
2% first year degradation
0.55% Annual Power Attenuation
(Please refer to product warranty for details)

PACKAGING CONFIGURATION

Modules per box: 36 pieces
Modules per 40' container: 828 pieces

Comprehensive Products and System Certificates



CAUTION: READ SAFETY AND INSTALLATION INSTRUCTIONS BEFORE USING THE PRODUCT.

© 2022 Trina Solar Co., Ltd. All rights reserved. Specifications included in this datasheet are subject to change without notice.

Version number: TSM_NA_2022_A

www.trinasolar.com

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swyssling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT

BYLD BETTER

BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

**MODULE
SPEC SHEET**

DATE: 4/2/2024

DRAWN BY: PRT

REVIEWED BY: SCP

SPECS-1


PRODUCT DATASHEET



BDM-600X MICROINVERTER BDM-300X2 CEC Listing as Utility Interactive Inverter (NC0142-US-BQ-A, NC0142-L-US-BQ-A)




STANDARD DIMENSIONS



Weight: 6.4 lbs. (2.9 kg)

Certifications

UL 1741, CSA C22.2, NO. 107.1, IEC/EN 62109-1, IEC/EN 62109-2, IEEE 1547, VDE-AR-N 4105*, VDE V 0126-1-1/A1, G83/2, CEI 21, AS 4777.2, AS 4777.3, EN50438, ABNT NBR 16149/16150



Per box: 6 pcs
Boxes per layer: 9
Layers: 3

Pallet Qty: 162 pcs
Pallet weight: 1072 lbs.

SPECIFICATIONS

Input (DC)	
Recommended Max PV Power:	450 W x 2
Max DC Open Circuit Voltage:	60 Vdc
Max DC Input Current:	14 A x 2
MPPT Tracking Accuracy:	> 99.5%
MPPT Tracking Range:	22 – 55 Vdc
ISC PV (Absolute Maximum):	18 A x 2
Maximum Backfeed Current to Array:	0 A

Output (AC)	
Peak AC Output Power:	600 W
Max Continuous Output Power:	580 W
Nominal Power Grid Voltage:	240 Vac 3φ: 208 Vac
Allowable Power Grid Voltage:	211-264 Vac 3φ: 183-228 Vac
Rated Output Current:	2.42 A 3φ: 2.79 A
Maximum Units Per Branch (20A):	6 units 3φ: 5 units

(All NEC adjustment factors considered)

Allowable Power Grid Frequency:	59.3 – 60.5 Hz
THD:	< 3% (at rated power)
Power Factor (cos phi, fixed):	-0.99 > 0.9 (adjustable)
Current (inrush) (Peak and Duration):	24 A, 15 US
Nominal Frequency:	60 Hz
Max Output Fault Current:	2.4 Arms for 3 cycles
Max Output Overcurrent Protection:	10 A

System Efficiency

Weighted Average Efficiency (CEC):	95.5%
Nighttime Tare Loss:	0.11 W

Protection Function

Over/Under Voltage Protection:	Yes
Over/Under Frequency Protection:	Yes
Anti-Islanding Protection:	Yes
Over Current Protection:	Yes
Reverse DC Polarity Protection:	Yes
Overload Protection:	Yes
Protection Degree:	NEMA-6 / IP-66 / IP-67
Ambient Temperature:	-40°F to +149°F (-40°C to +65°C)
Operating Temperature:	-40°F to +185°F (-40°C to +85°C)
Display:	LED Light
Communications:	Powerline Communications
Environment Category:	Indoor and outdoor
Wet Location:	Suitable
Pollution Degree:	PD 3
Over Voltage Category:	II(PV), III (AC MAINS)

All NEC required adjustment factors have been considered for AC outputs. AC current outputs will not exceed stated values for Rated output AC Current.

COMPLIANCE

- NEC 2020 Section 690.11 DC Arc-Fault Circuit Protection
- NEC 2020 Section 690.12 Rapid Shutdown of PV Systems on Buildings
- NEC 2020 Section 705.12 Point of Connection (AC Arc-Fault Protection)

DESIGN ENGINEER



76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004
swyssl@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT

BYLD BETTER

BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

INVERTER SPEC SHEET

DATE:	4/2/2024
DRAWN BY:	PRT
REVIEWED BY:	SCP

SPECS-2



Aire® Flush Mount System

Datasheet



Breathe easy with accelerated installations.

The Aire® racking system has been carefully engineered to streamline every part of the installation process. We've eliminated tiresome hassles, so that you get off the roof and on to your next project faster than ever.

Aire® retains the strength and reliability that IronRidge installers depend on. It also takes wire management to the next level with the first (and only) NEC-compliant rail, formally approved and listed as a cable tray.



Strength Tested

All components have been evaluated for superior structural performance.



PE Certified

Pre-stamped engineering letters are available online for most states.



Class A Fire Rating

Certified to maintain the fire resistance rating of the existing roof structure.



Approved Cable Tray

Open channel listed to NEMA VE 1, certified to hold PV and DG cables.



UL 2703 Listed System

Entire system and components meet the latest effective UL 2703 standards.



25-Year Warranty


Products are guaranteed to arrive without any impairing defects.

One-Tool System - 1/2" Hex-Head Components

Datasheet

Rails


Aire® A1 Rail



The lighter, open Aire® rail for standard conditions.

- 6' spanning capability
- Wire management tray
- Mill or anodized black

Aire® A2 Rail



The tougher, open Aire® rail for higher load capacity.

- 8' spanning capability
- Wire management tray
- Mill or anodized black

Aire® Rail Ties



Structurally connect and bond Aire™ Rails together.

- Reinstallable, up to 5x
- Internal splice design
- No more splice rules

Aire® Dock



Connects Aire® Rails to attachments with ease.

- Clicks on, slides easily
- Drops into open slots
- Anodized assembly

Clamps & Grounding

Aire® Lock Mids



Securely bond between modules to Aire® Rails.

- Fits 30-40mm modules
- Utilizes UFO® design
- Minimal 1/2" gap

Aire® Lock Ends



Securely bond modules to Aire® Rails along ends.

- Fits 30-40mm modules
- Easy rail engagement
- Clean aesthetics

Aire® Lock Stealth®



Securely bonds modules to rail ends, entirely hidden.

- Angled for easy install
- Robust tether leash
- Fits most modules

Aire® Lug



Bonds Aire® Rails to grounding conductors.

- Simplified with single bolt
- Low-profile form factor
- Works with 10-6 AWG

Accessories

Aire® Caps



Block entry and provide a finished look to Aire® Rails.

- Stay secure on rail ends
- Symmetrical, with drain
- Cover rough-cut ends


Aire® Clip



Keeps wiring contained in open Aire® Rail channels.

- No module interference
- Simple press-in design
- Slot for easy removal

Aire® MLPE Mount



Securely bonds MLPE and accessories to Aire® Rails.

- Glove-friendly installation
- Lays flush in rail channel
- Low profile form factor

Aire® All Tile Hook



Attaches rails to tile roofs, with Aire® Dock included.


- Works on flat, S, & W tiles
- Single-socket installation
- Optional deck flashing

Resources



Design Assistant

Quickly go from rough layout to fully engineered system.
Go to IronRidge.com/design



Approved for FL Hurricane Zones

Aire® has Florida Product Approval. Additional details can be found on the Florida Building Code website.
Learn More at bit.ly/florida-aire

© 2023 IronRidge, Inc. All rights reserved. U.S. Patents Pending. Version 1.03

DESIGN ENGINEER



76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004

swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT

BYLD BETTER

BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

RAIL SPEC SHEET

DATE: 4/2/2024

DRAWN BY: PRT

REVIEWED BY: SCP

SPECS-3

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA



Tech Brief

QuickMount® HUG

The Respect Your Roof Deserves

When integrating with a home, solar attachments must be dependable for the lifetime of the rooftop. Due to recent innovations, many asphalt shingles have bonded courses. A mount that protects without the need to pry shingles can really speed things up.

Halo UltraGrip® (HUG®) is here to respect the roof. Its Halo is a cast-aluminum barrier that encases the UltraGrip, our industrial-grade, foam-and-mastic seal. This allows HUG to accelerate the installation process and provide the utmost in waterproofing protection. Give your roof a HUG.®





Multi-Tiered Waterproofing
HUG® utilizes a multi-tiered stack of components to provide revolutionary waterproofing protection. The Halo cast-aluminum, raised-perimeter foundation surrounds the UltraGrip base—a foam-backed mastic seal combination that prevents water intrusion by adhering and sealing with the shingle surface.

Halo UltraGrip™ is part of the QuickMount® product line.

UltraGrip® Seal Technology

HUG UltraGrip utilizes a state-of-the-art seal design that uses a unique, foam-and-mastic combination. The foam-backed adhesive provides an entirely new flashing system that conforms and adheres to every nook and cranny of composition shingles, filling gaps and shingle step-downs (up to 1/8" in height).



Rafter & Deck Mounting Options

Mount HUG® to the roof rafters, the roof deck, or both with our custom-engineered RD (rafter-or-deck) Structural Screw. The RD Structural Screw anchors HUG to the roof with an EPDM sealing washer, completing the stack of waterproofing barriers. See backside for more installation information.

ETL
Intertek
Triple Rated & Certified to Respect the Roof™
UL 2703, 441 (27)
TAS 100(A)-95

Tech Brief

Adaptive, Rafter-Friendly Installation



Hit the rafter? Good to go!
When you find a rafter, you can move on. Only 2 RD Structural Screws are needed.



Miss the rafter? Try it again.
Place another screw to the left or right. If rafter is found, install 3rd and final screw.



Still no luck? Install the rest.
If more than 3 screws miss the rafter, secure six screws to deck mount it.

Trusted Strength & Less Hassle



25-Year Warranty
Product guaranteed free of impairing defects.

Structural capacities of HUG® were reviewed in many load directions, with racking rail running cross-slope or up-slope in relation to roof pitch.

For further details, see the HUG certification letters for attaching to rafters and decking.

IronRidge designed the HUG, in combination with the RD Structural Screw to streamline installs, which means the following:

- No prying shingles
- No roof nail interference
- No pilot holes necessary
- No sealant (in most cases)
- No butyl shims needed

Attachment Loading



The rafter-mounted HUG has been tested and rated to support 1004 (lbs) of uplift and 368 (lbs) of lateral load.

Structural Design



Parts are designed and certified for compliance with the International Building Code & ASCE/SEI-7.

Water Seal Ratings



HUG passed both the UL 441 Section 27 "Rain Test" and TAS 100(A)-95 "Wind Driven Rain Test" by Intertek.

UL 2703 System



Systems conform to UL 2703 mechanical and bonding requirements. See Flush Mount Manual for more info.

© 2023 IronRidge, Inc. All rights reserved. Visit www.ir-patents.com for patent information, Version 1.03

DESIGN ENGINEER



76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004

swysslng@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT

BYLD BETTER

BYLD BETTER
1213 W MOOREHEAD STREET SUITE 500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

MOUNTING SPEC SHEET

DATE: 4/2/2024

DRAWN BY: PRT

REVIEWED BY: SCP

ENGINEERED PLANS COMPLETED BY ENGINEERS IN THE USA

SPECS-4



pe.eaton.com



Eaton general duty cartridge fuse safety switch

DG222NRB

UPC:782113144221

Dimensions:

- **Height:** 14.38 IN
- **Length:** 14.8 IN
- **Width:** 9.7 IN

Weight:10 LB

Notes:Maximum hp ratings apply only when dual element fuses are used. 3-Phase hp rating shown is a grounded B phase rating, UL listed.

Warranties:

- Eaton Selling Policy 25-000, one (1) year from the date of installation of the Product or eighteen (18) months from the date of shipment of the Product, whichever occurs first.

Specifications:

- **Type:** General duty, cartridge fused
- **Amperage Rating:** 60A
- **Enclosure:** NEMA 3R
- **Enclosure Material:** Painted galvanized steel
- **Fuse Class Provision:** Class H fuses
- **Fuse Configuration:** Fusible with neutral
- **Number Of Poles:** Two-pole
- **Number Of Wires:** Three-wire
- **Product Category:** General duty safety switch
- **Voltage Rating:** 240V

Supporting documents:

- [Eatons Volume 2-Commercial Distribution](#)
- [Eaton Specification Sheet - DG222NRB](#)

Certifications:

- UL Listed

DESIGN ENGINEER



**76 N. MEADOWBROOK DRIVE
ALPINE, UTAH 84004**
swysling@wysslingconsulting.com
(201) 874-3483

NORTH CAROLINA COA NO. P-2308

SOLAR COMPANY/CLIENT



BYLD BETTER
1213 W MOOREHEAD STREET SUITE
500
CHARLOTTE, NC 28208

CAMBER, MOSELLE
56 COUNTESS COURT
CAMERON, NC 28326
7.800 KW DC 5.800 KW AC

REVISIONS

NO	DATE:	COMMENTS
1	4/02/2024	INVERTER AND MODULE UPDATED
2		

AC DISCONNECT SPEC SHEET

DATE: 4/2/2024
DRAWN BY: PRT
REVIEWED BY: SCP

SPECS-5