

© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.



**PV MATERIAL SUMMARY: DISTRIBUTOR**

|                        |    |
|------------------------|----|
| Q.TRON BLK M-G2+ 425   | 37 |
| MCI-1                  | 14 |
| MI-BHW                 | 14 |
| Tesla PW3 1707000-xx-y | 1  |
| Tesla BUG 1232100-00-X | 1  |
| XR-10-168B             | 17 |
| XR-10-204B             | 6  |
| XR10-BOSS-01-M1        | 6  |
| UFO-CL-01-B1           | 98 |
| UFO-STP-30MM-B1        | 48 |
| XR-LUG-03-A1           | 12 |
| 4 IN QB1               | 41 |
| QB DECK MOUNT 16317    | 82 |
| GC66803 Geocel Sealant | 3  |
| SOLADECK 0799-5B       | 5  |



**CLIENT INFO**  
 COLLIN PEREGOY  
 148 SALT MARKET CT  
 DUNN NC 28334

**PROJECT INFO**  
 DC INPUT: 15.725 kW  
 AC OUTPUT: 11.500 kW  
 DOI INSPT. METHOD: OPTION 2

**Model Energy**  
 300 Fayetteville St.  
 #1430  
 Raleigh, NC 27602  
 919-274-9905  
 ModelEnergy.com  
 P-1194



**CODE REFERENCES**  
 NATION ELECTRICAL CODE v. 2017  
 NC FIRE PROTECTION CODE v. 2018  
 NC BUILDING CODE v. 2018  
 NC RESIDENTIAL CODE v. 2018  
 ACSE v. 7-10

**SITE CONDITIONS**  
 WIND SPEED: 120 MPH  
 RISK CATEGORY: II  
 EXPOSURE: B  
 SNOW: 10 PSF

**SHEET INDEX**  
 PV-1: COVER SHEET  
 PV-2: PV STRUCTURAL  
 PV-3: PV ELECTRICAL  
 PV-4: PV EQUIPMENT LABELS  
 PV-5: PV INSTALL GUIDE

**VERSIONS**







| FOR:         | DESIGNER | DATE      |
|--------------|----------|-----------|
| CONSTRUCTION | MCP      | 4/30/2024 |

**PV SYSTEM COVER PAGE**


**PV-1.1**



© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.



**1** ROOF FASTENER DETAIL  
NOT TO SCALE



**2** ROOF A ARRAY LAYOUT  
1/8" = 1'-0"

**STATEMENT OF STRUCTURAL COMPLIANCE**

THE EXISTING ROOF STRUCTURE HAS BEEN DESIGNED TO SUPPORT THE ADDITIONAL LOADS OF THE PROPOSED PV SYSTEM. IN ADDITION, THE RACKING AND FASTENING SYSTEM SHALL BE CAPABLE OF SECURING THE SYSTEM TO THE STRUCTURE UNDER DESIGN CONDITIONS WHEN INSTALLED PROPERLY AND IN ACCORDANCE WITH THE RACKING AND FASTENING ARRANGEMENT DETAILED WITHIN THESE DRAWINGS.

NAME: ANDREW W. KING, PE

SIGNED:

| PV MODULES   |                      |
|--------------|----------------------|
| MAKE         | HANWHA               |
| MODEL        | Q.TRON BLK M-G2+ 425 |
| WIDTH        | 44.60 IN             |
| LENGTH       | 67.80 IN             |
| THICKNESS    | 30 MM                |
| WEIGHT       | 46.70 LBS.           |
| ARRAY AREA   | 231 SQFT.            |
| ARRAY WEIGHT | 577 LBS.             |

| ROOF SUMMARY   |                  |
|----------------|------------------|
| STRUCTURE:     |                  |
| TYPE           | RAFTERS          |
| MATERIAL       | SOUTHERN PINE #2 |
| SIZE           | 2 X 8            |
| SPACING        | 16 IN O.C.       |
| EFFECTIVE SPAN | 73 IN            |
| PITCH          | 10/12            |
| DENSITY        | 30 LBS./CU.FT.   |
| DECKING:       |                  |
| TYPE           | OSB              |
| MATERIAL       | COMPOSITE        |
| THICKNESS      | 7/16 IN          |
| WEIGHT         | 1.60 LBS./SQFT   |
| ROOFING:       |                  |
| TYPE           | ASPHALT SHINGLE  |
| MATERIAL       | ASPHALT          |
| WEIGHT         | 2.30 LBS./SQFT.  |

| ROOF MOUNT SUMMARY         |               |       |
|----------------------------|---------------|-------|
| MAXIMUM (IN) MOUNT SPACING | RAIL OVERHANG |       |
| WIND ZONE 1                | 64 IN         | 16 IN |
| WIND ZONE 2                | 64 IN         | 16 IN |
| WIND ZONE 3                | 48 IN         | 16 IN |

| ROOF LOADING      |                  |
|-------------------|------------------|
| GROUND SNOW LOAD: | 15 LBS./SQFT.    |
| LIVE LOAD         | 20 LBS./SQFT.    |
| DEAD LOAD         |                  |
| ROOFING           | 3.9 LBS./SQFT.   |
| PV ARRAY          | 2.5 LBS./SQFT.   |
| TOTAL             | 6.4 LBS./SQFT.   |
| WIND LOAD:        |                  |
| UPLIFT ZONE 1     | -24.6 LBS./SQFT. |
| UPLIFT ZONE 2     | -29.0 LBS./SQFT. |
| UPLIFT ZONE 3     | -29.0 LBS./SQFT. |
| DOWNWARD          | 23.0 LBS./SQFT.  |
| FASTENER LOAD:    |                  |
| UPLIFT ZONE 1     | -368 LBS.        |
| UPLIFT ZONE 2     | -434 LBS.        |
| UPLIFT ZONE 3     | -325 LBS.        |
| DOWNWARD          | 344 LBS.         |

| ROOF MOUNT & FASTENER |                  |
|-----------------------|------------------|
| ROOF MOUNT:           |                  |
| MAKE                  | QUICKBOLT        |
| MODEL                 | 4 IN QB1         |
| MATERIAL              | STAINLESS / EPDM |
| FASTENER:             |                  |
| MAKE                  | QUICK SCREWS     |
| MODEL                 | HANGER BOLT      |
| MATERIAL              | 304 SS           |
| SIZE                  | 5/16-18 X 5-1/4" |
| GENERAL:              |                  |
| WEIGHT                | 0.56 LBS.        |
| FASTENERS PER MOUNT   | 1                |
| MAX. PULL-OUT FORCE   | 960.0 LBS.       |
| SAFETY FACTOR         | 2                |
| DESIGN PULL-OUT FORCE | 480.0 LBS.       |

| MOUNTING RAILS |              |
|----------------|--------------|
| MAKE           | IRONRIDGE    |
| MODEL          | XR10         |
| MATERIAL       | ALUMINUM     |
| WEIGHT         | 0.425 LBS/IN |
| SPACING        | 34 IN        |



**CLIENT INFO**  
COLLIN PEREGOY  
148 SALT MARKET CT  
DUNN NC 28334

**PROJECT INFO**  
DC INPUT: 15.725 kW  
AC OUTPUT: 11.500 kW  
DOI INSPT. METHOD: OPTION 2

**Model Energy**  
300 Fayetteville St.  
#1430  
Raleigh, NC 27602  
919-274-9905  
ModelEnergy.com  
P-1194



**CODE REFERENCES**  
NATION ELECTRICAL CODE v. 2017  
NC FIRE PROTECTION CODE v. 2018  
NC BUILDING CODE v. 2018  
NC RESIDENTIAL CODE v. 2018  
ACSE v. 7-10

**SITE CONDITIONS**  
WIND SPEED: 120 MPH  
RISK CATEGORY: II  
EXPOSURE: B  
SNOW: 10 PSF

**SHEET INDEX**  
PV-1: COVER SHEET  
PV-2: PV STRUCTURAL  
PV-3: PV ELECTRICAL  
PV-4: PV EQUIPMENT LABELS  
PV-5: PV INSTALL GUIDE


**VERSIONS**

| FOR:         | DESIGNER: | DATE:     |
|--------------|-----------|-----------|
| CONSTRUCTION | MCP       | 4/30/2024 |

**PV SYSTEM STRUCTURAL**

**PV-2.1**

© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.








**STATEMENT OF STRUCTURAL COMPLIANCE**


THE EXISTING ROOF STRUCTURE HAS BEEN DESIGNED TO SUPPORT THE ADDITIONAL LOADS OF THE PROPOSED PV SYSTEM. IN ADDITION, THE RACKING AND FASTENING SYSTEM SHALL BE CAPABLE OF SECURING THE SYSTEM TO THE STRUCTURE UNDER DESIGN CONDITIONS WHEN INSTALLED PROPERLY AND IN ACCORDANCE WITH THE RACKING AND FASTENING ARRANGEMENT DETAILED WITHIN THESE DRAWINGS.

NAME: ANDREW W. KING, PE

SIGNED:



**1 ROOF FASTENER DETAIL**  
NOT TO SCALE



**2 ROOF B ARRAY LAYOUT**  
1/8" = 1'-0"

| PV MODULES   |                      |
|--------------|----------------------|
| MAKE         | HANWHA               |
| MODEL        | Q.TRON BLK M-G2+ 425 |
| WIDTH        | 44.60 IN             |
| LENGTH       | 67.80 IN             |
| THICKNESS    | 30 MM                |
| WEIGHT       | 46.70 LBS.           |
| ARRAY AREA   | 210 SQFT.            |
| ARRAY WEIGHT | 525 LBS.             |

| ROOF SUMMARY   |                  |
|----------------|------------------|
| STRUCTURE:     | RAFTERS          |
| TYPE           | SOUTHERN PINE #2 |
| MATERIAL       | 2 X 8            |
| SIZE           | 16 IN O.C.       |
| SPACING        | 146 IN           |
| EFFECTIVE SPAN | 12/12            |
| PITCH          | 30 LBS./CU.FT.   |
| DENSITY        | OSB              |
| DECKING:       | COMPOSITE        |
| TYPE           | 7/16 IN          |
| MATERIAL       | 1.60 LBS/SQFT    |
| THICKNESS      | ASPHALT SHINGLE  |
| WEIGHT         | ASPHALT          |
| ROOFING:       | 2.30 LBS./SQFT.  |
| TYPE           |                  |
| MATERIAL       |                  |
| WEIGHT         |                  |

| ROOF MOUNT SUMMARY            |                       |
|-------------------------------|-----------------------|
| MAXIMUM (IN) MOUNT SPACING    | RAIL OVERHANG         |
| WIND ZONE 1   PORT 40 LAND 61 | PORT 16 IN LAND 24 IN |
| WIND ZONE 2   PORT 31 LAND 47 | PORT 12 IN LAND 19 IN |
| WIND ZONE 3   PORT 27 LAND 42 | PORT 11 IN LAND 16 IN |

| ROOF LOADING      |                     |
|-------------------|---------------------|
| GROUND SNOW LOAD: | 15 LBS./SQFT.       |
| LIVE LOAD         | 20 LBS./SQFT.       |
| DEAD LOAD         |                     |
| ROOFING           | 3.9 LBS./SQFT.      |
| PV ARRAY          | 2.5 LBS./SQFT.      |
| TOTAL             | 6.4 LBS./SQFT.      |
| WIND LOAD:        |                     |
| UPLIFT ZONE 1     | -24.6 LBS./SQFT.    |
| UPLIFT ZONE 2     | -29.0 LBS./SQFT.    |
| UPLIFT ZONE 3     | -29.0 LBS./SQFT.    |
| DOWNWARD          | 23.0 LBS./SQFT.     |
| FASTENER LOAD:    |                     |
| UPLIFT ZONE 1     | PORT -230 LAND -232 |
| UPLIFT ZONE 2     | PORT -210 LAND -210 |
| UPLIFT ZONE 3     | PORT -183 LAND -188 |
| DOWNWARD          | PORT 215 LAND 216   |

| ROOF MOUNT & FASTENER |                     |
|-----------------------|---------------------|
| ROOF MOUNT:           | QUICKBOLT           |
| MAKE                  | QB DECK MOUNT 16317 |
| MODEL                 | STAINLESS / EPDM    |
| MATERIAL              |                     |
| FASTENER:             | QUICK SCREWS        |
| MAKE                  | HEX LAG PN# 16318   |
| MODEL                 | 304 SS              |
| MATERIAL              | 5/16" X 1-3/4"      |
| SIZE                  |                     |
| GENERAL:              |                     |
| WEIGHT                | 0.88 LBS.           |
| FASTENERS PER MOUNT   | 4                   |
| MAX. PULL-OUT FORCE   | 705.0 LBS.          |
| SAFETY FACTOR         | 3                   |
| DESIGN PULL-OUT FORCE | 235.0 LBS.          |


| MOUNTING RAILS |              |
|----------------|--------------|
| MAKE           | IRONRIDGE    |
| MODEL          | XR10         |
| MATERIAL       | ALUMINUM     |
| WEIGHT         | 0.425 LBS/IN |
| SPACING        | 34 IN        |



**CLIENT INFO**  
COLLIN PEREGOY  
148 SALT MARKET CT  
DUNN NC 28334

**PROJECT INFO**  
DC INPUT: 15.725 kW  
AC OUTPUT: 11.500 kW  
DOI INSPT. METHOD: OPTION 2

**Model Energy**  
300 Fayetteville St.  
#1430  
Raleigh, NC 27602  
919-274-9905  
ModelEnergy.com  
P-1194



**CODE REFERENCES**  
NATION ELECTRICAL CODE v. 2017  
NC FIRE PROTECTION CODE v. 2018  
NC BUILDING CODE v. 2018  
NC RESIDENTIAL CODE v. 2018  
ACSE v. 7-10

**SITE CONDITIONS**  
WIND SPEED: 120 MPH  
RISK CATEGORY: II  
EXPOSURE: B  
SNOW: 10 PSF


**SHEET INDEX**  
PV-1: COVER SHEET  
PV-2: PV STRUCTURAL  
PV-3: PV ELECTRICAL  
PV-4: PV EQUIPMENT LABELS  
PV-5: PV INSTALL GUIDE

| VERSIONS     |          |           |
|--------------|----------|-----------|
| FOR:         | DESIGNER | DATE      |
| CONSTRUCTION | MCP      | 4/30/2024 |

**PV SYSTEM STRUCTURAL**

**PV-2.2**


© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.



### STATEMENT OF STRUCTURAL COMPLIANCE

THE EXISTING ROOF STRUCTURE HAS BEEN DESIGNED TO SUPPORT THE ADDITIONAL LOADS OF THE PROPOSED PV SYSTEM. IN ADDITION, THE RACKING AND FASTENING SYSTEM SHALL BE CAPABLE OF SECURING THE SYSTEM TO THE STRUCTURE UNDER DESIGN CONDITIONS WHEN INSTALLED PROPERLY AND IN ACCORDANCE WITH THE RACKING AND FASTENING ARRANGEMENT DETAILED WITHIN THESE DRAWINGS.

NAME: ANDREW W. KING, PE  
 SIGNED:



| PV MODULES   |                      |
|--------------|----------------------|
| MAKE         | HANWHA               |
| MODEL        | Q.TRON BLK M-G2+ 425 |
| WIDTH        | 44.60 IN             |
| LENGTH       | 67.80 IN             |
| THICKNESS    | 30 MM                |
| WEIGHT       | 46.70 LBS.           |
| ARRAY AREA   | 210 SQFT.            |
| ARRAY WEIGHT | 525 LBS.             |

| ROOF SUMMARY   |                  |
|----------------|------------------|
| STRUCTURE:     | RAFTERS          |
| TYPE           | SOUTHERN PINE #2 |
| MATERIAL       | 2 X 8            |
| SIZE           | 16 IN O.C.       |
| SPACING        | 146 IN           |
| EFFECTIVE SPAN | 12/12            |
| PITCH          | 30 LBS./CU.FT.   |
| DENSITY        | OSB              |
| DECKING:       | COMPOSITE        |
| TYPE           | 7/16 IN          |
| MATERIAL       | 1.60 LBS./SQFT   |
| THICKNESS      | ASPHALT SHINGLE  |
| WEIGHT         | ASPHALT          |
| ROOFING:       | 2.30 LBS./SQFT.  |
| TYPE           |                  |
| MATERIAL       |                  |
| WEIGHT         |                  |



**CLIENT INFO**  
 COLLIN PEREGOY  
 148 SALT MARKET CT  
 DUNN NC 28334

**PROJECT INFO**  
 DC INPUT: 15.725 kW  
 AC OUTPUT: 11.500 kW  
 DOI INSPT. METHOD: OPTION 2

**Model Energy**  
 300 Fayetteville St.  
 #1430  
 Raleigh, NC 27602  
 919-274-9905  
 ModelEnergy.com  
 P-1194



**CODE REFERENCES**  
 NATION ELECTRICAL CODE v. 2017  
 NC FIRE PROTECTION CODE v. 2018  
 NC BUILDING CODE v. 2018  
 NC RESIDENTIAL CODE v. 2018  
 ACSE v. 7-10

**SITE CONDITIONS**  
 WIND SPEED: 120 MPH  
 RISK CATEGORY: II  
 EXPOSURE: B  
 SNOW: 10 PSF

**SHEET INDEX**  
 PV-1: COVER SHEET  
 PV-2: PV STRUCTURAL  
 PV-3: PV ELECTRICAL  
 PV-4: PV EQUIPMENT LABELS  
 PV-5: PV INSTALL GUIDE

| VERSIONS     |          |           |
|--------------|----------|-----------|
| FOR:         | DESIGNER | DATE      |
| CONSTRUCTION | MCP      | 4/30/2024 |

**PV SYSTEM STRUCTURAL**


# PV-2.3

| ROOF MOUNT SUMMARY            |                       |
|-------------------------------|-----------------------|
| MAXIMUM (IN) MOUNT SPACING    | RAIL OVERHANG         |
| WIND ZONE 1   PORT 40 LAND 61 | PORT 16 IN LAND 24 IN |
| WIND ZONE 2   PORT 31 LAND 47 | PORT 12 IN LAND 19 IN |
| WIND ZONE 3   PORT 27 LAND 42 | PORT 11 IN LAND 16 IN |


| ROOF LOADING      |                     |
|-------------------|---------------------|
| GROUND SNOW LOAD: | 15 LBS./SQFT.       |
| LIVE LOAD         | 20 LBS./SQFT.       |
| DEAD LOAD         |                     |
| ROOFING           | 3.9 LBS./SQFT.      |
| PV ARRAY          | 2.5 LBS./SQFT.      |
| TOTAL             | 6.4 LBS./SQFT.      |
| WIND LOAD:        |                     |
| UPLIFT ZONE 1     | -24.6 LBS./SQFT.    |
| UPLIFT ZONE 2     | -29.0 LBS./SQFT.    |
| UPLIFT ZONE 3     | -29.0 LBS./SQFT.    |
| DOWNWARD          | 23.0 LBS./SQFT.     |
| FASTENER LOAD:    |                     |
| UPLIFT ZONE 1     | PORT -230 LAND -232 |
| UPLIFT ZONE 2     | PORT -210 LAND -210 |
| UPLIFT ZONE 3     | PORT -183 LAND -188 |
| DOWNWARD          | PORT 215 LAND 216   |

| ROOF MOUNT & FASTENER |                     |
|-----------------------|---------------------|
| ROOF MOUNT:           | QUICKBOLT           |
| MAKE                  | QB DECK MOUNT 16317 |
| MODEL                 | STAINLESS / EPDM    |
| MATERIAL              |                     |
| FASTENER:             | QUICK SCREWS        |
| MAKE                  | HEX LAG PN# 16318   |
| MODEL                 | 304 SS              |
| MATERIAL              | 5/16" X 1-3/4"      |
| SIZE                  |                     |
| GENERAL:              |                     |
| WEIGHT                | 0.88 LBS.           |
| FASTENERS PER MOUNT   | 4                   |
| MAX. PULL-OUT FORCE   | 705.0 LBS.          |
| SAFETY FACTOR         | 3                   |
| DESIGN PULL-OUT FORCE | 235.0 LBS.          |

| MOUNTING RAILS |              |
|----------------|--------------|
| MAKE           | IRONRIDGE    |
| MODEL          | XR10         |
| MATERIAL       | ALUMINUM     |
| WEIGHT         | 0.425 LBS/IN |
| SPACING        | 34 IN        |




**1 ROOF FASTENER DETAIL**  
 NOT TO SCALE



**2 ROOF C ARRAY LAYOUT**  
 1/8" = 1'-0"



© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.



### STATEMENT OF STRUCTURAL COMPLIANCE

THE EXISTING ROOF STRUCTURE HAS BEEN DESIGNED TO SUPPORT THE ADDITIONAL LOADS OF THE PROPOSED PV SYSTEM. IN ADDITION, THE RACKING AND FASTENING SYSTEM SHALL BE CAPABLE OF SECURING THE SYSTEM TO THE STRUCTURE UNDER DESIGN CONDITIONS WHEN INSTALLED PROPERLY AND IN ACCORDANCE WITH THE RACKING AND FASTENING ARRANGEMENT DETAILED WITHIN THESE DRAWINGS.

NAME: ANDREW W. KING, PE  
 SIGNED: *Andrew W. King*

| PV MODULES   |                      |
|--------------|----------------------|
| MAKE         | HANWHA               |
| MODEL        | Q.TRON BLK M-G2+ 425 |
| WIDTH        | 44.60 IN             |
| LENGTH       | 67.80 IN             |
| THICKNESS    | 30 MM                |
| WEIGHT       | 46.70 LBS.           |
| ARRAY AREA   | 126 SQFT.            |
| ARRAY WEIGHT | 315 LBS.             |






| ROOF SUMMARY   |                  |
|----------------|------------------|
| STRUCTURE:     |                  |
| TYPE           | RAFTERS          |
| MATERIAL       | SOUTHERN PINE #2 |
| SIZE           | 2 X 8            |
| SPACING        | 16 IN O.C.       |
| EFFECTIVE SPAN | 198 IN           |
| PITCH          | 4/12             |
| DENSITY        | 30 LBS./CU.FT.   |
| DECKING:       |                  |
| TYPE           | OSB              |
| MATERIAL       | COMPOSITE        |
| THICKNESS      | 7/16 IN          |
| WEIGHT         | 1.60 LBS/SQFT    |
| ROOFING:       |                  |
| TYPE           | ASPHALT SHINGLE  |
| MATERIAL       | ASPHALT          |
| WEIGHT         | 2.30 LBS./SQFT.  |



**CLIENT INFO**  
 COLLIN PEREGOY  
 148 SALT MARKET CT  
 DUNN NC 28334

**PROJECT INFO**  
 DC INPUT: 15.725 kW  
 AC OUTPUT: 11.500 kW  
 DOI INSPT. METHOD: OPTION 2

**Model Energy**  
 300 Fayetteville St.  
 #1430  
 Raleigh, NC 27602  
 919-274-9905  
 ModelEnergy.com  
 P-1194



| ROOF MOUNT SUMMARY         |               |       |
|----------------------------|---------------|-------|
| MAXIMUM (IN) MOUNT SPACING | RAIL OVERHANG |       |
| WIND ZONE 1                | 64 IN         | 16 IN |
| WIND ZONE 2                | 48 IN         | 16 IN |
| WIND ZONE 3                | 16 IN         | 11 IN |

| ROOF LOADING      |                  |
|-------------------|------------------|
| GROUND SNOW LOAD: | 15 LBS./SQFT.    |
| LIVE LOAD         | 20 LBS./SQFT.    |
| DEAD LOAD         |                  |
| ROOFING           | 3.9 LBS./SQFT.   |
| PV ARRAY          | 2.5 LBS./SQFT.   |
| TOTAL             | 6.4 LBS./SQFT.   |
| WIND LOAD:        |                  |
| UPLIFT ZONE 1     | -23.0 LBS./SQFT. |
| UPLIFT ZONE 2     | -38.0 LBS./SQFT. |
| UPLIFT ZONE 3     | -57.1 LBS./SQFT. |
| DOWNWARD          | 13.6 LBS./SQFT.  |
| FASTENER LOAD:    |                  |
| UPLIFT ZONE 1     | -344 LBS.        |
| UPLIFT ZONE 2     | -426 LBS.        |
| UPLIFT ZONE 3     | -214 LBS.        |
| DOWNWARD          | 203 LBS.         |

**CODE REFERENCES**  
 NATION ELECTRICAL CODE v. 2017  
 NC FIRE PROTECTION CODE v. 2018  
 NC BUILDING CODE v. 2018  
 NC RESIDENTIAL CODE v. 2018  
 ACSE v. 7-10

**SITE CONDITIONS**  
 WIND SPEED: 120 MPH  
 RISK CATEGORY: II  
 EXPOSURE: B  
 SNOW: 10 PSF


**SHEET INDEX**  
 PV-1: COVER SHEET  
 PV-2: PV STRUCTURAL  
 PV-3: PV ELECTRICAL  
 PV-4: PV EQUIPMENT LABELS  
 PV-5: PV INSTALL GUIDE

| VERSIONS     |          |           |
|--------------|----------|-----------|
| FOR:         | DESIGNER | DATE      |
| CONSTRUCTION | MCP      | 4/30/2024 |

**PV SYSTEM STRUCTURAL**

**PV-2.4**

**1 ROOF FASTENER DETAIL**  
 NOT TO SCALE



**2 ROOF D ARRAY LAYOUT**  
 1/8" = 1'-0"

| ROOF MOUNT & FASTENER |                  |
|-----------------------|------------------|
| ROOF MOUNT:           |                  |
| MAKE                  | QUICKBOLT        |
| MODEL                 | 4 IN QB1         |
| MATERIAL              | STAINLESS / EPDM |
| FASTENER:             |                  |
| MAKE                  | QUICK SCREWS     |
| MODEL                 | HANGER BOLT      |
| MATERIAL              | 304 SS           |
| SIZE                  | 5/16-18 X 5-1/4" |
| GENERAL:              |                  |
| WEIGHT                | 0.56 LBS.        |
| FASTENERS PER MOUNT   | 1                |
| MAX. PULL-OUT FORCE   | 960.0 LBS.       |
| SAFETY FACTOR         | 2                |
| DESIGN PULL-OUT FORCE | 480.0 LBS.       |

| MOUNTING RAILS |              |
|----------------|--------------|
| MAKE           | IRONRIDGE    |
| MODEL          | XR10         |
| MATERIAL       | ALUMINUM     |
| WEIGHT         | 0.425 LBS/IN |
| SPACING        | 34 IN        |



© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.

### CONDUCTOR SCHEDULE

| TAG | CURRENT CARRYING CONDUCTORS |                  |            | GROUNDING CONDUCTORS |        |            | CONDUIT/RACEWAY |      |          | NOTES |
|-----|-----------------------------|------------------|------------|----------------------|--------|------------|-----------------|------|----------|-------|
|     | QTY.                        | SIZE             | INSULATION | QTY.                 | SIZE   | INSULATION | QTY.            | SIZE | LOCATION |       |
| C1  | 8                           | 10 AWG           | PV WIRE    | 1                    | 6 AWG  | BARE       | -               | -    | FREE AIR | 1     |
| C2  | 8                           | 10 AWG           | THWN-2     | 1                    | 10 AWG | THWN-2     | 2               | 3/4" | EXT/INT  | 2,4   |
| C3  | 3                           | 6 AWG            | THWN-2     | 1                    | 10 AWG | THWN-2     | 1               | 1"   | EXTERIOR | 2,4   |
| C4  | 3                           | 4/0 AWG ALUMINUM | XHHW       | 1                    | 6 AWG  | THWN-2     | 1               | 2"   | EXTERIOR | 2,4   |
| C5  | 3                           | 4/0 AWG ALUMINUM | XHHW       | -                    | -      | -          | 1               | 2"   | EXTERIOR | 2,4   |
| XC  | -                           | -                | -          | -                    | -      | -          | -               | -    | -        | 3     |

**NOTES:**

- MANUFACTURER PROVIDED, UL LISTED WIRING HARNESS FOR USE ON EXPOSED ROOFS
- CONDUIT SIZE SHOWN IS CODE MINIMUM. LARGER SIZES ARE ALLOWED.
- EXISTING CONDUCTORS, FIELD VERIFY
- EQUIPMENT TERMINAL RATING SHALL BE A MINIMUM OF 75°C AT BOTH END OF CONDUCTOR

### ENERGY MANAGEMENT

| MAKE                | TESLA            |
|---------------------|------------------|
| MODEL               | BACKUP GATEWAY 2 |
| ENCL. RATING        | NEMA 3R          |
| VOLT. RATING        | 240 VOLTS        |
| DISCONNECT CURR.    | 200 AMPS         |
| UL LIST. (Y/N)      | YES              |
| MAIN BREAKER (Y/N)  | YES              |
| MAIN BREAKER RATING | 200 AMPS         |

- TROUGH MAY BE USED IF NECESSARY
- INSTALL 200A EATON MAIN BREAKER THAT WILL SERVE AS THE NEW SERVICE DISCONNECT SWITCH
- INSTALL INTERNAL PANELBOARD KIT TO LAND POWERWALL 3
- INSTALL BONDING JUMPER FROM NEUTRAL TO GROUND
- FEED BACKED-UP LOADS PANEL VIA BACKUP LUGS

### PV MODULE

| MAKE               | HANWHA               |
|--------------------|----------------------|
| MODEL              | Q.TRON BLK M-G2+ 425 |
| NOM. POWER (PNOM)  | 425 WATTS            |
| NOM. VOLT. (VMPP)  | 32.7 VOLTS           |
| O.C. VOLT (VOC)    | 39.0 VOLTS           |
| MAX. SYS. VOLT.    | 1000 VOLTS           |
| NOM. CURR. (IMPP)  | 13.0 AMPS            |
| S.C. CURR. (ISC)   | 13.7 AMPS            |
| TEMP. COEF. (PMPP) | -0.30 %/C            |
| TEMP. COEF. (Voc)  | -0.24 %/C            |
| MAX SERIES FUSE    | 25 AMPS              |
| UL COMPLIANT (Y/N) | YES                  |

### MAX. DC VOLTAGE CALCULATION

$$V_{OC}MAX = V_{OC} * (1 + (T_{MIN} - T_{STC}) * (VTC / 100))$$

|                    |       |
|--------------------|-------|
| $V_{OC}MAX$        | 42.17 |
| MAX STRING VOLTAGE | 463.8 |

### MIN. DC VOLTAGE CALCULATION

$$V_{MP}MIN. = V_{MP} * (1 + ((T_{max} + T_{add} - T_{STC}) * (TK_{VMP} / 100)))$$

|              |       |
|--------------|-------|
| $V_{MP}MIN.$ | 28.05 |
|--------------|-------|

### MAX. DC CURRENT CALCULATION

$$I_{SC}MAX = I_{SC} * TCX$$

|                    |       |
|--------------------|-------|
| $I_{SC}MAX$ (AMPS) | 17.13 |
|--------------------|-------|

### MAX. PV STRING CALCULATION

MAX. MODULES PER STRING = INVERTER  $V_{MAX} / V_{OC}MAX$

MAX. MODULES/STRING 12

### MIN. PV STRING CALCULATION

MIN. MODULES PER STRING = INVERTER  $V_{MIN} / V_{MP}MIN.$

MIN. MODULES/STRING 5

### UTILITY METER

| MAKE           | MILBANK             |
|----------------|---------------------|
| MODEL          | OUTD-LAN UAT417-XGF |
| ENCL. RATING   | NEMA 3R             |
| VOLT. RATING   | 240 VOLTS           |
| AMP RATING     | 200 AMPS            |
| UL LIST. (Y/N) | YES                 |

- REMOVE EXISTING METER COMBO PANEL AND REPLACE WITH METER BASE THAT FEEDS ENERGY MANAGEMENT

### MID-CIRCUIT INTERRUPTER

| MAKE                   | TESLA          |
|------------------------|----------------|
| MODEL                  | MCI-1          |
| ENCL. RATING           | NEMA 4X / IP65 |
| DC INPUT:              |                |
| CONNECTOR TYPE         | MC4            |
| MAX IN-LINE PV MODULES | 3              |
| MAX MCI PER STRING     | 5              |
| MAX. SYSTEM VOLTAGE    | 600 VOLTS      |
| NOM. CURRENT (Imp)     | 13.00 AMPS     |
| MAX. CURRENT (Isc)     | 19.00 AMPS     |
| RSD COMPLIANT (Y/N)    | YES            |
| UL COMPLIANT (Y/N)     | YES            |

### JUNCTION BOX

| MAKE            | SOLADECK     |
|-----------------|--------------|
| PROTECT. RATING | NEMA TYPE 3R |
| UL LIST. (Y/N)  | YES          |

### BACKED-UP LOADS PANEL

| MAKE                | GENERIC  |
|---------------------|----------|
| MODEL               | N/A      |
| ENCL. RATING        | NEMA 3R  |
| VOLT. RATING        | 240      |
| BUS RATING          | 200 AMPS |
| UL LIST. (Y/N)      | YES      |
| MAIN BREAKER (Y/N)  | YES      |
| MAIN BREAKER RATING | 200 AMPS |

- RE-FEED BACKED-UP LOADS PANEL VIA GATEWAY OUTPUTS


### DC/AC INVERTER & BATTERY

| MAKE                 | TESLA POWERWALL 3 |
|----------------------|-------------------|
| MODEL                | 1707000-XX-Y      |
| INVERTER INFO:       |                   |
| DC INPUT:            |                   |
| MAX POWER            | 20000 WATTS       |
| INPUT VOLT. RANGE    | 60-550 VOLTS      |
| MPPT VOLT. RANGE     | 150-480 VOLTS     |
| MAX. MPPT CUR.       | 13 AMPS           |
| STRING INPUTS        | 6 MPPTs           |
| AC OUTPUT:           |                   |
| MAX. CONT. POWER     | 11500 WATTS       |
| NOM. VOLT.           | 240 VOLTS         |
| MAX. CONT. CURRENT   | 48.00 AMPS        |
| RAPID SHUTDOWN (Y/N) | YES               |
| PROTECT. RATING      | NEMA TYPE 3R      |
| BATTERY INFO:        |                   |
| USABLE ENERGY        | 13.5 kWh          |
| NOM. VOLT.           | 240 VOLTS         |
| MAX. CONT. CHARGE    | 5000 WATTS        |
| UL LIST. (Y/N)       | YES               |

### AC DISCONNECT

| MAKE           | GENERIC   |
|----------------|-----------|
| MODEL          | NA        |
| ENCL. RATING   | NEMA 3R   |
| VOLT. RATING   | 240 VOLTS |
| AMP RATING     | 60 AMPS   |
| UL LIST. (Y/N) | YES       |
| FUSED (Y/N)    | NO        |
| FUSE RATING    | N/A       |

- LOAD-BREAK RATED
- VISIBLE OPEN
- LOCKABLE IN OPEN POSITION
- INSTALL ADJACENT TO METER
- DISCONNECT TO BE READILY ACCESSIBLE TO UTILITY COMPANY PERSONNEL AT ALL TIMES
- DISCONNECT MARKED AND RATED PER NEC SECTION 690.13 AND 705.10



1 ELECTRICAL SCHEMATIC  
NTS



### CLIENT INFO

COLLIN PEREGOY  
148 SALT MARKET CT  
DUNN NC 28334

### PROJECT INFO

DC INPUT: 15.725 kW  
AC OUTPUT: 11.500 kW  
DOI INSP. METHOD: OPTION 2

### Model Energy

300 Fayetteville St.  
#1430  
Raleigh, NC 27602  
919-274-9905  
ModelEnergy.com



### CODE REFERENCES

NATION ELECTRICAL CODE v. 2017  
NC FIRE PROTECTION CODE v. 2018  
NC BUILDING CODE v. 2018  
NC RESIDENTIAL CODE v. 2018  
ACSE v. 7-10

### SITE CONDITIONS

WIND SPEED: 120 MPH  
RISK CATEGORY: II  
EXPOSURE: B  
SNOW: 10 PSF

### SHEET INDEX

PV-1: COVER SHEET  
PV-2: PV STRUCTURAL  
PV-3: PV ELECTRICAL  
PV-4: PV EQUIPMENT LABELS  
PV-5: PV INSTALL GUIDE

### VERSIONS

| FOR:         | DESIGNER | DATE      |
|--------------|----------|-----------|
| CONSTRUCTION | MCP      | 4/30/2024 |

### PV SYSTEM ELECTRICAL

# PV-3.1



© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.

**⚠ WARNING**  
THIS EQUIPMENT FED BY MULTIPLE SOURCES. TOTAL RATING OF ALL OVERCURRENT DEVICES EXCLUDING MAIN SUPPLY OVERCURRENT DEVICE SHALL NOT EXCEED AMPACITY OF BUSBAR.  
NEC 705.12 (B)(2)(3)(c)

**RAPID SHUTDOWN SWITCH FOR SOLAR PV SYSTEM**

**PV SYSTEM DISCONNECT**

**⚠ WARNING**  
ELECTRIC SHOCK HAZARD  
TERMINALS ON THE LINE AND LOAD SIDES MAY BE ENERGIZED IN THE OPEN POSITION  
NEC 690.13 (B)

**WARNING: PHOTOVOLTAIC POWER SOURCE**

**⚠ WARNING**  
**THREE POWER SOURCES**  
SOURCES: UTILITY GRID, BATTERY AND PV SOLAR ELECTRIC SYSTEM

**SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN**  
TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUT DOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN THE ARRAY

**PHOTOVOLTAIC SYSTEM AC DISCONNECT**  
OPERATING VOLTAGE 240 VOLTS  
OPERATING CURRENT 48.0 AMPS

**WARNING:**  
IN THE EVENT OF A UTILITY OUTAGE, THIS PANEL IS FED FROM ENERGY STORAGE SYSTEM.

**DIRECT CURRENT PHOTOVOLTAIC POWER SOURCE**  
MAXIMUM VOLTAGE 600 VDC  
MAX CIRCUIT CURRENT 68.52 AMPS

SERVICE DISCONNECT LOCATED:  
WEST WALL OF RESIDENCE  
BATTERY DISCONNECT LOCATED:  
WEST WALL OF RESIDENCE  
PV DISCONNECT LOCATED:  
WEST WALL OF RESIDENCE

1  
2  
6  
NEC 705.12(B)(3)  
PLACE ON ALL EQUIPMENT THAT IS SUPPLIED BY THREE POWER SOURCES

2  
NEC 690.56 (C)(1)(a)  
PLACE WITHIN 3FT OF SERVICE DISCONNECTING MEANS TO WHICH THE PV SYSTEMS ARE CONNECTED AND SHALL INDICATE THE LOCATIONS OF RAPID SHUTDOWN SWITCHES

3  
NEC 690.13 (B)  
PLACE ON PV SYSTEM DISCONNECTING MEANS.

3  
NEC 690.54  
PLACE ON INTERCONNECTION DISCONNECTING MEANS

2  
6  
PLACE ON BACKED UP LOAD PANEL(S).

2  
NEC 690.13 (B)  
PLACE ON PV SYSTEM DISCONNECTING MEANS.

4  
NEC 690.53  
PLACE ON ALL DC DISCONNECTING MEANS

5  
NEC 690.31 (G)(3)&(4)  
PLACE ON ALL JUNCTION BOXES, EXPOSED RACEWAYS, AND OTHER WIRING METHODS EVERY 10' AND ON EVERY SECTION SEPARATED BY ENCLOSURES, WALLS, PARTITIONS, CEILINGS, OR FLOORS.

2 3  
NEC 705.10  
PLACE AT SERVICE EQUIPMENT AND PV SYSTEM DISCONNECTING MEANS.

**LABEL NOTES**

1. LABELS SHOWN ARE HALF THEIR ACTUAL REQUIRED SIZE.
2. LABEL MATERIAL SHALL BE SUITABLE FOR THE EQUIPMENT ENVIRONMENT.
3. DC CONDUIT SHALL BE MARKED WITH REQUIRED LABEL EVERY 10 FEET.
4. LABELS WILL BE APPLIED IN ACCORDANCE WITH THE NEC. SOME LABELS MAY NOT BE NECESSARY.

**DC WIRING NOTES**

1. CONDUCTORS SHALL BE COPPER, RATED AT NOT LESS THAN 600 VOLTS FOR RESIDENTIAL CONSTRUCTION AND NOT LESS THAN 1000 VOLTS FOR COMMERCIAL CONSTRUCTION.
2. MINIMUM SIZE SHALL BE #10 AWG UNLESS OTHERWISE NOTED ON THE DRAWINGS.
3. EXPOSED WIRING CONDUCTOR INSULATION SHALL BE TYPE PV WIRE, USE-2, OR RHW-2 WHERE THE OUTER LAYER OF THE INSULATION IS UV, SUNLIGHT, AND MOISTURE RESISTANT.
6. EXTERIOR WIRING CONDUCTOR INSULATION SHALL BE TYPE THWN-2 AND INSTALLED IN ELECTRICAL METALLIC TUBING(EMT) OR RIGID POLYVINYL CHLORIDE CONDUIT(PVC). ALTERNATIVELY, METAL CLAD CABLE(MC) CAN BE USED AS WELL WHEN RATED FOR USE IN WET LOCATIONS.
7. INTERIOR WIRING CONDUCTOR INSULATION SHALL BE TYPE THHN-2 AND INSTALLED IN ELECTRICAL METALLIC TUBING(EMT), FLEXIBLE METAL CONDUIT(FMC), OR METAL CLAD CABLE(MC).
6. USE SCHEDULE 40 PVC OUTDOORS WHERE NOT SUBJECT TO PHYSICAL DAMAGE OR BELOW FLOOR SLAB. USE SCHEDULE 80 PVC OUTDOORS WHERE SUBJECT TO PHYSICAL DAMMAGE
7. MINIMUM CONDUIT SIZE TO BE 1/2".
8. WIRING METHODS TO CONFORM TO ARTICLES 330, 334, 348, 350, 352, 356, AND 358 OF THE 2017 NEC.

**AC WIRING NOTES**

1. CONDUCTORS SHALL BE COPPER RATED AT NOT LESS THAN 600 VOLTS.
2. MINIMUM SIZE SHALL BE #14 AWG UNLESS OTHERWISE NOTED ON THE DRAWINGS.
3. EXTERIOR WIRING CONDUCTOR INSULATION SHALL BE TYPE THWN AND INSTALLED IN ELECTRICAL METALLIC TUBING(EMT), RIGID POLYVINYL CHLORIDE CONDUIT(PVC), LIQUID-TIGHT FLEXIBLE METAL CONDUIT(LFMC), OR LIQUID-TIGHT FLEXIBLE NON-METALLIC CONDUIT(LFNC) . ALTERNATIVELY, METAL CLAD CABLE(MC) CAN BE USED AS WELL WHEN RATED FOR USE IN WET LOCATIONS.
4. INTERIOR WIRING CONDUCTOR INSULATION SHALL BE TYPE THHN AND INSTALLED IN ELECTRICAL METALLIC TUBING(EMT), FLEXIBLE METAL CONDUIT(FMC), METAL CLAD CABLE(MC), OR ROMEX.
5. USE SCHEDULE 40 PVC OUTDOORS WHERE NOT SUBJECT TO PHYSICAL DAMAGE OR BELOW FLOOR SLAB. USE SCHEDULE 80 PVC OUTDOORS WHERE SUBJECT TO PHYSICAL DAMMAGE
6. MINIMUM CONDUIT SIZE TO BE 1/2".
7. WIRING METHODS TO CONFORM TO ARTICLES 330, 334, 348, 350, 352, 356, AND 358 OF THE 2017 NEC.

**CONSTRUCTION NOTES**

1. ALL WORK IS TO BE PERFORMED IN ACCORDANCE WITH THE NEC, STATE, AND LOCAL APPLICABLE CODES.
2. FOLLOW MANUFACTURER'S INSTALLATION INSTRUCTIONS, BEST PRACTICES, AND SPECIFICATIONS.
3. ENSURE REQUIRED MAINTENANCE ACCESS AND CLEARANCES ARE MAINTAINED.
4. WIRES SHALL BE RATED AND LABELED "SUNLIGHT RESISTANT" WHERE EXPOSED TO AMBIENT CONDITIONS.
5. FUSES 0 - 600 AMPS SHALL BE UL CLASS "RK-1" LOW PEAK DUAL ELEMENT TIME DELAY WITH 200,000 AMPERE INTERRUPTING RATING AS MANUFACTURED BY BUSSMANN, UNLESS NOTED OTHERWISE.
6. ALL TERMINALS/LUGS SHALL BE 75° RATED. ALL TERMINALS, SPlicing CONNECTORS, LUGS, ETC SHALL BE IDENTIFIED FOR USE WITH THE MATERIAL (CU/AL) OF THE CONDUCTOR AND SHALL BE PROPERLY INSTALLED.
7. PROVIDE A PULLWIRE IN ALL EMPTY CONDUITS.
8. ALL PENETRATIONS THROUGH EXTERIOR ROOFS SHALL BE FLASHED IN A WATERPROOF MANNER.
9. ALL PENETRATIONS THROUGH ATTIC FIRE BARRIERS SHALL BE SEALED WITH FIRE-BARRIER SEALANT CAULK.
10. SUPPORT ALL CONDUIT AND EQUIPMENT IN ACCORDANCE W/ NEC. ANY SUSPENDED MATERIALS SHALL BE DIRECTLY SUPPORTED BY THE BUILDING STRUCTURE.
11. METAL CONDUIT COUPLINGS CAN BE COMPRESSION TYPE, THREADED, OR BE SET-SCREW TYPE. PLASTIC CONDUIT COUPLINGS TO BE SOCKET GLUED TYPE.
12. A COMPLETE GROUNDING SYSTEM SHALL BE PRESENT OR PROVIDED AND INSTALLED IN ACCORDANCE WITH ARTICLE 250 OF THE NEC, AND AS SHOWN ON THE DRAWINGS.
13. EACH ELECTRICAL APPLIANCE SHALL BE PROVIDED WITH A NAMEPLATE GIVING THE IDENTIFYING NAME AND THE RATING IN VOLTS AND AMPERES, OR VOLTS AND WATTS. IF THE APPLIANCE IS TO BE USED ON A SPECIFIC FREQUENCY OR FREQUENCIES, IT SHALL BE SO MARKED. WHERE MOTOR OVERLOAD PROTECTION EXTERNAL TO THE APPLIANCES IS REQUIRED, THE APPLIANCE SHALL BE SO MARKED.
14. WHERE APPLICABLE, GROUNDING ELECTRODE CONDUCTOR TO BE CONTINUOUS. GROUNDING CRIMPS TO BE IRREVERSIBLE.
15. PHOTOVOLTAIC SYSTEMS SHALL BE PERMANENTLY MARKED AT VARIOUS EQUIPMENT LOCATIONS TO IDENTIFY THAT A PHOTOVOLTAIC SYSTEM IS INSTALLED AND THAT VARIOUS DANGERS ARE PRESENT.
16. EACH PHOTOVOLTAIC SYSTEM DISCONNECTING MEANS SHALL BE PERMANENTLY MARKED TO IDENTIFY IT AS A PHOTOVOLTAIC SYSTEM DISCONNECT.
17. WHERE ALL TERMINALS OF A DISCONNECTING MEANS MAY BE ENERGIZED IN THE OPEN POSITION, A WARNING SIGN SHALL BE MOUNTED ON OR ADJACENT TO THE DISCONNECT.
18. A PERMANENT LABEL FOR THE DIRECT-CURRENT PHOTOVOLTAIC POWER SOURCE SHALL BE PROVIDED AT THE DC DISCONNECT MEANS.
19. A PERMANENT PLAQUE OR DIRECTORY, DENOTING ALL ELECTRIC POWER SOURCES SERVING THE PREMISES, SHALL BE INSTALLED AT EACH SERVICE EQUIPMENT LOCATION AND AT LOCATIONS OF ALL POWER PRODUCTION SOURCES.
20. ALL MODULE GROUND CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH NEC SECTION 690.4 (C).
21. A NORTH CAROLINA REGISTERED DESIGN PROFESSIONAL WILL BE REQUIRED TO SEAL THE STRUCTURAL DESIGN AT THE TIME OF PERMIT APPLICATION IF ANY OF THE FOLLOWING EXIST AND ARE ATTESTED TO BY THE APPLICANT:
  - I. THE WEIGHT OF THE PV SYSTEM EXCEEDS THREE (3) POUNDS PER SQUARE FOOT(PSF)
  - II. THE ROOF POSSESSES MORE THAN ONE (1) LAYER OF ASPHALT SHINGLES
  - III. THE ROOFING MATERIAL CONSISTS OF A TYPE OTHER THAN ASPHALT SHINGLES OR METAL
  - IV. THE ROOF IS LOCATED IN A 140 MPH OR GREATER WIND ZONE



**CLIENT INFO**  
COLLIN PEREGOY  
148 SALT MARKET CT  
DUNN NC 28334

**PROJECT INFO**  
DC INPUT: 15.725 kW  
AC OUTPUT: 11.500 kW  
DOI INSP. METHOD: OPTION 2

**Model Energy**  
300 Fayetteville St.  
#1430  
Raleigh, NC 27602  
919-274-9905  
ModelEnergy.com  
P-1194



**CODE REFERENCES**  
NATION ELECTRICAL CODE v. 2017  
NC FIRE PROTECTION CODE v. 2018  
NC BUILDING CODE v. 2018  
NC RESIDENTIAL CODE v. 2018  
ACSE v. 7-10

**SITE CONDITIONS**  
WIND SPEED: 120 MPH  
RISK CATEGORY: II  
EXPOSURE: B  
SNOW: 10 PSF

**SHEET INDEX**  
PV-1: COVER SHEET  
PV-2: PV STRUCTURAL  
PV-3: PV ELECTRICAL  
PV-4: PV EQUIPMENT LABELS  
PV-5: PV INSTALL GUIDE

**VERSIONS**


| FOR:         | DESIGNER | DATE      |
|--------------|----------|-----------|
| CONSTRUCTION | MCP      | 4/30/2024 |

**PV SYSTEM EQUIPMENT LABELS**


**PV-4.1**



© 2024 NC SOLAR NOW EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO ANY THIRD PARTY WITHOUT FIRST OBTAINING THE EXPRESSED WRITTEN PERMISSION AND CONSENT OF NC SOLAR NOW.



1 ARRAY LAYOUT DETAIL  
NOT TO SCALE



1 STRING WIRING + MCI DETAIL  
NOT TO SCALE



CLIENT INFO

COLLIN PEREGOY  
148 SALT MARKET CT  
DUNN NC 28334

PROJECT INFO

DC INPUT: 15.725 kW  
AC OUTPUT: 11.500 kW  
DOI INSPT. METHOD: OPTION 2

Model Energy

300 Fayetteville St.  
#1430  
Raleigh, NC 27602  
919-274-9905  
ModelEnergy.com  
P-1194



CODE REFERENCES

NATION ELECTRICAL CODE v. 2017  
NC FIRE PROTECTION CODE v. 2018  
NC BUILDING CODE v. 2018  
NC RESIDENTIAL CODE v. 2018  
ACSE v. 7-10

SITE CONDITIONS

WIND SPEED: 120 MPH  
RISK CATEGORY: II  
EXPOSURE: B  
SNOW: 10 PSF

SHEET INDEX

PV-1: COVER SHEET  
PV-2: PV STRUCTURAL  
PV-3: PV ELECTRICAL  
PV-4: PV EQUIPMENT LABELS  
PV-5: PV INSTALL GUIDE

VERSIONS

| FOR:         | DESIGNER | DATE      |
|--------------|----------|-----------|
| CONSTRUCTION | MCP      | 4/30/2024 |

PV SYSTEM INSTALL GUIDE

PV-5.1



# Q.TRON BLK M-G2+ SERIES



PRELIMINARY

410 - 430 Wp | 108 Cells  
22.4% Maximum Module Efficiency

MODEL Q.TRON BLK M-G2+



## High performance Qcells N-type solar cells

Q.ANTUM NEO Technology with optimized module layout boosts module efficiency up to 22.4%.



## A reliable investment

Inclusive 25-year product warranty and 25-year linear performance warranty<sup>1</sup>.



## Enduring high performance

Long-term yield security with Anti LeTID Technology, Anti PID Technology<sup>2</sup>, Hot-Spot Protect.



## Extreme weather rating

High-tech aluminium alloy frame, certified for high snow (5400 Pa) and wind loads (3600 Pa).



## Innovative all-weather technology

Optimal yields, whatever the weather with excellent low-light and temperature behaviour.



## The most thorough testing programme in the industry

Qcells is the first solar module manufacturer to pass the most comprehensive quality programme in the industry: The new "Quality Controlled PV" of the independent certification institute TÜV Rheinland.

<sup>1</sup> See data sheet on rear for further information.

<sup>2</sup> APT test conditions according to IEC/TS 62804-1:2015, method A (-1500 V, 96 h)

### The ideal solution for:



Rooftop arrays on residential buildings






# Q.TRON BLK M-G2+ SERIES

## Mechanical Specification

|              |  |
|--------------|--|
| Format       | 67.8 in × 44.6 in × 1.18 in (including frame)<br>(1722 mm × 1134 mm × 30 mm)   |
| Weight       | 47.2 lbs (21.4 kg)   |
| Front Cover  | 0.13 in (3.2 mm) thermally pre-stressed glass with anti-reflection technology  |
| Back Cover   | Composite film   |
| Frame        | Black anodised aluminium   |
| Cell         | 6 × 18 monocrystalline Q.ANTUM NEO solar half cells  |
| Junction box | 2.09-3.98 in × 1.26-2.36 in × 0.59-0.71 in<br>(53-101 mm × 32-60 mm × 15-18 mm), Protection class IP67, with bypass diodes |
| Cable        | 4 mm <sup>2</sup> Solar cable; (+) ≥ 59.4 in (1510 mm), (-) ≥ 59.4 in (1510 mm)  |
| Connector    | Stäubli MC4; IP68  |




## Electrical Characteristics

| POWER CLASS   |                                    |               | 410    | 415    | 420    | 425    | 430    |
|---|------------------------------------|---------------|--------|--------|--------|--------|--------|
| MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC <sup>1</sup> (POWER TOLERANCE +5W/-0W) |                                    |               |        |        |        |        |        |
| Minimum   | Power at MPP <sup>1</sup>          | $P_{MPP}$ [W] | 410    | 415    | 420    | 425    | 430    |
|   | Short Circuit Current <sup>1</sup> | $I_{SC}$ [A]  | 13.39  | 13.42  | 13.46  | 13.49  | 13.53  |
|   | Open Circuit Voltage <sup>1</sup>  | $V_{OC}$ [V]  | 38.58  | 38.61  | 38.64  | 38.67  | 38.70  |
|   | Current at MPP                     | $I_{MPP}$ [A] | 12.68  | 12.75  | 12.82  | 12.88  | 12.95  |
|   | Voltage at MPP                     | $V_{MPP}$ [V] | 32.32  | 32.55  | 32.77  | 32.98  | 33.20  |
|   | Efficiency <sup>1</sup>            | $\eta$ [%]    | ≥ 21.4 | ≥ 21.6 | ≥ 21.9 | ≥ 22.2 | ≥ 22.4 |
| MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT <sup>2</sup>                       |                                    |               |        |        |        |        |        |
| Minimum   | Power at MPP                       | $P_{MPP}$ [W] | 310.0  | 313.8  | 317.6  | 321.4  | 325.2  |
|   | Short Circuit Current              | $I_{SC}$ [A]  | 10.79  | 10.82  | 10.84  | 10.87  | 10.90  |
|   | Open Circuit Voltage               | $V_{OC}$ [V]  | 36.61  | 36.63  | 36.66  | 36.69  | 36.71  |
|   | Current at MPP                     | $I_{MPP}$ [A] | 9.97   | 10.03  | 10.09  | 10.15  | 10.21  |
|   | Voltage at MPP                     | $V_{MPP}$ [V] | 31.09  | 31.29  | 31.48  | 31.66  | 31.85  |

<sup>1</sup>Measurement tolerances  $P_{MPP} \pm 3\%$ ;  $I_{SC}$ ;  $V_{OC} \pm 5\%$  at STC: 1000 W/m<sup>2</sup>, 25 ± 2°C, AM 1.5 according to IEC 60904-3 • <sup>2</sup>800 W/m<sup>2</sup>, NMOT, spectrum AM 1.5

## Qcells PERFORMANCE WARRANTY




At least 98.5% of nominal power during first year. Thereafter max. 0.33% degradation per year. At least 95.53% of nominal power up to 10 years. At least 90.58% of nominal power up to 25 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Qcells sales organisation of your respective country.

<sup>\*</sup>Standard terms of guarantee for the 5 PV companies with the highest production capacity in 2021 (February 2021)

## PERFORMANCE AT LOW IRRADIANCE



Typical module performance under low irradiance conditions in comparison to STC conditions (25°C, 1000 W/m<sup>2</sup>).

## TEMPERATURE COEFFICIENTS

|                                      |                |       |                                      |               |                         |
|--------------------------------------|----------------|-------|--------------------------------------|---------------|-------------------------|
| Temperature Coefficient of $I_{SC}$  | $\alpha$ [%/K] | +0.04 | Temperature Coefficient of $V_{OC}$  | $\beta$ [%/K] | -0.24                   |
| Temperature Coefficient of $P_{MPP}$ | $\gamma$ [%/K] | -0.30 | Nominal Module Operating Temperature | NMOT [°F]     | 109 ± 5.4<br>(43 ± 3°C) |

## Properties for System Design

|  |                        |                            |   |   |
|--|------------------------|----------------------------|---|---|
| Maximum System Voltage                   | $V_{SYS}$ [V]          | 1000 (IEC)/1000 (UL)       | PV module classification                        | Class II                                  |
| Maximum Series Fuse Rating               | [A DC]                 | 20                         | Fire Rating based on ANSI/UL 61730              | C / TYPE 2                                |
| Max. Design Load, Push/Pull <sup>3</sup> | [lbs/ft <sup>2</sup> ] | 75 (3600 Pa)/50 (2400 Pa)  | Permitted Module Temperature on Continuous Duty | -40°F up to +185°F<br>(-40°C up to +85°C) |
| Max. Test Load, Push/Pull <sup>3</sup>   | [lbs/ft <sup>2</sup> ] | 113 (5400 Pa)/75 (3600 Pa) |   |   |

<sup>3</sup> See Installation Manual

## Qualifications and Certificates

Quality Controlled PV - TÜV Rheinland; IEC 61215:2016; IEC 61730:2016. This data sheet complies with DIN EN 50380.



Qcells pursues minimizing paper output in consideration of the global environment.

Note: Installation instructions must be followed. Contact our technical service for further information on approved installation of this product.

Hanwha Q CELLS America Inc. 400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 748 59 96 | EMAIL hqc-inquiry@qcells.com | WEB www.qcells.com

qcells



# Powerwall 3

## Power Everything

Powerwall 3 is a fully integrated solar and battery system, designed to accelerate the transition to sustainable energy. Customers can receive whole home backup, cost savings, and energy independence by producing and consuming their own energy while participating in grid services. Once installed, customers can manage their system using the Tesla App to customize system behavior to meet their energy goals.

Powerwall 3 achieves this by supporting up to 20 kW DC of solar and providing 11.5 kW AC of continuous power per unit. It has the ability to start heavy loads up to 150 A LRA, meaning a single unit can support the power needs of most homes. Powerwall 3 is designed for mass production, fast and efficient installations, easy system expansion, and simple connection to any electrical service.



# Powerwall 3 Technical Specifications

## System Technical Specifications

|  |  |
|--|--|
| Model Number                                   | 1707000-xx-y   |
| Nominal Grid Voltage (Input & Output)          | 120/240 VAC  |
| Grid Type                                      | Split phase  |
| Frequency                                      | 60 Hz  |
| Overcurrent Protection Device                  | Configurable up to 60 A  |
| Solar to Battery to Grid Round Trip Efficiency | 89% <sup>1,2</sup>   |
| Solar to Grid Efficiency                       | 97% <sup>3</sup>   |
| Supported Islanding Devices                    | Backup Gateway 2, Backup Switch  |
| Connectivity                                   | Wi-Fi (2.4 and 5 GHz), Dual-port switched Ethernet, Cellular (LTE/4G <sup>4</sup> )  |
| Hardware Interface                             | Dry contact relay, Rapid Shutdown (RSD) certified switch and 2-pin connector, RS-485 for meters  |
| AC Metering                                    | Revenue Grade (+/- 0.5%)   |
| Protections                                    | Integrated arc fault circuit interrupter (AFCI), Isolation Monitor Interrupter (IMI), PV Rapid Shutdown (RSD) using Tesla Mid-Circuit Interrupters |
| Customer Interface                             | Tesla Mobile App   |
| Warranty                                       | 10 years   |

## Solar Technical Specifications

|   |                   |
|---|-------------------|
| Maximum Solar STC Input                             | 20 kW             |
| Withstand Voltage                                   | 600 V DC          |
| PV DC Input Voltage Range                           | 60 – 550 V DC     |
| PV DC MPPT Voltage Range                            | 150 – 480 V DC    |
| MPPTs   | 6                 |
| Maximum Current per MPPT ( $I_{mp}$ )               | 13 A <sup>5</sup> |
| Maximum Short Circuit Current per MPPT ( $I_{sc}$ ) | 15 A <sup>5</sup> |

## Battery Technical Specifications

|                                    |                                     |
|------------------------------------|-------------------------------------|
| Nominal Battery Energy             | 13.5 kWh AC <sup>2</sup>            |
| Maximum Continuous Discharge Power | 11.5 kW AC                          |
| Maximum Continuous Charge Power    | 5 kW AC                             |
| Output Power Factor Rating         | 0 - 1 (Grid Code configurable)      |
| Maximum Continuous Current         | 48 A                                |
| Maximum Output Fault Current       | 10 kA                               |
| Load Start Capability (1 s)        | 150 A LRA                           |
| Power Scalability                  | Up to 4 Powerwall 3 units supported |

<sup>1</sup> Typical solar shifting use case.

<sup>2</sup> Values provided for 25°C (77°F), at beginning of life. 3.3 kW charge/discharge power.

<sup>3</sup> Tested using CEC weighted efficiency methodology.

<sup>4</sup> Cellular connectivity subject to network service coverage and signal strength.

<sup>5</sup> Where the DC input current exceeds the MPPT rating, a jumper can be used to combine two MPPTs into a single input to intake DC current up to 26 A  $I_{mp}$  / 30 A  $I_{sc}$ .



# Powerwall 3 Technical Specifications

## Environmental Specifications

|                         |  |
|-------------------------|--|
| Operating Temperature   | -20°C to 50°C (-4°F to 122°F) <sup>6</sup>   |
| Operating Humidity (RH) | Up to 100%, condensing   |
| Storage Temperature     | -20°C to 30°C (-4°F to 86°F), up to 95% RH, non-condensing, State of Energy (SOE): 25% initial |
| Maximum Elevation       | 3000 m (9843 ft)   |
| Environment             | Indoor and outdoor rated   |
| Enclosure Rating        | NEMA 3R  |
| Ingress Rating          | IPX7 (Battery & Power Electronics)<br>IPX5 (Wiring Compartment)                                |
| Pollution Rating        | PD3  |
| Operating Noise @ 1 m   | < 50 db(A) typical<br>< 62 db(A) maximum   |


<sup>6</sup> Performance may be de-rated at operating temperatures above 40°C (104°F).

## Compliance Information

|                 |  |
|-----------------|--|
| Certifications  | UL 1642, UL 1699B, UL 1741, UL 1741 SA, UL 1741 SB, UL 3741, UL 1973, UL 1998, UL 9540, IEEE 1547-2018, IEEE 1547.1, UN 38.3 |
| Grid Connection | United States  |
| Emissions       | FCC Part 15 Class B  |
| Environmental   | RoHS Directive 2011/65/EU  |
| Seismic         | AC156, IEEE 693-2005 (high)  |
| Fire Testing    | Meets the unit level performance criteria of UL 9540A  |

## Mechanical Specifications

|                  |   |
|------------------|---|
| Dimensions       | 1099 x 609 x 193 mm (43.25 x 24 x 7.6 in) |
| Weight           | 130 kg (287 lb)                           |
| Mounting Options | Floor or wall mount                       |



# Solar Shutdown Device Technical Specifications

The Solar Shutdown Device is a Mid-Circuit Interrupter (MCI) and is part of the PV system rapid shutdown (RSD) function in accordance with Article 690 of the applicable NEC. When paired with Powerwall 3, solar array shutdown is initiated by any loss of AC power.

|  |  |   |  |
|--|--|---|--|
| Electrical Specifications  | <b>Model</b>                                     | <b>MCI-1</b>  | <b>MCI-2</b>                           |
|  | Nominal Input DC Current Rating ( $I_{MP}$ )     | 12 A  | 13 A                                   |
|  | Maximum Input Short Circuit Current ( $I_{SC}$ ) | 19 A  | 17 A                                   |
|  | Maximum System Voltage (PVHCS)                   | 600 V DC  | 1000 V DC <sup>7</sup>                 |
| <sup>7</sup> Maximum System Voltage is limited by Powerwall to 600 V DC. |  |   |  |
| RSD Module Performance   | Maximum Number of Devices per String             | 5   | 5                                      |
|  | Control  | Power Line Excitation   | Power Line Excitation                  |
|  | Passive State                                    | Normally Open   | Normally Open                          |
|  | Maximum Power Consumption                        | 7 W   | 7 W                                    |
|  | Warranty   | 25 years  | 25 years                               |
|  |  |   |  |
| Environmental Specifications   | Operating Temperature                            | -40°C to 50°C<br>(-40°F to 122°F)   | -45°C to 70°C<br>(-49°F to 158°F)      |
|  | Storage Temperature                              | -30°C to 70°C<br>(-22°F to 158°F)   | -30°C to 70°C<br>(-22°F to 158°F)      |
|  | Enclosure Rating                                 | NEMA 4X / IP65  | NEMA 4X / IP65                         |
| Mechanical Specifications  | Electrical Connections                           | MC4 Connector   | MC4 Connector                          |
|  | Housing  | Plastic   | Plastic                                |
|  | Dimensions                                       | 125 x 150 x 22 mm<br>(5 x 6 x 1 in)   | 173 x 45 x 22 mm<br>(6.8 x 1.8 x 1 in) |
|  | Weight   | 350 g (0.77 lb)   | 120 g (0.26 lb)                        |
|  | Mounting Options                                 | ZEP Home Run Clip<br>M4 Screw (#10)<br>M8 Bolt (5/16")<br>Nail / Wood screw | Wire Clip                              |
| Compliance Information   | Certifications                                   | UL 1741 PVRSE, UL 3741,<br>PVRSA (Photovoltaic Rapid Shutdown Array)        |  |
|  | RSD Initiation Method                            | External System Shutdown Switch or<br>Powerwall 3 Enable Switch             |  |

## UL 3741 PV Hazard Control (and PVRSA) Compatibility

The following categories of solar module meet the UL 3741 PVHCS listing when installed with Powerwall 3 and Solar Shutdown Devices.

|   |  |
|---|--|
| Tesla Solar Roof  | <a href="#">PV Hazard Control System: BIPV compliance document</a>             |
| Tesla or Hanwha (Q.Peak Duo BLK or BLK-G6+)<br>Modules certified for use with ZEP racking | <a href="#">PV Hazard Control System: ZS PVHCS compliance document</a>         |
| Other module and racking combinations   | <a href="#">PV Hazard Control System: Generic PV Array compliance document</a> |



# Backup Gateway 2

Backup Gateway 2 controls connection to the grid when paired with Powerwall 3, automatically detecting outages and providing seamless transition to backup power. Backup Gateway 2 also provides energy metering for solar self-consumption, time-based control, and backup operation.

In this system configuration, Powerwall 3 acts as the Site Controller, with the Backup Gateway 2 Site Controller disabled.

## Performance Specifications

|   |  |
|---|--|
| <b>Model Number</b>                         | 1232100-xx-y                                     |
| <b>AC Voltage (Nominal)</b>                 | 120/240 V  |
| <b>Feed-in Type</b>                         | Split phase                                      |
| <b>Grid Frequency</b>                       | 60 Hz  |
| <b>Current Rating</b>                       | 200 A  |
| <b>Maximum Supply Short Circuit Current</b> | 10 kA <sup>8</sup>                               |
| <b>Overcurrent Protection Device</b>        | 100 - 200 A, Service entrance rated <sup>8</sup> |
| <b>Overvoltage Category</b>                 | Category IV                                      |
| <b>Internal Primary AC Meter</b>            | Revenue accurate (+/- 0.2%)                      |
| <b>Internal Auxiliary AC Meter</b>          | Revenue accurate (+/- 2%)                        |
| <b>Primary Connectivity</b>                 | Ethernet, Wi-Fi                                  |
| <b>Secondary Connectivity</b>               | Cellular (3G, LTE/4G) <sup>9</sup>               |

|                                     |  |
|-------------------------------------|--|
| <b>User Interface</b>               | Tesla App  |
| <b>Operating Modes</b>              | Support for solar self-consumption, time-based control, and backup   |
| <b>Backup Transition</b>            | Automatic disconnect for seamless backup   |
| <b>Modularity</b>                   | Supports up to 10 AC-coupled Powerwalls  |
| <b>Optional Internal Panelboard</b> | 200 A 6-space / 12 circuit breakers<br>Siemens QP or Square D HOM breakers rated 10 - 80A or Eaton BR breakers rated 10 - 125A |
| <b>Warranty</b>                     | 10 years   |

<sup>8</sup> When protected by Class J fuses, Backup Gateway 2 is suitable for use in circuits capable of delivering not more than 22kA symmetrical amperes.

<sup>9</sup> The customer is expected to provide internet connectivity for Backup Gateway 2; cellular should not be used as the primary mode of connectivity. Cellular connectivity subject to network operator service coverage and signal strength.

## Environmental Specifications


|                                |                               |
|--------------------------------|-------------------------------|
| <b>Operating Temperature</b>   | -20°C to 50°C (-4°F to 122°F) |
| <b>Operating Humidity (RH)</b> | Up to 100%, condensing        |
| <b>Maximum Elevation</b>       | 3000 m (9843 ft)              |
| <b>Environment</b>             | Indoor and outdoor rated      |
| <b>Enclosure Type</b>          | NEMA 3R                       |

## Compliance Information

|                       |  |
|-----------------------|--|
| <b>Certifications</b> | UL 67, UL 869A, UL 916, UL 1741 PCS, CSA 22.2 0.19, CSA 22.2 205 |
| <b>Emmissions</b>     | FCC Part 15, ICES 003  |

## Mechanical Specifications

|                         |  |
|-------------------------|--|
| <b>Dimensions</b>       | 660 x 411 x 149 mm<br>(26 x 16 x 6 in) |
| <b>Weight</b>           | 20.4 kg (45 lb)                        |
| <b>Mounting options</b> | Wall mount,<br>Semi-flush mount        |



# Backup Switch

The Tesla Backup Switch controls connection to the grid in a Powerwall system, and can be easily installed behind the utility meter or in a standalone meter panel downstream of the utility meter.

The Backup Switch automatically detects grid outages, providing a seamless transition to backup power. It communicates directly with Powerwall, allowing home energy usage monitoring from any mobile device with the Tesla app.

## Performance Specifications

|   |                                  |
|---|----------------------------------|
| <b>Model Number</b>                         | 1624171-xx-y                     |
| <b>Continuous Load Rating</b>               | 200 A, 120/240 V split phase     |
| <b>Maximum Supply Short Circuit Current</b> | 22 kA with breaker <sup>10</sup> |
| <b>Communication</b>                        | CAN                              |
| <b>AC Meter</b>                             | Revenue accurate (+/- 0.5%)      |
| <b>Expected Service Life</b>                | 21 years                         |
| <b>Warranty</b>                             | 10 years                         |

<sup>10</sup> Breaker maximum supply short circuit current rating must be equal to or greater than the available fault current.

## Environmental Specifications

|                              |                                |
|------------------------------|--------------------------------|
| <b>Operating Temperature</b> | -40°C to 50°C (-40°F to 122°F) |
| <b>Storage Temperature</b>   | -40°C to 85°C (-40°F to 185°F) |
| <b>Enclosure Rating</b>      | NEMA 3R                        |
| <b>Pollution Rating</b>      | PD3                            |


## Compliance Information

|                         |  |
|-------------------------|--|
| <b>Safety Standards</b> | USA: UL 414, UL 2735, UL 916, CA Prop 65 |
| <b>Emmissions</b>       | FCC, ICES                                |

## Mechanical Specifications

|                                       |   |
|---------------------------------------|---|
| <b>Dimensions</b>                     | 176 x 205 x 74 mm (6.9 x 8.1 x 2.9 in)                  |
| <b>Weight</b>                         | 2.8 lb  |
| <b>Meter and Socket Compatibility</b> | ANSI Type 2S, ringless or ring type                     |
| <b>External Service Interface</b>     | Contactor manual override <sup>11</sup><br>Reset button |
| <b>Conduit Compatibility</b>          | 1/2-inch NPT  |

<sup>11</sup> Manually overrides the contactor position during a service event.






# Powerwall 3 Example System Configurations


## Powerwall 3 with Backup Switch

Whole Home Backup



## Powerwall 3 with Backup Gateway 2

Partial Home Backup



RSTC Enterprises, Inc.  
2214 Heimstead Road  
Eau Claire, WI 54703  
715-830-9997



## Outdoor Photovoltaic Enclosures

Composition/Cedar Roof System

### ETL listed and labeled

Report # 3171411PRT-002 Revised May, 2018

- UL50 Type 3R, 11 Edition Electrical equipment enclosures
- CSA C22.2 No. 290 Nema Type 3R
- Conforms to UL 1741 Standard

### 0799 Series Includes:

- |          |                  |
|----------|------------------|
| 0799 - 2 | Wire size 2/0-14 |
| 0799 - 5 | Wire size 14-6   |
| 0799 - D | Wire size 14-8   |

Models available in Grey, Black or Stainless Steel

### Basic Specifications

Material options:

- Powder coated, 18 gauge galvanized 90 steel (1,100 hours salt spray)
- Stainless steel

Process - Seamless draw (stamped)

Flashing - 15.25" x 17.25"

Height - 3"



Cavity - 255 Cubic inches

### Base Plate:

- Fastened to base using toggle fastening system
- 5 roof deck knockouts
- Knockout sizes: (3) .5", (1) .75" and (1) 1"
- 8", 35mm slotted din rail
- Ground Block

Passthrough and combiner kits are available for either AC or DC applications.

## 0799 Series





# Product data sheet

Specifications

SQUARE D

Green Premium™



Safety switch, general duty, non fusible, 60A, 2 pole, 10hp, 240VAC, NEMA 3R, bolt on provision

DU222RB

Product availability : Stock - Normally stocked in distribution facility

Price\* : 353.00 USD

## Main

|                           |  |
|---------------------------|--|
| Product                   | Single Throw Safety Switch                 |
| Duty Rating               | General duty                               |
| Device Application        | Residential                                |
| Disconnect Type           | Non-fusible disconnect switch              |
| Factory Installed Neutral | None                                       |
| Phase                     | 3 phase                                    |
| Number of Poles           | 2  |
| Current Rating            | 60 A                                       |
| Voltage Rating            | 240 V AC                                   |
| Enclosure Rating NEMA     | NEMA 3R                                    |
| Motor power hp            | 10 hp at 240 V AC 60 Hz for 1 phase motors |

## Complementary

|                       |  |
|-----------------------|--|
| Mounting Type         | Surface  |
| Electrical Connection | Lugs   |
| Wiring configuration  | 2 wires  |
| Wire Size             | AWG 12...AWG 3 aluminium<br>AWG 14...AWG 3 copper  |
| Tightening torque     | 35 lbf.in (3.95 N.m) 0.00...0.01 in <sup>2</sup> (2.08...5.26 mm <sup>2</sup> ) (AWG 14...AWG 10)<br>35 lbf.in (3.95 N.m) (AWG 14...AWG 10)<br>45 lbf.in (5.08 N.m) 0.01 in <sup>2</sup> (8.37 mm <sup>2</sup> ) (AWG 8)<br>45 lbf.in (5.08 N.m) 0.02...0.03 in <sup>2</sup> (12.3...21.12 mm <sup>2</sup> ) (AWG 6...AWG 4)<br>50 lbf.in (5.65 N.m) 0.04 in <sup>2</sup> (26.67 mm <sup>2</sup> ) (AWG 3) |
| Depth                 | 3.75 in (95.25 mm)   |
| Width                 | 7.75 in (196.85 mm)  |
| Height                | 9.63 in (244.60 mm)  |
| Net Weight            | 16.98 lb(US) (7.7 kg)  |

## Environment

|                |                      |
|----------------|----------------------|
| Certifications | UL listed file E2875 |
|----------------|----------------------|

\* Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

## Ordering and shipping details

|                   |                                 |
|-------------------|---------------------------------|
| Category          | 00106-D & DU SW,NEMA3R, 30-200A |
| Discount Schedule | DE1A                            |
| GTIN              | 785901491491                    |
| Returnability     | Yes                             |
| Country of origin | MX                              |

## Packing Units

|                              |                            |
|------------------------------|----------------------------|
| Unit Type of Package 1       | PCE                        |
| Number of Units in Package 1 | 1                          |
| Package 1 Height             | 5.30 in (13.462 cm)        |
| Package 1 Width              | 7.20 in (18.288 cm)        |
| Package 1 Length             | 10.00 in (25.4 cm)         |
| Package 1 Weight             | 4.65 lb(US) (2.109 kg)     |
| Unit Type of Package 2       | PAL                        |
| Number of Units in Package 2 | 120                        |
| Package 2 Height             | 36.50 in (92.71 cm)        |
| Package 2 Width              | 40.00 in (101.6 cm)        |
| Package 2 Length             | 48.00 in (121.92 cm)       |
| Package 2 Weight             | 610.00 lb(US) (276.691 kg) |
| Unit Type of Package 3       | CAR                        |
| Number of Units in Package 3 | 5                          |
| Package 3 Height             | 10.70 in (27.178 cm)       |
| Package 3 Width              | 10.20 in (25.908 cm)       |
| Package 3 Length             | 23.50 in (59.69 cm)        |
| Package 3 Weight             | 24.60 lb(US) (11.158 kg)   |

## Offer Sustainability

|                            |   |
|----------------------------|---|
| Sustainable offer status   | Green Premium product   |
| California proposition 65  | WARNING: This product can expose you to chemicals including: Lead and lead compounds, which is known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to <a href="http://www.P65Warnings.ca.gov">www.P65Warnings.ca.gov</a> |
| REACH Regulation           | <a href="#">REACH Declaration</a>   |
| REACH free of SVHC         | Yes   |
| EU RoHS Directive          | Compliant<br><a href="#">EU RoHS Declaration</a>  |
| Toxic heavy metal free     | Yes   |
| Mercury free               | Yes   |
| China RoHS Regulation      | <a href="#">China RoHS declaration</a><br>Pro-active China RoHS declaration (out of China RoHS legal scope)   |
| RoHS exemption information | <a href="#">Yes</a>   |
| Environmental Disclosure   | <a href="#">Product Environmental Profile</a>   |
| PVC free                   | Yes   |

# Contractual warranty



---

Warranty

18 months



**Dimensions**



NEMA TYPE 3R


IN.  
[mm]

| KNOCKOUTS          |     |     |   |      |
|--------------------|-----|-----|---|------|
| SYMBOL             | A   | B   | C | D    |
| CONDUIT SIZE (IN.) | .50 | .75 | 1 | 1.25 |

TOP OF NEMA TYPE 3R SWITCHES HAVE PROVISIONS FOR MAXIMUM 2 1/2" BO LT-ON HUB.  
 ALL DIMENSIONS ARE APPROXIMATE. REFER TO TECHNICAL DRAWINGS AND DOCUMENTATION.

**Wiring Diagram**


---



**DU222RB**

**Recommended replacement(s)**

# FLUSH MOUNT





# CONTENTS

|  |              |
|--|--------------|
| <b>DISCLAIMER</b>  | <b>1</b>     |
| <b>RATINGS</b>   | <b>2</b>     |
| <b>MARKINGS</b>  | <b>2</b>     |
| <b>ATTACHMENTS</b>   | <b>3</b>     |
| <b>COMPONENTS</b>  | <b>4</b>     |
| <b>1. ATTACH BASES</b>   | <b>5</b>     |
| <b>2. PLACE RAILS</b>  | <b>5</b>     |
| <b>3. SECURE LUGS</b>  | <b>6</b>     |
| <b>4. SECURE MODULES</b>   | <b>6</b>     |
| <b>CAMO</b>  | <b>7</b>     |
| <b>BONDING JUMPER</b>  | <b>7</b>     |
| <b>EXPANSION JOINTS</b>  | <b>8</b>     |
| <b>ELECTRICAL DIAGRAM</b>  | <b>9</b>     |
| <b>COMPOSITION SHINGLE</b>   | <b>10-11</b> |
| <b>TILE</b>  | <b>12-14</b> |
| <b>ADDITIONAL ROOF TYPES</b>                                       | <b>14</b>    |
| <b>LOW SLOPE ROOFS</b>   | <b>15</b>    |
| <b>CONDUIT PENETRATION</b>   | <b>16</b>    |
| <b>CONDUIT MOUNT</b>   | <b>17</b>    |
| <b>END CAPS</b>  | <b>18</b>    |
| <b>WIRE CLIPS</b>  | <b>18</b>    |
| <b>JAYBOX</b>  | <b>18</b>    |
| <b>MICROINVERTER KITS</b>  | <b>19</b>    |
| <b>SYSTEMS USING ENPHASE MICROINVERTERS OR SUNPOWER AC MODULES</b> | <b>19</b>    |
| <b>SYSTEMS USING MICROSTORAGE PRODUCTS</b>                         | <b>20</b>    |
| <b>FRAMELESS MODULE KITS</b>                                       | <b>20</b>    |
| <b>CONTOUR</b>   | <b>21</b>    |
| <b>MODULE COMPATIBILITY</b>  | <b>22-27</b> |
| <b>FRAMELESS MODULE COMPATABILITY</b>                              | <b>28</b>    |

## DISCLAIMER

This manual describes proper installation procedures and provides necessary standards required for product reliability. Warranty details are [available on website](#). All installers must thoroughly read this manual and have a clear understanding of the installation procedures prior to installation. Failure to follow these guidelines may result in property damage, bodily injury or even death.

### IT IS THE INSTALLER'S RESPONSIBILITY TO:

- Ensure safe installation of all electrical aspects of the array. All electrical installation and procedures should be conducted by a licensed and bonded electrician or solar contractor. Routine maintenance of a module or panel shall not involve breaking or disturbing the bonding path of the system. All work must comply with national, state and local installation procedures, product and safety standards.
- Comply with all applicable local or national building and fire codes, including any that may supersede this manual.
- Ensure all products are appropriate for the installation, environment, and array under the site's loading conditions.
- Use only IronRidge parts or parts recommended by IronRidge; substituting parts may void any applicable warranty.
- Review the [Design Assistant](#) and [Certification Letters](#) to confirm design specifications.
- Ensure provided information is accurate. Issues resulting from inaccurate information are the installer's responsibility.
- Ensure bare copper grounding wire does not contact aluminum and zinc-plated steel components, to prevent risk of galvanic corrosion.
- If loose components or loose fasteners are found during periodic inspection, re-tighten immediately. Any components showing signs of corrosion or damage that compromise safety shall be replaced immediately.
- Provide an appropriate method of direct-to-earth grounding according to the latest edition of the National Electrical Code, including NEC 250: Grounding and Bonding, and NEC 690: Solar Photovoltaic Systems.
- Disconnect AC power before servicing or removing modules, AC modules, microinverters and power optimizers.
- Review module and any 3rd party manufacturer's documentation for compatibility and compliance with warranty terms and conditions.

## RATINGS

### UL 2703 LISTED



#5003807

Intertek

### Conforms to STD UL 2703 Standard for Safety First Edition: Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels

- Max Overcurrent Protective Device (OCPD) Rating: 40A
- Max Module Size: 30.5 ft<sup>2</sup>
- Module Orientation: Portrait or Landscape
- System Design Load Rating: 10 PSF downward, 5 PSF upward, 5 PSF lateral
- Actual system structural capacity including spans and cantilevers are defined by PE stamped [certification letters](#).
- CAMO Specific Design Load rating: 50 PSF downward, 50 PSF upward, 15 PSF lateral

### Certified to CSA TIL No. A-40 Photovoltaic Module Racking Systems

- Load Rating: 2400 PA [50 PSF]

### CLASS A SYSTEM FIRE RATING PER UL 2703

- Any Roof Slope with Module Types 1, 2, 3, 13, 19, 25 & 29: Allowed with any roof slope. Any module-to-roof gap is permitted, with no perimeter guarding required.
- Module Types 4 and 5: Allowed with Steep Slope Roofs ( $\geq 9.5^\circ$ ). Any module-to-roof gap is permitted, low edge guarding (Trim) required
- Class A rated PV systems can be installed on Class A, B, and C roofs without affecting the roof fire rating

### CLASS B SYSTEM FIRE RATING PER UL 2703

- Module Types 4 and 5: Allowed with Steep Slope Roofs ( $\geq 9.5^\circ$ ). Any module-to-roof gap is permitted, with no perimeter guarding required

### WATER SEAL RATINGS:

- UL 441 (Flashfoot2, All Tile Hook, Knockout Tile, Flashvue, L-Mount)
- TAS 100(A)-95 (Flashfoot2, All Tile Hook, Knockout Tile, Flashvue, L-Mount, Qbase)
- Tested and evaluated without sealant.
- Any roofing manufacturer approved sealant is allowed. Ratings applicable for roof slopes between 2:12 and 12:12

### STRUCTURAL CERTIFICATION



- Designed and Certified for Compliance with the International Building Code & ASCE/SEI-7

### FLORIDA PRODUCT APPROVAL #FL29843

- Conforms to TAS202, TAS100(A)
- Approved for installation both inside and outside High Velocity Hurricane Zones (HVHZ)
- Allowable design pressure up to +100/-100 PSF
- Additional details and full list of approved components can be found [Here](#).

## MARKINGS

Product markings are located on the Grounding Lug bolt head.



# ATTACHMENTS

## PRE-INSTALLATION

- ❑ Verify module compatibility. See [Page 21](#) for info.

## TOOLS REQUIRED

- ❑ Cordless Drill (non-impact)
- ❑ Impact Driver (for lag bolts)
- ❑ Torque Wrench (0-250 in-lbs)
- ❑ 7/16" Socket
- ❑ 1/2" Socket
- ❑ 9/16" Socket
- ❑ 7/32" Drill Bit
- ❑ 1/8" Drill Bit
- ❑ 1/4" Drill Bit
- ❑ T30 Bit
- ❑ Channel Lock Pliers
- ❑ #3 Phillips Bit
- ❑ 3/16" Hex Bit

## BONDING HARDWARE TORQUE VALUES

Please refer to each attachment's individual section for full details on all torque values and instructions.

- ❑ 3/8" Bonding Hardware Nuts (7/16" Socket): 250 in-lbs
- ❑ All Tile Hook Carriage Bolts (7/16" Socket): 132 in-lbs
- ❑ Flat Roof Attachment Nuts (9/16" Socket): 250 in-lbs
- ❑ Lynx Set Screw (3/16" Hex Drive): 150 in-lbs
- ❑ Lynx Flange Nut (1/2" Socket): 150 in-lbs


➤ If using previous version of Integrated Grounding Mid Clamps, End Clamps, Expansion Joints and for a list of approved 3rd party components please refer to Alternate Components Addendum (Version 1.9)

## ATTACHMENTS


### COMPOSITION SHINGLE




FlashFoot2




FlashVue




QM L-Mount



QM QBase




QM Classic Comp Mount




QM Composition Conduit Penetration


### TILE




Knockout Tile




QM Tile Replacement




All Tile Hook and Flashing (optional)



QM Quick Hook and Flashing (optional)




QM QBase Tile




QM Tile Conduit Penetration


### ADDITIONAL ROOF TYPES



QM Qbase Shake - Slate - Metal Shingle




QM Classic Mount Shake




QM Lynx Metal Roof Attachment

### LOW SLOPE ROOF



Flat Roof Attachment



QM QBase Mount



# COMPONENTS

## PRE-INSTALLATION

- Verify module compatibility. See [Page 21](#) for info.

## TOOLS REQUIRED

- Cordless Drill (non-impact)
- Impact Driver (for lag bolts)
- Torque Wrench (0-250 in-lbs)
- 7/16" Socket
- 1/2" Socket
- 9/16" Socket
- 7/32" Drill bit
- 1/8" Drill bit
- 1/4" Drill bit
- T30 Torx Bit
- Channel Lock Pliers
- #3 Phillips Bit
- Paddle Bit


## BONDING HARDWARE TORQUE VALUES

Please refer to each attachment's individual section for full details on all torque values and instructions.

- Universal Fastening Object (7/16" Socket): 80 in-lbs
- Rail Grounding Lug Nut (7/16" Socket): 80 in-lbs
- Module Grounding Lug Nut (7/16" Socket): 60 in-lbs
  - Grounding Lug Terminal Screws (7/16" Socket): 20 in-lbs
- Expansion Joint Nuts (7/16" Socket): 80 in-lbs
- Microinverter Kit Nuts (7/16" Socket): 80 in-lbs
- Frameless Module Kit Nuts (7/16" Socket): 80 in-lbs
- 3/8" Bonding Hardware Nuts (7/16" Socket): 250 in-lbs
- Contour Clamp (T-30 Torx Bit): 80 in-lbs

► Unless otherwise noted, all components have been evaluated for multiple use. They can be uninstalled and reinstalled in the same or new location.


## COMPONENTS




XR Rail



Wire Clip




BOSS



UFO and Stopper Sleeve (30-46MM)




CAMO




Ironridge L-Foot and QM L-Foot




End Cap




Rail Grounding Lug




Module Grounding Lug




Microinverter Kit




3/8" Bonding Hardware




8" Bonding Jumper Single Use Only




QM Classic Conduit Comp Mount



JAYBOX




Expansion Joint




QM Tile Conduit Mount




Frameless End/Mid Clamp



Frameless Module Kit




Contour Trim



Contour Clamp

# 1. PLACE ATTACHMENTS

The general installation method for attachments is to locate a rafter, drill a pilot hole and install the attachment. For composition roof attachments installation instructions refer to [page 10](#). For tile roof attachments refer to [page 12](#). For low slope roof attachments refer to [page 14](#). When using approved third party attachments, refer to manufacturer's install instructions.



Tested or evaluated third-party roof attachments:

- [S-5! Standing Seam Metal Roof Clamps](#) - Certification of metal roof clamps includes bonding to both painted and galvalume metal roofs. Tighten S-5! and S-5! Mini set screws to 130-150 in-lbs ( $\geq 24$  gauge) or 160-180 in-lbs (22 gauge) roofs. Tighten S-5! M10 bolt to 240 in-lbs or S-5! Mini M8 bolt to 160 in-lbs. Use the following fastening guidelines for other S-5! roof clamps: ProteaBracket™ - firmly seat roof screws and tighten hinge bolt to 225 in-lbs; RibBracket™ - firmly seat roof screws and tighten M8 bolt (M8-1.25 x 22mm sold separately) to 160 in-lbs; and SolarFoot™ - firmly seat roof screws and tighten M8 flange nut to 160 in-lbs.
- [EcoFasten Green Fasten GF-1 Anchors](#)

# 2. PLACE RAILS


## A. CONNECT SPLICES

Use BOSS(Bonded Structural Splice), as needed, to join multiple sections of Rail.

### **BOSS - Bonded Structural Splice**

Insert BOSS into first Rail up until the Stop Tab. Slide second Rail fully into place.


- Rows using BOSS and exceeding 100 feet of Rail must use [Expansion Joints](#).
- Boss Splices may be installed in any location within a span.
- UFO and Bonding Hardware must be installed 1" away from the point where two Rails join together.



## B. PREPARE HARDWARE

Slide square-headed bolts into side-facing rail slot. Space out bolts to match attachment spacing.


- Tape ends of rail, to keep bolts from sliding out while moving.
- If using T-bolts, carry hardware onto roof and proceed.



## C. ATTACH RAILS

Drop rail with hardware into roof attachment. Level rail at desired height, then torque to 250 in-lbs.

- Rail can face either upslope or downslope on roof.
- When using attachments with longer slots, do not install Rail lower than the top of the L-Foot to avoid damage to modules.



### 3. SECURE LUGS

#### Grounding Lugs

Only one Grounding Lug (Rail or Module) required per continuous subarray, regardless of subarray size (Unless frameless modules are used, see [Page 20](#)).

- **Grounding Lugs are intended to for use with one solid or stranded copper wire, conductor size 10-4 AWG.**

#### Rail Grounding Lug


Insert T-bolt in Top Rail slot and torque Hex Nut to **80 in-lbs**. Install a minimum 10 AWG solid copper or stranded grounding wire. Torque terminal screw to **20 in-lbs**.

- **Module Grounding Lugs can be installed anywhere along the Rail and in either orientation shown.**

#### Module Grounding Lug

Insert Bolt through Manufacturer approved grounding location and torque Hex nut to **60 in-lbs**. One Module Grounding Lug may be installed to one module per row. Install a minimum 10 AWG solid copper or stranded grounding wire. Torque terminal screw to **20 in-lbs**.

- **If using Enphase microinverters or Sunpower AC modules, Grounding Lugs may not be needed. See [Page 19](#) for more info.**
- **Refer to module manufacturer for mounting location and instructions.**



### 4. SECURE MODULES

#### A. SECURE FIRST END

Place first module in position on rails, a minimum of 1" from rail ends. Snap Stopper Sleeves onto UFO. Fasten module to rail using the UFO, ensuring that the UFO is hooked over the top of the module. Torque to **80 in-lbs**.

- **Ensure rails are square before placing modules.**
- **Hold Stopper Sleeves on end while torquing to prevent rotation.**
- **If using CAMO instead of UFO + Stopper Sleeve, refer to [Page 19](#) for CAMO installation procedure.**
- **UFO can be installed on modules 30 to 46mm.**

#### B. SECURE NEXT MODULES


Place UFO into each rail, placing them flush against first module. Slide second module against UFO. Torque to **80 in-lbs**. Repeat for each following module.

- **When reinstalling UFO, move modules a minimum of 1/16" so UFOs are in contact with a new section of module frame.**
- **When UFOs are loosened and re-tightened, ensure UFO T-bolt bottoms out in rail channel before re-torquing UFO to achieve full engagement between T-bolt and rail.**
- **If using Wire Clips, refer to [Page 18](#).**

#### C. SECURE LAST END

Place last module in position on rails, a minimum of 1" from rail ends. Snap Stopper Sleeves onto UFO. Secure UFO Clamps on rails, ensuring they are hooked over top of module. Torque to **80 in-lbs**.

- **Hold Stopper Sleeves on end while torquing to prevent rotation.**
- **Repeat all steps for each following row of modules, leaving a minimum 3/8" gap between rows**
- **If using CAMO instead of UFO + Stopper Sleeve, refer to [Page 6](#)**





## CAMO


### A. SLIDE INTO RAIL

Slide CAMO into rail channel far enough to clear the module frame. CAMO requires 6" of clearance from end of rail.




### B. PLACE MODULE

Place module on rails (module cells not shown for clarity). When installing CAMO the module can overhang the rail no more than 1/4".




### C. PULL TOWARDS END

Pull CAMO towards rail ends, at 45 degree angle, so the bonding bolt contacts the module flange edge.



### D. SECURE TO FRAME


Rotate handle with an upwards motion until CAMO snaps into rail channel. Ensure CAMO bonding pins are fully seated on top of module frame.



### FRAME COMPATIBILITY

CAMO has been tested or evaluated with all modules listed in the Module Compatibility section having frames within the referenced dimensions. Be sure the specific module being used meets the dimension requirements.

- For installations with Hanwha Q CELLS modules with 32 mm frame heights, the maximum ground snow is 45 PSF (33 PSF module pressure).
- CAMO is only compatible with Canadian Solar modules CS1YxxxMS and CS3N-xxxMS. "xxx" refers to the module power rating



## 8" BONDING JUMPER

8" Bonding Jumper is an electrical bonding jumper that can be used on the Flush Mount System for row to row bonding; making the module frames the medium for the equipment ground path.

- Bonding jumper is pushed onto the bottom flange of the module.
- New jumpers should be used if re-installation of jumper is required.
- Supports bottom flange thicknesses from 1.2mm to 3.1mm.



# EXPANSION JOINTS




Expansion Joints are required every 100' of continuous rail to allow for thermal expansion and contraction of the system.


➤ Do not install modules over expansion joint.

## BOSS

Insert BOSS into first Rail up to the Alignment Circle, Slide second Rail over BOSS to the second Alignment Circle, leaving a 1" gap between the Rails.

There must be a 1" of space between the edge of the Rail and the edge of the panel to allow proper installation of the UFO and Stopper Sleeve.





\*One Module Grounding Lug or Rail Grounding lug is required per row of a system.


\*\* The use of the 8" Bonding Jumper eliminates the need for row to row bonding. A minimum of one grounding lug per continuous array is required for earth ground.

Grounding Lugs and wire are not required in systems using certain Enphase microinverters or certain Sunpower modules. Equipment grounding is achieved with the Engage cable for Enphase or the AC module cable system for Sunpower via their integrated EGC.

## FLASHFOOT2

Locate roof rafters and mark locations on roof. Drill 1/4" pilot holes perpendicular to the roof and back fill with roofing manufacturers' approved sealant. Slide flashing between 1st and 2nd course of shingles, ensuring both that the flashing reaches under the 3rd shingle course and doesn't overhang the downhill shingle course. Line up with pilot hole and insert supplied lag bolt with washer through flashing. With a 7/16" Socket fully seat lag bolt. Place Cap onto flashing in desired orientation for E/W or N/S rails and rotate 180 degrees until it locks into place.

- Rail can be installed on either side of FlashFoot2 Cap.
- For additional details refer to the full FlashFoot2 [Installation Manual](#).




## FLASHVUE

Locate rafters and snap vertical and horizontal lines to mark locations of flashings. Drill 1/4" pilot holes, then backfill with an approved sealant. Slide flashing between 1st and 2nd course of shingles, ensuring both that the flashing reaches under the 3rd shingle course and doesn't overhang the downhill shingle course. Line up pilot hole with View Port. Press Grip Cap onto flashing in desired orientation for E/W or N/S rails. Insert Lag Bolt with mechanically bonded washer through flashing. With a 7/16" Socket drive Lag Bolt until fully seated. FlashVue is now installed and ready for IronRidge XR Rails. Attach rails to either side of the open slot using bonding hardware. Level rail at desired height, then torque to **250 in-lbs (21 ft-lbs)**.

When installing GripCap+ on roofs with undulations greater than 1 inch, install GripCap+ in low points across the array as required.

- For additional details refer to the full FlashVue [Installation Manual](#).
- For additional details on the GripCap+ refer to the full [GripCap+ Installation Manual](#).






## COMPOSITION SHINGLE

### QM L-MOUNT

Locate roof rafters and mark locations on roof. Drill 7/32" (Lag) or 1/8" (ST) pilot holes perpendicular to the roof and back fill with roofing manufacturers' approved sealant. Slide flashing between 1st and 2nd course of shingles, ensuring both that the flashing reaches under the 3rd shingle course and doesn't overhang the downhill shingle course. Place L-foot on flute and rotate into desired position. Prepare lag bolt or structural screw with sealing washer. Use 1/2" socket to drive prepared lag bolt through L-foot until fully seated and L-foot can no longer rotate easily. Torque Nut to **156 in-lbs (13 ft-lbs)** for ST. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.


- Structural screw can be driven with T-30 hex head bit.
- For additional details refer to the full QM [Installation Manual](#).



### QM QBASE COMPOSITION MOUNT

Locate roof rafters and mark locations on roof. Align QBase vertical holes over center rafter and mark. Drill two pilot holes with 7/32" drill bit, perpendicular to roof and back fill with roofing manufacturers' approved sealant. Set grade 8 cap screw through bottom of QBase, place QBase over drilled holes and secure lags. Screw Post to QBase. Proceed with roofing up until the flashing should be installed. Install flashing over mount. Allow roofing to proceed to the next course. Apply sealant where post and flashing meet, install EPDM counter flashing collar. Attach L-Foot on Standoff with hardware. Torque to **174 in-lbs (14.5 ft-lbs)**. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.


- For additional details refer to the full QM [Installation Manual](#).



### CLASSIC COMP MOUNT

Locate roof rafters and mark locations on roof. Drill 7/32" pilot holes perpendicular to the roof and back fill with roofing manufacturers' approved sealant. Slide flashing between 1st and 2nd course of shingles, ensuring both that the flashing reaches under the 3rd shingle course and doesn't overhang the downhill shingle course. Prepare Hanger Bolt with Hex Nut and Sealing Washer, insert into hole and using 1/2" socket drive hanger bolt until fully seated and QBlock stops rotating easily. Insert EPDM rubber washer over hanger bolt into block, using Rack Kit hardware secure L-Foot to the mount. Torque to **156 in-lbs (13 ft-lbs)**. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.

- For additional details refer to the full QM [Installation Manual](#).




# TILE

## KNOCKOUT TILE

Remove tile and mark rafter. Use base as guide to drill 1/4" pilot hole and fill with roofing manufacturer's approved sealant. Install optional Roof Flashing and seal appropriately. Insert lag bolt with bonded washer through base (and flashing if used) and drive until fully seated. Insert Tile Replacement Flashing, lower onto base and apply pressure over the threaded post until it dimples the flashing. Place L-Foot over dimple and tap with hammer to punch threaded post through the flashing. Ensure punched pieces of flashing are cleared away. Form flashing as needed to sit flush with surrounding tiles, position L-Foot in desired orientation and torque hardware to **132 in-lbs (11 ft-lbs)**. Attach rail to L-Foot with Aire Dock and torque to **250 in-lbs (21 ft-lbs)**.


- Base can be installed in any orientation relative to rafter.
- Ensure L-Foot does not extend above rail.
- Optional deck level flashing is available. Standalone [installation manual](#) available on website
- Standalone [Knockout Tile manual](#) available on website.



## QM TILE REPLACEMENT

Remove tile and mark rafter. Measure up 8 3/4" from the adjacent tiles and mark horizontal across rafter. Align baseplate over rafter so that the lag holes align with the post groove. The orientation of the plate can be adjusted cross roof, mark location of lag holes on the roof. Drill two 1/8" Pilot holes and back fill with roofing manufacturers' approved sealant. Waterproof at underlayment level according to roofing manufacturers' instructions and the Tile Roofing Industry Alliance guidelines. Use T-30 Torx bit to lag base into position. Insert Grade 8 Serrated Flange Bolt into bottom of the Post, slide Post into Base channel. Line up post with the hole in the Tile Replacement Flashing. Leave loose for adjustments. Place Tile Replacement Flashing over the Post and Mount, allowing the flashing to properly interlock with surrounding tiles. Secure Post by tightening with channel lock pliers. Replace all tiles. Apply a bead of sealant where the post meets the flashing, slip EPDM collar over post and down to flashing. Attach L-Foot on Standoff with hardware. Torque to **174 in-lbs (14.5 ft-lbs)**. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.


- If deck level flashing is required, approved flashing methods include user supplied adhesive backed flexible flashing.
- For additional details refer to the full QM [Installation Manual](#).



## ALL TILE HOOK

Remove tile and mark rafter. Position base over rafter, adjust arm if necessary and torque hardware to **132 in-lbs (11 ft-lbs)**. Use base as guide to drill 1/4" pilot holes, back fill with roofing manufacturer's approved sealant, then insert lag bolts and tighten until fully seated. Replace tiles and notch as necessary to ensure proper fit. Attach rails to either side of slot using Bonding Hardware and torque to **250 in-lbs (21-ft-lbs)**.


- Position arm near the center of valley for curved tiles.
- Position arm away from seam of joining flat tiles.
- Ensure top of hook does not extend above rail.
- Standalone [All Tile Hook manual](#) available on website.



## QM QUICK HOOK

Remove tile and mark rafter, use Base Plate to mark two holes on rafter. Drill two 7/32" pilot holes and back fill with roofing manufacturers' approved sealant. Use 1/2" socket to drive lag into place. Slide hook into place and adjust to desired position. Drive self-tapping screw using a #3 Phillips bit to lock hook in place. Clean underlayment and apply a bead of sealant compatible with roofing manufacturer, install flashing over mount. Fasten sub-flashing to deck with one roofing nail in each corner. Waterproof at underlayment level according to roofing manufacturers' instructions and the Tile Roofing Industry Alliance guidelines. Cut clearance notch in the weather guard of tile as needed or utilize QM Tile Replacement Flashings. Attach rails to either side of slot using Bonding Hardware and torque to **250 in-lbs (21-ft-lbs)**.

- Position arm near the center of valley for curved tiles.
- Position arm away from seam of joining flat tiles.
- Ensure top of hook does not extend above rail.
- For additional details refer to the full QM [Installation Manual](#).




## TILE

### QM QBASE UNIVERSAL TILE MOUNT

Remove tile and mark rafter. Measure up 6 5/8" from bottom of tiles and mark horizontally. Align QBase over rafter center and drill two 7/32" pilot holes, back fill with roofing manufacturers' approved sealant. Place grade-8 Cap Screw under QBase, lag QBase into rafter location. Install Sub-flashing, waterproof at underlayment level according to roofing manufacturers' instructions and the Tile Roofing Industry Alliance guidelines. Cut tile with diamond blade to allow post to pass through. Place tile in position and then install Post. Install 18"x18" flashing, pre-bent to follow the contour of the tile as required. Apply sealant where Post and Flashing meet and install EPDM counter flashing. Attach L-Foot on Standoff with hardware. Torque to **174 in-lbs (14.5 ft-lbs)**. Attach rails to L-Foot using Bonding Hardware and torque to **250 in-lbs (21-ft-lbs)**.

➤ For additional details refer to the full QM [Installation Manual](#).




## ADDITIONAL ROOF TYPES

### QM CLASSIC SHAKE MOUNT

Locate roof rafters and mark locations on roof, remove shakes directly above mount if needed to expose felt paper. Level out installation area and location installation point, mark. Drill 7/32" pilot hole, back fill with roofing manufacturers' approved sealant. Prepare Hanger Bolt with Hex Nut and Sealing washer, insert into QBlock hole and drive into rafter until fully seated and the QBlock no longer swivels easily. Insert EPDM washer over hanger bolt and then install L-Foot in desired orientation and torque hardware to **132 in-lbs (11 ft-lbs)**. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.

➤ For additional details refer to the full QM [Installation Manual](#).




### QM QBASE METAL, SHAKE AND SLATE

The QM QBase can be used to install on multiple roofing types with different installation methods.

➤ For instructions on installing the QBase on Slate refer to the full QM [Installation Manual](#).

➤ For instructions on installing the QBase on Shake refer to the full QM [Installation Manual](#).

➤ For instructions on installing the QBase on Metal Shingle refer to the full QM [Installation Manual](#).






## LOW SLOPE ROOFS

### FLAT ROOF ATTACHMENT

Flat Roof Attachment can be used with an L-foot for flush mounting modules on low sloped roofs. Mark locations for Flat Roof Attachment. Screws should be installed symmetrically to each other. If using a membrane flashing, remove the silicone washer's protective liner prior to attaching the membrane. Attach L-foot with washers and 3/8" hardware torqued to **250 in-lbs (21 ft-lbs)**. Seal attachment and/or membrane per roofing manufacturer's requirements.

- **Type, size, and quantity of roof screws to be specified by Structural Engineer. Fastener size not to exceed #15.**
- **Membrane flashing available for TPO, PVC, and KEE roofs. Ensure membrane flashing is compatible with existing roofing material.**
- **If membrane flashing is not used, only washer on top of L-Foot is required.**
- Standalone [Flat Roof Attachment Manual](#) available on website.




### QM QBASE MOUNT

Locate the desired mount placement over a rafter. Using the base as a template, mark the two penetration points. Drill two 7/32" pilot holes, back fill with roofing manufacturers' approved sealant. Place the grade-8 hex bolt in the bottom of the base and screw the Post. Attach L-Foot on Standoff with hardware. Torque to **174 in-lbs (14.5 ft-lbs)**. Attach rail to L-Foot with Bonding Hardware and torque to **250 in-lbs (21 ft-lbs)**.

The mount can be flashed with available 9", 12" or 18" aluminum flashings, pitch pocket or curb, or with a membrane cone flashing. If using a membrane flashing utilize the services of a qualified roofer

- For additional details refer to the full [QM Installation Manual](#).




## METAL ROOF

### QM LYNX

Locate the desired mount placement over a roofing seam, make sure block is fully seated on metal seam. Torque Set Screws to **150 in-lbs(12.5 ft-lbs)** using 3/16" Hex Drive, alternate driving each bolt till required torque is met. Slide Hex Bolt into slot and to desired position. Place rail attachment bracket over Hex Bolt and secure with Flange Nut, torque Flange Nut to **150 in-lbs(12.5 ft-lbs)** using 1/2" socket.


- For additional details refer to the full [QM Installation Manual](#).
- Certification of Lynx calmp includes bonding to both painted and galvalume metal roofs.



## CONDUIT PENETRATION FLASHINGS

### QM CONDUIT PENETRATION FLASHING - COMP SHINGLE


Mark a drill point so that the flashing reaches up to the 3rd shingle course. Drill your conduit hole next to the rafter so you can secure the conduit below the roof surface. Cut shingle and remove nails as needed to center the drilled hole and flashing hole. Apply roofing manufacturer's approved sealant on the underside of the flashing in a Upside down U and to top of flashing. Under the 3rd course and through the second course secure flashing with 2 roofing nails, apply sealant over the nail heads. Cut EPDM collar to appropriate size. Apply a bead of sealant compatible with the roofing manufacturer and EPDM rubber to anywhere the EPDM collar contacts.



- Be sure to secure conduit to rafters below the roof surface per local building codes and NEC code requirements.
- Cut EPDM collar to appropriate size using the sizing chart in the installation manual, approved for 1/2" to 1" EMT.
- For additional details refer to the full QM [Installation Manual](#).

### QM CONDUIT PENETRATION FLASHING - TILE

Drill your conduit hole next to the rafter so that you can secure the conduit below the roof surface. Apply roofing manufacturer approved sealant to the underside of the sub-flashing in the shape of an upside down U. Clear away any dust and debris to install sub-flashing. Waterproof at under laminate level according to roofing manufacturer instructions and Tile Roofing Institute Guidelines. Under the top layer of felt, secure the sub-flashing with two roofing nails. Cut EPDM collar to appropriate size. Apply a bead of sealant compatible with the roofing manufacturer and EPDM rubber to anywhere the EPDM collar contacts. With a diamond blade cut tile to allow conduit to pass through, replace all tiles. Bend the flashing to follow the contour of the tiles. Place flashing over the conduit and tuck up under the next course of tiles. Apply a bead of sealant compatible with the roofing manufacturer and EPDM rubber to anywhere the EPDM collar contacts. Slide collar onto conduit all the way down to the flashing.




- Be sure to secure conduit to rafters below the roof surface per local building codes and NEC code requirements.
- Cut EPDM collar to appropriate size using the sizing chart in the installation manual, approved for 1/2" to 1" EMT.
- For additional details refer to the full QM [Installation Manual](#).

## CONDUIT MOUNT

### QM CONDUIT MOUNT - COMPOSITION SHINGLE

Place conduit mounts along path of conduit. Lift shingle above mount location and insert flashing into position. Mark center for drilling, remove flashing and drill pilot hole with 1/8" bit. Clean area, fill hole with roofing manufacturer's approved sealant. Lift shingle and slide Conduit Mount into place. Prepare the lag bolt with sealing washer and pipe clamp (not included). Insert lag through hole in block and drill with 7/16" socket until block is tight.


- Install mounts as required to support conduit across the roof.
- For additional details refer to the full QM [Installation Manual](#).



### QM CONDUIT MOUNT - TILE

Remove the tile that the mount will be installed on, and the tiles in the course above it. Lift the bottom of the tile and slide the bottom clamp over the bottom edge of the tile. Insert the 4" tap bolt through the slot into the threaded hole and use a 7/16" socket to thread the screw. Tighten until the top clamp hook end unbends and forms a 90 degree angle with the tile. Use the Cap Screw (included) to attach your pipe clamp (not included) to bottom clamp. Insert conduit and tighten with 7/16" socket.

- The clamp is reversible, use the wider hook end on tile greater than 1" thick and the thinner hook end on tiles less than 1" thick.
- The installation process is the same on curved tile, make sure that the Conduit Mount is installed on the crown (high point) of the tile.
- Install mounts as required to support conduit across the roof.
- For additional details refer to the full QM [Installation Manual](#).




## WIRE CLIPS

End Caps add a completed look and keep debris and pests from collecting inside rail.

Firmly press End Cap onto rail end.


- End Caps come in sets of left and right. Check that the proper amount of each has been provided.



## WIRE CLIPS

Wire Clips offer a simple wire management solution.

Firmly press Wire Clip into top rail slot. Run electrical wire through open clip. Snap closed once all wires have been placed.




## JAYBOX

### A.

Prior to installation, use step drill bit to place pass through holes for conduits or water-tight connectors. Drill bit starter locations are provided on the sides and front of enclosure.



- Do not install conduit facing up roof.



### B (Rail).



Use rail-specific MLPE mounting hardware to attach Rail Hangers to rail. Ensure junction box is pushed as close to the rail as possible. Torque to 80-in lbs (1/2" or 7/16" socket).

- Do not overtighten
- If installing in areas with ground snow loads greater than 40 psf, install JayBox under module directly next to module frame edge.




### B (Shingle).

Align sealing oval of box to align with mating feature on flashing. An EPDM foam gasket is pre-installed to the underside of the junction box to seal the flashing to the box without the need for additional sealant. Secure with supplied #12 x 1-3/4" deck screws (2x) until the junction box is pulled tight to the flashing. Do not over-tighten screws to avoid stripping screws in OSB.




- If installing pass through fittings, ensure that the JayBox and roof deck are both properly prepared. Complete installation process before attaching the Jaybox to the deck.
- Do not install JayBox under shingle seam as illustrated below.



### C.

Install wiring, conduit and fittings per NEC requirements and following local AHJ guidance. Using Philips Head Driver tighten the bolt.

- For additional details refer to the full QM [Installation Manual](#).





## MICROINVERTER KITS

Use IronRidge's Microinverter Kit to bond compatible microinverters and power optimizers to the racking system.

Insert Microinverter Kit T-bolt into top rail slot. Place compatible microinverter or power optimizer into position and tighten hex nut to **80 in-lbs**.

- If installing in areas with ground snow loads greater than 40 psf, install MLPE devices directly next to module frame edge

### COMPATIBLE PRODUCTS

#### Enphase

M250-72, 250-60, M215-60, C250-72, S230, S280, IQ 6, IQ 6+, IQ IQ7, IQ 7A, IQ 7+, IQ7 PD, IQ 7X, Q Aggregator; IQ8-60, IQ8PLUS-72, IQ8A-72, IQ8H-208-72, IQ8H-240-72, IQ8M-72, may be followed by -2-US

#### Darfon

MIG240, MIG300, G320, G640

#### Solar Edge

M1600, P300, P320, P340, P370, P400, P401, P405, P485, P505, P600, P700, P730, P750, P800p, P800s, P801, P850, P860, P950, P960, P1100, P1101, S440, S500, S1200, S1201

#### SMA

RoofCommKit-P2-US, TS4-R Module Retrofit Kits (TS4-R-S, TS4-R-O, TS4-R-F)

#### Tigo

Tigo Access Point (TAP)

TS4-R-X (where X can be F, M, O, or S)

TS4-R-X-DUO (where X can be M, O, or S)

TS4-A-X (where X can be F, 2F, O, O-DUO, or S)

#### Generac

S2502




#### AP Systems

DS3, QS1, QT2 and YC600

#### NEP

BDM-300, BDM-300X2 and BDM-800

- Remove Grounding Washer on AP Systems QS1, QT2, DS3 and YC600 inverters before installing to XR rails.
- Remove the Stainless Steel Clip on Tigo-"A" MLPE Devices before attaching to XR rails.
- Use the number of IronRidge Microinverter kits allowed by the MLPE mounting flange. Some will require 1 kit and others 2 kits.



## SYSTEMS USING ENPHASE MICROINVERTERS OR SUNPOWER AC MOD-

IronRidge systems using approved Enphase products or SunPower modules eliminate the need for lay-in lugs and field installed equipment grounding conductors (EGC). This solution meets the requirements of UL 2703 for bonding and grounding and is included in this listing.

### COMPATIBLE PRODUCTS

#### Sunpower

Modules with model identifier Ab-xxx-YY and InvisiMount (G5) 46mm frame; where "A" is either E, or X; "b" can be 17, 18, 19, 20, 21, or 22; and "YY" can be C-AC, D-AC, BLK-C-AC, or BLK-D-AC.

#### Enphase

Microinverters M250-72, M250-60, M215-60, C250-72, and Engage cables ETXX-240, ETXX-208, ETXX-277.

- A minimum of two inverters mounted to the same rail and connected to the same Engage cable are required.
- The microinverters or Sunpower AC modules must be used with a maximum 20 A branch rated overcurrent protection device (OCPD).
- If an AC module is removed from a circuit for maintenance, you must first disconnect AC power and then install a temporary EGC to bridge the gap by inserting an AC extension cable (or via other NEC-compliant means), in order to maintain effective ground continuity to subsequent modules.

## SYSTEMS USING MICROSTORAGE PRODUCTS

Use IronRidge's Microinverter Kit to bond compatible microstorage devices to the racking system. Insert Microinverter Kit T-bolt into top rail slot. Place compatible microstorage into position and tighten hex nut to **80 in-lbs**.

### COMPATIBLE PRODUCTS

#### PHAZR

PHAZR Devices PHAZR-X, where X is 6-12.

#### Solpad


Solpad Inverter model SI-1k

Solpad Battery Storage model SB-2K


Solpad Junction Box model SJB-4k

- Running a separate equipment grounding conductor to the PHAZR or Solpad devices is not required.
- If installing in areas with ground snow loads greater than 40 psf and underneath a module, install PHAZR and Solpad devices as close as possible to module frame edge.
- Solpad may only be installed on XR-100 and XR-1000
- Solpad may only be installed with modules having a frame thickness of 35mm or greater.
- Use the number of IronRidge Microinverter kits allowed by the microstorage mounting flange. Some will require 1 kit and others 2 kits.

PHAZR



Solpad



## FRAMELESS MODULE KITS

Insert Frameless Kit T-bolt in top rail slot. Place star washer over T-bolt, allowing it to rest on top of rail. Secure module clamps with a hex nut and torque to **80 in-lbs**.

### COMPATIBLE PRODUCTS

#### Sunforson

Sunforson silver or black SFS-UTMC-200(B) mid and SFS-UTEC-200(B) end clamps.



#### Sunpreme

Sunpreme silver or black mid and end clamps with part numbers 7500105X where "X" is 1, 5, 6 or 7.

#### Ironridge

IronRidge silver or black mid and end clamps with part numbers FMLS-XC-001-Y where "X" is E or M and "Y" is B or blank.

- Follow module manufacturer's installation instructions to install the module clamps.
- Frameless modules require using a Grounding Lug on every rail.
- For Sunpreme Modules Only: If required to use slide prevention hardware, see Module Slide Prevention Addendum (Version 1.10).



## Install Contour

Install Contour on a completed array.

**A.** Start by placing Contour Clamp on module frame within 12 inches of the down roof corner of the array. Each piece of 84" Contour Trim must be supported by two Clamps. Clamps must be installed in the 12" clamping zones at edge of trim. Once trim is placed and in position, secure trim by tightening Clamp set screw to **80 in-lbs**.

**B.** Multiple Contour pieces can be joined using Contour Splice. Install Splice on existing Contour edge and install Clamps in appropriate clamping zones for next piece of trim. Place trim on Clamps, slide into splice to join two pieces together. Secure Contour by tightening Clamp set screw to **80 in-lbs**. Repeat as needed across the array.




**C.** Cut trim to line up with edge of array.

**D.** Install Clamps within clamping zones on side of array. Install second Clamp as needed up array. Place Corner Cap on trim and slide side trim to align with Cap. Repeat as needed along roof for both inside and outside corners.


**E.** Use optional End Caps to cover any exposed edges of Contour as desired.

- Do not install on side of array facing roof peak.
- Contour can be installed with 1 clamp if trim section is 12" long (or shorter) and has a splice attached on one end, on which the section of trim the 12" section is spliced to also has 2 clamps.
- Contour Trim when installed when installed up roof requires the use of Aire Stealth Clamps.
- Wind Speed: no restrictions
- Ground Snow: up to 90 PSF


**A.**




**B.**




**C.**



**D.**



**E.**



## MODULE COMPATIBILITY

The Flush Mount System may be used to ground and/or mount a PV module complying with UL 2703 only when the specific module has been evaluated for grounding and/or mounting in compliance with the included instructions. Unless otherwise noted, "xxx" refers to the module power rating and both black and silver frames are included in the certification.

### FRAMED MODULE LIST

| MAKE             | MODELS  |
|------------------|---|
| Adani            | Adani modules with 35 and 40mm frames<br>ASX-Y-ZZ-xxx<br>Where "X" can be B, M or P; "Y" can be 6, 7 or M10 and "ZZ" can be blank, 144, PERC, B-PERC, or AB-PERC  |
| AIONRISE         | AIONRISE modules with 35 and 40mm frames<br>AIONyyG1-xxx<br>Where "yy" can be 60 or 72  |
| Amerisolar       | Amerisolar modules with 35 and 40 mm frames<br>AS-bYxxxZ<br>Where "b" can be 5 or 6; "Y" can be M, P, M27, P27, M30, or P30; and "Z" can be blank, W or WB  |
| Aptos Solar      | Aptos modules with 35 and 40 mm frames<br>DNA-yy-zzaa-xxx<br>Where "yy" can be 120 or 144; "zz" can be MF or BF; and "aa" can be 23 or 26   |
| Astronergy Solar | Astronergy modules with 30, 35 and 40 mm frames<br>aaSMbbyyC/zz-xxx<br>Where "aa" can be CH or A; "bb" can be 60, 66, or 72; "yy" can be blank, 10 or 12; "C" can be M, P, M(BL), M-HC, M(BL)-HC, P-HC, M(DG), or M(DGT); and "zz" can be blank, HV, F-B, or F-BH |
| ASUN             | ASUN modules with 35 and 40 mm frames<br>ASUN-xxx-YYZZ-aa<br>Where "YY" can be 60 or 72; "ZZ" can be M, or MH5; and "aa" can be blank or BB   |
| Auxin            | Auxin modules with 40 mm frames<br>AXN6y6zAxxxB<br>Where "y" can be M or P; "z" can be 08, 09, 10, 11, or 12; and "A" can be F, M or T; and "B" can be blank, A, B or C   |
| Axitec           | Axitec Modules with 30, 35 and 40 mm frames<br>AC-xxxY/aaZZb<br>Where "Y" can be M, P, MB or MH; "aa" can be blank, 125- or 156-; "ZZ" can be 54, 60, 72, 108, 120, or 144; "b" can be S, X, V, VB, XV, or MX   |
| Bluesun Solar    | Bluesun modules with 30 and 35mm frames<br>BSMxxxY-AAA<br>Where "Y" can be M or M10; and "AAA" can be 54HPH, 60HPH or 72HBD   |
| Boviet           | Boviet modules with 35 and 40mm frames<br>BVMZZaaYY-xxxBcc<br>Where "ZZ" can be 66 or 76; "aa" can be 9, 10 or 12; "YY" is M or P; and "B" can be blank, L or S; and "cc" can be blank, H, H-BF, H-BF-DG, H-HC, H-HC-BF, H-HC-BF-DG, HC-BF or HC-BF-DG            |
| BYD              | BYD modules with 35 mm frames<br>BYDxxxAY-ZZ<br>Where "A" can be M6, P6, MH or PH; "Y" can be C or K; and "ZZ" can be 30 or 36  |
| Canadian Solar   | Canadian Solar modules with 30, 32, 35 and 40 mm frames<br>CSbY-xxxZ<br>Where "b" can be 1, 3, 6 or 7 "Y" can be H, K, L, N, P, R, U, V, W, X or Y; and "Z" can be M, P, MS, PX, M-SD, P-AG, P-SD, MB-AG, PB-AG, MS-AG, MS-HL, or MS-SD                           |
| CertainTeed      | CertainTeed modules with 35 and 40 frames<br>CTxxxYZZ-AA<br>Where "Y" can be M, P, or HC; "ZZ" can be 00, 01, 10, or 11; and "AA" can be 01, 02, 03, 04 or 06   |



## MODULE COMPATIBILITY

|                 |   |
|-----------------|---|
| CSUN            | <p>Csun modules with 35 and 40 mm frames<br/>YYxxx-zzAbb<br/>Where "YY" is CSUN or SST; "zz" is blank, 60, or 72; and "A" is blank, P, M or MM; "bb" is blank, BB, 5BB, BW, or ROOF</p>   |
| Dehui           | <p>Dehui modules with 30, 35 and 40mm frames<br/>DH-MYYYZ-xxx<br/>Where "YYY" can be 760, 772, 860, 872; and "Z" can be B, F or W</p>   |
| Ecosolargy      | <p>Ecosolargy modules with 35 and 40 mm frames<br/>ECOxxxYzzA-bbD<br/>Where "Y" can be A, H, S, or T; "zz" can be 125 or 156; "A" can be M or P; "bb" can be 60 or 72; and "D" can be blank or B</p>  |
| ET Solar        | <p>ET Solar modules with 30, 35 and 40 mm frames<br/>ET-YZZZxxxAA<br/>Where "Y" can be P, L, or M; "ZZZ" can be 660, 660BH, 672, 672BH, 754BH, 766BH, 772BH; and "AA" can be GL, TB, TW, WB, WW, BB, WBG, WWG, WBAC, WBCO, WWCO, WWBCO or BBAC</p>  |
| Flex            | <p>Flex modules with 35 and 40 mm frames<br/>FXS-xxxYY-ZZ;<br/>Where "YY" can be BB or BC; and "ZZ" can be MAA1B, MAA1W, MAB1W, SAA1B, SAA1W, SAC1B, SAC1W, SAD1W, SBA1B, SBA1W, SBC1B, or SBC1W</p>  |
| Freedom Forever | <p>Freedom Forever modules with 35mm frames<br/>FF-MP-BBB-xxx</p>   |
| GCL             | <p>GCL modules with 35 mm and 40 mm frames<br/>GCL-ab/YY xxx<br/>Where "a" can be M or P; "b" can be 3 or 6; and "YY" can be 60, 72, 72H, or 72DH</p>   |
| GigaWatt Solar  | <p>Gigawatt modules with 40 mm frames<br/>GWxxxYY<br/>Where "YY" can be either PB or MB</p>   |
| Hansol          | <p>Hansol modules with 35 and 40 frames<br/>HSxxxYY-zz<br/>Where "YY" can be PB, PD, PE, TB, TD, UB, UD, or UE; and "zz" can be AH2, AN1, AN3, AN4, HH2, HV1, or JH2</p>  |
| Hanwa Solar     | <p>Hanwa Solar modules with 40 mm frames<br/>HSLaaP6-YY-1-xxxZ<br/>Where "aa" can be either 60 or 72; "YY" can be PA or PB; and "Z" can be blank or B</p>   |
| Hanwa Q CELLS   | <p>Hanwa Q CELLS Modules with 32, 35, 40mm frames<br/>aaYY-ZZ-xxx<br/>where "aa" can be Q. or B.; "YY" can be PLUS, PRO, PEAK, LINE PRO, LINE PLUS, PLUS DUO or PEAK DUO; and "ZZ" can be G3, G3.1, G4, G4.1, L-G2, L-G2.3, L-G3, L-G3.1, L-G3y, L-G4, L-G4.2, L-G4y, LG4.2/ TAA, BFR-G3, BLK-G3, BFR-G3.1, BLK-G3.1, BFR-G4, BFR-G4.1, BFR G4.3, BLK-G4.1, G4/SC, G4.1/SC, G4.1/TAA, G4.1/MAX, BFR G4.1/TAA, BFR G4.1/MAX, BLK G4.1/TAA, BLK G4.1/SC, EC-G4.4, G5, G5/ SC, G5/TS, BLK-G5, BLK-G5/SC, BLK-G5/TS, L-G5, L-G5.1, L-G5.2, L-G5.2/H, L-G5.3, G6, G6/SC, G6/TS, G6+/TS, G6+, BLK-G6, L-G6, L-G6.1, L-G6.2, L-G6.3, G7, BLK-G6+, BLK-G6+/AC, BLK-G6+/HL, BLK-G6+/ SC, BLK-G6/TS, BLK-G6+/TS, BLK-G7, G7.2, G8, BLK-G8, G8+, BLK-G8+ L-G7, L-G7.1, L-G7.2, L-G7.3, L-G8, L-G8.1, L-G8.2, L-G8.3, L-G8.3/BFF, L-G8.3/BFG, L-G8.3/BGT, ML-G9, BLK ML-G9, ML-G9+, BLK ML-G9+, BLK-G10+, BLK G10+/AC, ML-G10, BLK ML-G10, ML-G10+, BLK ML-G10+, ML-G10.a, BLK ML-G10.a, ML-G10.a+, BLK ML-G10.a+, XL-G9, XL-G9.2, XL-G9.3, XL-G9.3/BFG, XL-G10.2, XL-G10.3, XL-G10.c, XL-G10.d, XL-G10.d/BFG, XL-G10.3/BFG, XL-G11.2, XL-G11.3 or XL-G11.3/BFG</p> |
| Heliene         | <p>Heliene modules with 35 and 40 mm frames<br/>YYZZxxxA<br/>Where "YY" can be 36, 60, 72, 96, 120 or 144; "ZZ" can be HC, M, P, or MBLK; and "A" can be blank, HomePV, Bifacial, M10 Bifacial or M10 SL-Bifacial</p>   |
| HT-SAAE         | <p>HT-SAAE modules with 35 and 40 mm frames<br/>HTyy-aaaZ-xxx<br/>Where "yy" can be 60, 66, 72 or 78, "aaa" can be 18, 156 or 166, "Z" can be M, P, M-C, P-C, M(S), M(VS), M(V), P(V), M(V)-C, P(V)-C, or X</p>   |

## MODULE COMPATIBILITY

|                      |   |
|----------------------|---|
| Hyundai              | Hyundai modules with 32, 33, 35 and 40mm frames<br>HiY-SxxxZZ<br>Where "Y" can be A, D or S; "S" can be M or S; and "ZZ" can be GI, HG, HI, KI, MI, MF, MG, PI, RI, RG, RG(BF), RG(BK), SG, TI, TG, YH(BK) or XG(BK)  |
| Itek                 | Itek Modules with 40 mm frames<br>IT-xxx-YY<br>Where "YY" can be blank, HE, or SE, or SE72  |
| JA Solar             | JA Solar modules with 30, 35 and 40 mm frames<br>JAyzz-bbww-xxx/aa<br>Where "yy" can be M, P, M6 or P6; "zz" can be blank, (K), (L), (R), (V), (BK), (FA), (TG), (FA)(R), (L)(BK), (L)(TG), (R)(BK), (R)(TG), (V)(BK), (BK)(TG), or (L)(BK)(TG); "bb" can be 48, 54, 60, 66, 72 or 78; "ww" can be D09, D10, D20, D30, S01, S02, S03, S06, S09, S10, S12, S17, S20, S30 or S31; and "aa" can be BP, MB, MR, SI, SC, PR, 3BB, 4BB, 4BB/RE, 5BB |
| Jinko                | Jinko modules with 35 and 40 mm frames<br>JKMYxxxZZ-aa<br>Where "Y" can either be blank or S; "ZZ" can be M, P, or PP; and "aa" can be blank, 60, 60B, 60H, 60L, 60BL, 60HL, 60HB, 60HBL, 6HBL-EP, 60-J4, 60B-J4, 60B-EP, 60(Plus), 60-V, 60-MX, 6RL3, 6RL3-B, 6TL3-B, 7RL3-V, 7RL3-TV, 72, 72B, 72-J4, 72B-J4, 72(Plus), 72-V, 72H-V, 72L-V, 72HL-V, 72HL4-V, 72HL4-TV, 72-MX, 72H-BDVP, 72HL-TV, or 72HL-V-MX3                              |
| Kyocera              | Kyocera Modules<br>KYxxxZZ-AA<br>Where "Y" can be D or U; "ZZ" can be blank, GX, or SX; and "AA" can be LPU, LFU, UPU, LPS, LPB, LFB, LFBS, LFB2, LPB2, 3AC, 3BC, 3FC, 4AC, 4BC, 4FC, 4UC, 5AC, 5BC, 5FC, 5UC, 6BC, 6FC, 8BC, 6MCA, or 6MPA   |
| LG                   | LG modules with 35 and 40 mm frames<br>LGxxxYaZ-bb<br>Where "Y" can be A, E, M, N, Q, S; "a" can be A, 1, 2 or 3 "Z" can be C, K, T, or W; and "bb" can be A3, A5, A6, B3, B6, E6, E6.AW5, G3, G4, J5, K4, L5, N5, V5, V6   |
| Longi                | Longi modules with 30, 35 and 40 mm frames<br>LRa-YYZZ-xxxM<br>Where "a" can be 4, 5 or 6; "YY" can be blank, 60, 66, or 72; and "ZZ" can be blank, BK, BP, HV, PB, PE, PH, HBD, HIB, HIH, HPB, HPH, or HIBD  |
| Maxeon               | Maxeon modules with 35, 40 and 46mm frames<br>SPR-AAAY-xxx-zzz<br>Where "AAA" can be MAX, P or X; "Y" can be 3, 5, 6, 21 or 22; and "zzz" can be BLK, COM or UPP  |
| Meyer Burger         | Meyer Burger Modules with 35mm frames<br>Meyer Burger Black or White  |
| Mission Solar        | Mission Solar modules with 33, 35 and 40 mm frames<br>YYYbb-xxxZZaa<br>Where "YYY" can be MSE or TXS; "bb" can be blank, 6 or 60A; "ZZ" can be blank, MM, SE, SO, SQ, SR, SX, TS, 120 or 144; and "aa" can be blank, BB, BW, 1J, 4J, 4S, 5K, 5R, 5T, 60, 6J, 6S, 6W, 6Z, 8K, 8T, or 9S  |
| Mitsubishi           | Mitsubishi modules<br>PV-MYYxxxZZ<br>Where "YY" can be LE or JE; and "ZZ" can be either HD, HD2, or FB  |
| Moltech              | IM and XS series modules with 40 mm frames  |
| Next Energy Alliance | Next Energy Alliance modules with 35 and 40mm frames<br>yyNEA-xxxZZ<br>where "yy" can be blank or US; "ZZ" can be M, MB or M-60   |
| Neo Solar Power      | Neo Solar Power modules with 35 mm frames<br>D6YxxxZZaa<br>Where "Y" can be M or P; "ZZ" can be B3A, B4A, E3A, E4A, H3A, H4A; and "aa" can be blank, (TF), ME or ME (TF)  |

## MODULE COMPATIBILITY

|                      |   |
|----------------------|---|
| Panasonic (HIT)      | Panasonic modules with 35 and 40 mm frames<br>VBHNxxxYYzzA<br>Where "YY" can be either KA, RA, SA or ZA; "zz" can be either 01, 02, 03, 04, 06, 06B, 11, 11B, 15, 15B, 16, 16B, 17, or 18; and "A" can be blank, E, G, or N                                   |
| Panasonic (EverVolt) | Panasonic modules with 30 mm frames<br>EVPVxxxA<br>Where "A" can be blank or H, K or PK   |
| Peimar               | Peimar modules with 40 mm frames<br>SbxxxYzz<br>Where "b" can be G, M or P; "Y" can be M or P; and "zz" can be blank, (BF) or (FB)  |
| Philadelphia Solar   | Philadelphia modules with 35 and 40 mm frames<br>PS-YzzAA-xxx<br>Where "Y" can be M or P; "zz" can be 60, 72 or 144; and "AA" can be blank, (BF), (HC) or (HCBF)  |
| Phono Solar          | Phono Solar modules with 30, 35 and 40mm frames<br>PSxxxY-ZZ/A<br>Where "Y" can be M, M1, MH, M1H, M4, M4H, M5GF, M5GFH, M6, M6H, M8GF, M8GFH or P; "ZZ" can be 18, 20 or 24; and "A" can be F, T, TH, U, UH, UHB, VH or VHB                                  |
| Prism Solar          | Prism Solar modules with 35mm frames<br>PST-xxxW-M72Y<br>Where "Y" can be H, HB or HBI  |
| Recom                | Recom modules with 35 and 40 mm frames<br>RCM-xxx-6yy<br>Where "yy" can be MA, MB, ME or MF   |
| REC Solar            | REC modules with 30 and 38 mm frames<br>RECxxxYYZZ<br>Where "YY" can be AA, M, NP, NP2, PE, PE72, TP, TP2, TP2M, TP2SM, TP2S, TP3M or TP4; and "ZZ" can be blank, Black, BLK, BLK2, SLV, 72, or Pure  |
| Renesola             | ReneSola modules with 35 and 40 mm frames<br>AAxxxY-ZZ<br>Where "AA" can be SPM(SLP) or JC; "Y" can be blank, F, M or S; and "ZZ" can be blank, Ab, Ab-b, Abh, Abh-b, Abv, Abv-b, Bb, Bb-b, Bbh, Bbh-b, Bbv, Bbv-b, Db, Db-b, or 24/Bb                        |
| Renogy               | Renogy Modules with 40 mm frames<br>RNG-xxxY<br>Where "xxx" is the module power rating; and "Y" can be D or P   |
| Risen                | Risen Modules with 30, 35 and 40 mm frames<br>RSMyy-a-xxxZZ<br>Where "yy" can be 60, 72, 110, 120, 132 or 144; "a" can be 6, 7 or 8; and "ZZ" can be M, P or BMDG   |
| S-Energy             | S-Energy modules with 35 and 40mm frames<br>SABB-CCYYY-xxxZ<br>Where "A" can be C, D, L or N; "BB" can be blank, 20, 25, 40 or 45; "CC" can be blank, 60 or 72; "YYY" can be blank, BDE, MAE, MAI, MBE, MBI, MCE or MCI; and "Z" can be V, M-10, P-10 or P-15 |
| SEG Solar            | SEG Solar with 30, 35 and 40 mm frames<br>SEG-aYY-xxxZZ<br>Where "a" can be blank, 6 or B; "YY" can be blank, MA, MB, PA, or PB; and "ZZ" can be blank, BB, BG, BW, HV, WB, WW, BMB, BMA-HV, BMA-BG, BMA-TB, BMB-TB, BMB-HV, BMD-HV, BMB-BG                   |
| Seraphim USA         | Seraphim modules with 30, 35 and 40 mm frames<br>SRP-xxx-YYY-ZZ<br>Where "xxx" is the module power rating; and "YYY" can be BMA, BMD, 6MA, 6MB, 6PA, 6PB, 6QA-XX-XX, and 6QB-XX-XX; ZZ is blank, BB, BG or HV   |
| Sharp                | Sharp modules with 35 and 40 mm frames<br>NUYYxxx<br>Where "YY" can be SA or SC   |

## MODULE COMPATIBILITY

|                     |   |
|---------------------|---|
| Shinsung E&G        | Shinsung Modules with 35mm frames<br>SSVxxx-144MH   |
| Silfab              | Silfab Modules with 35 and 38 mm frames<br>SYY-Z-xxxAb<br>Where "YY" can be IL, SA, LA, SG or LG; "Z" can be blank, M, P, or X; "A" can be blank, B, H, M, N; and "b" can be A, C, G, K, L, N, T, U or X  |
| Solaria             | Solaria modules with 35 and 40 mm frames<br>PowerA-xxxY-ZZ<br>Where "A" can be X or XT, "Y" can be R or C; and "ZZ" can be blank, AC, BD, BX, BY, PD, PL, PM, PM-AC, PX, PZ, WX or WZ   |
| Solarcity (Tesla)   | Solarcity modules with 40 mm frames<br>SCxxxYY<br>Where "YY" can be blank, B1 or B2   |
| SolarTech           | SolarTech modules with 40 mm frames<br>AAA-xxxYY<br>Where "AAA" can be PERCB-B, PERCB-W, HJT B-B, HJT B-W or STU; "YY" can be blank, PERC or HJT  |
| SolarWorld AG       | SolarWorld Sunmodule Plus, Protect, Bisun, XL, Bisun XL, may be followed by mono, poly, duo, black, bk, or clear; modules with 31 and 33 mm frames<br>SW-xxx  |
| SolarWorld Americas | SolarWorld Sunmodule Plus, Protect, Bisun, XL, Bisun XL, may be followed by mono, poly, duo, black, bk, or clear; modules with 33 mm frames<br>SWA-xxx  |
| Sonali              | Sonali Modules with 35 and 40 mm frames<br>SS-M-xxx<br>Where "M" can be blank or M  |
| Stion               | Stion Thin film modules with 35 mm frames<br>STO-xxx or STO-xxxA  |
| SunEdison           | SunEdison Modules with 35 and 40 mm frames<br>SE-YxxxZABCDE<br>Where "Y" can be B, F, H, P, R, or Z; "Z" can be 0 or 4; "A" can be B,C,D,E,H,I,J,K,L,M, or N ; "B" can be B or W; "C" can be A or C; "D" can be 3, 7, 8, or 9; and "E" can be 0, 1 or 2                                   |
| Suniva              | Suniva modules with 35, 38 and 40 mm frames<br>OPTxxx-AA-B-YYY-Z<br>MVXxxx-AA-B-YYY-Z<br>Where "AA" is either 60 or 72; "B" is either 4 or 5; "YYY" is either 100,101,700,1B0, or 1B1; and "Z" is blank or B  |
| Sunmac Solar        | Sunmac Solar modules with 30 and 35mm frames<br>SMxxxMaaaZZ-BB<br>Where "aaa" can be 660 or 754; and "ZZ" can be NH or SH   |
| Sunpower            | Sunpower standard (G3 or G4) or InvisiMount (G5) 35 and 40mm frames<br>SPR-Zb-xxx-YY<br>Where "Z" can be A, E, M, P or X; "b" can be blank, 17, 18, 19, 20, 21, or 22; and "YY" can be blank, BLK, COM, C-AC, D-AC, E-AC, BLK-E-AC, G-AC, BLK-G-AC, H-AC, BLK-H-AC, BLK-C-AC, or BLK-D-AC |
| Sunspark            | Sunspark modules with 40 mm frames<br>SYY-xxxZ-A<br>Where "YY" can be MX or ST; and "Z" can be M, MB, M3, M3B, P or W; and "A" can be 60 or 72  |
| Suntech             | Suntech Modules with 35 and 40mm frames<br>STPxxx-y-zz/aa<br>Where "y" is blank or S; and "zz" can be 20, 24, A60, A72U, B60 or B72; and "aa" can be Vd, Vem, Vfw, Vfh, Vnh, Wdb, Wde, Wd, Wfhb or Wnhb   |
| Talesun             | Talesun modules with 30, 35 and 40mm frames<br>TAByZZaa-xxx-b<br>Where "A" can be D or P; "B" can be 6 or 7; "y" can be blank, F, G, H, I or L; "ZZ" can be 60, 66, 72 or 78; "aa" can be M, M(H), or P; and "b" can be blank, B, T, or (H)   |

## MODULE COMPATIBILITY

|          |  |
|----------|--|
| Tesla    | <p>Tesla modules with 40 mm frames<br/>TxxxY<br/>Where "Y" can be H or S</p>   |
| Trina    | <p>Trina Modules with 30, 35 and 40mm frames<br/>TSM-xxxYYZZ<br/>Where "YY" can be DD05, DD06, DD14, DE14, DE15, DE15V, DEG15, DEG15VC, DE18M, DEG18MC, DE09, DE19, DEG19C.20, DE06X, PA05, PC05, PD05, PD06, PA14, PC14, PD14, PE14, or PE15 ; and "ZZ" can be blank, .05, .05(II), .08, .08(II), .10, .18, .08D, .18D, 0.82, .002, .00S, 05S, 08S, .20(II), A, A.05, A.08, A.10, A.18, (II), A(II), A.05(II), A.08(II), A.082(II), A.10(II), A.18(II), C.05, C.07, C.05(II), C.07(II), H, H(II), H.05(II), H.08(II), HC.20(II), HC.20(II), M, M(II), M.05(II), MC.20(II)</p> |
| URE      | <p>URE modules with 35 mm frames<br/>DyZxxxxa<br/>Where "D" can be D or F, "y" can be A, B, 6 or 7; "Z" can be K or M; and "aa" can be C8G, H3A, H4A, H8A, E7G-BB, E8G, E8G-BB or MFG-BB</p>   |
| Vikram   | <p>Vikram solar modules with 35 and 40 mm frames<br/>XVSyy.ZZ.AAA.bb<br/>Where "X" can be blank, Paradea, Prexos or Somera; "yy" can be M, P, MBB, MDH, MDHT, MH, MS, MHBB, or PBB; "ZZ" can be 60 or 72; "AAA" is the module power rating; and "bb" can be 03, 04 or 05</p>   |
| VSUN     | <p>VSUN modules with 30, 35 and 40 mm frames<br/>VSUNxxx-YYz-aa<br/>Where "YY" can be 60, 72, 108, 120, or 144; "z" can be M, P, MH, PH, or BMH; and "aa" can be blank, BB, BW, or DG</p>  |
| Waaree   | <p>Waaree modules with 40mm frames<br/>AAyy-xxx<br/>Where "AA" can be WS or Bi; and "yy" can be blank, M, MB, 55 or 66</p>   |
| Winaico  | <p>Winaico modules with 35 and 40 mm frames<br/>Wsy-xxxZa<br/>Where "y" can be either P or T; "Z" can be either M, P, or MX; and "a" can be blank or 6</p>   |
| Yingli   | <p>Yingli modules with 35 and 40 mm frames<br/>YLxxxZ-yy<br/>Where "Z" can be D or P; "yy" can be 29b, 30b, 34d, 35b, 36b or 40d</p>   |
| ZN Shine | <p>ZN Shine modules with 35mm frames<br/>ZXMY-AAA-xxx/M<br/>Where "Y" can be 6, 7 or 8; "AAA" can be 72, NH120, NH144, NHDB144, NHLDD144, SH144, SHDB144, SHLDD144 or TP120</p>  |



# MODULE COMPATIBILITY

## FRAMELESS MODULE LIST

| MAKE             | MODELS  |
|------------------|---|
| Astronergy Solar | Astronergy frameless modules<br>CHSM6610P(DG)-xxx   |
| Canadian Solar   | Canadian Solar frameless modules<br>CSbY-xxx-Z<br>Where "b" can be 3 or 6; "Y" is K, P, U, or X; and "Z" can be M-FG, MS-FG, P-FG, MB-FG, or PB-FG  |
| Heliene          | Heliene frameless modules<br>YYZZxxxA<br>Where "YY" can be 72; "ZZ" can be M; and "A" can be GH   |
| Jinko            | Jinko frameless modules<br>JKMxxxPP-DV  |
| Prism Solar      | Prism Solar frameless modules<br>BZYY-xxxAAA<br>Where "Z" can be i or N; "YY" can be 48, 60, 60S, 72 or 72S; and "AAA" can be blank or BSTC   |
| Risen            | Risen frameless modules<br>RSMyy-6-xxxZZ<br>Where "yy" can be 60, 72, 120 or 144; and "ZZ" can be MDG or PDG  |
| Stion            | Stion frameless modules<br>STL-xxx or STL-xxxA  |
| Sunpreme         | Sunpreme frameless modules<br>GXB-xxxYY<br>Where "YY" can be blank or SL  |
| Trina            | Trina frameless modules<br>TSM-xxxYY<br>Where "YY" can be either DEG5(II), DEG5.07(II), DEG5.40(II), DEG5.47(II), DEG14(II), DEG14C(II), DEG14C.07(II), DEG14.40(II), PEG5, PEG5.07, PEG5.40, PEG5.47, PEG14, or PEG14.40 |