


| ABBREVIATIONS  | ELECTRICAL NOTES  | JURISDICTION NOTES   |          |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
|--|---|--|----------|-----|----|------|----------|-------|------|------|----------|---|---|---|---|-------|----|-----------|---|---|---|---|---|---|---|---|---|
| <p>A AMPERE AC ALTERNATING CURRENT BLDG BUILDING CONC CONCRETE DC DIRECT CURRENT EGC EQUIPMENT GROUNDING CONDUCTOR (E) EXISTING EMT ELECTRICAL METALLIC TUBING FSB FIRE SET-BACK GALV GALVANIZED GEC GROUNDING ELECTRODE CONDUCTOR GND GROUND HDG HOT DIPPED GALVANIZED I CURRENT Imp CURRENT AT MAX POWER I<sub>sc</sub> SHORT CIRCUIT CURRENT kVA KILOVOLT AMPERE kW KILOWATT LBW LOAD BEARING WALL MIN MINIMUM (N) NEW NEUT NEUTRAL NTS NOT TO SCALE OC ON CENTER PL PROPERTY LINE POI POINT OF INTERCONNECTION PV PHOTOVOLTAIC SCH SCHEDULE S STAINLESS STEEL STC STANDARD TESTING CONDITIONS TYP TYPICAL UPS UNINTERRUPTIBLE POWER SUPPLY V VOLT V<sub>mp</sub> VOLTAGE AT MAX POWER V<sub>oc</sub> VOLTAGE AT OPEN CIRCUIT W WATT 3R NEMA 3R, RAIN TIGHT</p> | <p>1. THIS SYSTEM IS GRID-INTERTIED VIA A UL-LISTED POWER-CONDITIONING INVERTER.<br/> 2. A NATIONALLY – RECOGNIZED TESTING LABORATORY SHALL LIST ALL EQUIPMENT IN COMPLIANCE WITH ART. 110.3.<br/> 3. WHERE ALL TERMINALS OF THE DISCONNECTING MEANS MAY BE ENERGIZED IN THE OPEN POSITION, A SIGN WILL BE PROVIDED WARNING OF THE HAZARDS PER ART. 690.17.<br/> 4. EACH UNGROUNDED CONDUCTOR OF THE MULTIWIRE BRANCH CIRCUIT WILL BE IDENTIFIED BY PHASE AND SYSTEM PER ART. 210.5.<br/> 5. CIRCUITS OVER 250V TO GROUND SHALL COMPLY WITH ART. 250.97, 250.92(B).<br/> 6. DC CONDUCTORS EITHER DO NOT ENTER BUILDING OR ARE RUN IN METALLIC RACEWAYS OR ENCLOSURES TO THE FIRST ACCESSIBLE DC DISCONNECTING MEANS PER ART. 690.31(E).<br/> 7. ALL WIRES SHALL BE PROVIDED WITH STRAIN RELIEF AT ALL ENTRY INTO BOXES AS REQUIRED BY UL LISTING.<br/> 8. MODULE FRAMES SHALL BE GROUNDED AT THE UL – LISTED LOCATION PROVIDED BY THE MANUFACTURER USING UL LISTED GROUNDING HARDWARE.<br/> 9. MODULE FRAMES, RAIL, AND POSTS SHALL BE BONDED WITH EQUIPMENT GROUND CONDUCTORS.</p> | <h3>VICINITY MAP</h3>   |          |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| <h3>LICENSE</h3>   | <h3>GENERAL NOTES</h3> <p>1. ALL WORK SHALL COMPLY WITH THE 2018 NORTH CAROLINA RESIDENTIAL CODE.<br/> 2. ALL ELECTRICAL WORK SHALL COMPLY WITH THE 2017 NATIONAL ELECTRIC CODE.</p>  | <h3>INDEX</h3> <p>Sheet 1 COVER SHEET<br/> Sheet 2 SITE PLAN<br/> Sheet 3 STRUCTURAL VIEWS<br/> Sheet 4 UPLIFT CALCULATIONS<br/> Sheet 5 THREE LINE DIAGRAM<br/> Cutsheets Attached</p> <table border="1" data-bbox="2449 1554 3039 1739"> <thead> <tr> <th>REV</th> <th>BY</th> <th>DATE</th> <th>COMMENTS</th> </tr> </thead> <tbody> <tr> <td>REV A</td> <td>NAME</td> <td>DATE</td> <td>COMMENTS</td> </tr> <tr> <td>*</td> <td>*</td> <td>*</td> <td>*</td> </tr> <tr> <td>REV C</td> <td>RA</td> <td>4/12/2024</td> <td>*</td> </tr> <tr> <td>*</td> <td>*</td> <td>*</td> <td>*</td> </tr> <tr> <td>*</td> <td>*</td> <td>*</td> <td>*</td> </tr> </tbody> </table> |          | REV | BY | DATE | COMMENTS | REV A | NAME | DATE | COMMENTS | * | * | * | * | REV C | RA | 4/12/2024 | * | * | * | * | * | * | * | * | * |
| REV  | BY  | DATE   | COMMENTS |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| REV A  | NAME  | DATE   | COMMENTS |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| *  | *   | *  | *        |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| REV C  | RA  | 4/12/2024  | *        |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| *  | *   | *  | *        |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| *  | *   | *  | *        |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |
| <p>MODULE GROUNDING METHOD: ZEP SOLAR</p>  | <p>AHJ: Harnett County</p>  | <p>Maxar Technologies, U.S. Geological Survey, USDA/FPAC/GEO</p>   |          |     |    |      |          |       |      |      |          |   |   |   |   |       |    |           |   |   |   |   |   |   |   |   |   |

CONFIDENTIAL – THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00

MOUNTING SYSTEM:  
ZS Comp V4 w Flashing-Insert

MODULES:  
(37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405

INVERTER:  
Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER:  
Myron Adams  
219 Harvell Rd  
Coats, NC 27521

9105917506

DESCRIPTION:  
14.985 KW PV ARRAY  
11.5 KW (AC NAMEPLATE) PV ARRAY  
54 KWH ENERGY STORAGE SYSTEM


PAGE NAME:  
COVER SHEET

DESIGN:  
Ricky Alvarez

SHEET: 1 REV: C DATE: 4/12/2024



PV ARRAY DEAD LOAD = 3 LBS/SF



|     |   |
|-----|---|
| MP1 | PITCH: 30° (7:12) ARRAY PITCH: 30° (7:12)<br>AZIMUTH: 247 ARRAY AZIMUTH: 247<br>MATERIAL: Comp Shingle STORY: 2 Stories |
| MP4 | PITCH: 30° (7:12) ARRAY PITCH: 30° (7:12)<br>AZIMUTH: 67 ARRAY AZIMUTH: 67<br>MATERIAL: Comp Shingle STORY: 2 Stories   |

### LEGEND

- (E) UTILITY METER & WARNING LABEL
- INVERTER W/ INTEGRATED DC DISCO & WARNING LABELS
- AUTOMATIC RELAY
- DC DISCONNECT & WARNING LABELS
- AC DISCONNECT & WARNING LABELS
- DC JUNCTION/COMBINER BOX & LABELS
- ENERGY STORAGE SYSTEM FOR STAND ALONE OPERATION
- DISTRIBUTION PANEL & LABELS
- LOAD CENTER & WARNING LABELS
- DEDICATED PV SYSTEM METER
- RAPID SHUTDOWN
- STANDOFF LOCATIONS
- CONDUIT RUN ON EXTERIOR
- CONDUIT RUN ON INTERIOR
- GATE/FENCE
- HEAT PRODUCING VENTS ARE RED
- INTERIOR EQUIPMENT IS DASHED

### SITE PLAN

Scale: 1/16" = 1'



CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00

MOUNTING SYSTEM:  
ZS Comp V4 w Flashing-Insert

MODULES:  
(37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405

INVERTER:  
Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER:  
Myron Adams  
219 Harvell Rd  
Coats, NC 27521

9105917506


DESCRIPTION:  
14.985 KW PV ARRAY  
11.5 KW (AC NAMEPLATE) PV ARRAY  
54 KWH ENERGY STORAGE SYSTEM

PAGE NAME:  
SITE PLAN


DESIGN:  
Ricky Alvarez

SHEET: 2 REV: C DATE: 4/12/2024





**SV** **TYPICAL PV SIDE VIEW**  
NTS



CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00

MOUNTING SYSTEM:  
ZS Comp V4 w Flashing-Insert

MODULES:  
(37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405

INVERTER:  
Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER:  
Myron Adams  
219 Harvell Rd  
Coats, NC 27521

9105917506

DESCRIPTION:  
14.985 KW PV ARRAY  
11.5 KW (AC NAMEPLATE) PV ARRAY  
54 KWH ENERGY STORAGE SYSTEM

PAGE NAME:  
STRUCTURAL VIEWS

DESIGN:  
Ricky Alvarez

SHEET: 3 REV: C DATE: 4/12/2024



| Jobsite Specific Design Criteria |       |           |              |
|----------------------------------|-------|-----------|--------------|
| Design Code                      |       | ASCE 7-10 |              |
| Risk Category                    |       | II        | Table 1.5-1  |
| Ultimate Wind Speed              | V-Ult | 120       | Fig. 1609A   |
| Exposure Category                |       | C         | Section 26.7 |
| Ground Snow Load                 | pg    | 20        | Table 7-1    |

| MP Specific Design Information   |                              |                              |
|--|------------------------------|------------------------------|
| MP Name  | MP1                          | MP4                          |
| Roofing  | Comp Shingle                 | Comp Shingle                 |
| Standoff   | ZS Comp V4 w Flashing-Insert | ZS Comp V4 w Flashing-Insert |
| Pitch  | 30                           | 30                           |
| SL/RLL: PV   | 9.2                          | 9.2                          |
| SL/RLL: Non-PV   | 17.0                         | 17.0                         |
| Edge Zone Width  | 5.9 ft                       | 5.9 ft                       |
| Azimuth  | 247                          | 67                           |
| Stories  | 2                            | 2                            |
| Rafter Size/Spacing  | 2x6 @24" OC                  | 2x6 @24" OC                  |
| CJ Size/Spacing  | 2x6 @24" OC                  | 2x6 @24" OC                  |
| Standoff Spacing and Layout  |                              |                              |
| MP Name  | MP1                          | MP4                          |
| Applied Wind Zones <sub>2</sub>  | All □                        | All □                        |
| Wind Pressure  | -19.02                       | -19.02                       |
| Landscape X-Spacing  | 72                           | 72                           |
| Landscape X-Cantilever   | 24                           | 24                           |
| Landscape Y-Spacing  | 41                           | 41                           |
| Landscape Y-Cantilever   | -                            | -                            |
| Portrait X-Spacing   | 48                           | 48                           |
| Portrait X-Cantilever  | 16                           | 16                           |
| Portrait Y-Spacing   | 74                           | 74                           |
| Portrait Y-Cantilever  | -                            | -                            |
| Layout   | Staggered                    | Staggered                    |
| Notes:<br>1. X and Y are maximums that are always relative to the structure framing that supports the PV. X is across rafters and Y is along rafters.<br>2. Hatching in Applied Wind Zone rows corresponds to hatching on Site Plan.<br>3. Table lists consistent conservative standoff specifications and layout requirements across all wind zones to comply with the maximum wind pressure of any zone. |                              |                              |

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00

MOUNTING SYSTEM:  
ZS Comp V4 w Flashing-Insert

MODULES:  
(37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405

INVERTER:  
Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER:  
Myron Adams  
219 Harvell Rd  
Coats, NC 27521

9105917506


DESCRIPTION:  
14.985 KW PV ARRAY  
11.5 KW (AC NAMEPLATE) PV ARRAY  
54 KWH ENERGY STORAGE SYSTEM

PAGE NAME:  
UPLIFT CALCULATIONS

DESIGN:  
Ricky Alvarez

SHEET: 4 REV: C DATE: 4/12/2024

TESLA



**Emergency Stop Button (E-Stop)**

- Rapid Shutdown Initiation Device per Article 690.12(C) of the NEC
- Disconnecting Means as defined in Article 100 of the NEC
- Connection to generation sources with 12V, 1A communication wire

1. CONDUIT RUNS MAY BE CONDENSED DUE TO SITE CONDITIONS AND/OR INSTALLATION EASE. ALL CONDUIT FILL DERATES AND PROPER CALCULATIONS HAVE BEEN COMPLETED PER NEC CHAPTER 9, TABLE 4.
2. SOLAR SHUTDOWN DEVICE TO BE INSTALLED FOR SYSTEM RAPID SHUTDOWN (RSD) IN ACCORDANCE WITH ARTICLE 690 OF THE APPLICABLE NEC.
3. CONDUIT TYPE CAN CHANGE DUE TO SITE CONDITIONS AND WILL FOLLOW THE NEC REQUIREMENTS FOR THAT CONDUIT TYPE.

| PARTS |                    | DC CONDUCTOR TABLE   |   |                   |         |                |               |           |           |           |             | STRING TABLE |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-------|--------------------|--|---|-------------------|---------|----------------|---------------|-----------|-----------|-----------|-------------|--------------|--------------------|----------------|------------|-----------|----------------|--|--|--|--|--|-----|------|-----|------------|-------------------|---------|--|-------------|-----------|-----------|--|--|--|------|------|------|------|--|--|--|---|---|---------------------------|---|--------|---|-----|-----|-----|----------|--------|-----|----|-----|---|---|---|---|--------|---|------|------|-----|--------|--------|------|---|-----|---|------------------|---|--------|---|-----|-----|-----|--------|--------|-------|---|-----|---|---|---|---|--------|---|------|------|-----|--------|--------|------|---|-----|---|-------------------------------------|---|--------|---|------|------|-----|--------|--------|-----|---|-----|---|----|----------------------|---|--------|---|------|------|-----|--------|--------|------|---|-----|---|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|---|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|---|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| Ref   | Qty                | Description  | Ref   | Type              | Qty     | Size (AWG, Cu) | EGC (AWG, Cu) | Conduit   | Isc (ADC) | Imp (ADC) | Product Ref | String Ref   | Module per String  | MCI per String | Voc* (VDC) | Vmp (VDC) | Mounting Plane |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| B     | 1                  | Tesla # 1841000-01-C: Back-up Gateway 3.0 NA for PW  | 1   | PV Wire           | 2       | #10            | #10           | 3/4" EMT  | 11.17     | 10.83     | E           | S1A          | 8                  | 3              | 400.91     | 299.12    | MP1            |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| C     | 1                  | Disconnect; 200A, 240Vac, Fusible, NEMA 3R: 2P, 3W, Lockable                               | 2   | PV Wire           | 2       | #10            | #10           | 3/4" EMT  | 22.34     | 21.66     |             | S1B          | 8                  | 3              | 400.91     | 299.12    | MP1            |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|       | 1                  | Ground/Neutral Kit; 200A General, Heavy Duty (DG, DH), NEMA 1, 3R                          | <table border="1"> <thead> <tr> <th colspan="10">AC CONDUCTOR TABLE</th> </tr> <tr> <th>Ref</th> <th>Type</th> <th>Qty</th> <th>Size (AWG)</th> <th>Min EGC (AWG, Cu)</th> <th colspan="2">Conduit</th> <th>Length (ft)</th> <th>Imp (AAC)</th> <th>Vmp (VAC)</th> </tr> <tr> <td></td> <td></td> <td></td> <td>(Cu)</td> <td>(Al)</td> <td>(Cu)</td> <td>(Al)</td> <td></td> <td></td> <td></td> </tr> </thead> <tbody> <tr> <td>D</td> <td>4</td> <td>Breaker; 60A/2P, 2 Spaces</td> <td>3</td> <td>THWN-2</td> <td>3</td> <td>#06</td> <td>#04</td> <td>#10</td> <td>3/4" EMT</td> <td>1" EMT</td> <td>5ft</td> <td>48</td> <td>240</td> </tr> <tr> <td rowspan="2">E</td> <td>1</td> <td>Load Center; 400A, 120/240V, NEMA 3R: Main Lug, 1 a, 12 Spaces, 24 Circuits</td> <td>4</td> <td>THWN-2</td> <td>3</td> <td>#2/0</td> <td>#4/0</td> <td>#06</td> <td>2" PVC</td> <td>2" PVC</td> <td>10ft</td> <td>-</td> <td>240</td> </tr> <tr> <td>1</td> <td>Class R Fuse Kit</td> <td>5</td> <td>THWN-2</td> <td>3</td> <td>#06</td> <td>#04</td> <td>#10</td> <td>1" EMT</td> <td>1" EMT</td> <td>100ft</td> <td>-</td> <td>240</td> </tr> <tr> <td rowspan="2">F</td> <td>2</td> <td>EE-000550-001 MC4 Y-Connector, Receptacle</td> <td>6</td> <td>THWN-2</td> <td>3</td> <td>#2/0</td> <td>#4/0</td> <td>#06</td> <td>2" PVC</td> <td>2" PVC</td> <td>20ft</td> <td>-</td> <td>240</td> </tr> <tr> <td>2</td> <td>EE-000550-000 MC4 Y-Connector, Plug</td> <td>7</td> <td>THWN-2</td> <td>3</td> <td>#2/0</td> <td>#4/0</td> <td>#06</td> <td>2" PVC</td> <td>2" PVC</td> <td>5ft</td> <td>-</td> <td>240</td> </tr> <tr> <td>G</td> <td>13</td> <td>Tesla MCI, 650V, 12A</td> <td>8</td> <td>THWN-2</td> <td>3</td> <td>#2/0</td> <td>#4/0</td> <td>#06</td> <td>2" PVC</td> <td>2" PVC</td> <td>10ft</td> <td>-</td> <td>240</td> </tr> <tr> <td>H</td> <td>3</td> <td>Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh</td> <td colspan="15"></td> </tr> <tr> <td>I</td> <td>1</td> <td>UL 508 Emergency Stop Device - NEMA 4X</td> <td colspan="15"></td> </tr> <tr> <td>J</td> <td>1</td> <td>Square D # HOM816M200PFTRB:200A MB LC;200A sub feed lugs; 120/240 1PH; 8/16; NEMA3; 22kAIC</td> <td colspan="15"></td> </tr> </tbody> </table> |                   |         |                |               |           |           |           |             |              | AC CONDUCTOR TABLE |                |            |           |                |  |  |  |  |  | Ref | Type | Qty | Size (AWG) | Min EGC (AWG, Cu) | Conduit |  | Length (ft) | Imp (AAC) | Vmp (VAC) |  |  |  | (Cu) | (Al) | (Cu) | (Al) |  |  |  | D | 4 | Breaker; 60A/2P, 2 Spaces | 3 | THWN-2 | 3 | #06 | #04 | #10 | 3/4" EMT | 1" EMT | 5ft | 48 | 240 | E | 1 | Load Center; 400A, 120/240V, NEMA 3R: Main Lug, 1 a, 12 Spaces, 24 Circuits | 4 | THWN-2 | 3 | #2/0 | #4/0 | #06 | 2" PVC | 2" PVC | 10ft | - | 240 | 1 | Class R Fuse Kit | 5 | THWN-2 | 3 | #06 | #04 | #10 | 1" EMT | 1" EMT | 100ft | - | 240 | F | 2 | EE-000550-001 MC4 Y-Connector, Receptacle | 6 | THWN-2 | 3 | #2/0 | #4/0 | #06 | 2" PVC | 2" PVC | 20ft | - | 240 | 2 | EE-000550-000 MC4 Y-Connector, Plug | 7 | THWN-2 | 3 | #2/0 | #4/0 | #06 | 2" PVC | 2" PVC | 5ft | - | 240 | G | 13 | Tesla MCI, 650V, 12A | 8 | THWN-2 | 3 | #2/0 | #4/0 | #06 | 2" PVC | 2" PVC | 10ft | - | 240 | H | 3 | Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  | I | 1 | UL 508 Emergency Stop Device - NEMA 4X |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  | J | 1 | Square D # HOM816M200PFTRB:200A MB LC;200A sub feed lugs; 120/240 1PH; 8/16; NEMA3; 22kAIC |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|       | AC CONDUCTOR TABLE |  |   |                   |         |                |               |           |           |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| Ref   | Type               | Qty  | Size (AWG)  | Min EGC (AWG, Cu) | Conduit |                | Length (ft)   | Imp (AAC) | Vmp (VAC) |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|       |                    |  | (Cu)  | (Al)              | (Cu)    | (Al)           |               |           |           |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| D     | 4                  | Breaker; 60A/2P, 2 Spaces  | 3   | THWN-2            | 3       | #06            | #04           | #10       | 3/4" EMT  | 1" EMT    | 5ft         | 48           | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| E     | 1                  | Load Center; 400A, 120/240V, NEMA 3R: Main Lug, 1 a, 12 Spaces, 24 Circuits                | 4   | THWN-2            | 3       | #2/0           | #4/0          | #06       | 2" PVC    | 2" PVC    | 10ft        | -            | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|       | 1                  | Class R Fuse Kit   | 5   | THWN-2            | 3       | #06            | #04           | #10       | 1" EMT    | 1" EMT    | 100ft       | -            | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| F     | 2                  | EE-000550-001 MC4 Y-Connector, Receptacle  | 6   | THWN-2            | 3       | #2/0           | #4/0          | #06       | 2" PVC    | 2" PVC    | 20ft        | -            | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|       | 2                  | EE-000550-000 MC4 Y-Connector, Plug  | 7   | THWN-2            | 3       | #2/0           | #4/0          | #06       | 2" PVC    | 2" PVC    | 5ft         | -            | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| G     | 13                 | Tesla MCI, 650V, 12A   | 8   | THWN-2            | 3       | #2/0           | #4/0          | #06       | 2" PVC    | 2" PVC    | 10ft        | -            | 240                |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| H     | 3                  | Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh                                       |   |                   |         |                |               |           |           |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| I     | 1                  | UL 508 Emergency Stop Device - NEMA 4X   |   |                   |         |                |               |           |           |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| J     | 1                  | Square D # HOM816M200PFTRB:200A MB LC;200A sub feed lugs; 120/240 1PH; 8/16; NEMA3; 22kAIC |   |                   |         |                |               |           |           |           |             |              |                    |                |            |           |                |  |  |  |  |  |     |      |     |            |                   |         |  |             |           |           |  |  |  |      |      |      |      |  |  |  |   |   |                           |   |        |   |     |     |     |          |        |     |    |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                  |   |        |   |     |     |     |        |        |       |   |     |   |   |   |   |        |   |      |      |     |        |        |      |   |     |   |                                     |   |        |   |      |      |     |        |        |     |   |     |   |    |                      |   |        |   |      |      |     |        |        |      |   |     |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |   |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |

| SITE SPECIFICATIONS |                         | MODULE SPECIFICATIONS  |       |
|---------------------|-------------------------|--|-------|
| Main Panel Rating   | (E) 200A                | Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405: PV Module, 405W, 376.3WPFC, ZEP, Black Frame, MC4, 1000V |       |
| Main Breaker Rating | (E) 200A                | Qty  | 37    |
| General Notes       | DC Ungrounded Inverters | Voc  | 45.34 |
| Panel Number        | CMB1212B200BTS          | Vmp  | 37.39 |
| Meter Number        | 332298478               | Isc and Imp are in the DC Conductor Table  |       |
| Service Entrance    | Underground             |  |       |

CONFIDENTIAL - THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00  
 MOUNTING SYSTEM: ZS Comp V4 w Flashing-Insert  
 MODULES: (37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405  
 INVERTER: Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER: Myron Adams  
 219 Harvell Rd  
 Coats, NC 27521  
 9105917506

DESCRIPTION: 14.985 KW PV ARRAY  
 11.5 KW (AC NAMEPLATE) PV ARRAY  
 54 KWH ENERGY STORAGE SYSTEM  
 PAGE NAME: THREE LINE DIAGRAM

DESIGN: Ricky Alvarez  
 SHEET: 5 REV: C DATE: 4/12/2024






# SOLAR PV SYSTEM EQUIPPED WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN SWITCH TO THE "OFF"  
POSITION TO SHUT DOWN PV SYSTEM AND REDUCE  
SHOCK HAZARD IN THE ARRAY  
**CAUTION: MULTIPLE SOURCES OF POWER**

- Address: 219 Harvell Rd



CONFIDENTIAL – THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESLA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.

JOB NUMBER: JB-2752214 00

MOUNTING SYSTEM:  
ZS Comp V4 w Flashing-Insert

MODULES:  
(37) Hanwha # Q.PEAK DUO BLK ML-G10+/TS 405

INVERTER:  
Powerwall 3 [240V] # 1707000-25-G 11.5 kW / 13.5 kWh

CUSTOMER:  
Myron Adams  
219 Harvell Rd  
Coats, NC 27521

9105917506

DESCRIPTION:  
14.985 KW PV ARRAY  
11.5 KW (AC NAMEPLATE) PV ARRAY  
54 KWH ENERGY STORAGE SYSTEM

PAGE NAME:  
SITE PLAN PLACARD

DESIGN:  
Ricky Alvarez

SHEET: 6 REV: C DATE: 4/12/2024

TESLA

**WARNING: PHOTOVOLTAIC POWER SOURCE**

Label Location:  
(C)(CB)(JB)  
Per Code:  
NEC 690.31.G.3

**DC PHOTOVOLTAIC  
DISCONNECT**

Label Location:  
(DC)(INV)  
Per Code:  
NEC 690.13.B


**⚠ WARNING**

THIS EQUIPMENT FED BY  
MULTIPLE SOURCES. TOTAL  
RATING OF ALL OVER CURRENT  
DEVICES, EXCLUDING MAIN  
SUPPLY OVERCURRENT DEVICE,  
SHALL NOT EXCEED AMPACITY  
OF BUSBAR.

Label Location:  
(MSP)  
Per Code:  
NEC 705.12.B.2.3.C

|                                   |                      |   |
|-----------------------------------|----------------------|---|
| MAXIMUM POWER-POINT CURRENT (Imp) | <input type="text"/> | A |
| MAXIMUM POWER-POINT VOLTAGE (Vmp) | <input type="text"/> | V |
| MAXIMUM SYSTEM VOLTAGE (Voc)      | <input type="text"/> | V |
| SHORT-CIRCUIT CURRENT (Isc)       | <input type="text"/> | A |

Label Location:  
(DC) (INV)  
Per Code:  
NEC 690.53




Label Location:  
ABB/Delta Solivia Inverter  
Per Code:  
690.56(C)(1)(b)

**AC PHOTOVOLTAIC  
DISCONNECT**

Label Location:  
(AC)(POI)  
Per Code:  
NEC 690.13.B

|                              |                      |   |
|------------------------------|----------------------|---|
| MAXIMUM AC OPERATING CURRENT | <input type="text"/> | A |
| MAXIMUM AC OPERATING VOLTAGE | <input type="text"/> | V |

Label Location:  
(AC) (POI)  
Per Code:  
NEC 690.54



Label Location:  
SolarEdge and,Delta M-Series and,Telsa Inverter  
Per Code:  
690.56(C)(1)(a)

**⚠ WARNING**

ELECTRIC SHOCK HAZARD  
DO NOT TOUCH TERMINALS  
TERMINALS ON BOTH LINE  
AND LOAD SIDES MAY BE  
ENERGIZED IN THE OFF POSITION

Label Location:  
(AC)(POI)  
Per Code:  
690.13.B

**⚠ WARNING**

INVERTER OUTPUT  
CONNECTION  
DO NOT RELOCATE  
THIS OVERCURRENT  
DEVICE

Label Location:  
(POI)  
Per Code:  
NEC 705.12.B.2.3.B

(AC): AC Disconnect  
(C): Conduit  
(CB): Combiner Box  
(D): Distribution Panel  
(DC): DC Disconnect  
(IC): Interior Run Conduit  
(INV): Inverter With Integrated DC Disconnect  
(LC): Load Center  
(M): Utility Meter  
(POI): Point of Interconnection

**BACKUP LOAD CENTER**

Label Location:  
(BLC)  
Per Code:  
NEC 408.4

**CAUTION**  
TRI POWER SOURCE  
SECOND SOURCE IS PHOTOVOLTAIC SYSTEM  
THIRD SOURCE IS ENERGY STORAGE SYSTEM

Label Location:  
(MSP)  
Per Code:  
NEC 705.12(B)(3)

**CAUTION**  
DO NOT ADD NEW LOADS

Label Location:  
(BLC)  
Per Code:  
NEC 220

**WARNING**  
THIS EQUIPMENT FED BY  
MULTIPLE SOURCES. TOTAL  
RATING OF ALL OVER CURRENT  
DEVICES, EXCLUDING MAIN  
SUPPLY OVERCURRENT DEVICE,  
SHALL NOT EXCEED AMPACITY  
OF BUSBAR.

Label Location:  
(MSP)  
Per Code:  
NEC 705.12.B.2.3.c

**CAUTION**  
THIS PANEL HAS SPLICED FEED-  
THROUGH CONDUCTORS.  
LOCATION OF DISCONNECT AT ENERGY  
STORAGE BACKUP LOAD PANEL

Label Location:  
(MSP)  
Per Code:  
NEC 312.8.A(3)

**NOMINAL ESS VOLTAGE:** 120/240V  
**MAX AVAILABLE SHORT-  
CIRCUIT FROM ESS:** 32A  
**ARC FAULT CLEARING  
TIME FROM ESS:** 67ms  
**DATE OF  
CALCULATION:**

Label Location:  
(MSP)  
Per Code:  
Per 706.7(D) label to be marked in field

**CAUTION**  
DUAL POWER SOURCE  
SECOND SOURCE IS  
ENERGY STORAGE SYSTEM

Label Location:  
(MSP)  
Per Code:  
NEC 705.12(B)(3)

**ENERGY STORAGE SYSTEM ON SITE  
LOCATED WITHIN LINE OF SIGHT**

Label Location:  
(MSP)  
Per Code:

**ENERGY STORAGE SYSTEM ON SITE  
LOCATED ON ADJACENT WALL**

Label Location:  
(MSP)  
Per Code:

**ENERGY STORAGE SYSTEM ON SITE  
LOCATED ON OPPOSITE WALL**

Label Location:  
(MSP)  
Per Code:

**ENERGY STORAGE SYSTEM ON SITE  
LOCATED INSIDE**

Label Location:  
(MSP)  
Per Code:

(AC): AC Disconnect  
(BLC): Backup Load Center  
(MSP): Main Service Panel



# Powerwall 3

## Power Everything

Powerwall 3 is a fully integrated solar and battery system, designed to accelerate the transition to sustainable energy. Customers can receive whole home backup, cost savings, and energy independence by producing and consuming their own energy while participating in grid services. Once installed, customers can manage their system using the Tesla App to customize system behavior to meet their energy goals.

Powerwall 3 achieves this by supporting up to 20 kW DC of solar and providing 11.5 kW AC of continuous power per unit. It has the ability to start heavy loads up to 185 A LRA, meaning a single unit can support the power needs of most homes. Powerwall 3 is designed for mass production, fast and efficient installations, easy system expansion, and simple connection to any electrical service.



# Powerwall 3 Technical Specifications

|                                 |  |  |
|---------------------------------|--|--|
| System Technical Specifications | Model Number                             | 1707000-xx-y   |
|                                 | Nominal Grid Voltage (Input & Output)    | 120/240 VAC  |
|                                 | Grid Type                                | Split phase  |
|                                 | Frequency                                | 60 Hz  |
|                                 | Overcurrent Protection Device            | Configurable up to 60 A  |
|                                 | Solar to Battery to Home/Grid Efficiency | 89% <sup>1,2</sup>   |
|                                 | Solar to Home/Grid Efficiency            | 97.5% <sup>3</sup>   |
|                                 | Supported Islanding Devices              | Backup Gateway 2, Backup Switch  |
|                                 | Connectivity                             | Wi-Fi (2.4 and 5 GHz), Dual-port switched Ethernet, Cellular (LTE/4G <sup>4</sup> )  |
|                                 | Hardware Interface                       | Dry contact relay, Rapid Shutdown (RSD) certified switch and 2-pin connector, RS-485 for meters  |
|                                 | AC Metering                              | Revenue Grade (+/- 0.5%)   |
|                                 | Protections                              | Integrated arc fault circuit interrupter (AFCI), Isolation Monitor Interrupter (IMI), PV Rapid Shutdown (RSD) using Tesla Mid-Circuit Interrupters |
|                                 | Customer Interface                       | Tesla Mobile App   |
| Warranty                        | 10 years                                 |  |

|   |                                       |                   |
|---|---------------------------------------|-------------------|
| Solar Technical Specifications                      | Maximum Solar STC Input               | 20 kW             |
|   | Withstand Voltage                     | 600 V DC          |
|   | PV DC Input Voltage Range             | 60 – 550 V DC     |
|   | PV DC MPPT Voltage Range              | 150 – 480 V DC    |
|   | MPPTs                                 | 6                 |
|   | Maximum Current per MPPT ( $I_{mp}$ ) | 13 A <sup>5</sup> |
| Maximum Short Circuit Current per MPPT ( $I_{sc}$ ) | 15 A <sup>5</sup>                     |                   |

|                                  |                                    |                                     |
|----------------------------------|------------------------------------|-------------------------------------|
| Battery Technical Specifications | Nominal Battery Energy             | 13.5 kWh AC <sup>2</sup>            |
|                                  | Maximum Continuous Discharge Power | 11.5 kW AC                          |
|                                  | Maximum Continuous Charge Power    | 5 kW AC                             |
|                                  | Output Power Factor Rating         | 0 - 1 (Grid Code configurable)      |
|                                  | Maximum Continuous Current         | 48 A                                |
|                                  | Maximum Output Fault Current       | 10 kA                               |
|                                  | Load Start Capability (1 s)        | 185 A LRA                           |
|                                  | Power Scalability                  | Up to 4 Powerwall 3 units supported |

<sup>1</sup> Typical solar shifting use case.

<sup>2</sup> Values provided for 25°C (77°F), at beginning of life. 3.3 kW charge/discharge power.

<sup>3</sup> Tested using CEC weighted efficiency methodology.

<sup>4</sup> Cellular connectivity subject to network service coverage and signal strength.

<sup>5</sup> Where the DC input current exceeds the MPPT rating, a jumper can be used to combine two MPPTs into a single input to intake DC current up to 26 A  $I_{mp}$  / 30 A  $I_{sc}$ .

# Powerwall 3 Technical Specifications

## Environmental Specifications

|                         |  |
|-------------------------|--|
| Operating Temperature   | -20°C to 50°C (-4°F to 122°F) <sup>6</sup>   |
| Operating Humidity (RH) | Up to 100%, condensing   |
| Storage Temperature     | -20°C to 30°C (-4°F to 86°F), up to 95% RH, non-condensing, State of Energy (SOE): 25% initial |
| Maximum Elevation       | 3000 m (9843 ft)   |
| Environment             | Indoor and outdoor rated   |
| Enclosure Rating        | NEMA 3R  |
| Ingress Rating          | IPX7 (Battery & Power Electronics)<br>IPX5 (Wiring Compartment)                                |
| Pollution Rating        | PD3  |
| Operating Noise @ 1 m   | < 50 db(A) typical<br>< 62 db(A) maximum   |


<sup>6</sup> Performance may be de-rated at operating temperatures above 40°C (104°F).

## Compliance Information

|                 |  |
|-----------------|--|
| Certifications  | UL 1642, UL 1699B, UL 1741, UL 1741 SA, UL 1741 SB, UL 3741, UL 1973, UL 1998, UL 9540, IEEE 1547-2018, IEEE 1547.1, UN 38.3 |
| Grid Connection | United States  |
| Emissions       | FCC Part 15 Class B  |
| Environmental   | RoHS Directive 2011/65/EU  |
| Seismic         | AC156, IEEE 693-2005 (high)  |
| Fire Testing    | Meets the unit level performance criteria of UL 9540A  |

## Mechanical Specifications


|                  |   |
|------------------|---|
| Dimensions       | 1099 x 609 x 193 mm (43.25 x 24 x 7.6 in) |
| Weight           | 130 kg (287 lb)                           |
| Mounting Options | Floor or wall mount                       |



# Powerwall 3 Example System Configurations


## Powerwall 3 with Backup Switch

Whole Home Backup



## Powerwall 3 with Backup Gateway 2

Partial Home Backup



# Gateway 3

Tesla Gateway 3 controls connection to the grid in a Powerwall system, automatically detecting outages and providing seamless transition to backup power. It provides energy monitoring that is used by Powerwall for solar self-consumption, time-based control, and backup operation.

## Performance Specifications

|   |   |                                      |  |
|---|---|--------------------------------------|--|
| <b>Model Number</b>                         | 1841000-01-y  | <b>AC Meter</b>                      | Revenue accurate (+/- 0.5%)  |
| <b>Nominal Grid Voltage</b>                 | 120/240 V AC  | <b>Communication</b>                 | CAN  |
| <b>Grid Configuration</b>                   | Split phase   | <b>User Interface</b>                | Tesla App  |
| <b>Grid Frequency</b>                       | 60 Hz   | <b>Backup Transition</b>             | Automatic disconnect for seamless backup   |
| <b>Continuous Current Rating</b>            | 200 A   | <b>Overcurrent Protection Device</b> | 100-200 A<br>Service entrance rated Eaton CSR, BWH, or BW, or Square D QOM breakers                  |
| <b>Maximum Supply Short Circuit Current</b> | 22 kA with Square D or Eaton main breaker<br>25 kA with Eaton main breaker <sup>1</sup> | <b>Internal Panelboard</b>           | 200 A<br>8-space/16 circuit breakers Eaton BR, Siemens QP, or Square D HOM breakers rated to 10-125A |
| <b>IEC Protective Class</b>                 | Class I   | <b>Warranty</b>                      | 10 years   |
| <b>Overvoltage Category</b>                 | Category IV   |                                      |  |

<sup>1</sup>Only Eaton CSR or BWH main breakers are 25 kA rated

## Environmental Specifications


|                                |                               |
|--------------------------------|-------------------------------|
| <b>Operating Temperature</b>   | -20°C to 50°C (-4°F to 122°F) |
| <b>Operating Humidity (RH)</b> | Up to 100%, condensing        |
| <b>Maximum Elevation</b>       | 3000 m (9843 ft)              |
| <b>Environment</b>             | Indoor and outdoor rated      |
| <b>Enclosure Type</b>          | NEMA 3R                       |

## Compliance Information

|                       |  |
|-----------------------|--|
| <b>Certifications</b> | UL 67, UL 869A, UL 916, UL 1741 PCS, CSA 22.2 107.1, CSA 22.2 29 |
| <b>Emmissions</b>     | FCC Part 15, ICES 003  |

## Mechanical Specifications

|                         |  |
|-------------------------|--|
| <b>Dimensions</b>       | 660 x 411 x 149 mm<br>(26 x 16 x 6 in) |
| <b>Weight</b>           | 16.4 kg (36 lb)                        |
| <b>Mounting options</b> | Wall mount                             |




# ROOFING SYSTEM SPECIFICATIONS



|  |  |
|--|--|
| <b>DESCRIPTION</b>   | PV mounting solution for composition shingle roofs.  |
|  | Works with all Zep Compatible Modules.   |
|  | Auto bonding UL-listed hardware creates structural and electrical bond.  |
| <b>SPECIFICATIONS</b>  | Designed for pitched roofs.  |
|  | Installs in portrait and landscape orientations.   |
|  | Engineered for spans up to 72" and cantilevers up to 24".  |
|  | ZS Comp has a UL 1703 Class "A" Fire Rating when installed using modules from any manufacturer certified as "Type 1" or "Type 2".            |
|  | Attachment method UL listed to UL 2582 for Wind Driven Rain.   |
|  | ZS Comp supports 50 psf (2400 Pa) front and up to 72 psf (3450 Pa) rear side design load rating for Portrait module orientation per UL 2703. |
|  | ZS Comp supports 50 psf (2400 Pa) front side and up to 72 psf (3450 Pa) rear side design load rating for Landscape module orientation.       |
|  | Engineered for compliance with ASCE 7-05, 7-10, and 7-16 wind load requirements.   |
|  | Zep wire management products listed to UL 1565 for wire positioning devices.   |
| ZS Comp grounding products are listed to UL 2703 and UL 467. |  |
| ZS Comp bonding products are listed to UL 2703.              |  |


## MOUNTING BLOCK

Listed to UL 2703  
Part #850-1633




## FLASHING INSERT

Listed to UL 2703 and UL 2582 for Wind Driven Rain  
Part #850-1628




## CAPTURED WASHER LAG

Part #850-1631-002 and #850-1631-004




## GROUND ZEP

Listed to UL 2703  
Part #850-1511




## LEVELING FOOT

Listed to UL 2703  
Part #850-1397




## DC WIRE CLIP

Listed to UL 1565  
Part #850-1509




## HOME RUN CLIP

Listed to UL 1565  
Part #850-1510




## ARRAY SKIRT

Listed to UL 2703  
Part #850-1608




## END CAP

Listed to UL 2703  
Part #850-1586 (Left)  
Part #850-1588 (Right)




## SKIRT GRIP

Listed to UL 2703  
Part #850-1606




## INTERLOCK

Listed to UL 2703  
Part #850-1613



## HYBRID INTERLOCK

Listed to UL 2703  
Part #850-1281



# MCI WIRING DETAIL

## GENERAL NOTES


- DRAWING OF STANDARD MCI WIRING DETAIL FOR ANY GIVEN STRING LENGTH
- IF INITIATED, RAPID SHUTDOWN OCCURS WITHIN 30 SECONDS OF ACTIVATION AND LIMITS VOLTAGE ON THE ROOF TO NO GREATER THAN 165V (690.12.B.2.1)
- MID CIRCUIT INTERRUPTER (MCI) IS A UL 1741 PVRSE CERTIFIED RAPID SHUTDOWN DEVICE (RSD)

## RETROFIT PV MODULES

- MCIS ARE LOCATED AT ROOF LEVEL, JUST UNDER THE PV MODULES IN ACCORDANCE WITH 690.12 REQUIREMENTS
- THE QUANTITY OF MCIS PER STRING IS DETERMINED BY STRING LENGTH
  - NUMBER OF MODULES BETWEEN MCI UNITS = 0-3
  - MAXIMUM NUMBER OF MODULES PER MCI UNIT = 3
  - MINIMUM NUMBER MCI UNITS = MODULE COUNT/3

\*Exception: Tesla (Longi) modules installed in locations where the max Voc for 3 modules at low design temperature exceeds 165V shall be limited to 2 modules between MCIs.

PLEASE REFER TO MCI CUTSHEET AND PVRSA INSERT FOR MORE INFORMATION



① (2)AWG, PV Wire, 600V, Black

DC



# Q.PEAK DUO BLK ML-G10+ SERIES



385-405 Wp | 132 Cells  
20.5% Maximum Module Efficiency

MODEL Q.PEAK DUO BLK ML-G10+/TS



## Breaking the 20% efficiency barrier

Q.ANTUM DUO Z Technology with zero gap cell layout boosts module efficiency up to 20.5%.



## A reliable investment

Inclusive 25-year product warranty and 25-year linear performance warranty<sup>1</sup>.



## Enduring high performance

Long-term yield security with Anti LeTID Technology, Anti PID Technology<sup>2</sup> and Hot-Spot Protect.



## Innovative all-weather technology

Optimal yields, whatever the weather with excellent low-light and temperature behaviour.



## Zep compatible™ frame design

High-tech black Zep Compatible™ frame, for improved aesthetics, easy installation and increased safety.



## The most thorough testing programme in the industry


Qcells is the first solar module manufacturer to pass the most comprehensive quality programme in the industry: The new "Quality Controlled PV" of the independent certification institute TÜV Rheinland.

<sup>1</sup> See data sheet on rear for further information.  
<sup>2</sup> APT test conditions according to IEC/TS 62804-1:2015, method A (-1500 V, 96 h)

# Q.PEAK DUO BLK ML-G10+ SERIES

## Mechanical Specification

|              |   |
|--------------|---|
| Format       | 74.4 in × 41.2 in × 1.57 in (including frame)<br>(1890 mm × 1046 mm × 40 mm)                              |
| Weight       | 51.8 lbs (23.5 kg)  |
| Front Cover  | 0.13 in (3.2 mm) thermally pre-stressed glass with anti-reflection technology                             |
| Back Cover   | Composite film  |
| Frame        | Black anodised aluminium  |
| Cell         | 6 × 22 monocrystalline Q.ANTUM solar half cells   |
| Junction box | 2.09-3.98 in × 1.26-2.36 in × 0.59-0.71 in<br>(53-101 mm × 32-60 mm × 15-18 mm), IP67, with bypass diodes |
| Cable        | 4 mm <sup>2</sup> Solar cable; (+) > 52.2 in (1325 mm), (-) > 52.2 in (1325 mm)                           |
| Connector    | Stäubli MC4; IP68   |



## Electrical Characteristics


| POWER CLASS   |                                    | 385           | 390    | 395    | 400    | 405    |        |
|---|------------------------------------|---------------|--------|--------|--------|--------|--------|
| MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC <sup>1</sup> (POWER TOLERANCE +5 W/-0 W) |                                    |               |        |        |        |        |        |
| Minimum   | Power at MPP <sup>1</sup>          | $P_{MPP}$ [W] | 385    | 390    | 395    | 400    | 405    |
|   | Short Circuit Current <sup>1</sup> | $I_{SC}$ [A]  | 11.04  | 11.07  | 11.10  | 11.14  | 11.17  |
|   | Open Circuit Voltage <sup>1</sup>  | $V_{OC}$ [V]  | 45.19  | 45.23  | 45.27  | 45.3   | 45.34  |
|   | Current at MPP                     | $I_{MPP}$ [A] | 10.59  | 10.65  | 10.71  | 10.77  | 10.83  |
|   | Voltage at MPP                     | $V_{MPP}$ [V] | 36.36  | 36.62  | 36.88  | 37.13  | 37.39  |
|   | Efficiency <sup>1</sup>            | $\eta$ [%]    | ≥ 19.5 | ≥ 19.7 | ≥ 20.0 | ≥ 20.2 | ≥ 20.5 |

MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT<sup>2</sup>

|         |                       |               |       |       |       |       |       |
|---------|-----------------------|---------------|-------|-------|-------|-------|-------|
| Minimum | Power at MPP          | $P_{MPP}$ [W] | 288.8 | 292.6 | 296.3 | 300.1 | 303.8 |
|         | Short Circuit Current | $I_{SC}$ [A]  | 8.90  | 8.92  | 8.95  | 8.97  | 9.00  |
|         | Open Circuit Voltage  | $V_{OC}$ [V]  | 42.62 | 42.65 | 42.69 | 42.72 | 42.76 |
|         | Current at MPP        | $I_{MPP}$ [A] | 8.35  | 8.41  | 8.46  | 8.51  | 8.57  |
|         | Voltage at MPP        | $V_{MPP}$ [V] | 34.59 | 34.81 | 35.03 | 35.25 | 35.46 |

<sup>1</sup>Measurement tolerances  $P_{MPP} \pm 3\%$ ;  $I_{SC}$ ;  $V_{OC} \pm 5\%$  at STC: 1000 W/m<sup>2</sup>, 25 ± 2 °C, AM 1.5 according to IEC 60904-3 • <sup>2</sup>800 W/m<sup>2</sup>, NMOT, spectrum AM 1.5

## Qcells PERFORMANCE WARRANTY




At least 98% of nominal power during first year. Thereafter max. 0.5% degradation per year. At least 93.5% of nominal power up to 10 years. At least 86% of nominal power up to 25 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Qcells sales organisation of your respective country.

<sup>\*</sup>Standard terms of guarantee for the 5 PV companies with the highest production capacity in 2021 (February 2021)

## PERFORMANCE AT LOW IRRADIANCE



Typical module performance under low irradiance conditions in comparison to STC conditions (25 °C, 1000 W/m<sup>2</sup>).

## TEMPERATURE COEFFICIENTS

|                                      |                |       |                                      |               |                       |
|--------------------------------------|----------------|-------|--------------------------------------|---------------|-----------------------|
| Temperature Coefficient of $I_{SC}$  | $\alpha$ [%/K] | +0.04 | Temperature Coefficient of $V_{OC}$  | $\beta$ [%/K] | -0.27                 |
| Temperature Coefficient of $P_{MPP}$ | $\gamma$ [%/K] | -0.34 | Nominal Module Operating Temperature | NMOT [°F]     | 109 ± 5.4 (43 ± 3 °C) |

## Properties for System Design

|  |                        |                             |   |  |
|--|------------------------|-----------------------------|---|--|
| Maximum System Voltage                   | $V_{SYS}$ [V]          | 1000 (IEC)/1000 (UL)        | PV module classification                        | Class II                                   |
| Maximum Series Fuse Rating               | [A DC]                 | 20                          | Fire Rating based on ANSI/UL 61730              | TYPE 2                                     |
| Max. Design Load, Push/Pull <sup>3</sup> | [lbs/ft <sup>2</sup> ] | 85 (4080 Pa)/85 (4080 Pa)   | Permitted Module Temperature on Continuous Duty | -40 °F up to +185 °F (-40 °C up to +85 °C) |
| Max. Test Load, Push/Pull <sup>3</sup>   | [lbs/ft <sup>2</sup> ] | 128 (6120 Pa)/128 (6120 Pa) |   |  |

<sup>3</sup> See Installation Manual

## Qualifications and Certificates

UL 61730, CE-compliant, Quality Controlled PV - TÜV Rheinland; IEC 61215:2016, IEC 61730:2016, U.S. Patent No. 9,893,215 (solar cells)



## The ideal solution for:



Rooftop arrays on residential buildings



Rooftop arrays on commercial/industrial buildings



Qcells pursues minimizing paper output in consideration of the global environment.

Note: Installation instructions must be followed. Contact our technical service for further information on approved installation of this product.  
Hanwha Q CELLS America Inc. 400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 748 59 96 | EMAIL hqc-inquiry@qcells.com | WEB www.qcells.com

qcells



# Solar Shutdown Device 1 Technical Specifications

The Solar Shutdown Device is a Mid-Circuit Interrupter (MCI) and is part of the PV system rapid shutdown (RSD) function in accordance with Article 690 of the applicable NEC. When paired with Powerwall+ or Tesla Solar Inverter, solar array shutdown is initiated by any loss of AC power.


|                           |  |          |
|---------------------------|--|----------|
| Electrical Specifications | Nominal Input DC Current Rating ( $I_{MP}$ )     | 12 A     |
|                           | Maximum Input Short Circuit Current ( $I_{SC}$ ) | 19 A     |
|                           | Maximum System Voltage (PVHCS)                   | 600 V DC |

|                        |                                      |                       |
|------------------------|--------------------------------------|-----------------------|
| RSD Module Performance | Maximum Number of Devices per String | 5                     |
|                        | Control                              | Power Line Excitation |
|                        | Passive State                        | Normally Open         |
|                        | Maximum Power Consumption            | 7 W                   |
|                        | Warranty                             | 25 years              |

|                              |                     |                                |
|------------------------------|---------------------|--------------------------------|
| Environmental Specifications | Ambient Temperature | -40°C to 50°C (-40°F to 122°F) |
|                              | Storage Temperature | -30°C to 70°C (-22°F to 158°F) |
|                              | Enclosure Rating    | NEMA 4X / IP65                 |

|                        |                       |   |
|------------------------|-----------------------|---|
| Compliance Information | Certifications        | UL 1741 PVRSE, UL 3741, PVRSA (Photovoltaic Rapid Shutdown Array) |
|                        | RSD Initiation Method | PV System AC Breaker or Switch                                    |
|                        | Compatible Equipment  | See Compatibility Table below                                     |

|                           |                        |  |
|---------------------------|------------------------|--|
| Mechanical Specifications | Model Number           | MCI-1  |
|                           | Electrical Connections | MC4 Connector  |
|                           | Housing                | Plastic  |
|                           | Dimensions             | 125 mm x 150 mm x 22 mm<br>(5 in x 6 in x 1 in)        |
|                           | Weight                 | 350 g (0.77 lb)  |
|                           | Mounting Options       | ZEP Home Run Clip                                      |
|                           |                        | M4 Screw (#10)<br>M8 Bolt (5/16")<br>Nail / Wood screw |



## UL 3741 PV Hazard Control (and PVRSA) Compatibility

Tesla Solar Roof and Tesla/Zep ZS Arrays using the following modules are certified to UL 3741 and UL 1741 PVRSA when installed with Powerwall+ or Tesla Solar Inverter and Solar Shutdown Devices. See [Powerwall+ / Tesla Solar Inverter Rapid Shutdown: Module Selection Based on PV Hazard Control System Listing](#) for guidance on installing other modules.

| Brand  | Model  | Required Solar Shutdown Devices                    |
|--------|--|--|
| Tesla  | Solar Roof V3  | 1 Solar Shutdown Device per 10 modules             |
| Tesla  | Tesla TxxxS (where xxx = 405 to 450 W, increments of 5)<br>Tesla TxxxH (where xxx = 395 to 415 W, increments of 5) | 1 Solar Shutdown Device per 3 modules <sup>1</sup> |
| Hanwha | Q.PEAK DUO BLK-G5 or Q.PEAK DUO BLK-G6+  | 1 Solar Shutdown Device per 3 modules              |

<sup>1</sup> **Exception:** Tesla solar modules installed in locations where the max Voc for three modules at low design temperatures exceeds 165 V shall be limited to two modules between Solar Shutdown Devices.