

June 8, 2024

RE:

Project Address:

CERTIFICATION LETTER

#### GEOFFREY STODDARD 600 WARREN ROAD ERWIN, NC 28339

#### **Design Criteria:**

- Applicable Codes = 2018 NCSBC, 2018 NCSRC, ASCE 7-16 and 2018 NDS
- Risk Category = II
- Wind Speed = 130 mph, Exposure Category B, Partially/Fully Enclosed Method
- Ground Snow Load = 15 psf
- Roof 1,2 & 4-6: 2 x 8 @ 16" OC, Roof DL = 8 psf, Roof LL/SL = 12 psf (Non-PV), Roof LL/SL = 4.8 psf (PV)
- Roof 3: 2 x 8 @ 16" OC, Roof DL = 8 psf, Roof LL/SL = 18 psf (Non-PV), Roof LL/SL = 8.1 psf (PV)

To Whom It May Concern,

A structural evaluation of loading was conducted for the above address based on the design criteria listed above.

Existing roof structural framing has been reviewed for additional loading due to installation of Solar PV System on the roof. The structural review applies to the sections of roof that is directly supporting the Solar PV System.

Based on this evaluation, I certify that the alteration to the existing structure by installation of the Solar PV System meets the prescriptive compliance requirements of the applicable existing building and/or new building provisions adopted/referenced above.

Additionally, the Solar PV System assembly (including attachment hardware) has been reviewed to be in accordance with the manufacturer's specifications and to meet and/or exceed the requirements set forth by the referenced codes.

Sincerely,



This document is the property of Barun Corp and cannot be reproduced without prior consent. It is site specific and shall not be transferred to any other property, property owner, person(s), or entity. This document may include an expression of professional opinion by the engineer of record, which is based on his or her best knowledge, information provided by others, and belief. Other professionals may have different opinions. Barun Corp reserves the right to amend and/or supplement this document in the event additional information be uncovered or made available.



### **RESULTS SUMMARY**

#### GEOFFREY STODDARD, 600 WARREN ROAD, ERWIN, NC 28339

MOUNTING PLANE STRUCTURAL EVALUATION			
MOUNTING PLANE	ROOF PITCH	RESULT	GOVERNING ANALYSIS
Roof 1,2 & 4-6	45°	ОК	IEBC IMPACT CHECK
Roof 3	28°	ОК	IEBC IMPACT CHECK

#### Limits of Scope of Work and Liability:

The existing structure has been reviewed based on the assumption that it has been originally designed and constructed per appropriate codes. The structural analysis of the subject property is based on the provided site survey data. The calculations produced for this structure's assessment are only for the roof framing supporting the proposed PV installation referenced in the stamped planset and were made according to generally recognized structural analysis standards and procedures. All PV modules, racking and attachment components shall be designed and installed per manufacturer's approved guidelines and specifications. These plans are not stamped for water leakage or existing damage to the structural component that was not accessed during the site survey. Prior to commencement of work, the PV system installer should verify that the existing roof and connections are in suitable condition and inspect framing noted on the certification letter and inform the Engineer of Record of any discrepancies prior to installation. The installer should also check for any damages such as water damage, cracked framing, etc. and inform the Engineer of Record of existing deficiencies which are unknown and/or were not observable during the time of survey and have not been included in this scope of work. Any change in the scope of the work shall not be accepted unless such change, addition, or deletion is approved in advance and in writing by the Engineer of Record.

**BARUN CORP** 

## LOAD CALCULATION

Roof 1,2 & 4-6

GEOFFREY STODDARD, 600 WARREN ROAD, ERWIN, NC 28339

PV PANELS DEAD LOAD (PV-DL)		
PV Panels Weight	= 2.50 psf	
Hardware Assembly Weight	= 0.50 psf	
Total PV Panels Weight	PV-DL = 3.00 psf	

ROOF DEAD LOAD (R-DL)			
Existing Roofing Material Weight	Composite Shingle Roof	1 Layer(s)	= 2.50 psf
Underlayment Weight			= 0.50 psf
Plywood/OSB Sheathing Weight			= 1.50 psf
Framing Weight	2 x 8 @ 16 in. O.C.		= 2.27 psf
No Vaulted Ceiling			= 0.00 psf
Miscellaneous			= 1.50 psf
Total Roof Dead Load			R-DL = 8.30 psf

REDUCED ROOF LIVE LOAD (Lr)		
Roof Live Load	Lo = 20.00 psf	
Member Tributary Area	$At < 200 ft^2$	
Roof 1,2 & 4-6 Pitch	45° or 12/12	
Tributary Area Reduction Factor	R1 = 1.00	
Roof Slope Reduction Factor	R2 = 0.60	
Reduced Roof Live Load, Lr = Lo (R1) (R2)	Lr = 12.00 psf	

SNOW LOAD	
Ground Snow Load	pg = 15.00 psf
Effective Roof Slope	45°
Snow Importance Factor	Is = 1.00
Snow Exposure Factor	Ce = 1.00
Snow Thermal Factor	Ct = 1.10
Minimum Flat Roof Snow Load	pf-min = 0.00 psf
Flat Roof Snow Load	pf = 11.60 psf

SLOPED ROOF SNOW LOAD ON ROOF (Non-Slippery Surfaces)		
Roof Slope Factor Cs-roof = 0.77		
Sloped Roof Snow Load on Roof ps-roof = 8.90 psf		

SLOPED ROOF SNOW LOAD ON PV PANELS (Unobstructed Slippery Surfaces)		
Roof Slope Factor Cs-PV = 0.42		
Sloped Roof Snow Load on PV Panels ps-PV = 4.80 psf		

Lateral Capacity check for Ecofasten	Rockit Smart slide attachments.		
Attachment type =	Ecofasten RockIT Smart Slide	Number of rows in Array =	5
Attachment Max. X-spacing =	6.00 ft	Array Lateral Capacity factor =	1.20
Attachment Max. Y-spacing =	3.40 ft		
Lateral load on each attachment =	113.00 lbs		
Lateral capacity of the attachment =	170.40 lbs (Based on	hardware manufacturer)	
	Pass. Provided spacing is Oka	y.	



## **IEBC IMPACT CHECK**

### Roof 1,2 & 4-6

GEOFFREY STODDARD, 600 WARREN ROAD, ERWIN, NC 28339

	EXISTING	WITH PV PANELS	
Roof Dead Load (DL) =	8.30	11.30	F
Roof Live Load (Lr) =	12.00	0.00	F
Roof Snow Load (SL) =	8.90	4.80	F
	EXISTING	WITH PV PANELS	
(DL + Lr)/Cd =	16.24	12.56	
(DL + Lr)/Cd = (DL + SL)/Cd =	16.24 14.96	12.56 14.00	

The requirements of section 806.2 of 2018 IEBC are met and the structure is permitted to remain unaltered.

**BARUN CORP** 

# LOAD CALCULATION

#### Roof 3

GEOFFREY STODDARD, 600 WARREN ROAD, ERWIN, NC 28339

PV PANELS DEAD LOAD (PV-DL)		
PV Panels Weight	= 2.50 psf	
Hardware Assembly Weight	= 0.50 psf	
Total PV Panels Weight	PV-DL = 3.00 psf	

ROOF DEAD LOAD (R-DL)			
Existing Roofing Material Weight	Composite Shingle Roof	1 Layer(s)	= 2.50 psf
Underlayment Weight			= 0.50 psf
Plywood/OSB Sheathing Weight			= 1.50 psf
Framing Weight	2 x 8 @ 16 in. O.C.		= 2.27 psf
No Vaulted Ceiling			= 0.00 psf
Miscellaneous			= 1.50 psf
Total Roof Dead Load			R-DL = 8.30 psf

REDUCED ROOF LIVE LOAD (Lr)		
Roof Live Load	Lo = 20.00 psf	
Member Tributary Area	$At < 200 ft^2$	
Roof 3 Pitch	28° or 7/12	
Tributary Area Reduction Factor	R1 = 1.00	
Roof Slope Reduction Factor	R2 = 0.88	
Reduced Roof Live Load, Lr = Lo (R1) (R2)	Lr = 17.50 psf	

SNOW LOAD		
Ground Snow Load	pg = 15.00 psf	
Effective Roof Slope	28°	
Snow Importance Factor	Is = 1.00	
Snow Exposure Factor	Ce = 1.00	
Snow Thermal Factor	Ct = 1.10	
Minimum Flat Roof Snow Load	pf-min = 0.00 psf	
Flat Roof Snow Load	pf = 11.60 psf	

SLOPED ROOF SNOW LOAD ON ROOF (Non-Slippery Surfa	aces)
Roof Slope Factor	Cs-roof = 1.00
Sloped Roof Snow Load on Roof	ps-roof = 11.60 psf

SLOPED ROOF SNOW LOAD ON PV PANELS (Unobstructed Slippe	ry Surfaces)
Roof Slope Factor	Cs-PV = 0.70
Sloped Roof Snow Load on PV Panels	ps-PV = 8.10 psf

Lateral Capacity check for Ecofasten	Rockit Smart slide attachments.		
Attachment type =	Ecofasten RockIT Smart Slide	Number of rows in Array =	5
Attachment Max. X-spacing =	6.00 ft	Array Lateral Capacity factor =	1.20
Attachment Max. Y-spacing =	3.40 ft		
Lateral load on each attachment =	106.50 lbs		
Lateral capacity of the attachment =	170.40 lbs (Based on	hardware manufacturer)	
	Pass. Provided spacing is Oka	y.	



## **IEBC IMPACT CHECK**

### Roof 3

GEOFFREY STODDARD, 600 WARREN ROAD, ERWIN, NC 28339

	EXISTING	WITH PV PANELS	
Roof Dead Load (DL) =	8.30	11.30	ps
Roof Live Load (Lr) =	17.50	0.00	p
Roof Snow Load (SL) =	11.60	8.10	p
	EXISTING	WITH PV PANELS	
(DL + Lr)/Cd =	<b>EXISTING</b> 20.64	12.56	p
(DL + Lr)/Cd = (DL + SL)/Cd =			p p

The requirements of section 806.2 of 2018 IEBC are met and the structure is permitted to remain unaltered.