

RESIDENTIAL ROOFTOP SOLAR PERMIT PACKAGE



STEPHANIE RODGERS
 99 NECTAR LN
 BUNNLEVEL, North Carolina 28323
 14064371091



1403 N 630 E
 Orem, Utah 84097
 (800) 377-4480
 BlueRavenSolar.com

SCOPE OF WORK
 INSTALLATION OF ROOFTOP MOUNTED PHOTOVOLTAIC SOLAR SYSTEM



Sealed For Existing Roof & Attachment Only

SHEET INDEX

- PV1 COVER SHEET
- PV2 SITE PLAN
- PV3 ROOF PLAN
- PV4 STRUCTURAL
- PV5 ELECTRICAL 3-LINE
- PV6 ELECTRICAL CALCULATIONS
- PV7 LABELS
- PV8 PLACARD
- SS SPEC SHEETS

TYPICAL STRUCTURAL INFORMATION

- ROOF MATERIAL: Comp Shingle
- SHEATHING: OSB
- FRAMING: Manufactured Truss
- RACKING: UNIRAC SFM INFINITY
- ROOF ATTACHMENT: UNIRAC SFM INFINITY FLASHKIT
- TOTAL ATTACHMENTS: 18



NEW PV SYSTEM INFORMATION

- DC SYSTEM SIZE: 4.6 kW DC
- AC SYSTEM SIZE: 3.8 kW AC
- MODULE TYPE: (10) REC Solar REC460AA Pure-RX
- INVERTER TYPE: (10) Enphase IQ8X-80-M-US

| | |
|--------------------------------|--------------------------------|
| TOTAL PV DC SYSTEM SIZE | TOTAL PV AC SYSTEM SIZE |
| 4.600 kW DC | 3.800 kW AC |

DESIGN CRITERIA

- WIND SPEED: 115
- WIND EXPOSURE FACTOR: C
- RISK CATEGORY: II
- GROUND SNOW LOAD: 15
- ROOF SNOW LOAD: 10.5
- SEISMIC DESIGN CATEGORY: B

WEATHER STATION DATA

- WEATHER STATION: SEYMOUR-JOHNSON AFB
- HIGH TEMP 2% AVG: 35°C
- EXTREME MINIMUM TEMP: -10°C

APPLICABLE CODES

- *2017 NATIONAL ELECTRIC CODE (NEC)
- *2018 NORTH CAROLINA BUILDING CODE (NCBC)
- *2018 NORTH CAROLINA RESIDENTIAL CODE (NCRC), PLUMBING CODE (NCPC), AND ALL STATE AND LOCAL BUILDING, ELECTRICAL, AND PLUMBING CODES

GENERAL NOTES



10/10/2024
 Firm No. : D-0449

AHJ
 Harnett County
 Digitally signed by John A. Calvert

UTILITY COMPANY
 Duke Energy
 Date: 2024.10.10
 09:15:23 -06'00'

CUSTOMER NAME: **STEPHANIE RODGERS**
 99 NECTAR LN
 BUNNLEVEL, North Carolina 28323

AHJ: Harnett County
 UTILITY COMPANY: Duke Energy

PROJECT ID: **1036248**

PV DC SYSTEM SIZE: 4.600 kW DC

PV AC SYSTEM SIZE: 3.800 kW AC

REVISIONS:

| | |
|---|------------|
| A | 10/09/2024 |
| B | --- |
| C | --- |
| D | --- |

DRAWN BY: Brendan Fillmore

PLOT DATE: October 9, 2024


DRAWING TITLE: Cover Sheet

DRAWING NUMBER: **PV1**

Sealed For
Existing Roof &
Attachment Only



10/10/2024
Firm No. : D-0449



FRONT OF HOME
99 NECTAR LN

SITE PLAN
SCALE: 1/16" = 1'-0"

CUSTOMER NAME: STEPHANIE RODGERS
99 NECTAR LN
BUNNLEVEL, North Carolina 28323
AHJ: Harnett County
UTILITY COMPANY: Duke Energy

PROJECT ID:
1036248

PV DC SYSTEM SIZE:
4.600 kW DC

PV AC SYSTEM SIZE:
3.800 kW AC

REVISIONS:

| | |
|---|------------|
| A | 10/09/2024 |
| B | ---- |
| C | ---- |
| D | ---- |

DRAWN BY:
Brendan Fillmore

PLOT DATE:
October 9, 2024

DRAWING TITLE:
Site Plan

DRAWING NUMBER:
PV2

LEGEND


| | | | | |
|--------------------------|---------------------|-------------------------|-----------------------|---|
| UTILITY METER | BREAKER ENCLOSURE | ESS - BATTERY | FIRE SETBACK HATCH | TRENCH OR OVERHEAD |
| MAIN SERVICE PANEL | AC DISCONNECT | ESS - CONTROLLER | MICROINVERTER | PROPERTY LINE |
| SUBPANEL | PV PRODUCTION METER | REMOTE POWER OFF SWITCH | ROOF TOP JUNCTION BOX | <i>ICONS WITH DOTTED OUTLINE INDICATE INTERIOR LOCATION</i> |
| UTILITY METER CT CABINET | COMBINER BOX | GENERATOR ATS PANEL | INVERTER | |

PV SYSTEM SPECIFICATIONS

NEW PV SYSTEM INFORMATION

PV MODULE: (10) REC Solar REC460AA Pure-RX, **POWER RATING:** 460 W
INVERTER: (10) Enphase IQ8X-80-M-US, **POWER RATING:** 380 W


COMPASS



DC SYSTEM SIZE: 4.6 KW DCMODULE: REC 460INVERTER(S): Enphase IQ8X Microinverters



1403 N 630 E
Orem, Utah 84097
(800) 377-4480
BlueRavenSolar.com



MP1

MODULE QTY: 10
AZIMUTH: 32
PITCH: 30
TSRF: 57
AREA: 1407 ft²

Sealed For
Existing Roof &
Attachment Only



10/10/2024
Firm No. : D-0449

STEPHANIE RODGERS

99 NECTAR LN
BUNNLEVEL, North Carolina 28323

Harnett County

Duke Energy

CUSTOMER NAME:

AHJ:

UTILITY COMPANY:

PROJECT ID:

1036248

PV DC SYSTEM SIZE:

4.600 kW DC

PV AC SYSTEM SIZE:

3.800 kW AC

REVISIONS:

| | |
|---|------------|
| A | 10/09/2024 |
| B | ---- |
| C | ---- |
| D | ---- |

DRAWN BY:

Brendan Fillmore

PLOT DATE:

October 9, 2024

DRAWING TITLE:

Roof Plan

DRAWING NUMBER:

PV3

ROOF PLAN

SCALE: 1/8" = 1'-0"

LEGEND


| | | | | |
|--------------------------|---------------------|-------------------------|-----------------------|---|
| UTILITY METER | BREAKER ENCLOSURE | ESS - BATTERY | FIRE SETBACK HATCH | TRENCH OR OVERHEAD |
| MAIN SERVICE PANEL | AC DISCONNECT | ESS - CONTROLLER | MICROINVERTER | PROPERTY LINE |
| SUBPANEL | PV PRODUCTION METER | REMOTE POWER OFF SWITCH | ROOF TOP JUNCTION BOX | |
| UTILITY METER CT CABINET | COMBINER BOX | GENERATOR ATS PANEL | INVERTER | ICONS WITH DOTTED OUTLINE INDICATE INTERIOR LOCATION |

PV SYSTEM SPECIFICATIONS

NEW PV SYSTEM INFORMATION

PV MODULE: (10) REC Solar REC460AA Pure-RX, **POWER RATING:** 460 W
INVERTER: (10) Enphase IQ8X-80-M-US, **POWER RATING:** 380 W

COMPASS






| PANEL COUNT | AZIMUTH (DEG) | PITCH (DEG) | TSRF (%) | AREA (ft²) | ROOF MATERIAL | SHEATHING TYPE | FRAMING TYPE | FRAMING SIZE AND SPACING | CEILING JOIST/PURLINS SIZE AND SPACING | RACKING TYPE | ATTACHMENT TYPE | MAXIMUM ATTACHMENT SPACING (S) | MAXIMUM CANTILEVER (C) | |
|-------------|---------------|-------------|----------|------------|---------------|----------------|--------------|--------------------------|--|----------------|---------------------|--------------------------------|------------------------|-------------|
| MP1 | 10 | 32 | 30 | 57 | 1407 | Comp Shingle | OSB | Manufactured Truss | 2x4 @ 24 in OC | 2x4 @ 24 in OC | UNIRAC SFM INFINITY | UNIRAC SFM INFINITY FLASHKIT | 72"L / 48"P | 24"L / 16"P |
| MP2 | 0 | | | | | | | | | | | | | |
| MP3 | 0 | | | | | | | | | | | | | |
| MP4 | 0 | | | | | | | | | | | | | |
| MP5 | 0 | | | | | | | | | | | | | |
| MP6 | 0 | | | | | | | | | | | | | |
| MP7 | 0 | | | | | | | | | | | | | |
| MP8 | 0 | | | | | | | | | | | | | |
| MP9 | 0 | | | | | | | | | | | | | |
| MP10 | 0 | | | | | | | | | | | | | |

| | |
|-----------------------------|--------|
| TOTAL PV ARRAY AREA (ft²) | 224.16 |
| TOTAL ROOF AREA (ft²) | 2942 |
| DISTRIBUTED LOAD (psf) | 2.23 |
| ROOF COVERAGE (%) | 7.62 |
| TOTAL PV ARRAY WEIGHT (lbs) | 500 |
| TOTAL PV ATTACHMENTS | 18 |
| POINT LOAD (lbs/att.) | 27.8 |



1403 N 630 E
Orem, Utah 84097
(800) 377-4480
BlueRavenSolar.com



NOTES

Sealed For Existing Roof & Attachment Only

10/10/2024
Firm No. : D-0449

CUSTOMER NAME: **STEPHANIE RODGERS**
99 NECTAR LN
BUNNLEVEL, North Carolina 28323

AHJ: Harnett County

UTILITY COMPANY: Duke Energy


| | |
|--------------------|------------------|
| PROJECT ID: | 1036248 |
| PV DC SYSTEM SIZE: | 4.600 kW DC |
| PV AC SYSTEM SIZE: | 3.800 kW AC |
| REVISIONS: | |
| A | 10/09/2024 |
| B | --- |
| C | --- |
| D | --- |
| DRAWN BY: | Brendan Fillmore |
| PLOT DATE: | October 9, 2024 |
| DRAWING TITLE: | Structural |
| DRAWING NUMBER: | PV4 |

| | | | |
|----------|------------------------------------|--------------|----------|
| 4 | L1 (1) 10 AWG THHN/THWN-2 CU BLACK | 3/4 INCH EMT | Exterior |
| | L2 (1) 10 AWG THHN/THWN-2 CU RED | | |
| | N (1) 10 AWG THHN/THWN-2 CU WHITE | | |
| | G (1) 10 AWG THHN/THWN-2 CU GREEN | | |
| | | | |

| | | | |
|----------|---|---------------|----------|
| 3 | L1 (1) 10 AWG THHN/THWN-2 CU BLACK | 3/4 INCH EMT* | Exterior |
| | L2 (1) 10 AWG THHN/THWN-2 CU RED | | |
| | G (1) 10 AWG THHN/THWN-2 CU GREEN | | |
| | | | |
| | *TYPE UF CABLE MAY BE SUBSTITUTED FOR USE IN CONDUIT WHERE NEC CODE PERMITS | | |

| | | | |
|----------|--|------------|----------|
| 2 | L1 (1) 10 AWG THHN/THWN-2 CU BLACK | 3/4 INCH * | Exterior |
| | L2 (1) 10 AWG THHN/THWN-2 CU RED | | |
| | G (1) 10 AWG THHN/THWN-2 CU GREEN | | |
| | | | |
| | *TYPE NM (ROMEX) OR UF CABLE IS PERMITTED FOR INTERIOR OR ATTIC RUNS AND SHALL BE USED WHEN NEC CODE PERMITS | | |

| | | | |
|----------|------------------------------------|-----------------------------------|----------|
| 1 | L1 (1) 12 AWG THHN/THWN-2 CU BLACK | ENPHASE Q-CABLE, 2-WIRE, FREE AIR | Exterior |
| | L2 (1) 12 AWG THHN/THWN-2 CU RED | | |
| | G (1) 6 AWG BARE, CU | | |
| | | | |
| | | | |



INTERCONNECTION NOTES

Utility Meter Number: 325180472

Load Side Breaker in MSP, Interior POI

LEGEND

| | |
|----------------------|---------------------------------|
| (E) EXISTING | (PV) PV BREAKER |
| (N) NEW | (FIB) FACTORY INSTALLED BREAKER |
| (EL) EXISTING LOADS | SPD SURGE PROTECTIVE DEVICE |
| (RL) RELOCATED LOADS | MI MECHANICAL INTERLOCK |

EQUIPMENT NOTES

1 FINAL CONFIGURATION OF PV CIRCUITS TO BE DECIDED BY INSTALLER. MUST COMPLY WITH MAX MICROINVERTERS PER CIRCUIT AS LISTED ON ATTACHED SPEC SHEET.

2

3

4

5

6

7

8

9 GROUNDING ELECTRODE SYSTEM SHALL BE IN ACCORDANCE WITH NEC 250.53.

10

11

12

EQUIPMENT DESCRIPTIONS

(A) PV MODULE: REC Solar REC460AA Pure-RX, 460 W DC, UL 1703 / UL 61730 COMPLIANT

(B) MICROINVERTER: ENPHASE IQ8X-80-M-US, 380 W AC (0.380 kW), 1 PHASE, UL 1741 COMPLIANT

(C) ROOFTOP JUNCTION BOX: EZ SOLAR JB-1.2 JUNCTION BOX

(D) JUNCTION BOX: PVC 4 X 4 JUNCTION BOX

(E) PV COMBINER BOX: ENPHASE COMBINER 5 (X-IQ-AM1-240-5)

(F) SQUARE-D SAFETY SWITCH 30A, 2P, 240VAC, NON-FUSIBLE (DU221RB)

(G)

(H)

(I)

(J)

(K)

(L)

(M)

(N)

(O)

(P)

(Q)

(R)

(S)

(T)



OTHER NOTES

10 MICROINVERTERS X 380 W AC = 3.8 KW AC; PANEL WATTAGE = 460 W DC



1403 N 630 E
Orem, Utah 84097
(800) 377-4480
BlueRavenSolar.com

CUSTOMER NAME: STEPHANIE RODGERS
99 NECTAR LN
BUNNLEVEL, North Carolina 28323

AHJ: Harnett County

UTILITY COMPANY: Duke Energy

PROJECT ID: 1036248

PV DC SYSTEM SIZE: 4.600 kW DC

PV AC SYSTEM SIZE: 3.800 kW AC

REVISIONS:

| | |
|---|------------|
| A | 10/09/2024 |
| B | --- |
| C | --- |
| D | --- |

DRAWN BY: Brendan Fillmore

PLOT DATE: October 9, 2024

DRAWING TITLE: Electrical 3-Line

DRAWING NUMBER: PV5

| ELECTRICAL INFORMATION | |
|----------------------------------|----------------------------|
| UTILITY ELECTRICAL SYSTEM | |
| 1-Phase, 3-Wire, 60Hz, 120/240V | |
| NEW PV SYSTEM | |
| 1-Phase, 3-Wire, 60Hz, 120/240V | |
| AC SYSTEM SIZE | 3.8kW AC |
| DC SYSTEM SIZE | 4.6kW DC |
| PV MODULES | |
| QUANTITY | 10 |
| TYPE | REC Solar REC460AA Pure-RX |
| WATTAGE | 460W DC |
| MICROINVERTERS | |
| TYPE | Enphase IQ8X-80-M-US |
| OUTPUT CURRENT | 1.58A AC |
| NOMINAL VOLTAGE | 240V AC |
| OUTPUT POWER | 380W AC |

| PV BREAKER BACKFEED CALCULATIONS | | | |
|--|--------------------|------------|------------|
| NEC 705.12(B) -- "120% RULE" | | | |
| (BUSBAR RATING * 120%) - OCPD RATING = AVAILABLE BACKFEED | | | |
| | MAIN SERVICE PANEL | SUBPANEL 1 | SUBPANEL 2 |
| BUSBAR RATING | 225A | ---A | ---A |
| PANEL OCPD RATING | 200A | ---A | ---A |
| AVAILABLE BACKFEED (120% RULE) | 70A | ##A | ##A |
| PV BREAKER RATING | 20A | 20A | 20A |
| *THESE CALCULATIONS ARE ONLY APPLICABLE IF PV INTERCONNECTION IS A LOAD SIDE BREAKER. *PV BREAKER MUST BE RATED LESS THAN OR EQUAL TO AVAILABLE BACKFEED FOR CODE COMPLIANCE* | | | |

| DESIGN LOCATION AND TEMPERATURES | |
|----------------------------------|-----------------------------|
| DATA SOURCE | ASHRAE Weather Station Data |
| STATE | North Carolina |
| CITY | BUNNLEVEL |
| WEATHER STATION | SEYMOUR-JOHNSON AFB |
| HIGH TEMP 2% AVG | 35°C |
| EXTREME MINIMUM TEMP | -10°C |

| WIRE SIZE SPECIFICATIONS | | | | | | | | | | |
|---------------------------------------|-------------|-------------|-------------|-------------|---------|---------|---------|---------|---------|---------|
| | ① | ② | ③ | ④ | ⑤ | ⑥ | ⑦ | ⑧ | ⑨ | ⑩ |
| MINIMUM CONDUCTOR AMPACITY | 19.75A AC | 19.75A AC | 19.75A AC | 19.75A AC | ---A AC | ---A AC | ---A AC | ---A AC | ---A AC | ---A AC |
| CONDUCTOR MATERIAL | CU | CU | CU | CU | --- | --- | --- | --- | --- | --- |
| CONDUCTOR TYPE | THHN/THWN-2 | THHN/THWN-2 | THHN/THWN-2 | THHN/THWN-2 | --- | --- | --- | --- | --- | --- |
| CONDUCTOR SIZE | 12 AWG | 10 AWG | 10 AWG | 10 AWG | --- | --- | --- | --- | --- | --- |
| CONDUCTOR AMPACITY | 30A | 40A | 40A | 40A | ---A | ---A | ---A | ---A | ---A | ---A |
| AMBIENT TEMPERATURE ADJUSTMENT FACTOR | 0.96 | 0.96 | 0.96 | 0.96 | --- | --- | --- | --- | --- | --- |
| CONDUIT FILL ADJUSTMENT FACTOR | 1 | 1 | 1 | 1 | --- | --- | --- | --- | --- | --- |
| ADJUSTED CONDUCTOR AMPACITY | 28.8A | 38.4A | 38.4A | 38.4A | ---A | ---A | ---A | ---A | ---A | ---A |
| WIRE RUN DISTANCE (FT) | 66 | 55 | 20 | 5 | --- | --- | --- | --- | --- | --- |
| CALCULATED VOLTAGE DROP | 0.94% | 0.9% | 0.33% | 0.08% | 0% | 0% | 0% | 0% | 0% | 0% |

| PV CIRCUIT SPECIFICATIONS | | | | | | | | | | | | | |
|--|-------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--------------------|-----------|-----------|-----------|-----------|
| | PRIMARY STRUCTURE | | | | | | | | DETACHED STRUCTURE | | | | |
| | CIRCUIT 1 | CIRCUIT 2 | CIRCUIT 3 | CIRCUIT 4 | CIRCUIT 5 | CIRCUIT 6 | CIRCUIT 7 | CIRCUIT 8 | CIRCUIT 1 | CIRCUIT 2 | CIRCUIT 3 | CIRCUIT 4 | CIRCUIT 5 |
| NUMBER OF MODULES PER CIRCUIT | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| RATED AC OUTPUT CURRENT (I _{out}) | 15.8A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A |
| MINIMUM AMPACITY (I _{out} x 125%) | 19.8A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A | 0.0A |
| OVERCURRENT PROTECTION RATING | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A | 20A |
| COMBINED AC OUTPUT CURRENT (C _{out}) | 15.8A | | | | | | | | 0.0A | | | | |
| MINIMUM AMPACITY (C _{out} x 125%) | 19.8A | | | | | | | | 0.0A | | | | |
| COMBINED PV BREAKER RATING | 20AA | | | | | | | | 0AA | | | | |

| TOTAL VOLTAGE DROP | |
|--------------------|------------------|
| WIRE TAG # | VOLTAGE DROP |
| WIRE TAG #1 | 0.94% |
| WIRE TAG #2 | 0.9% |
| WIRE TAG #3 | 0.33% |
| WIRE TAG #4 | 0.08% |
| WIRE TAG #5 | 0% |
| WIRE TAG #6 | 0% |
| TOTAL | 2.250000% |



1403 N 630 E
Orem, Utah 84097
(800) 377-4480
BlueRavenSolar.com

STEPHANIE RODGERS
99 NECTAR LN
BUNNLEVEL, North Carolina 28323

AHJ: Harnett County
UTILITY COMPANY: Duke Energy

CUSTOMER NAME: **STEPHANIE RODGERS**

PROJECT ID: **1036248**

PV DC SYSTEM SIZE: 4.600 kW DC

PV AC SYSTEM SIZE: 3.800 kW AC

| REVISIONS: | |
|------------|------------|
| A | 10/09/2024 |
| B | --- |
| C | --- |
| D | --- |

DRAWN BY: Brendan Fillmore


PLOT DATE: October 9, 2024

DRAWING TITLE: Electrical Calculations


DRAWING NUMBER: **PV6**

WARNING LABELS


UTILITY METER



MAIN SERVICE PANEL



PV AC DISCONNECT



PV COMBINER BOX



1403 N 630 E
Orem, Utah 84097
(800) 377-4480
BlueRavenSolar.com

CUSTOMER NAME: **STEPHANIE RODGERS**
99 NECTAR LN
BUNNLEVEL, North Carolina 28323

AHJ: Harnett County

UTILITY COMPANY: Duke Energy

PROJECT ID: 1036248

PV DC SYSTEM SIZE: 4.600 kW DC

PV AC SYSTEM SIZE: 3.800 kW AC

REVISIONS:

| | |
|---|------------|
| A | 10/09/2024 |
| B | --- |
| C | --- |
| D | --- |

DRAWN BY: Brendan Fillmore

PLOT DATE: October 9, 2024

DRAWING TITLE: Warning Labels

DRAWING NUMBER: PV7


SOLAR'S MOST TRUSTED



REC ALPHA[®] PURE-RX SERIES

DATASHEET

470 W_P
22.6% EFFICIENCY
226 W/M²



EXPERIENCE




PERFORMANCE

REC ALPHA[®] PURE-RX SERIES DATASHEET



| GENERAL DATA | |
|--------------|--|
| Cell Type | 88 half-cut bifacial REC heterojunction cells, with gapless technology |
| Glass | 3.2 mm solar glass with anti-reflective surface treatment in accordance with EN12150 |
| Backsheet | Highly resistant polymer (Black) |
| Frame | Anodized aluminum (Black) |
| Junction Box | 4-part, 4 bypass diodes, IP68 rated, in accordance with IEC 62790 |
| Connectors | Stäubli MC4 PV-KBT4/KST4 (4 mm ²) in accordance with IEC 62852, IP68 only when connected |
| Cable | 4 mm ² solar cable, 1.7 m + 1.7 m in accordance with EN50618 |
| Dimensions | 1728 x 1205 x 30 mm (2.08 m ²) |
| Weight | 22.7 kg |
| Origin | Made in Singapore |



| ELECTRICAL DATA | | PRODUCT CODE*: RECxxxAA Pure-RX | | |
|-----------------|---|---------------------------------|-------|-------|
| STC | Power Output - P _{MAX} (W _p) | 450 | 460 | 470 |
| | Watt Class Sorting - (W) | 0/+10 | 0/ .0 | 0/+10 |
| | Nominal Power Voltage - V _{MPP} (V) | 54.3 | 54.9 | 55.4 |
| | Nominal Power Current - I _{MPP} (A) | 8.29 | 8.38 | 8.49 |
| | Open Circuit Voltage - V _{OC} (V) | 65.1 | 65.3 | 65.6 |
| | Short Circuit Current - I _{SC} (A) | 8.81 | 8.88 | 8.95 |
| | Power Density (W/m ²) | 216 | 221 | 226 |
| | Panel Efficiency (%) | 21.6 | 22.1 | 22.6 |
| NMOT | Power Output - P _{MAX} (W _p) | 343 | 350 | 358 |
| | Nominal Power Voltage - V _{MPP} (V) | 51.2 | 51.7 | 52.2 |
| | Nominal Power Current - I _{MPP} (A) | 6.70 | 6.77 | 6.86 |
| | Open Circuit Voltage - V _{OC} (V) | 61.3 | 61.6 | 61.8 |
| | Short Circuit Current - I _{SC} (A) | 7.11 | 7.17 | 7.23 |

Values at standard test conditions (STC: air mass AM 1.5, irradiance 1000 W/m², temperature 25°C), based on a production spread with a tolerance of P_{max}, V_{oc} & I_{sc} ±3% within one watt class. Nominal module operating temperature (NMOT: air mass AM 1.5, irradiance 800 W/m², temperature 20°C, windspeed 1 m/s). * Where xxx indicates the nominal power class (P_{max}) at STC above.

| MAXIMUM RATINGS* | |
|---------------------------|-----------------------------------|
| Operational Temperature | -40 °C - 85 °C |
| System Voltage | 1000 V |
| Maximum Test Load (front) | +7000 Pa (713 kg/m ²) |
| Maximum Test Load (rear) | -4000 Pa (407 kg/m ²) |
| Max Series Fuse Rating | 25 A |
| Max Reverse Current | 25 A |

| TEMPERATURE RATINGS* | |
|---|-------------|
| Nominal Module Operating Temperature | 44 °C ± 2°C |
| Temperature coefficient of P _{MAX} | -0.24% / °C |
| Temperature coefficient of V _{OC} | -0.24% / °C |
| Temperature coefficient of I _{SC} | 0.04% / °C |

| DELIVERY INFORMATION | |
|---|------------------|
| Panels per Pallet | 33 |
| Panels per 40 ft GP/high cube container | 594 (18 Pallets) |
| Panels per 13.6 m truck | 660 (20 Pallets) |

Available from:


Founded in 1996, REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power. As Solar's Most Trusted, REC is committed to high quality, innovation, and a low carbon footprint in the solar materials and solar panels it manufactures. Headquartered in Norway with operational headquarters in Singapore, REC also has regional hubs in North America, Europe, and Asia-Pacific.

| CERTIFICATIONS | |
|---|--|
| IEC 61215:2011; IEC61730:2016; UL61730 | |
| ISO 11925-2 Ignitability (EN 13501-1 Class E) | |
| IEC 62716 Ammonia Resistance | |
| IEC 61701 Salt Mist (SM6) | |
| IEC 61215:2016 Hailstone (35 mm) | |
| UL 61730 Fire Type 2 | |
| ISO 14001; ISO9001; IEC45001; IEC62941 | |



| WARRANTY | Standard | | | REC ProTrust | | |
|--|----------|--------|-----------|--------------|-----|-----|
| | No | Yes | Yes | No | Yes | Yes |
| Installed by an REC Certified Professional | | | | | | |
| System Size | All | <25 kW | 25-500 kW | | | |
| Product Warranty (yrs) | 20 | 25 | 25 | | | |
| Power Warranty (yrs) | 25 | 25 | 25 | | | |
| Labor Warranty (yrs) | 0 | 25 | 10 | | | |
| Power in Year 1 | 98% | 98% | 98% | | | |
| Annual Degradation | 0.25% | 0.25% | 0.25% | | | |
| Power in Year 25 | 92% | 92% | 92% | | | |

The REC ProTrust Warranty is only available on panels purchased through an REC Certified Solar Professional installer. Warranty conditions apply. See www.recgroup.com for more details



REC Solar PTE. LTD.
20 Tuas South Ave, 14
Singapore 637312
post@recgroup.com
www.recgroup.com



Specifications subject to change without notice.

Ref: PVI-DS-12-06-Rev-4.4.5.2024

DRAWING NUMBER:

SS

IQ8X Microinverter



IQ8X Microinverter

Our newest IQ8 Series Microinverters are the industry's first microgrid-forming*, software-defined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently. The brain of the semiconductor-based microinverter is our proprietary application-specific integrated circuit (ASIC), which enables the microinverter to operate in grid-tied or off-grid mode. This chip is built using advanced 55-nm technology with high-speed digital logic and superfast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.


IQ8X Microinverter is the latest addition to this family, designed to support PV modules with high input DC voltage and cell counts, such as 80-half-cut cells, 88-half-cut cells and 96-cells.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the IQ Battery, IQ Gateway, and the Enphase App monitoring and analysis software.



IQ8 Series Microinverters redefine reliability standards with more than one million cumulative hours of power-on testing, enabling an industry-leading limited warranty of up to 25 years.



Connect PV modules quickly and easily to the IQ8 Series Microinverters with integrated MC4 connectors.



IQ8 Series Microinverters are UL Listed as PV rapid shutdown equipment and conform with regulations when installed according to the manufacturer's instructions.

*Meets UL 1741 only when installed with IQ System Controller 2 and 3.

Easy to install

- Lightweight and compact with plug-and-play connectors
- Power line communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produces power even when the grid is down*
- More than one million cumulative hours of testing
- Class II double-insulated enclosure
- Optimized for the latest high-powered PV modules

Microgrid-forming

- Complies with the latest advanced grid support
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide range of grid profiles
- Meets CA Rule 21 (UL 1741-SA) and IEEE 1547:2018 (UL 1741-SB)

NOTE:

- IQ8 Series Microinverters cannot be mixed with previous generations of Enphase microinverters (IQ7 Series, IQ6 Series, and so on) in the same system.
- IQ Gateway is required to change the default grid profile at the time of installation to meet local Authority Having Jurisdiction (AHJ) requirements.

| INPUT DATA (DC) | UNIT | IQ8X-80-M-US |
|--|------|---|
| Commonly used module pairings ¹ | W | 320-540 |
| Module compatibility | — | To meet compatibility, PV modules must be within the following maximum input DC voltage and maximum module I _{sc} . Module compatibility can be checked at https://enphase.com/installers/microinverters/calculator |
| MPPT voltage range | V | 43-60 |
| Operating range | V | 25-79.5 |
| Minimum and maximum start voltage | V | 30-79.5 |
| Maximum input DC voltage | V | 79.5 |
| Maximum continuous operating DC current | A | 10 |
| Maximum input DC short-circuit current | A | 16 |
| Maximum module I _{sc} | A | 13 |
| Overvoltage class DC port | — | II |
| DC port backfeed current | mA | 0 |
| PV array configuration | — | Ungrounded array; no additional DC side protection required; AC side protection requires maximum 20 A per branch circuit |

| OUTPUT DATA (AC) | UNIT | IQ8X-80-M-US @240 VAC | IQ8X-80-M-US @208 VAC |
|--|------------------|-------------------------------|--|
| Peak output power | VA | 384 | 366 |
| Maximum continuous output power | VA | 380 | 360 |
| Nominal grid voltage (L-L) | V | 240, split-phase (L-L), 180° | 208, single-phase (L-L), 120° ⁴ |
| Minimum and maximum grid voltage ² | V | 211-264 | 183-229 |
| Max. continuous output current | A | 1.58 | 1.73 |
| Nominal frequency | Hz | 60 | |
| Extended frequency range | Hz | 47-68 | |
| AC short circuit fault current over three cycles | A _{rms} | 2.70 | |
| Maximum units per 20 A (L-L) branch circuit ³ | — | 10 | 9 |
| Total harmonic distortion | % | <5 | |
| Overvoltage class AC port | — | III | |
| AC port backfeed current | mA | 18 | |
| Power factor setting | — | 1.0 | |
| Grid-tied power factor (adjustable) | — | 0.85 leading ... 0.85 lagging | |
| Peak efficiency | % | 97.3 | 97.0 |
| CEC weighted efficiency | % | 96.5 | 96.5 |
| Nighttime power consumption | mW | 26 | 12 |

| MECHANICAL DATA | |
|--|--|
| Ambient temperature range | -40°C to 65°C (-40°F to 149°F) |
| Relative humidity range | 4% to 100% (condensing) |
| DC connector type | Stäubli MC4 |
| Dimensions (H × W × D); Weight | 212 mm (8.3") × 175 mm (6.9") × 30.2 mm (1.2"); 1.1 kg (2.43 lbs) |
| Cooling | Natural convection - no fans |
| Approved for wet locations; Pollution degree | Yes; PD3 |
| Enclosure | Class II double-insulated, corrosion-resistant polymeric enclosure |
| Environmental category; UV exposure rating | NEMA Type 6; outdoor |

| COMPLIANCE | |
|----------------|---|
| Certifications | CA Rule 21 (UL 1741-SA), UL 62109-1, IEEE 1547:2018 (UL 1741-SB), FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 This product is UL Listed as PV rapid shutdown equipment and conforms with NEC 2014, NEC 2017, NEC 2020, and NEC 2023 section 690.12 and C22.1-2018 Rule 64-218 rapid shutdown of PV systems for AC and DC conductors when installed according to the manufacturer's instructions. |

(1) No enforced DC/AC ratio.
 (2) Nominal voltage range can be extended beyond nominal if required by the utility.
 (3) Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.
 (4) IQ8X is not certified for use with Enphase Three Phase Network Protection Relay (NPR-3P-208-NA) and therefore designed for single-phase operation only. Check with the local utility requirements if you wish to install single phase inverter across three phases.

Enphase Q Cable Accessories

The **Enphase Q Cable™** and accessories are part of the latest generation Enphase IQ System™. These accessories provide simplicity, reliability, and faster installation times.



Enphase Q Cable

- Two-wire, double-insulated Enphase Q Cable is 50% lighter than the previous generation Enphase cable
- New cable numbering and plug and play connectors speed up installation and simplify wire management
- Link connectors eliminate cable waste

Field-Wireable Connectors

- Easily connect Q cables on the roof without complex wiring
- Make connections from any open connector and center feed any section of cable within branch limits
- Available in male and female connector types

Enphase Q Cable Accessories

CONDUCTOR SPECIFICATIONS

| | |
|---------------------|--|
| Certification | UL3003 (raw cable), UL 9703 (cable assemblies), DG cable |
| Flame test rating | FT4 |
| Compliance | RoHS, OIL RES I, CE, UV Resistant, combined UL for Canada and United States |
| Conductor type | THHN/THWN-2 dry/wet |
| Disconnecting means | The AC and DC bulkhead connectors have been evaluated and approved by UL for use as the load-break disconnect required by NEC 690. |





Q CABLE TYPES / ORDERING OPTIONS

| Connectorized Models | Size / Max Nominal Voltage | Connector Spacing | PV Module Orientation | Connector Count per Box |
|----------------------|----------------------------|-------------------|-----------------------|-------------------------|
| Q-12-10-240 | 12 AWG / 277 VAC | 1.3 m (4.2 ft) | Portrait | 240 |
| Q-12-17-240 | 12 AWG / 277 VAC | 2.0 m (6.5 ft) | Landscape (60-cell) | 240 |
| Q-12-20-200 | 12 AWG / 277 VAC | 2.3 m (7.5 ft) | Landscape (72-cell) | 200 |

ENPHASE Q CABLE ACCESSORIES

| Name | Model Number | Description |
|---|---------------|---|
| Raw Q Cable | Q-12-RAW-300 | 300 meters of 12 AWG cable with no connectors |
| Field-wireable connector (male) | Q-CONN-10M | Make connections from any open connector |
| Field-wireable connector (female) | Q-CONN-10F | Make connections from any Q Cable open connector |
| Cable Clip | Q-CLIP-100 | Used to fasten cabling to the racking or to secure looped cabling |
| Disconnect tool | Q-DISC-10 | Disconnect tool for Q Cable connectors, DC connectors, and AC module mount |
| Q Cable sealing caps (female) | Q-SEAL-10 | One needed to cover each unused connector on the cabling |
| Terminator | Q-TERM-10 | Terminator cap for unused cable ends |
| Enphase EN4 to MC4 adaptor ¹ | ECA-EN4-S22 | Connect PV module using MC4 connectors to IQ micros with EN4 (TE PV4-S SOLARLOK). 150mm/5.9" to MC4. |
| Enphase EN4 non-terminated adaptor ¹ | ECA-EN4-FW | For field wiring of UL certified DC connectors. EN4 (TE PV4-S SOLARLOK) to non-terminated cable. 150mm/5.9" |
| Enphase EN4 to MC4 adaptor (long) ¹ | ECA-EN4-S22-L | Longer adapter cable for EN4 (TE PV4-S SOLARLOK) to MC4. Use with split cell modules or PV modules with short DC cable. 600mm/23.6" |
| Replacement DC Adaptor (MC4) | Q-DCC-2 | DC adaptor to MC4 (max voltage 100 VDC) |
| Replacement DC Adaptor (UTX) | Q-DCC-5 | DC adaptor to UTX (max voltage 100 VDC) |

1. Qualified per UL subject 9703.

| | | | |
|---|---|---|---|
|  | TERMINATOR Terminator cap for unused cable ends, sold in packs of ten (Q-TERM-10) |  | SEALING CAPS Sealing caps for unused aggregator and cable connections (Q-BA-CAP-10 and Q-SEAL-10) |
|  | DISCONNECT TOOL Plan to use at least one per installation, sold in packs of ten (Q-DISC-10) |  | CABLE CLIP Used to fasten cabling to the racking or to secure looped cabling, sold in packs of one hundred (Q-CLIP-100) |

To learn more about Enphase offerings, visit enphase.com



X-IQ-AM1-240-5
X-IQ-AM1-240-5C


IQ Combiner 5/5C

The IQ Combiner 5/5C consolidates interconnection equipment into a single enclosure and streamlines IQ Series Microinverters and IQ Gateway installation by providing a consistent, pre-wired solution for residential applications. IQ Combiner 5/5C uses wired control communication and is compatible with IQ System Controller 3/3G and IQ Battery 5P.

The IQ Combiner 5/5C, IQ Series Microinverters, IQ System Controller 3/3G, and IQ Battery 5P provide a complete grid-agnostic Enphase Energy System.



IQ Series Microinverters
The high-powered smart grid-ready IQ Series Microinverters (IQ6, IQ7, and IQ8 Series) simplify the installation process.



IQ System Controller 3/3G
Provides microgrid interconnection device (MID) functionality by automatically detecting grid failures and seamlessly transitioning the home energy system from grid power to backup power.



IQ Battery 5P
Fully integrated AC battery system. Includes six field-replaceable IQ8D-BAT Microinverters.



IQ Load Controller
Helps prioritize essential appliances during a grid outage to optimize energy consumption and prolong battery life.





5-year limited warranty

*For country-specific warranty information, see the <https://enphase.com/installers/resources/warranty> page.

© 2024 Enphase Energy. All rights reserved. Enphase, the e and CC logos, IQ, and certain other marks listed at <https://enphase.com/trademark-usage-guidelines> are trademarks of Enphase Energy, Inc. in the U.S. and other countries. Data subject to change.

- Smart**
- Includes IQ Gateway for communication and control
 - Includes Enphase Mobile Connect (CELLMODEM-M1-06-SP-05), only with IQ Combiner 5C
 - Supports flexible networking: Wi-Fi, Ethernet, or cellular
 - Provides production metering (revenue grade) and consumption monitoring
- Easy to install**
- Mounts to one stud with centered brackets
 - Supports bottom, back, and side conduit entries
 - Supports up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
 - 80 A total PV branch circuits
 - Bluetooth-based Wi-Fi provisioning for easy Wi-Fi setup
- Reliable**
- Durable NRTL-certified NEMA type 3R enclosure
 - 5-year limited warranty
 - 2-year labor reimbursement program coverage included for both the IQ Combiner SKUs¹
 - UL1741 Listed

IQ Combiner 5/5C

| MODEL NUMBER | |
|--|---|
| IQ Combiner 5 (X-IQ-AM1-240-5) | IQ Combiner 5 with IQ Gateway printed circuit board for integrated revenue-grade PV production metering (ANSIC12.20 ±0.5%), consumption monitoring (± 2.5%), and IQ Battery monitoring (±2.5%). Includes a silver solar shield to deflect heat. |
| IQ Combiner 5C (X-IQ-AM1-240-5C) | IQ Combiner 5C with IQ Gateway printed circuit board for integrated revenue-grade PV production metering (ANSI C12.20 ±0.5%), consumption monitoring (±2.5%) and IQ Battery monitoring (±2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05) ¹ . Includes a silver solar shield to deflect heat. |
| WHAT'S IN THE BOX | |
| IQ Gateway printed circuit board | IQ Gateway is the platform for total energy management for comprehensive, remote maintenance, and management of the Enphase Energy System |
| Busbar | 80 A busbar with support for 1 × IQ Gateway breaker and 4 × 20 A breaker for installing IQ Series Microinverters and IQ Battery 5P |
| IQ Gateway breaker | Circuit breaker, 2-pole, 10 A/15 A |
| Production CT | Pre-wired revenue-grade solid-core CT, accurate up to ±0.5% |
| Consumption CT | Two consumption metering clamp CTs, shipped with the box, accurate up to ±2.5% |
| IQ Battery CT | One battery metering clamp CT, shipped with the box, accurate up to ±2.5% |
| CTRL board | Control board for wired communication with IQ System Controller 3/3G and the IQ Battery 5P |
| Enphase Mobile Connect (only with IQ Combiner 5C) | 4G-based LTE-M1 cellular modem (CELLMODEM-M1-06-SP-05) with a 5-year T-Mobile data plan |
| Accessories kit | Spare control headers for the COMMS-KIT-02 board |
| ACCESSORIES AND REPLACEMENT PARTS (NOT INCLUDED, ORDER SEPARATELY) | |
| CELLMODEM-M1-06-SP-05 | 4G-based LTE-M1 cellular modem with a 5-year T-Mobile data plan |
| CELLMODEM-M1-06-AT-05 | 4G-based LTE-M1 cellular modem with a 5-year AT&T data plan |
| Circuit breakers (off-the-shelf) | Supports Eaton BR2XX, Siemens Q2XX and GE/ABB THQL21XX Series circuit breakers (XX represents 10, 15, 20, 30, 40, 50, or 60). Also supports Eaton BR220B, BR230B, and BR240B circuit breakers compatible with the hold-down kit. |
| Circuit breakers (provided by Enphase) | BRK-10A-2-240V, BRK-15A-2-240V, BRK-20A-2P-240V, BRK-15A-2P-240V-B, and BRK-20A-2P-240V-B (more details in the "Accessories" section) |
| XA-SOLARSHIELD-ES | Replacement solar shield for IQ Combiner 5/5C |
| XA-ENV2-PCBA-5 | IQ Gateway replacement printed circuit board (PCB) for IQ Combiner 5/5C |
| X-IQ-NA-HD-125A | Hold-down kit compatible with Eaton BR-B Series circuit breakers (with screws) |
| XA-COMMS2-PCBA-5 | Replacement COMMS-KIT-02 printed circuit board (PCB) for IQ Combiner 5/5C |
| ELECTRICAL SPECIFICATIONS | |
| Rating | 80 A |
| System voltage and frequency | 120/240 VAC, 60 Hz |
| Busbar rating | 125 A |
| Fault current rating | 10 kAIC |
| Maximum continuous current rating (input from PV/storage) | 64 A |
| Branch circuits (solar and/or storage) | Up to four 2-pole Eaton BR, Siemens Q, or GE/ABB THQL Series distributed generation (DG) breakers only (not included) |
| Maximum total branch circuit breaker rating (input) | 80 A of distributed generation/95 A with IQ Gateway breaker included |
| IQ Gateway breaker | 10 A or 15 A rating GE/Siemens/Eaton included |
| Production metering CT | 200 A solid core pre-installed and wired to IQ Gateway |
| Consumption monitoring CT (CT-200-CLAMP) | A pair of 200 A clamp-style current transformers is included with the box |
| IQ Battery metering CT | 200 A clamp-style current transformer for IQ Battery metering, included with the box |

1. A plug-and-play industrial-grade cell modem for systems of up to 60 microinverters. Available in the United States, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.

Accessories



Mobile Connect

4G-based LTE-M1 cellular modem with a 5-year data plan (CELLMODEM-M1-06-SP-05 for Sprint and CELLMODEM-M1-06-AT-05 for AT&T)



Circuit breakers

BRK-10A-2-240V Circuit breaker, 2-pole, 10 A, Eaton BR210
BRK-15A-2-240V Circuit breaker, 2-pole, 15 A, Eaton BR215
BRK-20A-2P-240V Circuit breaker, 2-pole, 20 A, Eaton BR220
BRK-15A-2P-240V-B Circuit breaker, 2-pole, 15 A, Eaton BR215B with hold-down kit support
BRK-20A-2P-240V-B Circuit breaker, 2-pole, 20 A, Eaton BR220B with hold-down kit support



CT-200-SOLID

200 A revenue-grade solid core Production CT with <0.5% error rate (replacement SKU)



CT-200-CLAMP

200 A clamp-style consumption and battery metering CT with <2.5% error rate (replacement SKU)

MECHANICAL DATA

| | |
|---|---|
| Dimensions (W × H × D) | 37.5 cm × 49.5 cm × 16.8 cm (14.75" × 19.5" × 6.63"). Height is 21.06" (53.5 cm) with mounting brackets |
| Weight | 7.5 kg (16.5 lbs) |
| Ambient temperature range | -40°C to 46°C (-40°F to 115°F) |
| Cooling | Natural convection, plus heat shield |
| Enclosure environmental rating | Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction |
| Wire sizes | <ul style="list-style-type: none"> 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors 60 A breaker branch input: 4 to 1/0 AWG copper conductors Main lug combined output: 10 to 2/0 AWG copper conductors Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizing |
| Communication (in-premise connectivity) | Built-in CTRL board for wired communication with IQ Battery 5P and IQ System Controller 3/3G. Integrated power line communication for IQ Series Microinverters |
| Altitude | Up to 2,600 meters (8,530 feet) |

COMMUNICATION INTERFACES

| | |
|---------------------------|---|
| Integrated Wi-Fi | 802.11b/g/n (dual band 2.4 GHz/5 GHz), for connecting the Enphase Cloud through the internet |
| Wi-Fi range (recommended) | 10 m (32.8 feet) |
| Bluetooth | BLE4.2, 10 m range to configure Wi-Fi SSID |
| Ethernet | Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included), for connecting to the Enphase Cloud through the internet |
| Cellular/Mobile Connect | CELLMODEM-M1-06-SP-05 or CELLMODEM-M1-06-AT-05 (included with IQ Combiner 5C) |
| Digital I/O | Digital input/output for grid operator control |
| USB 2.0 | Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P |
| Access point (AP) mode | For connection between the IQ Gateway and a mobile device running the Enphase Installer App |
| Metering ports | Up to two Consumption CTs, one IQ Battery CT, and one Production CT |
| Power line communication | 90–110 kHz |
| Web API | See https://developer-v4.enphase.com |
| Local API | See guide for local API |

COMPLIANCE

| | |
|-----------------------------|---|
| IQ Combiner with IQ Gateway | UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) |
|-----------------------------|---|

COMPATIBILITY

| | | |
|---------------------------|------------------------|--|
| PV | Microinverters | IQ6, IQ7, and IQ8 Series Microinverters |
| | IQ System Controller | EP200G101-M240US00 |
| COMMS-KIT-01 ² | IQ System Controller 2 | EP200G101-M240US01 |
| | IQ Battery | ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA |
| COMMS-KIT-02 ³ | IQ System Controller 3 | SC200D111C240US01, SC200G111C240US01 |
| | IQ Battery | IQBATTERY-5P-1P-NA |

2. For information about IQ Combiner 5/5C compatibility with the 2nd-generation batteries, refer to the [compatibility matrix](#).
3. IQ Combiner 5/5C comes pre-equipped with COMMS-KIT-02.

Enphase IQ Envoy

The **Enphase IQ Envoy™** communications gateway delivers solar production and energy consumption data to Enphase Enlighten™ monitoring and analysis software for comprehensive, remote maintenance and management of the Enphase IQ System.

With integrated revenue grade production metering and optional consumption monitoring, Envoy IQ is the platform for total energy management and integrates with the Enphase Ensemble™ and the Enphase IQ Battery™.



Smart

- Enables web-based monitoring and control
- Bidirectional communications for remote upgrades
- Supports power export limiting and zeroexport applications

Simple

- Easy system configuration using Enphase Installer Toolkit™ mobile app
- Flexible networking with Wi-Fi, Ethernet, or cellular

Reliable

- Designed for installation indoors or outdoors
- Five-year warranty

Enphase IQ Envoy

MODEL NUMBERS

| | |
|-------------------------------------|---|
| Enphase IQ Envoy™ ENV-IQ-AM1-240 | Enphase IQ Envoy communications gateway with integrated revenue grade PV production metering (ANSI C12.20 +/- 0.5%) and optional consumption monitoring (+/- 2.5%). Includes one 200A continuous rated production CT (current transformer). |
|-------------------------------------|---|

ACCESORIES (Order Separately)

| | |
|--|---|
| Enphase Mobile Connect™ CELLMODEM-M1 (4G based LTE-M/5-year data plan) CELLMODEM-M1-B (4G-based LTE-M1/5-year data plan) | Plug and play industrial grade cellular modem with data plan for systems up to 60 microinverters. (Available in the US, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.) |
| Consumption Monitoring CT CT-200-SPLIT | Split-core consumption CTs enable whole home metering. |
| Ensemble Communications Kit COMMS-KIT-01 | Installed at the IQ Envoy. For communications with Enphase Encharge™ storage and Enphase Enpower™ smart switch. Includes USB cable for connection to IQ Envoy or Enphase IQ Combiner™ and allows wireless communication with Encharge and Enpower. |

POWER REQUIREMENTS

| | |
|---------------------------|---|
| Power requirements | 120/240 VAC split-phase. Max 20 A overcurrent protection required. |
| Typical Power Consumption | 5W |

CAPACITY

| | |
|---------------------------------|-----------|
| Number of microinverters polled | Up to 600 |
|---------------------------------|-----------|

MECHANICAL DATA

| | |
|---------------------------|--|
| Dimensions (WxHxD) | 21.3 x 12.6 x 4.5 cm (8.4" x 5" x 1.8") |
| Weight | 17.6 oz (498 g) |
| Ambient temperature range | -40° to 65° C (-40° to 149° F) -40° to 46° C (-40° to 115° F) if installed in an enclosure |
| Environmental rating | IP30. For installation indoors or in an NRTL-certified, NEMA type 3R enclosure. |
| Altitude | To 2000 meters (6,560 feet) |
| Production CT | - Limited to 200A of continuous current / 250A OCPD – 72kW AC - Internal aperture measures 19.36mm to support 250MCM THWN conductors (max) - UL2808 certified for revenue grade metering |
| Consumption CT | - For electrical services to 250A with parallel runs up to 500A - Internal aperture measures 0.84" x 0.96" (21.33mm x 24.38mm) to support 3/0 THWN conductor - UL2808 certified, for use at service entrance for services up to 250Vac |

INTERNET CONNECTION OPTIONS

| | |
|------------------|--|
| Integrated Wi-Fi | 802.11b/g/n |
| Ethernet | 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) |
| Mobile | CELLMODEM-M1 (4G) or CELLMODEM-M1-B (4G). Not included. Note that an Enphase Mobile Connect cellular modem is required for all Ensemble installations. |

COMPLIANCE

| | |
|------------|--|
| Compliance | UL 61010-1 CAN/CSA C22.2 No. 61010-1 47 CFR, Part 15, Class B, ICES 003 IEC/EN 61010-1:2010, EN50065-1, EN61000-4-5, EN61000-6-1, EN61000-6-2 Metering: ANSI C12.20 accuracy class 0.5 (PV production only) |
|------------|--|



1403 N. Research Way
Orem, UT 84097

800.377.4480
WWW.BLUERAVENSOLAR.COM

CONFIDENTIAL- THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT BLUE RAVEN SOLAR NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE RECIPIENTS ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF BLUE RAVEN SOLAR LLC.



PV INSTALLATION
PROFESSIONAL
Scott Gurney
#PV-011719-015866

CONTRACTOR:
BRS FIELD OPS
385-498-6700

DRAWING BY:

PLOT DATE:

PROJECT NUMBER:

SHEET NAME:

SPEC SHEET

REVISION:

PAGE NUMBER:

SS






To learn more about Enphase offerings, visit enphase.com




To learn more about Enphase offerings, visit enphase.com

© 2021 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ Envoy, and other trademarks or service names are the trademarks of Enphase Energy, Inc. Data subject to change. 06-30-2021





NEMA TYPE 3R
ILLUSTRATED



TERMINAL LUGS ‡

| AMPERES | MAX. WIRE | MIN. WIRE | TYPE |
|---------|-----------|-----------|------|
| 30 | # 6 AWG | # 12 AWG | AL |
| | # 6 AWG | # 14 AWG | CU |

KNOCKOUTS

| SYMBOL | A | B | C | D |
|--------------|-----|-----|---|------|
| CONDUIT SIZE | .50 | .75 | 1 | 1.25 |

DUAL DIMENSIONS: INCHES
MILLIMETERS

| CATALOG NUMBER | VOTAGE RATINGS | WIRING DIAG. | HORSEPOWER RATINGS | | | | | |
|----------------|----------------|--------------|--------------------|------|--------|-----|------|--------|
| | | | 120VAC | | 240VAC | | | |
| | | | STD. | MAX. | STD. | | MAX. | |
| | | | 1 Ø | 1 Ø | 1 Ø | 3 Ø | 1 Ø | 3 Ø |
| D211NRB●■ | 240VAC | A | 1/2 | 2 | 1 1/2 | - | 3 | - |
| D221NRB | 240VAC | A | - | - | 1 1/2 | 3* | 3 | 7 1/2* |
| D321NRB | 240VAC | B | - | - | 1 1/2 | 3 | 3 | 7 1/2 |
| DU221RB | 240VAC | C | - | - | - | - | 3 | - |
| DU321RB | 240VAC | D | - | - | - | - | 3 | 7 1/2 |

NOTES:
 FINISH - GRAY BAKED ENAMEL ELECTRODEPOSITED OVER CLEANED PHOSPHATIZED STEEL.
 UL LISTED - FILE E-2875
 ALL NEUTRALS - INSULATED GROUNDABLE
 SUITABLE FOR USE AS SERVICE EQUIPMENT
 TOP OF NEMA TYPE 3R SWITCHES HAVE PROVISIONS FOR MAXIMUM 2 1/2" BOLT-ON HUB.
 SHORT CIRCUIT CURRENT RATINGS:
 ● 10,000 AMPERES.
 ■ 10,000 AMPERES WHEN USED WITH OR PROTECTED BY CLASS H OR K FUSES.
 ■ 100,000 AMPERES WITH CLASS R FUSES.
 * FOR CORNER GROUNDED DELTA SYSTEMS.
 ■ PLUG FUSES
 ‡ LUGS SUITABLE FOR 60°C OR 75° CONDUCTORS.

GENERAL DUTY SAFETY SWITCHES
 VISIBLE BLADE TYPE
 30 AMPERE
 ENCLOSURE - NEMA TYPE 3R RAINPROOF



DWG# 1852
NO.

A. System Specifications and Ratings

- Maximum Voltage: 1,000 Volts
- Maximum Current: **JB-1.2:** 80 Amps; **JB-1.XL:** 120 Amps
- Allowable Wire: 14 AWG – 6 AWG
- Spacing: Please maintain a spacing of at least ½” between uninsulated live parts and fittings for conduit, armored cable, and uninsulated live parts of opposite polarity.
- Enclosure Rating: Type 3R
- Roof Slope Range: 2.5 – 12:12
- Max Side Wall Fitting Size: 1”
- Max Floor Pass-Through Fitting Size: 1”
- Ambient Operating Conditions: (-35°C) - (+75°C)
- Compliance:
 - **JB-1.2:** UL1741, CSA C22.2 No. 290; **JB-1.XL:** UL1741, CSA C22.2 No. 290
 - Approved wire connectors: must conform to UL1741, CSA C22.2 No. 290
- System Marking: **Interekt Symbol and File #5019942**
- Periodic Re-inspections: If re-inspections yield loose components, loose fasteners, or any corrosion between components, components that are found to be affected are to be replaced immediately.



Table 1: Typical Wire Size, Torque Loads and Ratings


| | 1 Conductor | 2 Conductor | Torque | | | | |
|---|-------------|-------------|---------|-------------|-------------|---------|---------|
| | | | Type | NM | Inch Lbs | Voltage | Current |
| ABB ZS6 terminal block | 10-24 awg | 16-24 awg | Sol/Str | 0.5-0.7 | 6.2-8.85 | 600V | 30 amp |
| ABB ZS10 terminal block | 6-24 awg | 12-20 awg | Sol/Str | 1.0-1.6 | 8.85-14.16 | 600V | 40 amp |
| ABB ZS16 terminal block | 4-24 awg | 10-20 awg | Sol/Str | 1.6-2.4 | 14.6-21.24 | 600V | 60 amp |
| ABB M6/8 terminal block | 8-22 awg | | Sol/Str | .08-1 | 8.85 | 600V | 50 amp |
| Ideal 452 Red <small>WING-NUT Wire Connector</small> | 8-18 awg | | Sol/Str | Self-Torque | Self-Torque | 600V | |
| Ideal 451 Yellow <small>WING-NUT Wire Connector</small> | 10-18 awg | | Sol/Str | Self-Torque | Self-Torque | 600V | |
| Ideal, In-Sure <small>Push-In Connector Part #39</small> | 10-14 awg | | Sol/Str | Self-Torque | Self-Torque | 600V | |
| WAGO, 2204-1201 | 10-20 awg | 16-24 awg | Sol/Str | Self-Torque | Self-Torque | 600V | 30 amp |
| WAGO, 221-612 | 10-20 awg | 10-24 awg | Sol/Str | Self-Torque | Self-Torque | 600V | 30 amp |
| Dottie DRC75 | 6-12 awg | | Sol/Str | Snap-In | Snap-In | | |
| ESP NG-53 | 4-6 awg | | Sol/Str | | 45 | 2000V | |
| | 10-14 awg | | Sol/Str | | 35 | | |
| ESP NG-717 | 4-6 awg | | Sol/Str | | 45 | 2000V | |
| | 10-14 awg | | Sol/Str | | 35 | | |
| Brumall 4-5,3 | 4-6 awg | | Sol/Str | | 45 | 2000V | |
| | 10-14 awg | | Sol/Str | | 35 | | |

Table 2: Minimum wire-bending space for conductors through a wall opposite terminals in mm (inches)

| Wire size, AWG or kcmil (mm2) | Wires per terminal (pole) | | | |
|----------------------------------|---------------------------|----------------|----------------|------------------------|
| | 1 mm (inch) | 2 mm (inch) | 3 mm (inch) | 4 or More mm (inch) |
| 14-10 (2.1-5.3) | Not Specified | - | - | - |
| 8 (8.4) | 38.1 (1-1/2) | - | - | - |
| 6 (13.3) | 50.8 (2) | - | - | - |

| ITEM NO. | PART NUMBER | DESCRIPTION | QTY |
|----------|--------------------------------------|----------------------------------|-----|
| 1 | JB-1.2 BODY | POLYCARBONATE WITH UV INHIBITORS | 1 |
| 2 | JB-1.2 LID | POLYCARBONATE WITH UV INHIBITORS | 1 |
| 3 | #10 X 1-1/4" PHILLIPS PAN HEAD SCREW | | 6 |
| 4 | #8 X 3/4" PHILLIPS PAN HEAD SCREW | | 6 |

| SIZE | DWG. NO. | REV |
|-----------------------|---------------------------------------|--------------|
| B | JB-1.2 | |
| SCALE: 1:2 | WEIGHT: 1.45 LBS | SHEET 1 OF 3 |
| TORQUE SPECIFICATION: | 15-20 LBS | |
| CERTIFICATION: | UL 1741, NEMA 3R CSA C22.2 NO. 290 | |
| WEIGHT: | 1.45 LBS | |



PROPRIETARY AND CONFIDENTIAL: THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF EZ SOLAR. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF EZ SOLAR IS PROHIBITED.



DRAWING NUMBER:

SS

RIGID PVC CONDUIT FITTINGS

JB444 JUNCTION BOXES

ISSUE DATE:
DATE D'EMISSION: 2009 04 30


SUPERCEDES:
REPLACE: 2004 07 15

RIGID PVC CONDUIT FITTINGS



JB444 JUNCTION BOXES

ISSUE DATE:
DATE D'EMISSION: 2009 04 30

SUPERCEDES:
REPLACE: 2004 07 15



COVER DIMENSIONS




| PRODUCT CODE | PART NUMBER | NOMINAL SIZE | | A | | B | | C | |
|--------------|------------------|--------------|------|-------|------|-------|------|-------|------|
| | | (in) | (mm) | (in) | (mm) | (in) | (mm) | (in) | (mm) |
| 076668 | J444 STAHLIN | 4 | 103 | 3.675 | 93 | 4.000 | 102 | 3.450 | 88 |
| 076259 | AMJB444 ALLIED | 4 | 103 | 3.675 | 93 | 4.000 | 102 | 3.450 | 88 |
| 077643* | 2037-424T CANLET | 4 | 103 | 3.675 | 93 | 4.000 | 102 | 3.450 | 88 |
| 077696 | JB 444 | 4 | 103 | 4.000 | 101 | 4.395 | 112 | 3.950 | 101 |

| PRODUCT CODE | PART NUMBER | NOMINAL SIZE | | D | | E | | VOLUME | |
|--------------|------------------|--------------|------|-------|------|-------|------|----------|----------|
| | | (in) | (mm) | (in) | (mm) | (in) | (mm) | (cu. In) | (cu. Cm) |
| 076668 | J444 STAHLIN | 4 | 103 | 4.180 | 106. | 3.850 | 98 | 51.5 | 844.6 |
| 076259 | AMJB444 ALLIED | 4 | 103 | 4.180 | 106 | 3.850 | 98 | 51.5 | 844.6 |
| 077643* | 2037-424T CANLET | 4 | 103 | 4.180 | 106 | 3.850 | 98 | 51.5 | 844.6 |
| 077696 | JB 444 | 4 | 103 | 4.170 | 106 | 3.930 | 100 | 51.5 | 844.6 |

| PRODUCT CODE | PART NUMBER | NOMINAL SIZE | | GASKET CODE | INSERT CODE | SCREW CODE | M.FEET CODE |
|--------------|------------------|--------------|------|-------------|--------------------------|--------------------------|-------------|
| | | (in) | (mm) | | | | |
| 076668 | J444 STAHLIN | 4 | 103 | | 072538 (4) | | |
| 076259 | AMJB444 ALLIED | 4 | 103 | | 072538 (4) | | |
| 077643* | 2037-424T CANLET | 4 | 103 | | 072538 (4) | | |
| 077696 | JB 444 | 4 | 103 | 097731 | 072538 (4) 072539 (2) | 072522 (4) 072513 (2) | 097747 |

* BOX WITH MOLDED MOUNTING FEET, INSERT ONLY; NO COVER, OR GASKET, UL LISTED 576J



"Stay Connected" with **HEYCO** Solar Power Components
a PennEngineering® Company

Heyco®-Tite Liquid Tight Cordgrips for Enphase Q Cables

Straight-Thru, NPT Hubs with Integral Sealing Ring


The Ultimate in Liquid Tight Strain Relief Protection

ALL NEW
PRODUCT!



| GLAND CONFIGURATION | PART NO. | DESCRIPTION | UL/CSA or SAUS | PART DIMENSIONS | | | | | | | | | | | |
|--------------------------------------|------------------|-------------|----------------|---------------------------------|------------------|---------------|-------------------------|-----------|------|-----|------|-----|-----|------|------|
| | | | | A | B | C | D | E | | | | | | | |
| Type | Size | No. | Black | Clearance Hole Dia. | Max. O.A. Length | Thread Length | Wrenching Nut Thickness | Flat Size | | | | | | | |
| * | mm. | | | in. | mm. | in. | mm. | in. | mm. | | | | | | |
| Oval Gland | | | | | | | | | | | | | | | |
| Q Cable | 6.1 x 9.7 | 1 | M3231GCZ | LTCC 1/2 6.1x9.7MM | UL/CSA | .875 | 22.2 | 1.70 | 43.2 | .61 | 15.5 | .21 | 5.3 | .98 | 24.9 |
| Break-Thru Skinned Over Gland | | | | | | | | | | | | | | | |
| Q Cables plus Ground | 6.1 x 9.7 3.3 | 2 1 | M3234GDA-SM | SMCG 3/4 2-6.1x9.7MM 1-3.3MM | UL/CSA | 1.040 | 26.4 | 2.00 | 50.8 | .62 | 15.7 | .25 | 6.4 | 1.30 | 33.0 |

Metal Locknuts INCLUDED.



| | |
|---------------------|---|
| Material | Nylon 6/6 with TPE Sealing Gland |
| Certifications | UL Listed under Underwriters' Laboratories File E504900 CSA Certified by the Canadian Standards Association File 93876 |
| Flammability Rating | 94V-2 |
| Temperature Range | Static -40°F (-40°C) to 239°F (115°C) Dynamic -4°F (-20°C) to 212°F (100°C) |
| IP Rating | IP 68 |


- Two new cordgrips now accommodate the Enphase Q Cable – M3231GCZ (1/2" NPT) and M3234GDA-SM (3/4" NPT).
- The 1/2" version provides liquid tight entry for one Enphase Q Cable – .24 x .38" (6,1 x 9,7 mm).
- The 3/4" version provides liquid tight entry for up to two Enphase Q Cables – .24 x .38" (6,1 x 9,7 mm) and an additional .130" (3,3 mm) dia. hole for a #8 solid grounding cable.
- The 3/4" version utilizes our skinned-over technology so any unused holes will retain a liquid tight seal.
- Rated for use with DG Cable.

Heyco® Helios® UVX Clip – Blind Mount

ALL NEW
PRODUCT!




| PANEL THICKNESS RANGE | | WIRE DIAMETER RANGE | | PART NO. | DESCRIPTION | MOUNTING HOLE DIA. A | OVERALL HEIGHT C |
|-----------------------|---------|---------------------|-----|--|----------------|--|-------------------|
| Minimum | Maximum | 1-2 Wires | | | | | |
| in. | mm. | in. | mm. | | | in. | mm. |
| 1-2 Wires | | | | | | | |
| .028 | 0,7 | .250 | 6,4 | .23 (5,8 mm) - .32 (8,0 mm) each cable | S6520 S6560 | Helios UVX Clip 100 Pack Helios UVX Clip Bulk | .260 6,6 .96 24,4 |



| | |
|---------------------|---|
| Material | Nylon 6/6 with extended UV Capabilities |
| Flammability Rating | 94V-2 |
| Temperature Range | Dynamic -4°F (-20°C) to 185°F (85°C) |

- The jersey pine tree mounting style installs easily with superior holding power.
- UVX nylon protects from corrosion due to outdoor exposure.
- Installs into .260" (6,6 mm) mounting hole.
- Holds up to 2 cables between .230 - .315" (5,8 - 8,0 mm) each.
- Cables install with fingertip pressure.
- Molded from our robust UVX nylon 6/6 with extended UV capabilities for our Solar 20 Year Warranty.



LISTED **UL2703** FIXING & BRACING
REPAIRING, LEADING
SYSTEM PER CLASSIFICATION



2 INSTALLS PER DAY

Make two installs per day your new standard. **SFM INFINITY** has fewer roof attachments, one tool installation, and pre-assembled components to get you off the roof 40% faster.


87% OF HOMEOWNERS PREFER

BETTER AESTHETICS

Install the system with the aesthetics preferred by homeowners, with integrated front trim, trim end caps, dark components, and recessed hardware.

MAXIMUM POWER DENSITY

Easily mix module orientations to achieve optimal power density without incurring the increased bill of materials, labor, and attachments required by rail.



SYSTEM OVERVIEW


| | PART NAME | DESCRIPTION |
|---|-------------------|---|
| 1 | TRIMRAIL | Structural front trim provides aesthetic and aligns modules. |
| 2 | TRIMRAIL SPLICE | Connects and electrically bonds sections of TRIMRAIL . |
| 3 | TRIMRAIL FLASHKIT | Attaches TRIMRAIL to roof. Available for comp shingle or tile. |
| 4 | MODULE CLIPS | Secure modules to TRIMRAIL . |
| 5 | MICRORAIL | Connects modules to SLIDERS. Provides post-install array leveling. |
| 6 | SPLICE | Connects and supports modules. Provides east-west bonding. ATTACHED SPLICE also available. |
| 7 | SLIDER FLASHKIT | Roof attachment and flashing. Available for comp shingle and tile. |

BONDING AND ACCESSORIES


| | PART NAME | DESCRIPTION |
|--|------------------------|---|
| | TRIMRAIL ENDCAPS | Covers ends of TRIMRAIL for refined aesthetic. |
| | TRIMRAIL BONDING CLAMP | Electrically bonds TRIMRAIL and modules |
| | N/S BONDING CLAMP | Electrically bonds rows of modules |

20% FEWER ATTACHMENTS

Save time and money on every project: **SFM INFINITY** requires fewer attachments than rail systems.



SFM INFINITY 15 Attachments




RAIL 20 Attachments

30% LOGISTICS SAVINGS

With fewer SKUs and compact components, **SFM INFINITY** is easier to stock, easier to transport, and easier to lift to the roof. Plus, make more efficient use of your vehicle fleet.



SFM INFINITY REVOLUTIONIZES ROOFTOP SOLAR WITH BENEFITS ACROSS YOUR BUSINESS, FROM DESIGN AND LOGISTICS, THROUGH ARRAY INSTALLATION AND SERVICE.



Star Washer is Single Use Only



TERMINAL TORQUE,
Install Conductor and torque to the following:
4-6 AWG: 35in-lbs
8 AWG: 25 in-lbs
10-14 AWG: 20 in-lbs

LUG DETAIL & TORQUE INFO
IlSCO Lay-In Lug (GBL-4DBT)

- 10-32 mounting hardware
- Torque = 5 ft-lb
- AWG 4-14 - Solid or Stranded

TERMINAL TORQUE,
Install Conductor and torque to the following:
4-14 AWG: 35in-lbs



LUG DETAIL & TORQUE INFO
IlSCO Flange Lug (SGB-4)

- 1/4" mounting hardware
- Torque = 75 in-lb
- AWG 4-14 - Solid or Stranded

WEEBLUG Single Use Only




TERMINAL TORQUE,
Install Conductor and torque to the following:
6-14 AWG: 7ft-lbs

LUG DETAIL & TORQUE INFO
Wiley WEEBLug (6.7)

- 1/4" mounting hardware
- Torque = 10 ft-lb
- AWG 6-14 - Solid or Stranded



NOTE: ISOLATE COPPER FROM ALUMINUM CONTACT TO PREVENT CORROSION

System bonding is accomplished through modules. System grounding accomplished by attaching a ground lug to any module at a location on the module specified by the module manufacturer.





E-W BONDING PATH:

E-W module to module bonding is accomplished with 2 pre-installed bonding pins which engage on the secure side of the Microrail™ and splice.



N-S BONDING PATH:

N-S module to module bonding is accomplished with bonding clamp with 2 integral bonding pins. (refer also to alternate method)



TRIMRAIL BONDING PATH:

Trimrail to module bonding is accomplished with bonding clamp with integral bonding pin and bonding T-bolt. (refer also to alternate method)

SYSTEM LEVEL FIRE CLASSIFICATION

The system fire class rating requires installation in the manner specified in the SUNFRAME MICRORAIL (SFM) Installation Guide. SFM has been classified to the system level fire portion of UL 1703. This UL 1703 classification has been incorporated into the UL 2703 product certification. SFM has achieved Class A, B & C system level performance for low slope & steep sloped roofs when used in conjunction with type 1 and type 2 modules. Class A, B & C system level fire

performance is inherent in the SFM design, and no additional mitigation measures are required. The fire classification rating is valid for any roof pitch. There is no required minimum or maximum height limitation above the roof deck to maintain the Class A, B & C fire rating for SFM. SUNFRAME MICRORAIL™ components shall be mounted over a fire resistant roof covering rated for the application.

| Module Type | Roof Slope | System Level Fire Rating | Microrail Direction | Module Orientation | Mitigation Required |
|-------------------|-------------------------|--------------------------|---------------------|-----------------------|---------------------|
| Type 1 and Type 2 | Steep Slope & Low Slope | Class A, B & C | East-West | Landscape OR Portrait | None Required |

UL2703 TEST MODULES

See pages 22 and 23 for a list of modules that were electrically and mechanically tested or qualified with the SUNFRAME MICRORAIL (SFM) components outlined within this Installation Guide.

- Maximum Area of Module = 27.76 sqft
- UL2703 Design Load Ratings:
 - a) Downward Pressure – 113 PSF / 5400 Pa
 - b) Upward Pressure – 50 PSF / 2400 Pa
 - c) Down-Slope Load – 21.6 PSF / 1034 Pa
- Tested Loads:
 - a) Downward Pressure – 170 PSF / 8000 Pa
 - b) Upward Pressure – 75 PSF / 3500 Pa
 - c) Down-Slope Load – 32.4 PSF / 1550 Pa
- Maximum Span = 6ft
- Use with a maximum over current protection device OCPD of 30A
- System conforms to UL Std 2703, certified to LTR AE-001-2012
- Rated for a design load of 2400 Pa / 5400 Pa with 24 inch span
- PV modules may have a reduced load rating, independent of the SFM load rating. Please consult the PV module manufacturer's installation guide for more information
- Down-Slope design load rating of 30 PSF/ 1400 Pa for module areas of 22.3 sq ft or less

| Manufacture | Module Model / Series |
|---------------------|---|
| Aleo | P-Series |
| Aptos | DNA-120-(BF/MF)26 DNA-144-(BF/MF)26 |
| Astronergy | CHSM6612P, CHSM6612P/HV, CHSM6612M, CHSM6612M/HV, CHSM6610M (BL)(BF)/(HF), CHSM72M-HC |
| Auxin | AXN6M610T, AXN6P610T, AXN6M612T & AXN6P612T |
| Axitec | AXIblackpremium 60 (35mm), AXIpower 60 (35mm), AXIpower 72 (40mm), AXIpremium 60 (35mm), AXIpremium 72 (40mm). |
| Boviet | BVM6610, BVM6612 |
| BYD | P6K & MHK-36 Series |
| Canadian Solar | CS1(H/K/U/Y)-MS CS3(K/L/U), CS3K-MB-AG, CS3K-(MS/P) CS3N-MS, CS3U-MB-AG, CS3U-(MS/P), CS3W CS5A-M, CS6(K/U), CS6K-(M/P), CS6K-MS CS6P-(M/P), CS6U-(M/P), CS6V-M, CS6X-P |
| Centrosolar America | C-Series & E-Series |
| CertainTeed | CT2xxMxx-01, CT2xxPxx-01, CTxxxMxx-02, CTxxxM-03, CTxxxMxx-04, CTxxxHC11-04 |
| Dehui | DH-60M |

| Manufacture | Module Model / Series |
|-----------------|---|
| Eco Solargy | Orion 1000 & Apollo 1000 |
| ET Solar | ET-M672BHxxxTW |
| Freedom Forever | FF-MP-BBB-370 |
| FreeVolt | Mono PERC |
| GCL | GCL-P6 & GCL-M6 Series |
| Hansol | TD-AN3, TD-AN4, UB-AN1, UD-AN1 |
| Heliene | 36M, 60M, 60P, 72M & 72P Series, 144HC M6 Monofacial/ Bifacial Series, 144HC M10 SL Bifacial |
| HT Solar | HT60-156(M) (NDV) (-F), HT 72-156(M/P) |
| Hyundai | KG, MG, TG, RI, RG, TI, MI, HI & KI Series HiA-SxxxHG |
| ITEK | iT, iT-HE & iT-SE Series |
| Japan Solar | JPS-60 & JPS-72 Series |
| JA Solar | JAP6 60-xxx, JAM6-60-xxx/SI, JAM6(K)-60/ xxx, JAP6(k)-72-xxx/4BB, JAP72SYY-xxx/ZZ, JAP6(k)-60-xxx/4BB, JAP60SYY-xxx/ZZ, JAM6(k)-72-xxx/ZZ, JAM72SYY-xxx/ZZ, JAM6(k)-60-xxx/ZZ, JAM60SYY-xxx/ZZ. i. YY: 01, 02, 03, 09, 10 ii. ZZ: SC, PR, BP, HiT, IB, MW, MR |
| Jinko | JKM & JKMS Series Eagle JKMxxxM JKMxxxM-72HL-V |
| Kyocera | KU Series |

| Manufacture | Module Model / Series | |
|----------------|--|------------------|
| LG Electronics | LGxxxN2T-A4 LGxxx(A1C/E1C/E1K/N1C/N1K/N2T/N2W/ Q1C/Q1K/S1C/S2W)-A5 LGxxxN2T-B5 LGxxxN1K-B6 LGxxx(A1C/M1C/M1K/N1C/N1K/Q1C/Q1K/ QAC/QAK)-A6 LGxxx(N1C/N1K/N2T/N2W)-E6 LGxxx(N1C/N1K/N2W/S1C/S2W)-G4 LGxxxN2T-J5 LGxxx(N1K/N1W/N2T/N2W)-L5 LGxxx(N1C/Q1C/Q1K)-N5 LGxxx (N1C/N1K/N2W/Q1C/Q1K)-V5 | |
| | LR4-60(HIB/HiH/HPB/HPH)-xxxM LR4-72(HiH/HPH)-xxxM LR6-60(BP/HBD/HIBD)-xxxM (30mm) LR6-60(BK)(PE)(HPB)(HPH)-xxxM (35mm) LR6-60(BK)(PE)(PB)(PH)-xxxM (40mm) LR6-72(BP)(HBD)(HIBD)-xxxM (30mm) LR6-72(HV)(BK)(PE)(PH)(PB)(HPH)-xxxM (35mm) LR6-72(BK)(HV)(PE)(PB)(PH)-xxxM (40mm) | |
| | Mission Solar Energy | MSE Series |
| | Mitsubishi | MJE & MLE Series |
| | Neo Solar Power Co. | D6M & D6P Series |

- Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"
- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- Please see the SFM UL2703 Construction Data Report at Unirac.com to ensure the exact solar module selected is approved for use with SFM
- SFM Infinity is not compatible with module frame height of less than 30mm and more than 40mm. See Module Mounting section, page 12 for further information

| Manufacture | Module Model / Series |
|-------------|---|
| Panasonic | EVPVxxx (H/K/PK), VBHNxxxSA15 & SA16, VBHNxxxSA17 & SA18, VBHNxxxSA17(E/G) & SA18E, VBHNxxxKA01 & KA03 & KA04, VBHNxxxZA01, VBHNxxxZA02, VBHNxxxZA03, VBHNxxxZA04 |
| Peimar | SGxxxM (FB/BF) |
| Phono Solar | PS-60, PS-72 |
| Prism Solar | P72 Series |
| Q.Cells | Plus, Pro, Peak, G3, G4, G5, G6(+), G7, G8(+) Pro, Peak L-G2, L-G4, L-G5, L-G6, L-G7 Q.PEAK DUO BLK-G6+ Q.PEAK DUO BLK-G6+/TS Q.PEAK DUO (BLK)-G8(+) Q.PEAK DUO L-G8.3/BFF Q.PEAK DUO (BLK) ML-G9(+) Q.PEAK DUO XL-G9/G9.2/G9.3 Q.PEAK DUO (BLK) ML-G10(+) Q.PEAK DUO XL-G(10/10.2/10.3/10.c/10.d) Q.PEAK DUO BLK ML-G10+ / t |
| REC Solar | Alpha (72) (Black) (Pure) RECxxxAA PURE-R RECxxxNP3 Black N-Peak (Black) N-Peak 2 (Black) PEAK Energy Series PEAK Energy BLK2 Series PEAK Energy 72 Series |

| Manufacture | Module Model / Series |
|-------------------|---|
| REC Solar (cont.) | TwinPeak Series TwinPeak 2 Series TwinPeak 2 BLK2 Series TwinPeak 2S(M)72(XV) TwinPeak 3 Series (38mm) TP4 (Black) |
| Renesola | Vitrus2 Series & 156 Series |
| Risen | RSM72-6 (MDG) (M), RSM60-6 |
| SEG Solar | SEG-xxx-BMD-HV SEG-xxx-BMD-TB |
| S-Energy | SN72 & SN60 Series (40mm) |
| Seraphim | SEG-6 & SRP-6 Series |
| Sharp | NU-SA & NU-SC Series |
| Silfab | SLA, SLG, BC Series & SILxxx(BL/NL/NT/HL/ML/BK/NX/NU/HC) |
| Solarever USA | SE-166*83-xxxM-120N |
| Solaria | PowerXT-xxxR-(AC/PD/BD) PowerXT-xxxC-PD PowerXT-xxxR-PM (AC) |
| SolarWorld | Sunmodule Protect, Sunmodule Plus |
| Sonali | SS-M-360 to 390 Series, SS-M-390 to 400 Series, SS-M-440 to 460 Series, SS-M-430 to 460 BiFacial Series, SS 230 - 265 |
| SunEdison | F-Series, R-Series & FLEX FXS Series |

| Manufacture | Module Model / Series |
|-------------------------------|---|
| Suniva | MV Series & Optimus Series |
| SunPower | A-Series A400-BLK, SPR-MAX3-XXX-R, X-Series, E-Series & P-Series |
| Suntech | STP, STPXXXS - B60/Wnhb |
| Talesun | TP572, TP596, TP654, TP660, TP672, Hipor M, Smart |
| Tesla | SC, SC B, SC B1, SC B2 TxxxH, TxxxS |
| Trina | PA05, PD05, DD05, DE06, DD06, PE06, PD14, PE14, DD14, DE09.05, DE14, DE15, PE15H |
| Upsolar | UP-MxxxP(-B), UP-MxxxM(-B) |
| United Renewable Energy (URE) | D7MxxxH7A, D7(M/K)xxxH8A FAKxxx(C8G/E8G), FAMxxxE7G-BB FAMxxxE8G(-BB) FBMxxxMFG-BB |
| Vikram | Eldora, Solivo, Somera |
| Waaree | AC & Adiya Series |
| Winaico | WST & WSP Series |
| Yingli | YGE & YLM Series |
| ZN Shine | ZXM6-72, ZXM6-NH144-166_2094 |

- Unless otherwise noted, all modules listed above include all wattages and specific models within that series. Variable wattages are represented as "xxx"
- Items in parenthesis are those that may or may not be present in a compatible module's model ID
- Slashes "/" between one or more items indicates that either of those items may be the one that is present in a module's model ID
- Please see the SFM UL2703 Construction Data Report at Unirac.com to ensure the exact solar module selected is approved for use with SFM
- SFM Infinity is not compatible with module frame height of less than 30mm and more than 40mm. See Module Mounting section, page 12 for further information

AUTHORIZATION TO MARK

This authorizes the application of the Certification Mark(s) shown below to the models described in the Product(s) Covered section when made in accordance with the conditions set forth in the Certification Agreement and Listing Report. This authorization also applies to multiple listee model(s) identified on the correlation page of the Listing Report.

This document is the property of Intertek Testing Services and is not transferable. The certification mark(s) may be applied only at the location of the Party Authorized To Apply Mark.

Applicant: Unirac, Inc **Manufacturer:**
Address: 1411 Broadway Blvd NE **Address:** Albuquerque, NM 87102
Country: USA **Country:**
Party Authorized To Apply Mark: Same as Manufacturer
Report Issuing Office: Intertek Testing Services NA, Inc., Lake Forest, CA
Control Number: 5019851 **Authorized by:** *Kenneth Leary*
for L. Matthew Snyder, Certification Manager



This document supersedes all previous Authorizations to Mark for the noted Report Number.

This Authorization to Mark is for the exclusive use of Intertek's Client and is provided pursuant to the Certification agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this Authorization to Mark. Only the Client is authorized to permit copying or distribution of this Authorization to Mark and then only in its entirety. Use of Intertek's Certification mark is restricted to the conditions laid out in the agreement and in this Authorization to Mark. Any further use of the Intertek name for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. Initial Factory Assessments and Follow up Services are for the purpose of assuring appropriate usage of the Certification mark in accordance with the agreement, they are not for the purposes of production quality control and do not relieve the Client of their obligations in this respect.

Intertek Testing Services NA Inc.
545 East Algonquin Road, Arlington Heights, IL 60005
Telephone 800-345-3851 or 847-439-5667 Fax 312-283-1672

| | |
|---------------------|--|
| Standard(s): | Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703:2015 Ed.1+R:24Mar2021] PV Module and Panel Racking Mounting System and Accessories [CSA TIL No. A-40:2020] |
| Product: | Photovoltaic Mounting System, Sun Frame Microrail Installation Guide, PUB2023MAY10 |
| Brand Name: | Unirac |
| Models: | Unirac SFM |

AUTHORIZATION TO MARK

This authorizes the application of the Certification Mark(s) shown below to the models described in the Product(s) Covered section when made in accordance with the conditions set forth in the Certification Agreement and Listing Report. This authorization also applies to multiple listee model(s) identified on the correlation page of the Listing Report.

This document is the property of Intertek Testing Services and is not transferable. The certification mark(s) may be applied only at the location of the Party Authorized To Apply Mark.

Applicant: Unirac, Inc **Manufacturer:**
Address: 1411 Broadway Blvd NE **Address:** Albuquerque, NM 87102
Country: USA **Country:**
Party Authorized To Apply Mark: Same as Manufacturer
Report Issuing Office: Intertek Testing Services NA, Inc., Lake Forest, CA
Control Number: 5021866 **Authorized by:** *Kenneth Leary*
for L. Matthew Snyder, Certification Manager



This document supersedes all previous Authorizations to Mark for the noted Report Number.

This Authorization to Mark is for the exclusive use of Intertek's Client and is provided pursuant to the Certification agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this Authorization to Mark. Only the Client is authorized to permit copying or distribution of this Authorization to Mark and then only in its entirety. Use of Intertek's Certification mark is restricted to the conditions laid out in the agreement and in this Authorization to Mark. Any further use of the Intertek name for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. Initial Factory Assessments and Follow up Services are for the purpose of assuring appropriate usage of the Certification mark in accordance with the agreement, they are not for the purposes of production quality control and do not relieve the Client of their obligations in this respect.

Intertek Testing Services NA Inc.
545 East Algonquin Road, Arlington Heights, IL 60005
Telephone 800-345-3851 or 847-439-5667 Fax 312-283-1672

| | |
|---------------------|--|
| Standard(s): | Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703:2015 Ed.1+R:24Mar2021] PV Module and Panel Racking Mounting System and Accessories [CSA TIL No. A-40:2020] |
| Product: | Photovoltaic Mounting System, Sun Frame Microrail Installation Guide, PUB2023MAY10 |
| Brand Name: | Unirac |
| Models: | Unirac SFM |

| 1.0 Reference and Address | | |
|---------------------------|--|--|
| Report Number | 102393982LAX-002 | Original 11-Apr-2016 Revised: 5-Oct-2022 |
| Standard(s) | Mounting Systems, Mounting Devices, Clamping/Retention Devices, and Ground Lugs for Use with Flat-Plate Photovoltaic Modules and Panels [UL 2703:2015 Ed.1+R:24Mar2021] PV Module and Panel Racking Mounting System and Accessories [CSA TIL No. A-40:2020] | |
| Applicant | Unirac, Inc | Manufacturer 2 |
| Address | 1411 Broadway Blvd NE Albuquerque, NM 87102 | Address |
| Country | USA | Country |
| Contact | Klaus Nicolaedis Todd Ganshaw | Contact |
| Phone | 505-462-2190 505-843-1418 | Phone |
| FAX | NA | FAX |
| Email | klaus.nicolaedis@unirac.com toddg@unirac.com | Email |
| Manufacturer 3 | | Manufacturer 4 |
| Address | | Address |
| Country | | Country |
| Contact | | Contact |
| Phone | | Phone |
| FAX | | FAX |
| Email | | Email |
| Manufacturer 5 | | |
| Address | | |
| Country | | |
| Contact | | |
| Phone | | |
| FAX | | |

| 1.0 Reference and Address | | |
|---------------------------|------------------|--|
| Report Number | 102393982LAX-002 | Original 11-Apr-2016 Revised: 5-Oct-2022 |
| Email | | |

| 2.0 Product Description | |
|-------------------------|--|
| Product | Photovoltaic Mounting System, Sun Frame Microrail Installation Guide, PUB2022SEP28 |
| Brand name | Unirac |
| Description | <p>The product covered by this report is the Sun Frame Micro Rail roof mounted Photovoltaic Rack Mounting System. This system is designed to provide bonding and grounding to photovoltaic modules. The mounting system employs anodized or mill finish aluminum brackets that are roof mounted using the slider, outlined in section 4 of this report. There are no rails within this product, whereas the 3" Micro Rail, Floating Splice, and 9" Attached Splice electrically bond the modules together forming the path to ground.</p> <p>The Micro Rails are installed onto the module frame by using a stainless steel bolt anodized with black oxide with a stainless type 300 bonding pin, torqued to 20 ft-lbs, retaining the modules to the bracket. The bonding pin of the Micro Rail when bolted and torqued, penetrate the anodized coating of the photovoltaic module frame (at bottom flange) to contact the metal, creating a bonded connection from module to module.</p> <p>The grounding of the entire system is intended to be in accordance with the latest edition of the National Electrical Code, including NEC 250: Grounding and Bonding, and NEC 690: Solar Photovoltaic Systems or the Canadian Electrical Code, CSA C22.1 Part 1 in accordance to the revision in effect in the jurisdiction in which the project resides. Any local electrical codes must be adhered in addition to the national electrical codes. The Grounding Lug is secured to the photovoltaic module, torqued in accordance with the installation manual provided in this document.</p> <p>Other optional grounding includes the use of the Enphase UL2703 certified grounding system, which requires a minimum of 2 micro-inverters mounted to the same rail, and using the same engage cable.</p> |

| 2.0 Product Description | |
|-------------------------|---|
| Models | Unirac SFM |
| Model Similarity | NA |
| Ratings | <p>Fuse Rating: 30A</p> <p>Module Orientation: Portrait or Landscape Maximum Module Size: 17.98 ft² UL2703 Design Load Rating: 33 PSF Downward, 33 PSF Upward, 10 PSF Down-Slope Tested Loads - 50 psf/2400Pa Downward, 50psf/2400Pa Uplift, 15psf/720Pa Down Slope Trina TSM-255PD05.08 and Sunpower SPR-E20-327 used for Mechanical Loading</p> <p>Increased size ML test: Maximum Module Size: 22.3 ft² UL2703 Design Load Rating: 113 PSF Downward, 50 PSF Upward, 30 PSF Down-Slope LG355S2W-A5 used for Mechanical Loading test. Mounting configuration: Four mountings on each long side of panel with the longest span of 24" UL2703 Design Load Rating: 46.9 PSF Downward, 40 PSF Upward, 10 PSF Down-Slope LG395N2W-A5, LG360S2W-A5 and LG355S2W-A5 used for used for Mechanical Loading test. Mounting configuration: Six mountings for two modules used with the maximum span of 74.5" IEC 61646 Test Loads - 112.78 psf/5400Pa Downward, 50psf/2400Pa Uplift</p> <p>Mechanical Load test to add FlashLoc Slider and Trim Assemblies to UL2703 and IEC 61646 Certifications, & Increase SFM System UL2703 Module Size: Maximum Module Size: 27.76 ft² UL2703 Design Load Rating: 113 PSF Downward, 50 PSF Upward, 21.6 PSF Down-Slope Jinko Eagle 72HM G5 used for Mechanical Loading test. Mounting configuration: Four mountings on each long side of panel with the longest span of 24" Maximum module size: 21.86 ft² IEC 61646 Test Loads - 112.78 psf/5400Pa Downward, 75psf/3600Pa Uplift SunPower model SPR-A430-COM-MLSD used for Mechanical Loading</p> <p>Fire Class Resistance Rating: - Class A for Steep Slope Applications when using Type 1 Modules. Can be installed at any interstitial gap. Installations must include Trim Rail. - Class A for Steep Slope Applications when using Type 2 Modules. Can be installed at any interstitial gap. Installations must include Trim Rail. - Class A Fire Rated for Low Slope applications with Type 1 or 2 listed photovoltaic modules. This system was evaluated with a 5" gap between the bottom of the module and the roof's surface</p> <p>See section 7.0 illustrations # 1, 1a and 1b for a complete list of PV modules evaluated with these racking systems</p> |
| Other Ratings | NA |

