

PROJECT DESCRIPTION:

12 x TRINA SOLAR: TSM-NE09RC.05 395W MONO MODULES
ROOF MOUNTED SOLAR PHOTOVOLTAIC MODULES
DC SYSTEM SIZE: (N) 4.740 kW DC + (E) 4.680 kW DC = 9.420 kW DC
AC SYSTEM SIZE: (N) 7.600 kW AC + (E) 5.700 kW AC = 13.300 kW AC
ROOF ARRAY AREA #1:- 211.32 SQ FT.

EQUIPMENT SUMMARY


- (N) 12 - TRINA SOLAR: TSM-NE09RC.05 395W MONO MODULES WITH
- (N) 01 - TESLA: 1538000-XX-Y 7.6 kW (240V) INVERTER
- (N) 04 - TESLA: RSD MCI-2
- (E) 12 - JINKO SOLAR: JKM390M-72HBL-V 390W MONO MODULES WITH
- (E) 01 - SOLAREEDGE HOME HUB: SE5700H-US (240V) INVERTER

AUTHORITIES HAVING JURISDICTION
BUILDING: HARNETT COUNTY
ZONING: HARNETT COUNTY
UTILITY: CENTRAL EMC

APPLICABLE CODES & STANDARDS
NEC 2020
NCFC 2018
NCBC 2018
NCRC 2018
NCECC 2018

- EXISTING PLUMBING VENTS, SKYLIGHTS, EXHAUST OUTLETS, VENTILATION'S INTAKE AIR OPENINGS SHALL NOT BE COVERED BY THE SOLAR PHOTOVOLTAIC SYSTEM.
- ALL EQUIPMENT SHALL BE LISTED AND LABELED BY A RECOGNIZED ELECTRICAL TESTING LABORATORY AND INSTALLED PER THE LISTING REQUIREMENTS AND THE MANUFACTURER'S INSTRUCTIONS. [NEC 690.4(D)]
- ALL OUTDOOR EQUIPMENT SHALL BE NEMA 3R RATED, INCLUDING ALL ROOF MOUNTED TRANSITION BOXES AND SWITCHES.
- PAINT PV CONDUIT TO MATCH THE DWELLING EXTERIOR.
- CONTACT THE SERVICING UTILITY BEFORE POWERING ON THE PHOTOVOLTAIC SYSTEM
- NCFC SETBACKS ARE REQUIRED TO BE DISCUSSED WITH THE AHJ PRIOR TO CONSTRUCTION.

AREA OF LOT: 15246 SQFT.
AREA OF HOUSE : 1956 SQFT.
GPS COORDINATES :
35.264652, -79.084620



1 PLOT PLAN WITH ROOF PLAN

PV-1 SCALE: 1"=20'-0"



2 HOUSE PHOTO

PV-1 SCALE: NTS



3 VICINITY MAP

PV-1 SCALE: NTS

SHEET INDEX	
PV-1	PLOT PLAN & VICINITY MAP
PV-2	ROOF PLAN & MODULES
PV-2A	STRING LAYOUT
PV-3	ATTACHMENT DETAIL
PV-4	ELECTRICAL LINE DIAGRAM
PV-5	LABELS
PV-6+	EQUIPMENT SPECIFICATIONS



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
PLOT PLAN &
VICINITY MAP

SHEET SIZE
ANSI B
11" X 17"


SHEET NUMBER
PV-1

MODULES TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULE = 12 MODULES
MODULE TYPE = TRINA SOLAR: TSM-NE09RC.05 395W MONO MODULES
MODULE WEIGHT = 47.0 LBS / 21.3 kg.
COMPONENT WEIGHT: 2.20 LBS. PER MODULE
MODULE DIMENSIONS = 69.37"x 44.65" = 21.50 SF
UNIT WEIGHT OF ARRAY = 2.19 PSF



IRONRIDGE HALO ULTRAGRIP ATTACHMENTS @ 48" O.C. = 28 TOTAL



(N) (4) TESLA: RSD MCI-2 RAPID SHUTDOWN

ROOF #1
PITCH - 35°
AZIM. - 287°

(N) IRONRIDGE XR10 RAIL (TYP.)

(28) IRONRIDGE HALO ULTRAGRIP
ATTACHMENTS @ 48" O.C.

(E) (12) JINKO SOLAR:
JKM390M-72HBL-V 390W
MONO MODULES

ROOF #1
(12) TRINA SOLAR: TSM-NE09RC.05
395W MONO MODULES

(N) JUNCTION BOX

(N) 3/4" EMT/LFMC CONDUIT

(E) UTILITY METER/MAIN COMBO

(E) NON-FUSED AC DISCONNECT

(E) SOLAREEDGE HOME HUB: SE5700H-US (240V) INVERTER


(N) NON-FUSED AC DISCONNECT

(N) TESLA:1538000-XX-Y 7.6 kW (240V) INVERTER

(E) SUB PANEL
(INSIDE BASEMENT)

ROOF DESCRIPTION				
ROOF TYPE		COMPOSITION SHINGLE		
ROOF LAYER		1 LAYER		
ROOF	ROOF TILT	AZIMUTH	TRUSS SIZE	TRUSS SPACING
#1	35°	287°	2"X4"	24"

ARRAY AREA & ROOF AREA CALC'S				
ROOF	# OF MODULES	ARRAY AREA (Sq. Ft.)	ROOF AREA (Sq. Ft.)	ROOF AREA COVERED BY ARRAY (%)
#1	12	211.32	391.06	54
TOTAL	(N) 12 + (E) 12	471.12	1956	24



LEGEND

- SUB - SUB PANEL
- CP - COMBINER PANEL
- JB - JUNCTION BOX
- INV - INVERTER
- ACD - AC DISCONNECT
- UM - UTILITY METER
- MSP - MAIN SERVICE PANEL
- TESLA: RSD MCI-2 RAPID SHUTDOWN
- VENT, ATTIC FAN (ROOF OBSTRUCTION)
- ROOF ATTACHMENT
- TRUSS
- CONDUIT



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW


DRAWN BY
ESR

SHEET NAME
ROOF PLAN
& MODULES


SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-2

STRING LEGEND	
<div><div></div></div>	STRING #1



STRING #1
(12 MODULES)



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND

33 LOCKWOOD DR,
CAMERON, NC 28326

A

DC SIZE:9.420 kW

AC SIZE:13.300kW

DRAWN BY

ESR

SHEET NAME


STRING
LAYOUT

SHEET SIZE


ANSI B
11" X 17"

SHEET NUMBER

PV-2A



Load		Rail Span					
Snow (PSF)	Wind (MPH)	4'	5' 4"	6'	8'	10'	12'
None	100	XR10		XR100		XR1000	
	120						
	140						
	160						
10-20	100						
	120						
	140						
	160						
30	100						
	160						
40	100						
	160						
50-70	160						
80-90	160						



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME


SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER

DC SYSTEM SIZE: (N) 4.740 kW DC + (E) 4.680 kW DC = 9.420 kW DC
AC SYSTEM SIZE: (N) 7.600 kW AC + (E) 5.700 kW AC = 13.300 kW AC

(N) (12) TRINA SOLAR: TSM-NE09RC.05 395W MONO MODULES WITH
(N) (01) TESLA: 1538000-XX-Y 7.6 kW (240V) INVERTER
(N) (04) TESLA: RSD MCI-2
(E) (12) JINKO SOLAR: JKM390M-72HBL-V 390W MONO MODULES WITH
(E) (01) SOLAREEDGE HOME HUB: SE5700H-US (240V) INVERTER

(01) STRING OF 12 MODULES ARE CONNECTED IN SERIES



NOTE:-
1. RACEWAYS AND CABLES EXPOSED TO SUNLIGHT ON ROOFTOPS SHOULD BE INSTALLED MORE THAN 7/8" ABOVE THE ROOF USING CONDUIT SUPPORTS.
2. TEMPERATURE RATINGS OF ALL CONDUCTORS, TERMINATIONS, BREAKERS, OR OTHER DEVICES ASSOCIATED WITH THE SOLAR PV SYSTEM SHALL BE RATED FOR AT LEAST 75 DEGREE C.
3. THE GINLONG SOLIS INVERTER MONITORS VOLTAGE BETWEEN THE L1 AND L2, THE NEUTRAL CONDUCTOR IS OPTIONAL WHEN TYING THE INVERTER TO A 240V GRID (240 3Y SYSTEM). GROUND MUST BE CONNECTED TO THE PE TERMINAL. (REF: SHEET PV-9 FOR INSTALLATION MANUAL)
4. ALL NEW SERVICE INSTALLATIONS AND REPLACEMENTS REQUIRE A SURGE-PROTECTIVE DEVICE (SPD) IN ACCORDANCE WITH [NEC 230.67]. THE SPD SHALL BE TYPE 1 OR TYPE 2 AND IS REQUIRED TO BE AN INTEGRAL PART OF THE SERVICE EQUIPMENT OR LOCATED IMMEDIATELY ADJACENT THERETO.

INSTALLER/ELECTRICIAN NOTE:
EC IS TO MEASURE VOLTAGE BEFORE STARTING WORK. IF RESULT IS ANY OTHER VOLTAGE MEASURED THAN 120/240V IS OBSERVED, DO NOT PROCEED. CONTACT ENGINEER.

ELECTRICAL EQUIPMENT LIST				
SL NO:	ITEM	DESCRIPTION	QTY	
1	PV MODULE	TRINA SOLAR: TSM-NE09RC.05 395W MONO MODULES VOC = 48.8 V, VMP = 41.0 V ISC = 10.26 A, IMP = 9.77 A	12	
2	INVERTER	TESLA:1538000-XX-Y 7.6 kW INVERTER OUTPUT: 240 VAC, 32A 98.0% CEC WEIGHTED EFFICIENCY NEMA 3R, UL LISTED	01	
3	JUNCTION BOX	JUNCTION BOX UL 1741, NEMA 3R CSA C22.2 NO.290	01	
4	AC DISCONNECT	EATON AC DISCONNECT: 60A NON-FUSED, 240V NEMA 3R, UL LISTED	01	
5	MAIN SERVICE PANEL	(E) MAIN SERVICE PANEL AND METER: 200A MAIN BUSBAR	01	
6	RAPID SHUTDOWN	TESLA:RSD MCI-2 RATED MAXIMUM DC INPUT CURRENT - 13 ADC MAXIMUM SHORT STRING CURRENT - 17 ADC LIMITATIONS - 1 TO 3 MODULES, 1000 V DC MAXIMUM SYSTEM VOLTAGE	4	
7	BOLT	BX MLPE HARDWARE (BX-CMA-MI-M1)	4	

QTY	CONDUCTOR INFORMATION	CONDUIT TYPE	CONDUIT SIZE
(2)	CU#10AWG - PV WIRE/USE-2	N/A	N/A
(1)	CU#6AWG - BARE COPPER IN FREE AIR		
(2)	CU#10AWG - THWN-2 (L1,L2)	EMT OR LFMC IN ATTIC	3/4"
(1)	CU#10AWG - THWN-2 GND		
(2)	CU#8AWG - THWN-2 (L1,L2)	EMT, LFNC OR LFMC	3/4"
(1)	CU#8AWG - THWN-2 N		
(1)	CU#10AWG - THWN-2 GND	EMT, LFNC OR LFMC	3/4"
(2)	CU#8AWG - THWN-2 (L1,L2)		
(1)	CU#8AWG - THWN-2 N	EMT, LFNC OR LFMC	3/4"
(1)	CU#10AWG - THWN-2 GND		

NOTE: RELOCATE 30A/2P BREAKER FROM MSP TO SUB PANEL TO MAKE ROOM FOR SOLAR BREAKER IN THE MAIN PANEL

NOTE: WIRE SCHEDULE CALLOUT (E) IS EXISTING SYSTEM

NOTE: CONDUIT TO BE UL LISTED FOR WET LOCATIONS AND UV PROTECTED (EX.- EMT,PVC OR EQUIVALENT)

LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
ELECTRICAL LINE DIAGRAM

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-4

LABEL 1
LABEL LOCATION:
EMT/CONDUIT RACEWAY
SOLADECK / JUNCTION BOX
CODE REF: NEC 690.13 (G)
ON ALL CONDUITS SPACED AT MAX 10FT

**WARNING: PHOTOVOLTAIC
POWER SOURCE**

LABEL 2
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.13(B)

⚠ WARNING

ELECTRIC SHOCK HAZARD

**TERMINALS ON THE LINE AND
LOAD SIDES MAY BE ENERGIZED
IN THE OPEN POSITION**

LABEL 3
LABEL LOCATION:
MAIN SERVICE PANEL, AC DISCONNECT
AND SUB PANEL (IF APPLICABLE)
CODE REF: NEC 705.12(C) & NEC 690.59

⚠ WARNING

**DUAL POWER SUPPLY
SOURCE: UTILITY GRID AND
PV SOLAR ELECTRIC SYSTEM**

LABEL 4
LABEL LOCATION:
MAIN SERVICE PANEL OR SUB PANEL
(ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 705.12(C) & NEC 690.59

**SOLAR PV BREAKER:
BREAKER IS BACKFED
DO NOT RELOCATE**

LABEL 5
LABEL LOCATION:
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
SUB PANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 705.12(B)(3)(2)


⚠ WARNING

**POWER SOURCE OUTPUT
CONNECTION. DO NOT
RELOCATE THIS
OVERCURRENT DEVICE**

LABEL 6
LABEL LOCATION:
INVERTER
CODE REF: [NEC 690.56(C)(1)(A)]

**SOLAR PV SYSTEM EQUIPPED
WITH RAPID SHUTDOWN**

TURN RAPID SHUTDOWN
SWITCH TO THE
"OFF" POSITION TO
SHUT DOWN PV SYSTEM
AND REDUCE
SHOCK HAZARD
IN THE ARRAY



LABEL 7
LABEL LOCATION:
AC DISCONNECT
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 690.56(C)(2)

**RAPID SHUTDOWN SWITCH
FOR SOLAR PV SYSTEM**

LABEL 8
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.13(B)

DC DISCONNECT

LABEL 9
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.54

**AC DISCONNECT
PHOTOVOLTAIC SYSTEM
POWER SOURCE**

NOMINAL OPERATING AC VOLATGE

RATED AC OUTPUT CURRENT

LABEL 10
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.53

MAXIMUM VOLTAGE

MAXIMUM CIRCUIT CURRENT

MAX. RATED OUTPUT CURRENT
OF THE CHARGE CONTROLLER OR
DC-TO-DC CONVERTER (IF INSTALLED)

LABEL 11
LABEL LOCATION:
MAIN SERVICE PANEL AND SUB PANEL
CODE REF: NEC 110.27(C) & OSHA 1910.145 (f) (7)

⚠ WARNING

**TURN OFF PHOTOVOLTAIC
AC DISCONNECT PRIOR TO
WORKING INSIDE PANEL**

LABEL 12
LABEL LOCATION:
UTILITY METER
CODE REF: NEC 690.13(B)

⚠ WARNING


**THIS SERVICE METER
IS ALSO SERVED BY A
PHOTOVOLTAIC SYSTEM**

LABEL 13
LABEL LOCATION:
MAIN SERVICE PANEL
CODE REF: 2020 NEC 705.13

NOTES

1. NEC ARTICLES 690 AND 705 AND CRC SECTION R324 MARKINGS SHOWN HEREON
2. ALL MARKINGS SHALL CONSIST OF THE FOLLOWING:
 - A. UV RESISTANT SIGN MATERIAL WITH ENGRAVED OR MACHINE PRINTED LETTERS OR ELECTRO-PLATING
 - B. RED BACKGROUND COLOUR WITH WHITE TEXT AND LINE WORK
 - C. ARIAL FONT
3. ALL SIGNS SHALL BE SIZED APPROPRIATELY AND PLACED IN THE LOCATION SPECIFIED
4. SIGNS SHALL BE ATTACHED TO THE SERVICE EQUIPMENT USING POP-RIVETS OR SCREW
5. PLACARD ONLY REQUIRED WHEN PV UTILITY DISCONNECT & METER ARE NOT WITH IN 10'.

**CAUTION:
MULTIPLE SOURCES OF POWER**



33 LOCKWOOD DR, CAMERON, NC 28326

"WARNING"

PHOTOVOLTAIC ARRAY

DISCONNECTION OF NEUTRAL OR GROUNDED CONDUCTORS MAY RESULT IN OVERVOLTAGE ON ARRAY
OR INVERTER



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS

DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

**DC SIZE:9.420 kW
AC SIZE:13.300kW**

DRAWN BY

ESR

SHEET NAME

LABELS

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-5



BACKSHEET MONOCRYSTALLINE MODULE

PRODUCT: TSM-NE09RC.05
PRODUCT RANGE: 380-430W

430W


MAXIMUM POWER OUTPUT

0~+5W

POSITIVE POWER TOLERANCE

21.5%

MAXIMUM EFFICIENCY



Small in size, bigger on power

- Up to 430W, 21.5% module efficiency with high density interconnect technology
- Reduce installation cost with higher power bin and efficiency
- Boost performance in warm weather with low temperature coefficient and operating temperature



High Reliability

- Innovative non-destructive cutting for improved mechanical resistance and strength
- Excellent fire rating, weather resistance, salt spray, sand dust, ammonia performance which is fully applicable in coastal, high temperature, humidity area and harsh environment



Ultra-low Degradation, longer warranty, higher output


- First-year degradation 1% and annual degradation at 0.4%
- Up to 25 years product warranty and 25 years power warranty



Universal solution for residential and C&I rooftops


- Easy for integration, designed for compatibility with existing mainstream inverters and diverse mounting systems
- Perfect size and low weight for handling and installation
- Most valuable solution on low load capacity rooftops (weight similar to backsheet version)
- Mechanical performance up to 6000 Pa positive load and 4000 Pa negative load

Trina Solar's Vertex Bifacial Backsheet Performance Warranty




BACKSHEET MONOCRYSTALLINE MODULE


DIMENSIONS OF PV MODULE(mm)



I-V CURVES OF PV MODULE(415 W)



P-V CURVES OF PV MODULE(415W)



ELECTRICAL DATA (STC)

Peak Power Watts- P_{MAX} (Wp)*	380	385	390	395	400	405	410	415	420	425	430
Power Tolerance- $PMAX$ (W)									0 ~ +5		
Maximum Power Voltage- V_{MPP} (V)	39.8	40.2	40.6	41.0	41.3	41.7	42.1	42.5	42.8	43.2	43.6
Maximum Power Current- I_{MPP} (A)	9.54	9.57	9.73	9.77	9.68	9.71	9.73	9.77	9.80	9.84	9.87
Open Circuit Voltage- V_{OC} (V)	47.5	48.0	48.4	48.8	49.2	49.6	50.1	50.5	50.9	51.4	51.8
Short Circuit Current- I_{SC} (A)	10.15	10.19	10.22	10.26	10.30	10.33	10.37	10.40	10.43	10.47	10.50
Module Efficiency η_m (%)	19.0	19.3	19.5	19.8	20.0	20.3	20.5	20.8	21.0	21.3	21.5

STC: Irradiance 1000W/m², Cell Temperature 25°C, Air Mass AM1.5. *Measuring tolerance: ±3%.

Electrical characteristics with different power bin (reference to 10% Irradiance ratio)

Total Equivalent power- P_{MAX} (Wp)	389	394	399	405	426	431	437	442	447	453	458
Maximum Power Voltage- V_{MPP} (V)	38.7	39.1	39.5	39.8	41.3	41.7	42.1	42.5	42.8	43.2	43.6
Maximum Power Current- I_{MPP} (A)	10.05	10.09	10.13	10.16	10.31	10.34	10.36	10.41	10.44	10.48	10.51
Open Circuit Voltage- V_{OC} (V)	47.1	47.1	47.1	47.5	49.2	49.6	50.1	50.5	50.9	51.4	51.8
Short Circuit Current- I_{SC} (A)	10.71	10.74	10.78	10.81	10.97	11.00	11.04	11.08	11.11	11.15	11.18
Irradiance ratio (rear/front)	10%										

Power Bifaciality: 85±10%.

ELECTRICAL DATA (NOCT)

Maximum Power- P_{MAX} (Wp)	289	293	296	301	312	308	312	316	319	324	328
Maximum Power Voltage- V_{MPP} (V)	37.2	37.6	37.9	38.3	38.6	39.0	39.3	39.7	40.0	40.4	40.7
Maximum Power Current- I_{MPP} (A)	7.76	7.80	7.82	7.86	7.88	7.91	7.93	7.96	7.98	8.01	8.04
Open Circuit Voltage- V_{OC} (V)	45.0	45.5	45.9	46.3	46.6	47.0	47.5	47.8	48.2	48.7	49.1
Short Circuit Current- I_{SC} (A)	8.18	8.21	8.24	8.27	8.30	8.32	8.36	8.38	8.41	8.44	8.46

NOCT: Irradiance at 800W/m², Ambient Temperature 20°C, Wind Speed 1m/s.

MECHANICAL DATA

Solar Cells	Topcon Bifacial
No. of cells	144cells
Module Dimensions	1762×1134×30 mm (69.37×44.65×1.18 inches)
Weight	21.3kg (47.0 lb)
Front Glass	3.2 mm (0.12inches), High Transmission, Tempered Glass
Encapsulant material	POE/EVA
BackSheet	Black Grid Transparent Backsheet
Frame	30mm (1.18 inches) Anodized Aluminium Alloy, Black
J-Box	IP 68 rated
Cables	Photovoltaic Technology Cable 4.0mm ² (0.006 inches ²) Landscape: N 1100 mm/ P 1100 mm (43.31/43.31 inches)
Connector	MC4 EV02
Fire Type	Type 1 or Type2

TEMPERATURE RATINGS

NOCT (Nominal Operating Cell Temperature)	43°C (±2°C)
Temperature Coefficient of P_{MAX}	-0.30%/°C
Temperature Coefficient of V_{OC}	-0.24%/°C
Temperature Coefficient of I_{SC}	0.04%/°C

WARRANTY

25 year Product Workmanship Warranty
25 year Power Warranty
1% first year degradation
0.4% Annual Power Attenuation
(Please refer to product warranty for details)

MAXIMUM RATINGS

Operational Temperature	-40 ~ +85°C
Maximum System Voltage	1500V DC (IEC)
Max Series Fuse Rating	25 A

PACKAGING CONFIGURATION

Modules per box: 36 pieces
Modules per 40' container: 792 pieces

Comprehensive Products and System Certificates



IEC61215/IEC61730/IEC61701/IEC62716/UL61730
ISO 9001: Quality Management System
ISO 14001: Environmental Management System
ISO 14064: Greenhouse Gases Emissions Verification
ISO 45001: Occupational Health and Safety Management System



CAUTION: READ SAFETY AND INSTALLATION INSTRUCTIONS BEFORE USING THE PRODUCT.

© 2023 Trina Solar Co., Ltd. All rights reserved. Specifications included in this datasheet are subject to change without notice.

Version number: TSM_NA_EN_2023_A_51

www.trinasolar.com



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS

DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR.,
CAMERON, NC 28326

DC SIZE: 9.420 kW

AC SIZE: 13.300kW

DRAWN BY

ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-6

Tesla Solar Inverter
with Site Controller

Tesla Solar Inverter completes the Tesla home solar system, converting DC power from solar to AC power for home consumption. Tesla's renowned expertise in power electronics has been combined with robust safety features and a simple installation process to produce an outstanding solar inverter that is compatible with both Solar Roof and traditional solar panels. Once installed, homeowners use the Tesla mobile app to manage their solar system and monitor energy consumption, resulting in a truly unique ecosystem experience.

KEY FEATURES

- Built on Powerwall technology for exceptional efficiency and reliability
 - Wi-Fi, Ethernet, and cellular connectivity with easy over-the-air updates
- Designed to integrate with Tesla Powerwall and Tesla App
 - 0.5% revenue-grade metering for Solar Renewable Energy Credit (SREC) programs included



March 17, 2024

Tesla Solar Inverter Technical Specifications

Electrical Specifications: Output (AC)	Model Number	1538000-xx-y			
	Output (AC) ¹	3.8 kW	5 kW	5.7 kW	7.6 kW
	Nominal Power	3,800 W	5,000 W	5,700 W	7,600 W
	Maximum Apparent Power	3,840 VA	5,040 VA	6,000 VA	7,680 VA
	Maximum Continuous Current	16 A	21 A	24 A	32 A
	Breaker (Overcurrent Protection)	20 A	30 A	30 A	40 A
	Nominal Power Factor	1 - 0.9 (leading / lagging)			
	THD (at Nominal Power)	<5%			

Electrical Specifications: Input (DC)	MPPT	4
	Input Connectors per MPPT	1-2-1-2
	Maximum Input Voltage	600 VDC
	DC Input Voltage Range	60 - 550 VDC
	DC MPPT Voltage Range	60 - 480 VDC ¹
	Maximum Current per MPPT (I _{MP})	13 A ²
	Maximum Short Circuit Current per MPPT (I _{SC})	17 A ²

¹Maximum current.
²Where the DC input current exceeds an MPPT rating, jumpers can be used to allow a single MPPT to intake additional DC current up to 26 A I_{MP} / 34 A I_{SC}.

Performance Specifications	Peak Efficiency	98.6% at 240 V
	CEC Efficiency	98.0% at 240 V
	Allowable DC/AC Ratio	1.7
	Customer Interface	Tesla Mobile App
	Internet Connectivity	Wi-Fi (2.4 GHz, 802.11 b/g/n), Ethernet, Cellular (LTE/4G) ³
	Revenue Grade Meter	Revenue Accurate (+/- 0.5%)
	AC Remote Metering Support	Wi-Fi (2.4 GHz, 802.11 b/g/n)
	Protections	Integrated arc fault circuit interrupter (AFCI), Rapid Shutdown
	Supported Grid Types	60 Hz, 240 V Split Phase
	Warranty	12.5 years

³Cellular connectivity subject to network operator service coverage and signal strength.



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW


DRAWN BY
ESR
SHEET NAME
EQUIPMENT SPECIFICATION
SHEET SIZE
ANSI B 11" X 17"
SHEET NUMBER
PV-7

Tesla Solar Inverter Technical Specifications

Mechanical Specifications

Dimensions

660 mm x 411 mm x 158 mm (26 in x 16 in x 6 in)



Weight 52 lb⁴
Mounting Options Wall mount (bracket)

⁴Door and bracket can be removed for a mounting weight of 37 lb.

Environmental Specifications

Operating Temperature -30°C to 45°C (-22°F to 113°F)⁵
Operating Humidity (RH) Up to 100%, condensing
Storage Temperature -30°C to 70°C (-22°F to 158°F)
Maximum Elevation 3000 m (9843 ft)
Environment Indoor and outdoor rated
Enclosure Rating Type 3R
Ingress Rating IP55 (Wiring compartment)
Pollution Rating PD2 for power electronics and terminal wiring compartment, PD3 for all other components
Operating Noise @ 1 m < 40 db(A) nominal, < 50 db(A) maximum

⁵Performance may be de-rated to 6.2 kW at 240 V when operating at temperatures greater than 45°C.

Compliance Information

Grid Certifications UL 1741, UL 1741 SA, UL 1741 SB, UL 1741 PCS, IEEE 1547-2018, IEEE 1547.1
Safety Certifications UL 1741 PVRSS, UL 1699B, UL 1998 (US), UL 3741
Emissions EN 61000-6-3 (Residential), FCC 47CFR15.109 (a)



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-8

Solar Shutdown Device Technical Specifications

The Solar Shutdown Device is a Mid-Circuit Interrupter (MCI) and is part of the PV system rapid shutdown (RSD) function in accordance with Article 690 of the applicable NEC. When paired with Tesla Solar Inverter, solar array shutdown is initiated by any loss of AC power.

Electrical Specifications	Model	MCI-1	MCI-2
	Nominal Input DC Current Rating (I_{mp})	12 A	13 A
	Maximum Input Short Circuit Current (I_{sc})	19 A	17 A
	Maximum System Voltage (PVHCS)	600 V DC	1000 V DC ⁷
⁷ Maximum System Voltage is limited by Tesla Solar Inverter to 600 V DC.			
RSD Module Performance	Maximum Number of Devices per String	5	5
	Control	Power Line Excitation	Power Line Excitation
	Passive State	Normally Open	Normally Open
	Maximum Power Consumption	7 W	7 W
Environmental Specifications	Warranty	25 years	25 years
	Operating Temperature	-40°C to 50°C (-40°F to 122°F)	-45°C to 70°C (-49°F to 158°F)
	Storage Temperature	-30°C to 70°C (-22°F to 158°F)	-30°C to 70°C (-22°F to 158°F)
	Enclosure Rating	NEMA 4X / IP65	NEMA 4X / IP65
Mechanical Specifications	Electrical Connections	MC4 Connector	MC4 Connector
	Housing	Plastic	Plastic
	Dimensions	125 x 150 x 22 mm (5 x 6 x 1 in)	173 x 45 x 22 mm (6.8 x 1.8 x 1 in)
	Weight	350 g (0.77 lb)	120 g (0.26 lb)
Compliance Information	Mounting Options	ZEP Home Run Clip M4 Screw (#10) M8 Bolt (5/16") Nail / Wood screw	Wire Clip
	Certifications	UL 1741 PVRSE, UL 3741, PVRSA (Photovoltaic Rapid Shutdown Array)	
	RSD Initiation Method	PV System AC Breaker or Switch	

UL 3741 PV Hazard Control (and PVRSA) Compatibility

The following categories of solar module meet the UL 3741 PVHCS listing when installed with Tesla Solar Inverter and Solar Shutdown Devices.

Tesla Solar Roof	PV Hazard Control System: BIPV compliance document
Tesla or Hanwha (Q.Peak Duo BLK or BLK-G6+) Modules certified for use with ZEP racking	PV Hazard Control System: ZS PVHCS compliance document
Other module and racking combinations	PV Hazard Control System: Generic PV Array compliance document



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

A

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR
SHEET NAME
EQUIPMENT SPECIFICATION
SHEET SIZE
ANSI B 11" X 17"
SHEET NUMBER
PV-9





Tech Brief

XR Rail® Family

Solar Is Not Always Sunny

Over their lifetime, solar panels experience countless extreme weather events. Not just the worst storms in years, but the worst storms in 40 years. High winds capable of ripping panels from a roof, and snowfalls weighing enough to buckle a panel frame.

XR Rails® are the structural backbone preventing these results. They resist uplift, protect against buckling and safely and efficiently transfer loads into the building structure. Their superior spanning capability requires fewer roof attachments, reducing the number of roof penetrations and the amount of installation time.



Force-Stabilizing Curve
Sloped roofs generate both vertical and lateral forces on mounting rails which can cause them to bend and twist. The curved shape of XR Rails® is specially designed to increase strength in both directions while resisting the twisting. This unique feature ensures greater security during extreme weather and a longer system lifetime.

Compatible with Flat & Pitched Roofs



XR Rails® are compatible with FlashFoot® and other pitched roof attachments. IronRidge® offers a range of tilt leg options for flat roof mounting applications.

Corrosion-Resistant Materials

All XR Rails® are made of 6000-series aluminum alloy, then protected with an anodized finish. Anodizing prevents surface and structural corrosion, while also providing a more attractive appearance.



XR Rail® Family

The XR Rail® Family offers the strength of a curved rail in three targeted sizes. Each size supports specific design loads, while minimizing material costs. Depending on your location, there is an XR Rail® to match.



XR10

XR10 is a sleek, low-profile mounting rail, designed for regions with light or no snow. It achieves spans up to 6 feet, while remaining light and economical.

- 6' spanning capability
- Moderate load capability
- Clear & black anodized finish
- Internal splices available



XR100

XR100 is a residential and commercial mounting rail. It supports a range of wind and snow conditions, while also maximizing spans up to 10 feet.

- 10' spanning capability
- Heavy load capability
- Clear & black anodized finish
- Internal splices available



XR1000

XR1000 is a heavyweight among solar mounting rails. It's built to handle extreme climates and spans up to 12 feet for commercial applications.

- 12' spanning capability
- Extreme load capability
- Clear anodized finish
- Internal splices available

Rail Selection

The table below was prepared in compliance with applicable engineering codes and standards.* Values are based on the following criteria: ASCE 7-16, Gable Roof Flush Mount, Roof Zones 1 & 2e, Exposure B, Roof Slope of 8 to 20 degrees and Mean Building Height of 30 ft. Visit IronRidge.com for detailed certification letters.

Load		Rail Span					
Snow (PSF)	Wind (MPH)	4'	5' 4"	6'	8'	10'	12'
None	90	XR10		XR100		XR1000	
	120						
	140						
	160						
20	90						
	120						
	140						
	160						
30	90						
	160						
40	90						
	160						
80	160						
120	160						

*Table is meant to be a simplified span chart for conveying general rail capabilities. Use approved certification letters for actual design guidance.

Tech Brief



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS

DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY

ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-10



UFO® Family of Components

Tech Brief

Simplified Grounding for Every Application


The UFO® family of components eliminates the need for separate grounding hardware by bonding solar modules directly to IronRidge® XR Rails®. All system types that feature the UFO® family—Flush Mount®, Tilt Mount® and Ground Mount®—are fully listed to the UL 2703 standard.

UFO® hardware forms secure electrical bonds with both the module and the rail, resulting in many parallel grounding paths throughout the system. This leads to safer and more reliable installations.

Only for installation and use with IronRidge products in accord with written instructions. See IronRidge.com/UFO



Stopper Sleeve
The Stopper Sleeve snaps onto the UFO®, converting it into a bonded end clamp.



Universal Fastening Object (UFO®)
The UFO® securely bonds solar modules to XR Rails®. It comes assembled and lubricated, and can fit a wide range of module heights.



BOSS® Splice
Bonded Structural Splice connects rails with built-in bonding teeth. No tools or hardware needed.




Grounding Lug
A single Grounding Lug connects an entire row of PV modules to the grounding conductor.



Bonded Attachments
The bonding bolt attaches and bonds the L-foot® to the rail. It is installed with the same socket as the rest of the system.

System Diagram



Approved Enphase microinverters can provide equipment grounding of IronRidge systems, eliminating the need for grounding lugs and field installed equipment ground conductors (EGC). A minimum of two microinverters mounted to the same rail and connected to the same Engage cable is required. Refer to installation manuals for additional details.

UL Certification

The IronRidge® Flush Mount®, Tilt Mount®, and Ground Mount Systems have been listed to UL 2703 by Intertek Group plc.

UL 2703 is the standard for evaluating solar mounting systems. It ensures these devices will maintain strong electrical and mechanical connections over an extended period of time in extreme outdoor environments.

Go to [IronRidge.com/UFO](https://www.ironridge.com/UFO)

Cross-System Compatibility			
Feature	Flush Mount	Tilt Mount	Ground Mount
XR Rails®	✓	✓	XR100 & XR1000
UFO®/Stopper	✓	✓	✓
BOSS® Splice	✓	✓	N/A
Grounding Lugs	1 per Row	1 per Row	1 per Array
Microinverters & Power Optimizers	Compatible with most MLPE manufacturers. Refer to system installation manual.		
Fire Rating	Class A	Class A	N/A
Modules	Tested or Evaluated with over 400 Framed Modules. Refer to installation manuals for a detailed list.		

Tech Brief



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326


DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION





SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-11




Installation

Compatibility: Fits modules with bottom flanges noted below. See IronRidge Flush, Tilt, Ground, or Ground Mount On The Roof Manual for full ratings and list of compatible modules.



Module Compatibility and Certifications



UL 2703
Conforms to STD UL 2703 (2015) requirements. See IronRidge Flush, Tilt, Ground, or Ground Mount On The Roof Manual for full ratings and list of compatible modules.

Allowable Design Load Rating
50 PSF downward, 50 PSF upward, 15 PSF lateral. Actual system structural capacity is defined by PE stamped [certification letters](#).



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE: 9.420 kW
AC SIZE: 13.300 kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-12



QuickMount® Halo UltraGrip

Cut Sheet

RD STRUCTURAL SCREW PN RD-1430-01-M1
SOLD SEPARATELY
SHOWN FOR REFERENCE

Release Liner
shown for reference

ITEM NO	DESCRIPTION	QTY IN KIT
1	QM Halo UltraGrip(Mill or Black)	1

PART NUMBER	DESCRIPTION
QM-HUG-01-M1	Halo UltraGrip - Mill
QM-HUG-01-B1	Halo UltraGrip - Black

Cut Sheet

1. Halo UltraGrip

Property	Value
Material	3000 Series Aluminium
Finish	Mill or Black



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326


DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"


SHEET NUMBER
PV-13



ITEM NO.	DESCRIPTION	QTY.
1	FLANGE HEAD CAP SCREW 5/16-18	20
2	CAGENUT, 5/16	20

Part Number	Description
BX-CMA-MI-M1	BX MLPE MOUNTING ASSEMBLY

1) Flange Head Cap Screw 5/16-18 2) Cagenut, 5/16-18



Property	Value
Material	300 Series Stainless Steel
Finish	Clear

v1.0



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE:9.420 kW
AC SIZE:13.300kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-14



SIZE B	DWG. NO.		REV
		JB-1.XL	
SCALE: 1:2	WEIGHT: 1.9 LBS	SHEET 1 OF 3	

TORQUE SPECIFICATION:	15-20 LBS
CERTIFICATION:	UL 1741, NEMA 3R CSA C22.2 NO. 290
WEIGHT:	1.9 LBS



REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A


YUBEI MEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

PV-15


ETL
Intertek
501570

SIZE	DWG. NO.	REV
B	JB-1.XL	
SCALE: 1:2	WEIGHT: 1.9 LBS	SHEET 2 OF 3


SIZE	DWG. NO.	REV
B	JB-1.XL	
SCALE: 1:2	WEIGHT: 1.9 LBS	SHEET 3 OF 3



OUTSIDE



INSIDE



LuminaSun Smart Home LLC
114 Morlake Drive suite 201,
Mooresville, NC 28117

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL	02/07/2025	
REVISION	04/09/2025	A

SIGNATURE WITH SEAL

PROJECT NAME & ADDRESS

YUBEIMEYE RAYMOND
33 LOCKWOOD DR,
CAMERON, NC 28326

DC SIZE: 9.420 kW
AC SIZE: 13.300 kW

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-16