









PHOTOVOLTAIC ROOF MOUNT SYSTEM			SR.#	PROJECT INFORMATION		<div><p>5112 Departure Drive, Raleigh NC 27616 O: 919.948.6474 E: info@8msolar.com</p></div>
<div>CODE AND STANDARDS</div> <p>THE INSTALLATION OF SOLAR ARRAYS AND PHOTOVOLTAIC POWER SYSTEMS SHALL COMPLY WITH THE FOLLOWING CODES:</p> <ul style="list-style-type: none">2020 NATIONAL ELECTRICAL CODE2018 NORTH CAROLINA RESIDENTIAL CODE2018 NORTH CAROLINA BUILDING CODEALL OTHER ORDINANCE ADOPTED BY THE LOCAL GOVERNING AGENCIES <div>SITE NOTES / OSHA REGULATION</div> <ol style="list-style-type: none">A LADDER SHALL BE IN PLACE FOR INSPECTION IN COMPLIANCE WITH OSHA REGULATIONS.THE SOLAR PV INSTALLATION SHALL NOT OBSTRUCT ANY PLUMBING, MECHANICAL, OR BUILDING ROOF VENTS.ROOFTOP MOUNTED PHOTOVOLTAIC PANELS AND MODULES SHALL BE TESTED, LISTED AND IDENTIFIED BY RECOGNIZED ELECTRICAL TESTING LABORATORY.MODULES AND SUPPORT STRUCTURES SHALL BE GROUNDEDSOLAR INVERTER SHALL BE LISTED TO UL1741ALL CONDUCTORS SHALL BE COPPER AND SHOULD BE 75 AND 90 DEG RATEDREMOVAL OF AN INTERACTIVE INVERTER OR OTHER EQUIPMENT SHALL NOT DISCONNECT THE BONDING CONNECTION BETWEEN THE GROUNDING ELECTRODE CONDUCTOR, THE PHOTOVOLTAIC SOURCE AND OUTPUT CIRCUIT GROUNDED CONDUCTORS.LIVE PARTS OF PV SOURCE CIRCUITS AND PV OUTPUT CIRCUITS OVER 150V TO GROUND SHALL NOT BE ACCESSIBLE TO OTHER THAN QUALIFIED PERSONS WHILE ENERGIZED.ALL PV MODULES AND ASSOCIATED EQUIPMENT AND WIRING SHALL BE PROTECTED FROM PHYSICAL DAMAGE. <div>SOLAR CONTRACTOR</div> <ol style="list-style-type: none">MODULE CERTIFICATIONS INCLUDE UL1703, IEC61646, IEC61370.IF APPLICABLE, MODULE GROUNDING LUGS MUST BE INSTALLED AT THE MARKED GROUNDING LUG HOLES PER THE MANUFACTURERS INSTALLATION REQUIREMENTS.AS INDICATED BY DESIGN, OTHER NRTL LISTED MODULE GROUNDING DEVICES MAY BE USED IN PLACE OF STANDARD GROUNDING LUGS AS SHOWN IN MANUFACTURER DOCUMENTATION AND APPROVED BY THE AHJ.ALL MICROINVERTERS, PHOTOVOLTAIC MODULES, AC COMBINERS, DC-AC CONVERTERS AND SOURCE CIRCUIT COMBINERS INTENDED FOR USE IN A PHOTOVOLTAIC POWER SYSTEM WILL BE IDENTIFIED AND LISTED FOR THE APPLICATION PER NEC690.4(B).ALL SIGNAGE TO BE INSTALLED IN ACCORDANCE WITH LOCAL BUILDING CODE.TERMINALS AND LUGS WILL BE TIGHTENED TO MANUFACTURER TORQUE SPECIFICATIONS (WHEN PROVIDED) IN ACCORDANCE WITH NEC CODE 110.14(D) ON ALL ELECTRICAL CONNECTIONS.MAX DC VOLTAGE CALCULATED USING MANUFACTURER PROVIDED TEMP COEFFICIENT FOR VOC UNLESS NOT AVAILABLE.			1	PV MODULES	28 x AXITEC AC-440TGB/108BB	
			2	INVERTER + BATTERY	01 X POWERWALL3	
			3	ROOF TYPE	ASPHALT SHINGLES	
			4	RACKING	PSR-B84 RAILS (BLACK)	
			5	MOUNTING TYPE	COMP MOUNT FLASHING (BLACK)	
			6	DC SIZE	12.32 KW	
			7	AC SIZE	11.5 KVA	
			SR.#	PROJECT INFORMATION		<div>Customer Information:</div> <div>Gary Neff</div> <div>91 Grading Stick Ct Angier, NC 27501</div> <div>Customer Signature:</div> <div></div> <div>Sheet Name:</div> <div>Drawing Index</div> <div>JOB NUMBER:</div> <div>25-106-GA</div> <div><div>Date:06/12/2025</div><div>Revision:A</div><div>Sheet Size:ANSI C 17" X 22"</div><div>Sheet Number:PV1</div></div> <div><p>NABCEP CERTIFIED PV Installation Professional Ali Buttar PVIP #031310-32</p></div>
			1	PV1	DRAWING INDEX	
			2	PV2	SITE LAYOUT	
			3	PV3	STRING MAPPING	
			4	PV4	ELECTRICAL ONE LINE DIAGRAM	
			5	PV5	DETAILED ELECTRICAL WIRING SCHEMATIC	
			6	PV6	PV LABELS	
			7	PV7	BILL OF MATERIALS	
			8	PV8	ATTACHMENT DETAILS	
						
<div>DESIGN CRITERIA WIND SPEED: 120 MPH GROUND SNOW LOAD: 15 PSF WIND EXPOSURE FACTOR: B</div>	<div>UTILITY COMPANY: DUKE ENERGY PERMIT ISSUER (AHJ): HARNETT COUNTY</div>	<div>SCOPE OF WORK INSTALLATION OF UTILITY INTERACTIVE PHOTOVOLTAIC SOLAR SYSTEM.</div>	VICINITY MAP		TOP VIEW OF THE BUILDING	

ROOF DESCRIPTION				MODULE DIMENSIONS	PV System Dead Load (Panel + Racking weight) / PV System Area (No. of panels x Weight of panel(lbs.) +Length of racking(ft.) x 1.15 lb.ft) / (No. of panels x Height x Width) = Total psf					<div><div>MSP</div><div>UTILITY METER</div><div>AC DISCONNECT</div></div> 
ROOF	PITCH	AZIMUTH	NO. OF MODULES		ROOF	A	B			
A	34°	284°	21		DEAD LOAD (PSF)	2.77	2.77			
B	40°	194°	07							
Vent		<ul style="list-style-type: none">Roof B have no ventsNo vent will be covered by PV modules during the installation.		SYSTEM DETAILS NUMBER OF PANELS : 28 PANELS MODEL : AXITEC AC-440TGB/108BB DC SIZE : 12.32 KW						



5112 Departure Drive,
Raleigh NC 27616
O: 919.948.6474
E: info@8msolar.com

Customer Information:

Gary Neff

91 Grading Stick Ct
Angier, NC 27501

Customer Signature:

Sheet Name:

Site Layout

JOB NUMBER:

25-106-GA

Date:

06/12/2025

Revision:



A

Sheet Size:


ANSI C
17" X 22"



Sheet Number:


PV2



SITE LAYOUT
SCALE: 1/8" - 1'



ROOF DESCRIPTION				MODULE DIMENSIONS	STRING LAYOUT																	
ROOF	PITCH	AZIMUTH	NO. OF MODULES		TESLA POWERWALL3																	
A	34°	284°	21		Strings #	No. of Modules	Color	Strings #	No. of Modules	Color												
B	40°	194°	07		String 1	12																
					String 2	09																
					String 3	07																
Tesla MCI (Mid Circuit Interrupter)				<div>SYSTEM DETAILS</div> <div>NUMBER OF PANELS : 28</div> <div>PANELS MODEL : AXITEC AC-440TGB/108BB</div>																		



5112 Departure Drive,
Raleigh NC 27616
O: 919.948.6474
E: info@8msolar.com

Customer Information:

Gary Neff

91 Grading Stick Ct
Angier, NC 27501

Customer Signature:

Sheet Name:

String Mapping

JOB NUMBER:

25-106-GA

Date:

06/12/2025

Revision:


A

Sheet Size:


ANSI C
17" X 22"

Sheet Number:

PV3



STRING MAPPING
SCALE: 1/8" - 1'



STRING CALCULATION

String #	No of Modules	Estimated Power	Imax	Impp	Voc	Vmpp
1	12	5,280 W	21.40 Adc	13.72 Adc	462.6 Vdc	550 Vdc
2	09	3,960 W	21.40 Adc	13.72 Adc	346.95 Vdc	550 Vdc
3	07	3,080 W	21.40 Adc	13.72 Adc	269.85 Vdc	550 Vdc

28 X AXITEC AC-440TGB/108BB
440W
TESLA MCI-2 HIGH CURRENT (Mid Circuit Interrupter)
RAPID SHUTDOWN EQUIPPED

NEC Code (2020) and UL Standard References

Rapid Shut Down	NEC 690.12 (A-D), UL1741	Grounding	NEC Article 250.30(A)
Disconnecting Means	NEC 690.13	Conduit Fill	NEC Table C.9, 310.15(B)(3)(a)
Feeder Sizing	NEC Table 310, 15(B)(16, 17)	Interconnection	NEC 705.12
Over current Protection	NEC 690.9		

Service Side Work: Power Drop Required

FROM UTILITY

Utility Meter

7

NEW METER BASE TO BE INSTALLED BY 8MSOLAR

60A BREAKER CONNECTION INSIDE THE BACKUP GATEWAY 3

Backup Gateway 3

60A/2P

200A/2P

8

NEW MAIN LOAD PANEL TO BE INSTALLED BY 8MSOLAR

MAIN LOAD PANEL

B.B RATING: 200A

M.B RATING: 200A

SUB LOAD PANEL

B.B. RATING: 225A

String 1

String 2

String 3

Sola Deck

Attic

Crawlspace

Tesla Powerwall3
1707000-00-J

(Battery Section)

System Shutdown Switch (E-Stop)

60A NON-FUSIBLE AC DISCONNECT

Note: Following existing breakers will be installed in the new main load panel.

Sr.No	Breaker Amperage	Quantities
1	90/2P	1
2	60/2P	1
3	50/2P	1
4	35/2P	3

• System Size: 12,320W DC

• Battery Total Energy: 13.5 KWh

• (28) Axitec AC-440TGB/108BB

• (10) 1879359-15-B: Tesla MCI-2 High Current

• (01) Tesla Powerwall3 (1707000-00-J)

• Inverter Output: 48A max @ 240 VAC (each)

• 11.5 kVA AC output max

• Grounding will be done via Pegasus grounding lugs and mid-clamps to ensure the rail and panels are continuously grounded.

• Rapid Shutdown is included in the Mid Circuit Interrupter , refer to Mid Circuit Interrupter and Inverter attached datasheets.

• The load center/disconnect will be visible, lockable, accessible to utility linesmen, and properly labeled per NEC requirements. It will be located on the exterior wall next to the utility meter.

• Prepare cable in usual manner.

• Stretch tape and apply half-lapped to form void-free joint. Degree of stretch is not critical and may vary in different sections of joint to accomplish void-free application.

• Protect the joint with two half-lapped layers of any scotch vinyl plastic electrical tape.

Sr.No	#Wire	Conduit Size	Ground Wire	Amperage
1	2 x #10 PV		#10 Bare Cu	21.40
2	6 x #10 THHN Cu	3/4" LFMC	#10 Green Cu	21.40
3	6 x #10 THHN Cu	3/4" EMT	#10 Green Cu	21.40
4	3 x #6 THHN Cu	1" EMT	#6 Green Cu	60
5	3 x #6 THHN Cu	1" LFMC	#6 Green Cu	60
6	3 x #6 THHN Cu	1" LFNC	#6 Green Cu	60
7	3 x #3/0 THHN Cu	2" PVC		200
8	3 x #3/0 THHN Cu	2" PVC	#6 Green Cu	200
9	4-conductor shielded (1 twisted pair) 16 AWG			
10	2-conductor shielded (1 twisted pair) 16 AWG	1/2" LFNC		

8MSOLAR

ADVANCING ENERGY INDEPENDENCE

5112 Departure Drive,
Raleigh NC 27616
O: 919.948.6474
E: info@8msolar.com

Customer Information:

Gary Neff

91 Grading Stick Ct
Angier, NC 27501

Customer Signature:

Sheet Name:
Electrical One Line Diagram

JOB NUMBER:
25-106-GA

Date:
06/12/2025

Revision:
A


Sheet Size:
ANSI C
17" X 22"

Sheet Number:
PV4


NABCEP
CERTIFIED

PV Installation
Professional

Ali Buttar
PVIP #031310-32



ROOF DESCRIPTION				MODULE DIMENSIONS	Rails and Splices : PSR-B84 (BLACK)	Roof Attachment : Pegasus Comp Mount
ROOF	PITCH	AZIMUTH	NO. OF MODULES			
A	34°	284°	21			There is one layer of shingles Roofing material is asphalt shingles
B	40°	194°	07		Rafter Spacing : 24 in	
					Attachment Span: 6ft	The roof is located in 120mph wind zone



5112 Departure Drive,
Raleigh NC 27616
O: 919.948.6474
E: info@8msolar.com

Customer Information:

Gary Neff

91 Grading Stick Ct
Angier, NC 27501

Customer Signature:

Sheet Name:

Bill of Material

JOB NUMBER:

25-106-GA

Date:

06/12/2025

Revision:

A

Sheet Size:


ANSI C
17" X 22"

Sheet Number:

PV7



PV LABELS		
Sr. No	Code	Qty
01	02-314	12
02	03-301	01
03	03-302	01
04	02-316	02
05	03-308	01
06	03-390	01
07	03-306	01
08	05-215	02
09	05-230	02
10	03-230	01
11	05-372	01
12	05-216	01
13	05-342	01
14	07-111	01
15	8M-001	03
16	8M-002	03
17	03-395	01
18	04-304	01
19	8M-004	03
20	03-511	01



Roof A
21 Modules

Roof B
07 Modules

RAILS AND MOUNTING SYSTEM

- 36 x PSR-B84: Pegasus Rail, Black, 84" (7 Feet)
- 26 x PSR-SPLS: Pegasus - Bonded, Structural Splice
- 46 x PSR-MCB: Pegasus - Multiclamp, Mid/End, 30 to 40 mm, Black
- 20 x PSR-HEC: Pegasus - Hidden End Clamp
- 09 x PSR-LUG: Pegasus - Grounding Lug
- 43 x PSR-WMC: Pegasus - Wire Management Clip
- 06 x PSR-CBG: Pegasus - Cable Grip
- 20 x PSR-CAP: Pegasus - End Cap
- 48 x PSCR-UBBDT: Pegasus Comp Mount - Open Slot, Black L Foot, Black Flashing, Dovetail 3/8" T-Bolt
- 56 x Heyco Wire Clips
- 05 x GEOC GC66100: SEALANT 2300 10.3OZ CLEAR (20) GEOCEL 230 TRIPOLY CLEAR
- 15 x MULTI 32.0017P0001-UR: PV MC4 MALE (10) [1000]
- 15 x MULTI 32.0016P0001-UR: PV MC4 FEMALE (10) [1000]

SOLAR MODULES

- 28 x Axitec AC-440TGB/108BB

INVERTER & SUPPORTING ITEMS

- 01 x 1707000-00-J :Tesla Powerwall3
- 10 x 1879359-15-B: Tesla MCI-2 High Current
- 01 x 1841000-01-C: Backup GateWay 3
- 01 x 1549184-00-X: 02" Conduit Hub Kit

WIRE

- 01 x WIRPV 2KVPV10STRBLK500: #10 PV WIRE BLK (Cu) 500ft

ELECTRICAL ITEMS


- 01 x BW2200: Gateway Main Breaker-Eaton BW2200
- 01 x BR260: Eaton BR 60/2
- 01 x DG222URB: 250volt/60amp/2pole non fusible disconnect (NEMA 3R)
- 01 x EATON UTRS213BE: Eaton 200A Meter Base
- 01 x CHP24B200R: Eaton CH main breaker 200A Load Center
- 01 x EATON M22PVK01: 22.5MM PB EMG STOP W/ CONTACTOR
- 01 x Eaton M22I1PG: SFC MTG ENC Emergency Stop Enclosure
- 01 x EZSLR JB-1.2: SolaDeck


ROOF FLASHINGS

- 06 x PSCA-OMB0: Roof Flashing Conduit Supports
- 06 x BPT 921S: 3/4" 1H EMT PIPE STRAP STEEL

6in setback from
sides of the roof

BILL OF MATERIAL
SCALE: 1/8" - 1'






L-FOOT

FLASHING

RAFTER

LAG WITH WASHER

ROOF DECKING









L-FOOT

SUPPORT BLOCK


COMP FLASHING


LAG WITH WASHER

					
Multi-Clamp	Hidden End Clamp	MLPE Mount	Dovetail T-Bolt	Ground Lug	Cable Grip
Torque Value 100 in-lbs.	Torque Value 135 in-lbs.	Torque Value 135 in-lbs.	Torque Value 300 in-lbs.	Torque Value 135 in-lbs.	Torque Value 135 in-lbs.

PV Dead Load

Roof A	<div>PV System Dead Load (Panel + Racking weight) / PV System Area (21 panels x 47.2 lbs./panel + 15 ft. of racking x 1.17 lb.ft) / (21 panels x 5.65' x 3.71') = 2.77 psf</div>
Roof B	<div>PV System Dead Load (Panel + Racking weight) / PV System Area (07 panels x 47.2 lbs./panel + 15 ft. of racking x 1.17 lb.ft) / (07 panels x 5.65' x 3.71') = 2.77 psf</div>





5112 Departure Drive,
Raleigh NC 27616
O: 919.948.6474
E: info@8msolar.com

Customer Information:

Gary Neff

91 Grading Stick Ct
Angier, NC 27501

Customer Signature:

Sheet Name:

Attachment Details

JOB NUMBER:

25-106-GA

Date:

06/12/2025

Revision:


A

Sheet Size:

ANSI C
17" X 22"

Sheet Number:

PV8



Ali Buttar
PVIP #031310-32