

MABRY'S ELECTRICAL SERVICE, INC.
731 MABRY RD
ANGIER, NC, 27501
+1 (919) 639-4837

Sizing Report

Rated Nominal Voltage 120 / 240 Single Phase
Generator Fuel Choice Liquid Propane
Sizing Method (NEC 220) Part IV

General Lighting & Receptacles		Load (kW)
Square Footage Being Covered (ft^2)	1300	3.9
Small Appliance Circuits (20 amps)		
Kitchen Circuits	2.0	3.0
Laundry Circuits	1.0	1.5

Fixed-In-Place Appliances & Motors	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)
Dishwasher		1.5	12.5		1.5
Dryer		5.5	22.92	X	5.5
Freezer		0.8	6.67		0.8
Microwave		1.25	10.42		1.25
Range - Oven w/ Top		8.5	35.42	X	8.5
Refrigerator		0.8	6.67		0.8
Water Heater		5.0	20.83	X	5.0

Air Conditioning & Cooling	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)
3.0 Ton Unit		3.0	12.5	X	3.0

Heating & Heat Pumps	Managed Loads	Estimated (kW)	Nameplate (amps)	240 V	Load (kW)
----------------------	---------------	----------------	------------------	-------	-----------

Transient Requirement	Estimated (LRA)	Actual (LRA)	Utilized (LRA)
Largest Motor's Starting Amps (LRA)	86.3	91.0	91.0

Summary NEC Load	Load (kW)	NEC Required
General Lighting & Receptacles	8.4	
Fixed-in-Place Appliances & Motors	23.35	
Sum of all General Loads	31.75	18.700
Cooling	3.0	3.0
Heating (w/demand factors)	0	0
Larger of Heating & Cooling	3.0	3.0

Sizing based on requirements of NEC Article 220: Part IV	21.700
Elevation	0
Minimum size generator for motor starting requirements	14
BTU load required	355000

22 kW Generac Model Generator Recommended