PHOTOVOLTAIC SYSTEM SPECIFICATIONS:

SYSTEM SIZE: 5.265W DC

3,770W AC

(13) JA SOLAR JAM54S31-405/MR MODULE TYPE & AMOUNT:

MODULE DIMENSIONS: (L/W/H) 67.8"/44.65"/1.18"

INVERTER: (13) ENPHASE IQ8PLUS-72-M-US [240V]

INTERCONNECTION METHOD: LINE SIDE TAP AHJ: **COUNTY OF HARNETT**


GOVERNING CODES

ALL WORK SHALL CONFORM TO THE FOLLOWING CODES

- 2020 NATIONAL ELECTRICAL CODE
- 2018 NC BUILDING CODE
- 2018 NC RESIDENTIAL CODE
- 2015 INTERNATIONAL RESIDENTIAL CODE
- 2018 NC PLUMBING CODE
- 2018 NC MECHANICAL CODE
- 2018 NC FIRE CODE
- COUNTY OF HARNETT CODE
- ANY OTHER LOCAL AMENDMENTS

GENERAL NOTES:

- 1. APPLICABLE CODE: 2018 NC BUILDING CODE & ASCE 7-16 MINIMUM DESIGN LOADS FOR BUILDING AND OTHER STRUCTURES.
- 2. LAG SCREW DIAMETER AND EMBEDMENT LENGTHS ARE DESIGNED PER 2018 NC BUILDING CODE REQUIREMENTS. ALL BOLT CAPACITIES ARE BASED ON A SOUTHER YELLOW PINE (SYP) RESIDENTIAL WOOD ROOF RAFTERS AS EMBEDMENT MATERIAL.
- 3. ROOF SEALANTS SHALL CONFORM TO ASTM C920 AND ASTM 6511, AND IS THE RESPONSIBILITY OF THE CONTRACTOR TO PILOT DRILL AND FILL ALL HOLES.
- 4. ALL DISSIMILAR MATERIALS SHALL BE SEPARATED WITH NEOPRENE WASHERS, PADS, ETC OR SIMILAR.
- 5. ALL ALUMINIUM COMPONENTS SHALL BE ANODIZED ALUMINIUM 6105-T5 UNLESS OTHERWISE NOTED.
- 6. ALL LAG SCREW SHALL BE ASTM A276 STAINLESS STEEL UNLESS OTHERWISE NOTED.
- 7. ALL SOLAR RAILING AND MODULES SHALL BE INSTALLED PER MANUFACTURER INSTRUCTIONS.
- 8. CONTRACTOR SHALL ENSURE ALL ROOF PENETRATIONS TO BE INSTALLED AND SEALED PER 2018 NC BUILDING CODE OR LOCAL GOVERNING CODE.







A-00: **COVER SHEET** A-01: SITE PLAN

S-01: MOUNTING DETAILS

S-02: MOUNTING PLAN 3-LINE DIAGRAM E-01: E-02: **ELECTRICAL NOTES**

E-03: WARNING LABELS



DC, ,265W MODULES-ROOF MOUNTED

S

EPC SOLAR 379 DOUGLAS RD E OLDSMAR, FL 34677 PHONE: 727-267-4033

DESCRIPTION DATE REV

PROJECT NAME:

MIKE WOOD

PROJECT ADDRESS: 325 COLESHILL RD, ANGIER, NC 27501 SHEET NAME:


COVER SHEET

SHEET SIZE:

SHEET NUMBER: A-00

ANSI B 11"x17"

GENERAL INSTALLATION PLAN NOTES: 1. ROOF ATTACHMENTS SHALL BE INSTALLED AS SHOWN IN SHEET S-01 AND AS FOLLOWS FOR EACH WIND ZONE. WIND ZONE 1: 6'-0" O.C. WIND ZONE 2: 6'-0" O.C. WIND ZONE 3: 6'-0" O.C. THE PERIMETER WIDTH OF WIND UPLIFT ZONES IS 3 FT SYSTEM LEGEND **EXISTING UTILITY METER** MP **EXISTING MAIN SERVICE PANEL** С NEW DEDICATED PV SYSTEM COMBINER PANEL. NEW JUNCTION BOX. EXACT LOCATION TBD ON SITE EXISTING PHOTOVOLTAIC UTILITY DISCONNECT SWITCH. LOCATED WITHIN 10' OF METER. NEW PHOTOVOLTAIC UTILITY DISCONNECT SWITCH. LOCATED WITHIN 10' OF METER. RA **ROOF ACCESS POINT** SE EXISTING SOLAREDGE 5000H-US INVERTER 13 EXISTING Q CELLS 405W PV MODULES 13 NEW JA SOLAR JAM54S31-405/MR MODULES WITH ENPHASE IQ8PLUS-72-M-US [240V] INVERTERS, MOUNTED ON THE BACK OF EACH **MODULE** ROOF OBSTRUCTIONS 36" FIRE PATHWAY = 18" FIRE PATHWAY **ROOF SECTIONS** MODULE: 8 SLOPE: 36° R00F AZIMUTH: 315° #01 MATERIAL: COMPOSITION SHINGLES RAFTER SIZE: 2"X4" @ 24 0.C. MODULE: 3 SLOPE: 36° R00F AZIMUTH: 225° #02 MATERIAL: COMPOSITION SHINGLES RAFTER SIZE: 2"X4" @ 24 0.C. MODULE: 2 NEW, 13 EXISTING SLOPE: 36° R00F AZIMUTH: #03 MATERIAL: COMPOSITION SHINGLES RAFTER SIZE: 2"X4" @ 24 O.C.






ROOF ACCESS POINTS SHALL BE DEFINED AS AREAS WHERE FIRE DEPARTMENT LADDERS ARE NOT PLACED OVER OPENINGS (WINDOWS OR DOORS), ARE LOCATED AT STRONG POINTS OF BUILDING CONSTRUCTION, AND ARE IN LOCATIONS WHERE THEY WILL NOT CONFLICT WITH OVERHEAD OBSTRUCTIONS (TREE LIMBS, WIRES, OR SIGNS). (NFPA 1 11.12.2.2.1.3)

- PHOTOVOLTAIC MODULES SHALL BE LOCATED IN A MANNER THAT PROVIDES TWO 3 FT WIDE ACCESS PATHWAYS FROM THE EAVE TO THE RIDGE ON EACH ROOF SLOPE WHERE THE MODULES ARE LOCATED. (NFPA 1 11.10.2.2.2.1.2)
- FIRST RESPONDER ACCESS WILL BE A MINIMUM OF 36" UNOBSTRUCTED
- · CABLES, WHEN RUN BETWEEN ARRAYS, SHALL BE ENCLOSED IN CONDUIT.

TOTAL PLAN AREA OF ROOF: 2,176.90 FT² TOTAL AREA OF MODULES: 546,50 FT² MODULE COVERAGE: 25.10%






EPC SOLAR 379 DOUGLAS RD E OLDSMAR, FL 34677 PHONE: 727-267-4033


REVISIONS DESCRIPTION DATE REV						
REVI	REVISIONS					
DESCRIPTION	DATE	REV				


PROJECT NAME MIKE WOOD 325 COLESHILL RD, ANGIER, NC 27501 SHEET NAME: SITE PLAN SHEET NUMBER: SHEET SIZE: A-01 ANSI B 11"x17"





IRONRIDGE XR-10 RAIL







MOUNTING PLAN NOTES:

- 1. DESIGNED AS PER ASCE7-16. 2018 NCBC
- 2. MEAN ROOF HEIGHT IS 15 FEET
- 3. EXPOSURE CATEGORY: C
- 4. DESIGN WIND SPEED: 120 MPH
- 5. DESIGN SNOW LOAD: 30 PSF
- 6. EXISTING ROOF HAS ONE LAYER
- 7. ANCHORAGE OF SOLAR PANELS WILL BE TO
- **EXISTING ROOF SUPPORTING MEMBERS**
- 8. INSTALLATION IS IN COMPLIANCE WITH 15.14.2.5.2, RAS111, & RAS120.10
- 9. PENETRATIONS WILL BE FLASHED AND SEALED WITH ULTRAGRIP FLASHING SYSTEM.

QUICKMOUNT HALO ULTRAGRIP



EPC SOLAR 379 DOUGLAS RD E OLDSMAR, FL 34677 PHONE: 727-267-4033

REVISIONS						
DESCRIPTION	DATE	REV				

REVISIONS				
DESCRIPTION	DATE	REV		
			PR	
			1111	

PROJECT NAME:	MIKE WOOD
PROJECT ADDRESS:	325 COLESHILL RD, ANGIER, NC 27501

SHEET NAME: MOUNTING DETAILS SHEET NUMBER: SHEET SIZE: S-01 ANSI B 11"x17"

SYSTEM LEGEND

13 NEW JA SOLAR JAM54S31-405/MR MODULES
WITH ENPHASE IQ8PLUS-72-M-US [240V]
INVERTERS, MOUNTED ON THE BACK OF EACH
MODULE

____ =

= ROOF OBSTRUCTIONS

• =

ATTACHMENT POINTS

RΛII

GENERAL INSTALLATION PLAN NOTES:


1. ROOF ATTACHMENTS SHALL BE INSTALLED AS SHOWN IN SHEET S-01 AND AS FOLLOWS FOR EACH WIND ZONE.


WIND ZONE 1: 6'-0" O.C. WIND ZONE 2: 6'-0" O.C. WIND ZONE 3: 6'-0" O.C.

MAXIMUM CANTILEVER SPAN = $\frac{1}{3}$ *MOUNT SPANS 2. THE PERIMETER WIDTH OF WIND UPLIFT ZONES IS 3 FT

- 3. THE VERTICAL DISTANCE BETWEEN ROOF SURFACE AND PV MODULES IS 6 INCHES PER ASCE7-16 SECT 29.4.4.
- 4. SOLAR RAIL TO BE INSTALLED TO SOLAR PANEL MANUFACTURER'S SPECIFICATION.
- 5. INSTALLATION IS IN COMPLIANCE WITH THE FOLLOWING: NCBC RESIDENTIAL 903.2, NCBC RESIDENTIAL TABLE R301.2(7), 15.14.2.5.2, 301.2 & RAS111.
- 6. MEETS THE REQUIREMENTS OF SECTION 1512 THROUGH 1525 & NCBC 1510.7.1
- 7. PLANS SATISFY ZONES PER NCBC 1510.7.1

TYPICAL ATTACHMENT SPACING ESTIMATED MOUNT QUANTITY: 30





		MODULE, ARRAY WEI	GHT (LO	DAD CAL	CS)	
		NUMBER OF MODULES		13		
		MODULE WEIGHT	43	LBS		
		TOTAL MODULE WEIGHT		559	LBS	
		TOTAL MICROINVERTER WEIGH	T	52	LBS	
		NUMBER OF ATTACHMENT POIN	NTS	30		
		TOTAL RAIL LENGTH		48.36	FT	
		MOUNTING SYSTEM WEIGHT		48.36	LBS	
		TOTAL SYSTEM WEIGHT		659.36	LBS	
		WEIGHT AT EACH ATTACHMENT (ARRAY WEIGHT/NUMBER OF ATTACHMENT PO	F POINT	21.98	LBS	
		MODULE AREA		21.02	SQFT	
		TOTAL ARRAY AREA		273.23	SQFT	
		DISTRIBUTED LOAD (TOTAL SYSTEM WEIGHT/TOTAL ARRAY AREA)		2.41	PER SQFT	
		PULLOUT VALUE PER MOUNT	1004	LBS		
		DESIGN C	RITERI <i>A</i>	١		
		GROUND SNOW LOAD (PSF)	30			
		WIND SPEED (MPH)	120			
		EXPOSURE CATEGORY	С			
		MEAN ROOF HEIGHT (FT.)	15			
		DESIGN CALCULATIONS				
ASCE	29.4-7	PRESSURE COEFFICIENT GC _p	$p = q_{h^*} K_d$	$*GC_p*Y_E*Y_a$	(PSF)	
	ZONE 1:	-1.21		-23.5		
	ZONE 2:	-1.68		-33.8		
	ZONE 3:	-1.70		-33.8		
	=	POINT LOAD CA				
ASCE	29.4-7	11 d P E u ' '	PL = p *	A _e (LBS)		
	ZONE 1:	-23.5	-178.6			
	ZONE 2:	-33.8		-240.8		
	ZONE 3:	-33.8		-240.8		
		WIND LOAD PARAMETERS				
IND SPI	V = 135.5 MPH + 1.00 FBC 1.00 FBC					

ZONE 3:	-33.8	-240.8
WIND L	OAD PARAMETERS	
WIND SPEED	V = 135.5 MPH	FRC R301.2.1.3
EFFECTIVE WIND AREA	$A_e = 21.67 \text{ft}^2$	26.2
WIND DIRECTIONALITY	$K_d = 0.85$	TABLE 26.6-1
GROUND ELEVATION FACTOR	$K_e = 1.0$	TABLE 26.9-1
TOPOGRAPHIC FACTOR	$K_{zt} = 1.0$	26.8, 26.8.2
VELOCITY EXPOSURE COEFFICIENT	$K_{z} = 0.85$	TABLE 26.10-1
ARRAY EDGE FACTOR	$Y_E = 1.5$	29.4.4
SOLAR PANEL EQUALIZATION FACTOR	$Y_{a} = 0.67$	FIGURE 29.4-8
VELOCITY PRESSURE	$q_h = 39.98 PSF$	$q_h = 0.00256 * K_z * K_{zt} * K_{e} * V^2$

ALL MODULES ARE ASSUMED TO BE EXPOSED

REFER TO SHEET S-01 FOR ROOF, MOUNT, & RAIL DETAILS



EPC SOLAR 379 DOUGLAS RD E OLDSMAR, FL 34677 PHONE: 727-267-4033

REVISIONS						
DESCRIPTION DATE REV						

REV	PROJECT NAME: MIKE WOOD	SH
	325 COLESHILL RD, ANGIER, NC 27501	SH

SHEET NAME:	
MOL	JNTING PLAN
S-02	SHEET SIZE: ANSI B 11"x17"

WIRE TAG #	WIRE FROM	CONDUIT (TBD ON SITE)	WIRE QTY	WIRE GAUGE	WIRE RATING	GRND SIZE	GRND WIRE TYPE
1	ARRAY TO JUNCTION BOX	TRUNK CABLE	2	#12	TRUNK CABLE	#6 OR #8	SBC
2	JUNCTION BOX TO COMBINER PANEL	MIN 3/4" CONDUIT	2	#10	THHN	#8	THWN-2
3	COMBINER PANEL TO ACD	MIN 3/4" CONDUIT	3	#10	THHN	#8	THWN-2
4	ACD TO MAIN SERVICE PANEL	MIN 3/4" CONDUIT	3	#6	THHN	N/A	N/A
5	SERVICE WIRES	MIN 1.5" CONDUIT	3	#2/0	THHN	N/A	N/A
E	EXISTING WIRES	-	-	-	-	-	-

SYSTEM DATA	
# STRINGS:	1
LARGEST STRING:	13
TOTAL MODULES:	13
TOTAL INVERTERS:	13
SYSTEM RATINGS:	5,265W DC ST
	3,770W AC ST

TOTAL AC OUPUT:

MICROINVERTER CALCULATIONS	INVERTER QTY	R	NOC		NECS	STRING AMPS	OCP	WIRE GAUGE
MAXIMUM STRING OUTPUT	13	Χ	1.21A	Х	1.25	= 19.66A	20A	#10
TOTAL OUTPUT	13	х	1.21A	Х	1.25	= 19.66A	20A	#10


ENPHASE Q CABLE TO BE ATTACHED TO RAIL MIN. 3-1/2" ABOVE ROOF SURFACE

GROUNDING CONDUCTOR TO BE PROTECTED #8 AWG OR TO BE UNPROTECTED #6 AWG 250.64(B) 250.66 & 250.120(C)

LINE SIDE TAP IS IN COMPLIANCE WITH NEC 705.11(D)

15.73A

POINT OF INTERCONNECT, LINE SIDE TAP EXISTING 240V/200A BUS BAR RATING, MAIN SERVICE PANEL, SINGLE PHASE, WITH A 200A MAIN BREAKER





EPC SOLAR 379 DOUGLAS RD E OLDSMAR, FL 34677 PHONE: 727-267-4033

REVISIONS							
DESCRIPTION	DATE	REV					

PROJECT NAME:

MIKE WOOD 325 COLESHILL RD, ANGIER, NC 27501

3-LINE DIAGRAM SHEET NUMBER: E-01 ANSI B 11"x17"

ELECTRICAL NOTES:

- ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL, AND LABELED FOR ITS APPLICATION.
- ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600 V AND 90 DEGREE C WET ENVIRONMENT.
- WIRING, CONDUIT, AND RACEWAYS MOUNTED ON ROOFTOPS SHALL BE ROUTED DIRECTLY TO, AND LOCATED AS CLOSE AS POSSIBLE TO THE NEARES RIDGE, HIP. OR VALLEY.
- WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- WHERE SIZES OF JUNCTION BOXES, RACEWAYS, AND CONDUITS ARE NOT SPECIFIED. THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
- ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
- MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR ILSCO GBL-4DBT LAY-IN LUG.
- 10. UTILITY HAS 24-HR UNRESTRICTED ACCESS TO ALL PHOTOVOLTAIC SYSTEM COMPONENTS LOCATED AT THE SERVICE ENTRANCE.
- 11. WORKING CLEARANCES AROUND THE EXISTING AND NEW ELECTRICAL EQUIPMENT WILL BE MAINTAINED IN ACCORDANCE WITH NEC ARTICLE 110.26.
- 12. ALL EQUIPMENT INSTALLED SHALL BE LISTED BY A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL) PER NEC ARTICLE 110.3.
- 13. RACKING CONFORMS TO AND IS LISTED UNDER UL 2703.
- 14. ALL LABELS OR MARKINGS SHALL BE VISIBLE AFTER INSTALLATION. THE LABELS SHALL BE REFLECTIVE, AND ALL LETTERS SHALL BE CAPITALIZED AND SHALL BE A MINIMUM HEIGHT OF 9.5 MM (3/8 IN) IN WHITE ON A RED BACKGROUND.
- 15. CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC ARTICLE 310.10.
- 16. CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE I WET LOCATIONS PER NEC ARTICLE 310.10.
- 17. ALL EXTERIOR EQUIPMENT IS A MINIMUM OF NEMA-R3 RATED.
- 18. ALL ELECTRICAL EQUIPMENT WILL BE LOCATED AT OR ABOVE BFE+1' OR 8.00' NAVD.
- 19. SMOKE ALARMS PER F.S. 553.883.
- 20. GROUNDING WILL BE IN COMPLIANCE WITH NEC 2020.
- 21. SYSTEM MEETS THE GROUNDING REQUIREMENTS OF NEC 2020
- GROUND RODS WILL BE AT LEAST 8' LONG AND 5/18" IN DIAMETER (NEC 250.52(A)(5).
- 23. SYSTEM MEETS THE REQUIREMENTS OF NEC 2020.
- 24. SUPPLEMENTAL ELECTRODES WILL BE ADDED IF REQUIRED.

SYSTEM NOTES:

- ENPHASE IQ8 / 8PLUS / 8M / 8A MICROINVERTERS DO NOT REQUIRE GROUNDING ELECTRODE CONDUCTORS OR EQUIPMENT GROUNDING CONDUCTORS. THE MICROINVERTERS ITSELF HAS CLASS II DOUBLE-INSULATED RATING, WHICH INCLUDES GROUND FAULT PROTECTION.
- ENPHASE Q CABLE HAS NO NEUTRAL WIRE (2 WIRE DOUBLE INSULATED CABLING)
- 3. MODULES ARE BONDED TO RAIL USING INTEGRATED GROUNDING.
- RAILS ARE BONDED WITH UL 2703 RATED LAY-IN LUGS
- 5. SYSTEM IS UNGROUNDED
- BARE COPPER IS TRANSITIONED TO THHN/THWN-2 VIA IRREVERSIBLE CRIMP; GEC TO BE CONTINUOUS PER CEC 250.64(C)
- SUB-BRANCHES ARE CENTER-FED AT JBOX TO MAKE ONE TOTAL BRANCH CIRCUIT.
- ENPHASE IQ ENVOY INSIDE IQ COMBINER REQUIRES A NEUTRAL TO BE LANDED AT THE NEUTRAL BUS AT MAIN PANEL PER ENPHASE INSTALLATION INSTRUCTIONS.
- ENPHASE MICROINVERTERS ARE ALL RAPID SHUTDOWN READY PER NEC 690.12

INVERTER OUTPUT CIRCUIT								
TO OVERCURRENT PROTECTION DEVICE								
DESIGN TEMPERATURE (°F)	94							
MAXIMUM AMBIENT TEMPERATURE RANGE (°F)	87-95	310.15(B)						
TEMPERATURE RATING OF CONDUCTOR	75°C							
# OF CARRYING CONDUCTORS	<4	310.15(C)(1)						
AC MAX OUTPUT CURRENT	15.73 A	690.8(A)(3)						
AC MAX OUTPUT CURRENT * 1.25%	19.66A	690.8(B)						
OVERCURRENT PROTECTION (A)	20A							
AMBIENT TEMPERATURE CORRECTION FACTOR	0.94	310.15(B)						
CONDUCTOR ADJUSTMENT FACTOR	100%	310.15(B)						
CONDUCTOR GAUGE (AWG)	10	310.16						
CONDUCTOR ALLOWABLE AMPACITY (AMPS)	35							
CONDUCTOR ADJUSTED AMPACITY (AMPS)	32.9	35*.94*1=32.9						

INVERTER SPECIFICATIONS						
MANUFACTURER	ENPHASE IQ8PLUS-	72-M-US [240V]				
MAX DC VOLT RATING	60 VOLTS					
MAX CONT POWER	290 WATTS					
NOMINAL AC VOLTAGE	240 VOLTS					
MAX AC CURRENT	1.21 AMPS					
MAX OCPD RATING	20 AMPS					
MAX PANELS/CIRCUIT	13					
SHORT CIRCUIT CURRENT	15 AMPS					
PHOTOVOLTAIC OUTPUT						
AC OUTPUT CURRENT 15.73						
NOMINAL AC VOLTAGE 24						

EPC SULAR
379 DUUGLAS RD E
ULDSMAR, FL 34677
PHUNE: 727-267-4033

REVISIONS

DESCRIPTION
DATE
REV

REV PROJECT NAME

PROJECT ADDRI

MIKE WOOD

325 COLESHILL RD, ANGIER, NC 27501

SHEET NAME:

ELECTRICAL NOTES

SHEET NUMBER: SH

ANSI B 11"x17"

WARNING

ELECTRICAL SHOCK HAZARD

DO NOT TOUCH TERMINALS. TERMINALS ON LINE AND LOAD MAY BE ENERGIZED IN THE OPEN POSITION

LABEL LOCATION:

INVERTER(S), AC DISCONNECT(S), AC COMBINER PANEL (IF APPLICABLE).

WARNING

PHOTOVOLTAIC SYSTEM **COMBINER PANEL**

DO NOT ADD LOADS

LABEL LOCATION: PHOTOVOLTAIC AC COMBINER (IF APPLICABLE).

EMERGENCY RESPONDER THIS SOLAR PV SYSTEM IS **EQUIPPED WITH RAPID SHUTDOWN**

TURN RAPID SHUTDOWN SWITCH TO THE "OFF" POSITION TO SHUTDOWN ENTIRE PV SYSTEM



NOTES AND SPECIFICATIONS:

- SIGNS AND LABELS SHALL MEET THE REQUIREMENTS OF THE NEC 2020. UNLESS SPECIFIC INSTRUCTIONS ARE REQUIRED, OR IF REQUESTED BY THE LOCAL AHJ.
- SIGNS AND LABELS SHALL ADEQUATELY WARN OF HAZARDS USING EFFECTIVE WORDS, COLORS AND SYMBOLS.
- LABELS SHALL BE PERMANENTLY AFFIXED TO THE EQUIPMENT OR WIRING METHOD AND SHALL NOT BE HAND WRITTEN.
- LABEL SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED.
- SIGNS AND LABELS SHALL COMPLY WITH ANSI Z535.4-2011, PRODUCT SAFETY SIGNS AND LABELS, UNLESS OTHERWISE SPECIFIED.
- DO NOT COVER EXISTING MANUFACTURER LABELS.

WARNING

DUAL POWER SUPPLY

SOURCES: UTILITY GRID AND PV SOLAR ELECTRIC SYSTEM

LABEL LOCATION:

UTILITY SERVICE METER AND MAIN SERVICE PANEL



INVERTER OUTPUT CONNECTION

DO NOT RELOCATE THIS OVERCURRENT DEVICE

LABEL LOCATION:

ADJACENT TO PV BREAKER (IF APPLICABLE).

WARNING: PHOTOVOLTAIC **POWER SOURCE**

LABEL LOCATION:

INTERIOR AND EXTERIOR DC CONDUIT EVERY 10 FT, AT EACH TURN. ABOVE AND BELOW PENETRATIONS. ON EVERY JB/PULL BOX CONTAINING DC CIRCUITS.

LABEL LOCATION: AC DISCONNECT

ON-SITE GENERATION

UTILITY DISCONNECT

SWITCH

WARNING

IN CASE OF EMERGENCY, CONTACT: **EPC SOLAR** PH. NO. 727-267-4033

LABEL LOCATION: MAIN DISCONNECT


> **RAPID SHUTDOWN SWITCH FOR SOLAR PV SYSTEM**

LABEL LOCATION: RSD SWITCH

CAUTION **MULTIPLE SOURCES OF POWER**

POWER TO THIS BUILDING IS ALSO SUPPLIED FROM THE FOLLOWING SOURCES WITH **DISCONNECT LOCATED AS SHOWN**





PHOTOVOLTAIC AC DISCONNECT MAXIMUM AC OPERATING CURRENT: 15.73 AMPS NOMINAL OPERATING AC VOLTAGE: 240 VAC

LABEL LOCATION:

AC DISCONNECT(S), PHOTOVOLTAIC SYSTEM POINT OF INTERCONNECTION

EPC SOLAR 379 DOUGLAS RD E DLDSMAR, FL 34677 PHDNE: 727-267-4033

REVISIONS DESCRIPTION DATE REV

PROJECT NAME

MIKE WOOD

325 COLESHILL RD, ANGIER, NC 27501

SHEET NAME:

WARNING LABELS

SHEET NUMBER: E-03

SHEET SIZE: ANSI B 11"x17" July 3, 2025

Harnett County Central Permit

420 McKinney Pkwy

Lillington, NC 27546

RE: Solar PV System

Mike Wood

325 Coleshill Rd

Angier, NC 27501

Dear Plans Reviewer,

Consider this as a statement by Rafael Gonzalez Soto, P.E, regarding the project referenced above.

The proposed solar installation for this project will add approximately 3 PSF of additional deadload. This includes the solar modules & microinverters, racking, and all other accessories. Based on my evaluation of the building, the existing roof structure can support the additional load of the proposed PV system. The proposed solar system is designed and complies with the 2018 North Carolina Building Code structural requirements. The contractor is responsible for installing the solar system according to the manufacturer's recommendations and instructions.

Please feel free to contact me at 786-393-4740 if you have any questions or require any further information.

Regards,

Rafael Gonzalez Soto, P.E 237 S Dixie Hwy, 4th Floor, Suite 13, Coral Gables, FL 33133 786-393-4740










Less shading and lower resistive loss



Better mechanical loading tolerance

Superior Warranty





■ New linear power warranty
■ Standard module linear power warranty

Comprehensive Certificates

- IEC 61215, IEC 61730,UL 61215, UL 61730
- ISO 9001: 2015 Quality management systems
- ISO 14001: 2015 Environmental management systems
- ISO 45001: 2018 Occupational health and safety management systems
- IEC 62941: 2019 Terrestrial photovoltaic (PV) modules Quality system for PV module manufacturing














SPECIFICATIONS

Packaging Configuration

MECHANICAL DIAGRAMS



Cell Mono Weight 19.5kg Dimensions 1722±2mm×1134±2mm×30±1mm Cable Cross Section Size 4mm² (IEC) , 12 AWG(UL) No. of cells 108(6x18) Junction Box IP68, 3 diodes QC 4.10-35/ MC4-EVO2A Connector Portrait: 200mm(+)/300mm(-); 800mm(+)/800mm(-)(Leapfrog) Landscape: 1100mm(+)/1100mm(-) Cable Length (Including Connector) Front Glass

36pcs/Pallet

936pcs/40HQ Container

Remark: customized frame color and cable length available upon request

ELECTRICAL PARAMETERS AT STC							
TYPE	JAM54S31 -380/MR	JAM54S31 -385/MR	JAM54S31 -390/MR	JAM54S31 -395/MR	JAM54S31 -400/MR	JAM54S31 -405/MR	
Rated Maximum Power(Pmax) [W]	380	385	390	395	400	405	
Open Circuit Voltage(Voc) [V]	36.58	36.71	36.85	36.98	37.07	37.23	
Maximum Power Voltage(Vmp) [V]	30.28	30.46	30.64	30.84	31.01	31.21	
Short Circuit Current(Isc) [A]	13.44	13.52	13.61	13.70	13.79	13.87	
Maximum Power Current(Imp) [A]	12.55	12.64	12.73	12.81	12.90	12.98	
Module Efficiency [%]	19.5	19.7	20.0	20.2	20.5	20.7	
Power Tolerance			0~+5W				
Temperature Coefficient of $Isc(\alpha_Isc)$			+0.045%°C				
Temperature Coefficient of $Voc(\beta_Voc)$			-0.275%/°C				
Temperature Coefficient of $Pmax(\gamma_Pmp)$			-0.350%/°C				

Remark: Electrical data in this catalog do not refer to a single module and they are not part of the offer. They only serve for comparison among different module types.


ELECTRICAL PARAM	METERS		OPERATING CONDI	TIONS				
TYPE	JAM54S31 -380/MR	JAM54S31 -385/MR	JAM54S31 -390/MR	JAM54S31 -395/MR	JAM54S31 -400/MR	JAM54S31 -405/MR	Maximum System Voltage	1000V/1500V DC
Rated Max Power(Pmax) [W]	286	290	294	298	302	306	Operating Temperature	-40°C~+85°C
Open Circuit Voltage(Voc) [V]	34.36	34.49	34.62	34.75	34.88	35.12	Maximum Series Fuse Rating	25A
Max Power Voltage(Vmp) [V]	28.51	28.68	28.87	29.08	29.26	29.47	Maximum Static Load,Front* Maximum Static Load,Back*	5400Pa(112lb/ft²) 2400Pa(50lb/ft²)
Short Circuit Current(Isc) [A]	10.75	10.82	10.89	10.96	11.03	11.10	NOCT	45±2°C
Max Power Current(Imp) [A]	10.03	10.11	10.18	10.25	10.32	10.38	Safety Class	Class Ⅱ
NOCT	Irradian	ce 800W/m²,	ambient tem	perature 20°C	wind speed	1m/s, AM1.5G	Fire Performance	UL Type 1


Irradiance 1000W/m², cell temperature 25°C, AM1.5G


CHARACTERISTICS

STC

Current-Voltage Curve JAM54S31-405/MR













IQ8 and IQ8+ Microinverters

Our newest IQ8 Microinverters are the industry's first microgrid-forming, software-defined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently. The brain of the semiconductor-based microinverter is our proprietary application-specific integrated circuit (ASIC) which enables the microinverter to operate in grid-tied or off-grid modes. This chip is built in advanced 55nm technology with high speed digital logic and has super-fast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the Enphase IQ Battery, Enphase IQ Gateway, and the Enphase App monitoring and analysis software.



Connect PV modules quickly and easily to the IQ8 Series Microinverters that has Integrated MC4 connectors.



IQ8 Series Microinverters redefine reliability standards with more than one million cumulative hours of power-on testing, enabling an industry-leading limited warranty of up to 25 years.



IQ8 Series Microinverters are UL Listed as PV Rapid Shut Down Equipment and conform with various regulations, when installed according to manufacturer's instructions.

Easy to install

- Lightweight and compact with plug-n-play connectors
- Power Line Communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produce power even when the grid is down*
- More than one million cumulative hours of testing
- Class II double-insulated enclosure
- Optimized for the latest highpowered PV modules

Microgrid-forming

- Complies with the latest advanced grid support**
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide range of grid profiles
- Meets CA Rule 21 (UL 1741-SB) requirements

- * Only when installed with IQ System Controller 2, meets UL 1741.
- ** IQ8 and IQ8Plus support split phase, 240V installations only.

^{© 2022} Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ8 Microinverters, and other names are trademarks of Enphase Energy, Inc. Data subject to change.

IQ8 and IQ8+ Microinverters

INPUT DATA (DC)		IQ8-60-M-US	IO8PLUS-72-M-US
Commonly used module pairings ¹	W	235 – 350	235 - 440
Module compatibility		60-cell / 120 half-cell	60-cell / 120 half-cell, 66-cell / 132 half-cell and 72-cell / 14 half-cell
MPPT voltage range	V	27 – 37	29 - 45
Operating range	V	25 – 48	25 - 58
Min / Max start voltage	V	30 / 48	30 / 58
Max input DC voltage	V	50	60
Max DC current ² [module I _{sc}]	Α	1!	5
Overvoltage class DC port		I	II
DC port backfeed current	mA		0
PV array configuration		1x1Ungrounded array; No additional DC side protection requ	uired; AC side protection requires max 20A per branch circuit
DUTPUT DATA (AC)		108-60-M-US	IQ8PLUS-72-M-US
Peak output power	VA	245	300
Max continuous output power	VA	240	290
Nominal (L-L) voltage / range ³	٧	240 / 2	:11 – 264
Max continuous output current	Α	1.0	1.21
Nominal frequency	Hz	6	60
Extended frequency range	Hz	50 -	- 68
AC short circuit fault current over 3 cycles	Arms	2	2
Max units per 20 A (L-L) branch circuit ⁴		16	13
Total harmonic distortion		<5	5%
Overvoltage class AC port		II	II
AC port backfeed current	mA	3	50
Power factor setting		1.	0
Grid-tied power factor (adjustable)		0.85 leading -	- 0.85 lagging
Peak efficiency	%	97.5	97.6
CEC weighted efficiency	%	97	97
Night-time power consumption	mW	6	60
MECHANICAL DATA			
Ambient temperature range		-40°C to +60°C ((-40°F to +140°F)
Relative humidity range		4% to 100% ((condensing)
DC Connector type		Stäub	li MC4
Dimensions (H x W x D)		212 mm (8.3") x 175 mm	n (6.9") x 30.2 mm (1.2")
Weight		1.1 kg (2	2.43 lbs)
Cooling		Natural conve	ction – no fans
Approved for wet locations		Ye	es
Pollution degree		PI	D3
Enclosure		Class II double-insulated, corrosi	ion resistant polymeric enclosure
Environ. category / UV exposure rating		NEMA Type	6 / outdoor
COMPLIANCE		CA Rule 21 (UL 1741-SB), UL 62109-1, UL1741 / IEEE1547, FCC Part	t 15 Class B ICES-0003 Class B CAN / CSA-C22 2 NO 1071-0
Certifications		This product is UL Listed as PV Rapid Shut Down Equipment and 690.12 and C22.1-2018 Rule 64-218 Rapid Shutdown of PV Syste	conforms with NEC 2014, NEC 2017, and NEC 2020 section





X-IQ-AM1-240-5 X-IQ-AM1-240-5C

IQ Combiner 5/5C

The IQ Combiner 5/5C consolidates interconnection equipment into a single enclosure and streamlines IQ Series Microinverters and IQ Gateway installation by providing a consistent, pre-wired solution for residential applications. IQ Combiner 5/5C uses wired control communication and is compatible with IQ System Controller 3/3G and IQ Battery 5P.

The IQ Combiner 5/5C, IQ Series Microinverters, IQ System Controller 3/3G, and IQ Battery 5P provide a complete grid-agnostic Enphase Energy System.



IQ Series Microinverters The high-powered smart grid-ready IQ Series Microinverters (IQ6, IQ7, and IQ8 Series) simplify the installation process.



IQ Battery 5P

Fully integrated AC battery system. Includes six field-replaceable IQ8D-BAT Microinverters.











IQ System Controller 3/3G

Provides microgrid interconnection device (MID) functionality by automatically detecting grid failures and seamlessly transitioning the home energy system from grid power to backup power.



IQ Load Controller

Helps prioritize essential appliances during a grid outage to optimize energy consumption and prolong battery life.



Smart

- · Includes IQ Gateway for communication and control
- · Includes Enphase Mobile Connect (CELLMODEM-M1-06-SP-05), only with IQ Combiner 5C
- · Supports flexible networking: Wi-Fi, Ethernet, or cellular
- · Provides production metering (revenue grade) and consumption monitorina

Easy to install

- · Mounts to one stud with centered
- · Supports bottom, back, and side conduit entries
- · Supports up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- · 80 A total PV branch circuits
- · Bluetooth-based Wi-Fi provisioning for easy Wi-Fi setup

Reliable

- · Durable NRTL-certified NEMA type 3R enclosure
- · 5-year limited warranty
- · 2-year labor reimbursement program coverage included for both the IQ Combiner SKUs*
- · UL1741 Listed

5-year limited warranty

*For country-specific warranty information, see the https://enphase.com/installers/resources/warranty page.

IQ Combiner 5/5C

MODEL NUMBER	
IQ Combiner 5 (X-IQ-AM1-240-5)	IQ Combiner 5 with IQ Gateway printed circuit board for integrated revenue-grade PV production metering (ANSIC12.20 ±0.5%), consumption monitoring (±2.5%), and IQ Battery monitoring (±2.5%). Includes a silver solar shield to deflect heat.
IQ Combiner 5C (X-IQ-AM1-240-5C)	IQ Combiner 5C with IQ Gateway printed circuit board for integrated revenue-grade PV production metering (ANSI C12.20 ±0.5%), consumption monitoring (±2.5%) and IQ Battery monitoring (±2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05)¹. Includes a silver solar shield to deflect heat.
WHAT'S IN THE BOX	
IQ Gateway printed circuit board	IQ Gateway is the platform for total energy management for comprehensive, remote maintenance, and management of the Enphase Energy System
Busbar	80 A busbar with support for one IQ Gateway breaker and four 20 A breaker for installing IQ Series Microinverters and IQ Battery 5P
IQ Gateway breaker	Circuit breaker, 2-pole, 10 A/15 A
Production CT	Pre-wired revenue-grade solid-core CT, accurate up to ±0.5%
Consumption CT	Two consumption metering clamp CTs, shipped with the box, accurate up to $\pm 2.5\%$
IQ Battery CT	One battery metering clamp CT, shipped with the box, accurate up to ±2.5%
CTRL board	Control board for wired communication with IQ System Controller 3/3G and the IQ Battery 5P
Enphase Mobile Connect (only with IQ Combiner 5C)	4G-based LTE-M1 cellular modem (CELLMODEM-M1-06-SP-05) with a 5-year T-Mobile data plan
Accessories kit	Spare control headers for the COMMS-KIT-02 board
ACCESSORIES AND REPLACEMENT PARTS (NOT INCLUDED, O	ORDER SEPARATELY)
CELLMODEM-M1-06-SP-05	4G-based LTE-M1 cellular modem with a 5-year T-Mobile data plan
CELLMODEM-M1-06-AT-05	4G-based LTE-M1 cellular modem with a 5-year AT&T data plan
Circuit breakers (off-the-shelf)	Supports Eaton BR2XX, Siemens Q2XX and GE/ABB THQL21XX Series circuit breakers (XX represents 10, 15, 20, 30, 40, 50, or 60). Also supports Eaton BR220B, BR230B, and BR240B circuit breakers compatible with the hold-down kit.
Circuit breakers (provided by Enphase)	BRK-10A-2-240V, BRK-15A-2-240V, BRK-20A-2P-240V, BRK-15A-2P-240V-B, and BRK-20A-2P-240V-B (more details in the "Accessories" section)
XA-SOLARSHIELD-ES	Replacement solar shield for IQ Combiner 5/5C
XA-ENV2-PCBA-5	IQ Gateway replacement printed circuit board (PCB) for IQ Combiner 5/5C
X-IQ-NA-HD-125A	Hold-down kit compatible with Eaton BR-B Series circuit breakers (with screws)
XA-COMMS2-PCBA-5	Replacement COMMS-KIT-02 printed circuit board (PCB) for IQ Combiner 5/5C
ELECTRICAL SPECIFICATIONS	
Rating	80 A
System voltage and frequency	120/240 VAC, 60 Hz
Busbar rating	125 A
Fault current rating	10 KAIC
Maximum continuous current rating (input from PV/storage)	64 A
Branch circuits (solar and/or storage)	Up to four 2-pole Eaton BR, Siemens Q, or GE/ABB THQL Series distributed generation (DG) breakers only (not included)
Maximum total branch circuit breaker rating (input)	80 A of distributed generation/95 A with IQ Gateway breaker included
IQ Gateway breaker	10 A or 15 A rating GE/Siemens/Eaton included
Production metering CT	200 A solid core pre-installed and wired to IQ Gateway
Consumption monitoring CT (CT-200-CLAMP)	A pair of 200 A clamp-style current transformers is included with the box
IQ Battery metering CT	200 A clamp-style current transformer for IQ Battery metering, included with the box

¹ A plug-and-play industrial-grade cell modem for systems of up to 60 microinverters. Available in the United States, Canada, Mexico, Puerto Rico, and the US Virgin Islands, where there is adequate cellular service in the installation area.

Dimensions (W+H+D) 37.5 cm + 49.5 cm + 10.8 cm (14.75" + 10.5" + 6.63"). Height is 33.5 cm (21.06") with mounting brackets. Weight 75 kg (16.5 lb) Ambient temperature range 440°C to 46°C (-40°E to 119°F) Cooling Natural convection, plus heat shield Enclosure environmental rating Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction Wire sizes 29.0 km 50 A breaker insults: 14 to 4 MWS copper conductors - Main have been or great insults: 14 to 4 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Main have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been or great insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declared insults: 14 to 10 MWS copper conductors - Maint have been declare					
Height is 53.5 or In (20.67) with mounting brackets. Weight 7.5 kg (16.5 is)	MECHANICAL DATA				
Anbient temperature range - 40°C to 46°C (-40°F to 18°F) Cooling - Natural convection, plus heat shield Enclosure environmental rating - Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction - 20 A to 50 A breaker inputs: 14 to 170 AWG copper conductors - 60 A breaker branch input: 4 to 170 AWG copper conductors - Natural and ground-18 to 170 Copper conductors - Natural And and ground-18 to 170 Copper conductors - Natural And and ground-18 to 170 Copper conductors - Natural And and ground-18 to 170 Copper conductors - Natural And ground-18 to 170 Copper conductors - Natural And ground-18 to 170 Copper c	Dimensions (W × H × D)				
Cooling Natural convection, plus heat shield Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction 2 0.0 A to 50 A breaker inputs: 14 to 4 AWG copper conductors 8 0.0 A breaker branch input; 4 to 10 AWG copper conductors 1 Main lug combined output; 10 to 2/0 AWG copper conductors 1 Main lug combined output; 10 to 2/0 AWG copper conductors 2 Neutral and ground: 14 to 170 copper conductors 3 Main lug combined output; 10 to 2/0 AWG copper conductors 3 Main lug combined output; 10 to 2/0 AWG copper conductors 4 Main lug combined output; 10 to 2/0 AWG copper conductors 4 May 10 flow local code requirements for conductor sizing 4 May 11 Aug combined output; 10 to 2/0 AWG copper conductors 5 Neutral and ground: 14 to 170 copper conductors 5 Neutral and ground: 14 to 170 copper conductors 6 Main lug combined output; 10 to 2/0 AWG copper conductors 6 Altitude Communication (in-premise connectivity) 8 Mittiu-16 (TR) based for wired communication with the 18 Dates 49 Part 41 to 170 copper conductors 8 Mittiude 10 to 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2,	Weight		7.5 kg (16.5 lb)		
Enclosure environmental rating Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction - 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors - 80 A breaker tranch inputs: 14 to 4 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG copper conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductor sizing - 80 A breaker tranch inputs: 14 to 70 AWG conductor sizing - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs: 14 to 70 AWG conductors - 80 A breaker tranch inputs	Ambient temperature range		-40°C to 46°C (-40°F to 115°F)		
. 20 A to 50 A breaker inputs: 14 to 4 AWG copper conductors . 60 A breaker pranch input: 4 to 10 AWG copper conductors . Main lug combined output: 10 to 20 AWG copper conductors . Natin lug combined output: 10 to 20 AWG copper conductors . Neutral and ground: 14 to 10 copper set Microlinearises of the 10 copper conductors . Neutral and ground: 14 to 10 copper set Microlinearises of the 10 copper set Microlinearises. **COMMUNICATION INTERFACES** **Deptition** **Dept	Cooling		Natural convection, plus heat shield		
Wire sizes - 60 A breaker branch input: 4 to 1/0 AWG copper conductors - Main lug combined output IT to 2 /0 AWG copper conductors - Neutral and ground: 14 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and ground: 15 to 1/0 copper conductors - Neutral and	Enclosure environmental rating		Outdoor, NRTL-certified, NEMA type 3R, polycarbonate construction		
Altitude Up to 2,600 meters (8,530 feet) COMMUNICATION INTERFACES Integrated Wir-Fi 802.11b/g/n (dual band 2.4 GHz/5 GHz) for connecting the Enphase Cloud through the internet. Wir-Fi range (recommended) 10 m (32.8 feet) Bluetooth BLE4.2, 10 m range to configure Wir-Fi SSID Ethernet Cellular/Mobile Connect Ce	Wire sizes		 60 A breaker branch input: 4 to 1/0 AWG copper conductors Main lug combined output: 10 to 2/0 AWG copper conductors Neutral and ground: 14 to 1/0 copper conductors 		
Integrated Wi-Fi 802.1lb/g/n (dual band 2.4 GHz/5 GHz) for connecting the Enphase Cloud through the internet. Wi-Fi range (recommended) 10 m (32.8 feet) Bluetooth BLE4.2, 10 m range to configure Wi-Fi SSID Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) for connecting to the Enphase Cloud through the internet. Cellular/Mobile Connect CELLMODEM-MI-06-SP-05 or CELLMODEM-MI-06-AT-05 (included with the IQ Combiner 5C) Digital I/O Digital input/output for grid operator control USB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/37/10/10T, COMMS-KIT-02 for IQ Battery 5P Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90-110 kHz See https://developer-v4.amphase.com See Guide for local API at https://developer-v4.amphase.com COMPLIANCE IQ Combiner with IQ Gateway UL 741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA C22.2 No. 10071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-201	Communication (in-premise conn	ectivity)	Built-in CTRL board for wired communication with the IQ Battery 5P and the IQ System Controller 3/3G. Integrated power line communication for IQ Series Microinverters.		
Integrated Wi-Fi Wi-Fi range (recommended) Billetooth BillE4.2, 10 m range to configure Wi-Fi SSID Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) for connecting the Enphase Cloud through the internet. Cellular/Mobile Connect Commetain To Fide Call Connect Connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90-110 kHz See https://developer-v4.amphase.com See Builde for local API at https://developer-v4.amphase.com Compliant Connection Connectio	Altitude		Up to 2,600 meters (8,530 feet)		
Wi-Fi range (recommended) 10 m (32.8 feet)	COMMUNICATION INTERFACES				
Bluetooth BLE4.2, 10 m range to configure Wi-Fi SSID Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) for connecting to the Enphase Cloud through the internet. Cellular/Mobile Connect CELLMODEM-MI-06-SP-05 or CELLMODEM-MI-06-AT-05 (included with the IQ Combiner 5C) Digital I/O Digital input/output for grid operator control WSB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery SP Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90-110 kHz See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ul-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CAN/CSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G10-M240US01 EP200G10-M240US01 EP200G10-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-101-IP-NA	Integrated Wi-Fi		802.11b/g/n (dual band 2.4 GHz/5 GHz) for connecting the Enphase Cloud through the internet.		
Ethernet Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not included) for connecting to the Enphase Cloud through the internet. Cellular/Mobile Connect CELLMODEM-MI-06-SP-05 or CELLMODEM-MI-06-AT-05 (included with the IQ Combiner 5C) Digital I/O Digital input/output for grid operator control USB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication Web API See https://developer-w4.enphase.com See Guide for local API at https://enphase.com/download/accessing-ig-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-I/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller IQ System Controller 2 EP200G101-M240US00 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-10-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Wi-Fi range (recommended)		10 m (32.8 feet)		
Enphase Cloud through the internet. Cellular/Mobile Connect Cellular/Mobile Connect Cellular/Mobile Connect Cellular/Mobile Connect Cellular/Mobile Connect Digital input/output for grid operator control USB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication Web API See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-ig-gateway-local-apis-or-local-ul-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CAN/CSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-012 IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA, ENC	Bluetooth		BLE4.2, 10 m range to configure Wi-Fi SSID		
Digital I/O Digital input/output for grid operator control USB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90-110 kHz See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE IQ Combiner with IQ Gateway UL 1741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2. No. 61010-1, IEEE 1547; 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 EP200G101-M240US01 EP200G101-M240US01 ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA	Ethernet				
USB 2.0 Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90-110 kHz Web API See https://developer-v4.enphase.com See Quide for local API at https://enphase.com/download/accessing-ig-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE IQ Combiner with IQ Gateway UL 1741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-012 IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Cellular/Mobile Connect		CELLMODEM-M1-06-SP-05 or CELLMODEM-M1-06-AT-05 (included with the IQ Combiner 5C)		
Access point (AP) mode For connection between the IQ Gateway and a mobile device running the Enphase Installer App Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90–110 kHz See https://developer-v4.enphase.com Local API See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA	Digital I/O		Digital input/output for grid operator control		
Metering ports Up to two Consumption CTs, one IQ Battery CT, and one Production CT Power line communication 90–110 kHz See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-ig-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-10-IP-NA, ENCHARGE-10T-IP-NA	USB 2.0		Mobile Connect, COMMS-KIT-01 for IQ Battery 3/3T/10/10T, COMMS-KIT-02 for IQ Battery 5P		
Power line communication 90-110 kHz See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE IQ Combiner with IQ Gateway UL 1741, CAN/CSA C22.2 No. 1071, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Access point (AP) mode		For connection between the IQ Gateway and a mobile device running the Enphase Installer App		
Web API Local API See https://developer-v4.enphase.com See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE IQ Combiner with IQ Gateway UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Metering ports		Up to two Consumption CTs, one IQ Battery CT, and one Production CT		
Local API See Guide for local API at https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ 6, IQ7, and IQ8 Series Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-10-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Power line communication		90–110 kHz		
Local API https://enphase.com/download/accessing-iq-gateway-local-apis-or-local-ui-token-based-authentication COMPLIANCE UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ6, IQ7, and IQ8 Series Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01 ² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Web API		See https://developer-v4.enphase.com		
UL 1741, CAN/CSA C22.2 No. 107.1, Title 47 CFR, Part 15, Class B, ICES 003, NOM-208-SCFI-2016, UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-012 IQ System Controller 2 IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-10-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	Local API				
UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP Compliant, Production metering: ANSI C12.20 accuracy class 0.5 (PV production) COMPATIBILITY PV Microinverters IQ6, IQ7, and IQ8 Series Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01 ² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-10T-1P-NA	COMPLIANCE				
PV Microinverters IQ6, IQ7, and IQ8 Series Microinverters IQ System Controller EP200G101-M240US00 COMMS-KIT-01 ² IQ System Controller 2 EP200G101-M240US01 IQ Battery ENCHARGE-3-IP-NA, ENCHARGE-10-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	IQ Combiner with IQ Gateway		UL 60601-1/CANCSA 22.2 No. 61010-1, IEEE 1547: 2018 (UL 1741-SB, 3rd Ed.), IEEE 2030.5/CSIP		
IQ System Controller EP200G101-M240US00 COMMS-KIT-01 ² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA	COMPATIBILITY				
COMMS-KIT-01 ² IQ System Controller 2 EP200G101-M240US01 ENCHARGE-3-IP-NA, ENCHARGE-3T-IP-NA, ENCHARGE-10T-IP-NA	PV	Microinverters	IQ6, IQ7, and IQ8 Series Microinverters		
IQ Battery ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA		IQ System Controller	EP200G101-M240US00		
	COMMS-KIT-01 ²	IQ System Controller 2	EP200G101-M240US01		
		IQ Battery	ENCHARGE-3-1P-NA, ENCHARGE-10-1P-NA, ENCHARGE-3T-1P-NA, ENCHARGE-10T-1P-NA		
IQ System Controller 3 SC200D111C240US01, SC200G111C240US01	COMMS-KIT-02 ³	IQ System Controller 3	SC200D111C240US01, SC200G111C240US01		
IQ Battery IQBATTERY-5P-1P-NA	COMMO KIT OZ	IQ Battery	IQBATTERY-5P-1P-NA		

² For information about IQ Combiner 5/5C compatibility with the 2nd-generation batteries, refer to the compatibility matrix at https://enphase.com/download/compatibility-matrix.
³ IQ Combiner 5/5C comes pre-equipped with COMMS-KIT-02.

Accessories



Mobile Connect

4G-based LTE-M1 cellular modem with a 5-year data plan

(CELLMODEM-M1-06-SP-05 for Sprint and CELLMODEM-M1-06-AT-05 for AT&T)



Circuit breakers

BRK-10A-2-240V Circuit breaker, 2-pole, 10 A, Eaton BR210 BRK-15A-2-240V Circuit breaker, 2-pole, 15 A, Eaton BR215 BRK-20A-2P-240V Circuit breaker, 2-pole, 20 A, Eaton BR220 BRK-15A-2P-240V-B Circuit breaker, 2-pole, 15 A, Eaton BR215B with hold-down kit support

BRK-20A-2P-240V-B Circuit breaker, 2-pole, 20 A, Eaton BR220B with hold-down kit support



CT-200-SOLID

200 A revenue-grade solid core Production CT with <0.5% error rate (replacement SKU)



CT-200-CLAMP

200 A clamp-style consumption and battery metering CT with <2.5% error rate (replacement SKU)

Revision history

REVISION	DATE	DESCRIPTION
DSH-00007-4.0	June 2024	Updated the UL smart mark.
DSH-00007-3.0	March 2024	Updated accessories and replacement parts, communication interfaces, and compatibility specifications.
DSH-00007-2.0	September 2023	Included Bluetooth specifications.
DSH-00007-1.0	May 2023	Initial release.




XR Rail® Family

Solar Is Not Always Sunny

Over their lifetime, solar panels experience countless extreme weather events. Not just the worst storms in years, but the worst storms in 40 years. High winds capable of ripping panels from a roof, and snowfalls weighing enough to buckle a panel frame.

XR Rails® are the structural backbone preventing these results. They resist uplift, protect against buckling and safely and efficiently transfer loads into the building structure. Their superior spanning capability requires fewer roof attachments, reducing the number of roof penetrations and the amount of installation time.



Force-Stabilizing Curve

Sloped roofs generate both vertical and lateral forces on mounting rails which can cause them to bend and twist. The curved shape of XR Rails[®] is specially designed to increase strength in both directions while resisting the twisting. This unique feature ensures greater security during extreme weather and a longer system lifetime.

Compatible with Flat & Pitched Roofs



XR Rails® are compatible with FlashFoot® and other pitched roof attachments.



IronRidge® offers a range of tilt leg options for flat roof mounting applications.

Corrosion-Resistant Materials

All XR Rails® are made of 6000-series aluminum alloy, then protected with an anodized finish. Anodizing prevents surface and structural corrosion, while also providing a more attractive appearance.



XR Rail[®] Family

The XR Rail[®] Family offers the strength of a curved rail in three targeted sizes. Each size supports specific design loads, while minimizing material costs. Depending on your location, there is an XR Rail[®] to match.



XR10

XR10 is a sleek, low-profile mounting rail, designed for regions with light or no snow. It achieves spans up to 6 feet, while remaining light and economical.

- · 6' spanning capability
- · Moderate load capability
- · Clear & black anodized finish
- · Internal splices available



XR100

XR100 is a residential and commercial mounting rail. It supports a range of wind and snow conditions, while also maximizing spans up to 10 feet.

- · 10' spanning capability
- · Heavy load capability
- · Clear & black anodized finish
- · Internal splices available



XR1000

XR1000 is a heavyweight among solar mounting rails. It's built to handle extreme climates and spans up to 12 feet for commercial applications.

- · 12' spanning capability
- · Extreme load capability
- Clear anodized finish
- · Internal splices available

Rail Selection


The table below was prepared in compliance with applicable engineering codes and standards.* Values are based on the following criteria: ASCE 7-16, Gable Roof Flush Mount, Roof Zones 1 & 2e, Exposure B, Roof Slope of 8 to 20 degrees and Mean Building Height of 30 ft. Visit IronRidge.com for detailed certification letters.

Lo	ad		Rail Span						
Snow (PSF)	Wind (MPH)	4'	5' 4"	6'	8'	10'	12'		
	90								
None	120								
None	140	XR10		XR100		XR1000			
	160								
	90								
20	120								
20	140								
	160								
30	90								
30	160								
40	90								
40	160								
80	160								
120	160								

^{*}Table is meant to be a simplified span chart for conveying general rail capabilities. Use approved certification letters for actual design guidance.



QuickMount® Halo UltraGrip®



ITEM NO	DESCRIPTION	QTY IN KIT
1	QM Halo UltraGrip(Mill or Black)	1

PART NUMBER	DESCRIPTION
QM-HUG-01-M1	Halo UltraGrip - Mill
QM-HUG-01-B1	Halo UltraGrip - Black



