



PV LETTERS

Top Tier Solar Solutions

Contractor Address: 1530 Center Park Dr #2911,
Charlotte, NC 28217

June 30, 2025

Subject: Proposed Solar Panel Installation
Jennifer Lampley Residence, 501 S 11th St, Erwin, NC
DC System Size: 6.885 kW
PV Letters Job #004-26262

To Whom it May Concern,

We have reviewed information, provided by our client, related to the proposed solar panel installation at the above-referenced address. The purpose of the review was to determine if the existing roof is structurally adequate for the proposed installation. Based on our review and analysis of the given information, and in accordance with governing building codes, I certify that the capacity of the structural roof framing that directly supports the additional gravity loading due to the solar panel supports and modules had been reviewed and determined to meet or exceed the requirements in accordance with the Design Criteria.

Design Parameter Summary

Governing Building Code: 2018 North Carolina Residential Code
Risk Category: II
Wind Exposure: C
Design Wind Speed: 120 mph
Ground Snow Load: 15 psf

Roof Information

Roof Structure: 2x4 Manufactured Trusses @ 24" O.C. (assumed)
Roofing Material: Asphalt Shingles
Roof Slope: 18 degrees

Roof Connection Details

Framing Mount Wood Screws: (2) #14 Self-Drilling Screw with a minimum penetration depth of 1.75" into roof truss top chord only, at 72" O.C. max

Decking Mount Wood Screws: (6) #14 Self-Drilling Screw with a minimum penetration depth of 0.25", at 72" O.C. max

Note: Required installation of 75% / 25% between Framing and Decking Mounts.

Engineering Analysis

The proposed installation - including weight of panels, racking, mounts, and inverters where applicable - will be approximately 3 psf. In the areas where panels are installed, roof live loads will not be present. The reduction of roof live load is adequate to fully or partially compensate for the addition of the panel installation. Because the member forces in the area of the solar panels are not increased by more than 5%, and so per provisions in the adopted building codes, the structure need not be altered for gravity loading.

The proposed installation will be 6" max. above the roof surface (flush mounted) and parallel to the roof surface. Therefore, any increase in wind loading on the building structure from the solar panel installation is expected to be negligible. Wind is the governing lateral load case. Because the increase in lateral loading is not increased by more than 10%, per provisions in the adopted building codes, the structure need not be altered for lateral loading.

Wind uplift on the panels has been calculated in accordance with the relevant provisions of ASCE 7-10. This loading has been used to verify the adequacy of the connection specified above. Connection locations should be in accordance with design drawings.

IronRidge XR10 rails will support the modules and will fasten to the roof structure with IronRidge QuickMount Halo Ultragrip along the rail.

Conclusion

The roof structure need not be altered for either gravity loading (including snow) or lateral loading (including wind). Therefore, the existing structure is permitted to remain unaltered. Connections to the roof must be made per the "Roof Connection Details" section above. Copies of all relevant calculations are enclosed.

Limitations and Disclaimers

Electrical design is excluded from this analysis. Waterproofing is the sole responsibility of the installer and is also excluded from this analysis. Solar panels must be installed per manufacturer specifications. Structural design and analysis of the adequacy of solar panels, racks, mounts, and other components is performed by each component's respective manufacturer; the undersigned makes no statement of opinion regarding such components. This letter and the opinions expressed herein are rendered solely for the benefit of the permitting authority (city or county building department) and your office, and may not be utilized or relied on by any other party.


If you have any questions or concerns, please contact us at (208)-994-1680, or by email at Projects@pvletters.com.

Sincerely,



Trevor A. Jones, P.E.

6/30/2025





PV LETTERS

Standard Loading Comparison

This calculation justifies the additional solar load by comparing existing to proposed gravity loads in the location of the solar panels.

	<u>Without Solar</u>	<u>With Solar</u>	
Dead Load			
Asphalt Shingles	5	5	psf
1/4" Plywood	1	1	psf
Framing	4	4	psf
Insulation	1	1	psf
1/2" Gypsum Ceiling	2	2	psf
M,E, & Misc	1.5	1.5	psf
Solar Panel	0	3	psf
Total Dead Load	14.5	17.5	psf
Snow Load			
Ground Snow Load, P_g	15		psf
Exposure Factor, C_e	1.00		
Thermal Factor, C_t	1.1		
Importance Factor, I_s	1		
Flat Roof Snow Load	12		ASCE 7 Eqn. 7.3-1 or jurisdiction min.
Slope	18		degrees
Unobstructed Slippery Surface?	No	No	
Slope Factor, C_s	1.00	1.00	
Sloped Roof Snow Load	11.6	11.6	psf
Live Load			
Roof Live Load	20	0	psf
Load Combination			
D + L _r	34.5	17.5	psf
D + S	26.1	29.1	psf
Max. Load	34.5	29.1	psf
% of original		84.20%	

Result:

Because the total forces are decreased, per the relevant code provisions stated in the body of the letter, the existing roof structure is permitted to remain unaltered.



PV LETTERS

Wood Screw Calculation (per ASCE 7-10)

This calculation justifies the connection of the solar panels to existing roof members, by showing the connection capacity is equal to or greater than the uplift force demands.

Connection Demand

Spacing perpendicular to rail, in	34	
Roof Angle, degrees	18	
Roof Layout	Gable	
Wind Speed, mph	120	
Exposure Coefficient, K_z	0.85	(Table 26.10-1)
Topographic Factor, K_{zt}	1.00	(Table 26.8.1)
Directionality Factor, K_d	0.85	(Table 26.6-1)
Elevation Factor, K_e	1.00	(Table 26.9-1)
Velocity Pressure q_z , psf	26.5	(Table 26.10-1)

Zones:

	<u>1</u>	<u>2</u>	<u>3</u>
Spacing parallel to rail, in	72	72	72
GC_p (max)(Figure 29.4-7)	0.90	2.20	2.60
Exposed Panels? ($\gamma_E = 1.5$) (Fig. 29.4-7)	No	No	No
Effective Wind Area on each con., ft ²	16.9	16.9	16.9
Pressure Equalization Factor, γ_a (Figure 29.4-8)	0.71	0.71	0.71
Uplift Force, psf (Equation 29.4-7)	16.9	41.3	48.8
Max. Uplift Force / Connection (0.6 WL), lbs	171.8	420.0	496.3
Solar Dead Load (0.6 DL), Lbs	30.5	30.5	30.5
Max. Uplift Force (0.6 WL - 0.6 DL), lbs	141.3	389.5	465.8

Connection Capacity

Attachment FTG	IronRidge QuickMount Halo Ultragrip	
Attachment location	Framing	Decking
Fastener Type	Wood Screw	Wood Screw
Fastener Diameter, in	0.242	0.242
Embedment Length, in	1.75	0.25
Lumber Species & Grade	SPF #2 (Assumed)	
Nominal Withdrawal Capacity W, lbs	213	30.4
# of Screws	2	6
Load Duration Factor C_d	1.6	1.6
Screw Adj. Withdrawal Cap. W', lbs	681	292
Attachment FTG Strength with C_d , lbs	1606	374
Assumed attachment distribution	75%	25%
Max applied load, lbs	466	
Max allowable load, lbs	584	

Compare Adjusted Withdrawal Capacity to ASD Factored Demand

<u>Zones:</u>	<u>1</u>	<u>2</u>	<u>3</u>
	O.K.	O.K.	O.K.

PROJECT DESCRIPTION:

17 X JA SOLAR: JAM54S31-405/MR 405W MONO MODULES
ROOF MOUNTED SOLAR PHOTOVOLTAIC MODULES
DC SYSTEM SIZE: 6.885 KW DC
AC SYSTEM SIZE: 5.700 KW AC
EQUIPMENT SUMMARY
17 JA SOLAR: JAM54S31-405/MR 405W MONO MODULES
17 SOLAREGE: S440 POWER OPTIMIZERS
01 SOLAREGE: SE5700H-US (240V/5700W) INVERTER
ROOF ARRAY AREA #1: 315.15 SQ. FT.
ROOF ARRAY AREA #2: 42.02 SQ. FT.
NOTE: VISIBLE, LOCKABLE, LABELED AC DISCONNECT
LOCATED WITHIN 10' OF UTILITY METER

(N) SOLAREGE: SE5700H-US
(240V/5700W) INVERTER
(N) VISIBLE, LOCKABLE,
LABELED FUSED AC DISCONNECT
(LOCATED WITHIN 10' OF UTILITY METER)
(E) UTILITY METER
(E) MAIN SERVICE PANEL
(INSIDE HOUSE)

(E) CHIMNEY
ROOF #1
(15) JA SOLAR: JAM54S31-405/MR
405W MONO MODULES WITH
SOLAREGE: S440 POWER OPTIMIZERS

(E) TREES

DESIGN SPECIFICATION


OCCUPANCY: II
CONSTRUCTION: SINGLE-FAMILY
ZONING: RESIDENTIAL
GROUND SNOW LOAD: REFER STRUCTURAL LETTER
WIND EXPOSURE: REFER STRUCTURAL LETTER
WIND SPEED: REFER STRUCTURAL LETTER



TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2011,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	DATE	REV
DESCRIPTION		
INITIAL DESIGN	06/30/2025	



STRUCTURAL ONLY
06/30/2025


PROJECT NAME & ADDRESS
JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST
ERWIN, NC 28339

DRAWN BY
ESR

SHEET NAME
SITE PLAN

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-2




MODULE TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULES = 17 MODULES
MODULE TYPE = JA SOLAR: JAM54S31-405W MONO MODULES
MODULE WEIGHT = 47.39 LBS / 21.5 kg
MODULE DIMENSIONS = 67.79" x 44.65" = 21.01 SF
(E) MAIN SERVICE PANEL (INSIDE HOUSE)



ROOF #1
PITCH - 18°
AZIM. - 89°



ROOF DESCRIPTION

ROOF TYPE		ASPHALT SHINGLE			
ROOF LAYER		1 LAYER			
ROOF	# OF MODULES	ROOF PITCH	AZIMUTH	TRUSS SIZE	TRUSS SPACING
#1	15	18°	89°	2"x4"	24"
#2	2	18°	179°	2"x4"	24"

ARRAY AREA & ROOF AREA CALC'S

TOTAL PV ARRAY AREA (SQ. FT.)	TOTAL ROOF AREA (SQ. FT.)	ROOF AREA COVERED BY ARRAY (%)
357.17	2443.74	15

IRONRIDGE HALO ULTRAGRIP ATTACHMENTS
IN ROOF TRUSS TOP CHORD ONLY

(N) IRONRIDGE XR-10 RAIL (TYP.)

ROOF #1
(15) JA SOLAR: JAM54S31-405W MR
405W MONO MODULES WITH
SOLAREEDGE: S440 POWER OPTIMIZERS

ROOF #2
(2) JA SOLAR: JAM54S31-405W MR
405W MONO MODULES WITH
SOLAREEDGE: S440 POWER
OPTIMIZERS


LEGEND

- JUNCTION BOX
- INVERTER
- AC DISCONNECT
- UTILITY METER
- MAIN SERVICE PANEL
- SUB PANEL
- VENT, ATTIC FAN (ROOF OBSTRUCTION)
- ROOF ATTACHMENT
- TRUSS
- CONDUIT

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2511,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	DATE	REV
DESCRIPTION	06/30/2025	
INITIAL DESIGN		



STRUCTURAL ONLY
06/30/2025

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST.
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME
ROOF PLAN &
MODULES

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER


PV-3

1 ROOF PLAN & MODULES

SCALE: 1/8" = 1'-0"

SCALE: 1/8" = 1'-0"

REVISIONS	
DESCRIPTION	DATE
INITIAL DESIGN	06/30/2025



STRUCTURAL ONLY
06/30/2025

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST.
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME

STRUCTURAL DETAIL


SHEET SIZE

ANSI B

11" X 17"

SHEET NUMBER


PV-5



1 STRUCTURAL ATTACHMENT (Side view)

PV-5

SCALE: N.T.S



2 ATTACHMENT DETAIL (enlarged view)


PV-5

SCALE: NTS

DC SYSTEM SIZE: 6.885 kW DC
AC SYSTEM SIZE: 5.700 kW AC

(17) JA SOLAR: JAM54531-405MR 405W MONO MODULES
WITH (17) SOLAREGE: S440 POWER OPTIMIZERS
LOCATED UNDER EACH PANEL (240V) AND
(01) SOLAREGE: SE5700H-US (240V/5700W) INVERTER
(01) STRING OF 8 MODULES AND
(01) STRING OF 9 MODULES ARE CONNECTED IN SERIES

(17) JA SOLAR: JAM54531-405MR
405W MODULES



SOLAREGE POWER OPTIMIZERS S440 RATED
DC INPUT POWER: 440WATTS
MAXIMUM INPUT VOLTAGE: 60 VDC
MAXIMUM SHORT CIRCUIT CURRENT: 14.5 ADC
MAXIMUM OUTPUT CURRENT: 15 ADC
STRING LIMITATIONS: 8 TO 25 OPTIMIZERS,
5700 WATTS STC PER STRING MAXIMUM


INTERCONNECTION NOTES:

1. INTERCONNECTION, SIZING, LIMITATIONS, AND COMPLIANCE DETERMINED IN ACCORDANCE WITH NEC 705.121, AND (NEC 690.59).
2. GROUND FAULT PROTECTION IN ACCORDANCE WITH (NEC 215.9), (NEC 230.99).
3. ALL EQUIPMENT TO BE RATED FOR BACKFEEDING.
4. PV BREAKER TO BE POSITIONED AT THE OPPOSITE END OF THE BUSBAR RELATIVE TO THE MAIN BREAKER.

DISCONNECT NOTES:

1. DISCONNECTING SWITCHES SHALL BE WIRED SUCH THAT WHEN THE SWITCH IS OPENED THE CONDUCTORS REMAINING LIVE ARE CONNECTED TO THE TERMINALS MARKED "LINE SIDE" (TYPICALLY THE UPPER TERMINALS).
2. AC DISCONNECT MUST BE ACCESSIBLE TO QUALIFIED UTILITY PERSONNEL BEING CAPABLE AND BEE VISIBLE GREEN SWITCH.
3. DISCONNECTING MEANS THEIR LOCATION SHALL BE IN ACCORDANCE WITH (NEC 225.31) AND (NEC 225.32).

SOLAREGE: SE5700H-US
HOME HUB INVERTER
OUTPUT: 240 VAC, 24.00A
99.5% CEC WEIGHTED EFFICIENCY
NEMA 3R, UL LISTED, INTERNAL SPD
WITH INTEGRATED DC DISCONNECT




GROUNDING & GENERAL NOTES:

1. PV GROUNDING ELECTRODE SYSTEM NEEDS TO BE INSTALLED IN ACCORDANCE WITH (NEC 690.43).
2. PV INVERTER IS UNGROUNDED, TRANSFORMER-LESS TYPE.
3. DC GEC AND AC GEC TO REMAIN UNSPLICED, OR SPLICED TO EXISTING ELECTRODE.
4. ANY EXISTING WIRING INVOLVED WITH PV SYSTEM CONNECTION THAT IS FOUND TO BE INADEQUATE PER CODE SHALL BE CORRECTED PRIOR TO FINAL INSPECTION.
5. JUNCTION BOX QUANTITIES, AND PLACEMENT SUBJECT TO CHANGE IN THE FIELD. JUNCTION BOX DEPICTED ON ELECTRICAL DIAGRAM REPRESENT WIRE TYPE AND SIZING.
6. AC DISCONNECT NOTED IN EQUIPMENT SCHEDULE OPTIONAL IF OTHER AC DISCONNECTING MEANS IS LOCATED WITHIN 10' OF SERVICE DISCONNECT.
7. RACEWAYS AND CABLES EXPOSED TO SUNLIGHT ON ROOFTOPS SHOULD BE INSTALLED MORE THAN 7/8" ABOVE THE ROOF USING CONDUIT SUPPORTS.

RACKING NOTE:

1. BOND EVERY OTHER RAIL WITH #6 BARE COPPER



NOTE: CONDUIT TO BE UL LISTED FOR
WET LOCATIONS AND UV PROTECTED

QTY	CONDUCTOR INFORMATION	CONDUIT TYPE	CONDUIT SIZE
1	(4) #10AWG - PV WIREUSE-2	N/A	N/A
2	(1) #6AWG - BARE COPPER IN FREE AIR		
3	(1) #10AWG - CU THWN-2	EMT OR LFMC IN ATTIC	3/4"
4	(1) #10AWG - CU THWN-2 GND		
5	(2) #6AWG - CU THWN-2	EMT-LFMC OR PVC	3/4"
6	(1) #6AWG - CU THWN-2 N		
7	(2) #6AWG - CU THWN-2 GND		
8	(1) #6AWG - CU THWN-2	EMT, LFMC OR PVC	3/4"

1 ELECTRICAL LINE DIAGRAM

SCALE: NTS

PV-6

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	DATE	REV
DESCRIPTION		
INITIAL DESIGN	06/03/2025	

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

PROJECT NAME & ADDRESS

DRAWN BY
ESR

SHEET NAME

ELECTRICAL LINE DIAGRAM

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-6

SOLAR MODULE SPECIFICATIONS	
MANUFACTURER / MODEL #	JA SOLAR- JAM65S1-405MR 405W MODULE
VMP	31.21V
VMP	12.98A
VOC	37.23V
ISC	13.87A
TEMP. COEFF. VOC	-0.275%/°C
MODULE DIMENSION	57.75" L x 44.55" W x 1.18" D (In Inch)

INVERTER SPECIFICATIONS	
MANUFACTURER / MODEL #	SOLAREDGE- SEG700H-US (240V/6700W)
NOMINAL AC POWER	5700 KW
NOMINAL OUTPUT VOLTAGE	240 VAC
NOMINAL OUTPUT CURRENT	24.00A
PERCENT OF VALUES	NUMBER OF CURRENT CARRYING CONDUCTORS IN EMT
80	4-6
70	7-9
50	10-20

AMBIENT TEMPERATURE SPECS	
AMBIENT TEMP (HIGH TEMP 2%)	38°
RECORD LOW TEMPERATURE	-8°
MODULE TEMPERATURE COEFFICIENT OF Voc	-0.275%/°C



TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	
DESCRIPTION	DATE
INITIAL DESIGN	06/06/2025

DC FEEDER CALCULATIONS											
CIRCUIT ORIGIN	CIRCUIT DESTINATION	VOLTAGE (V)	FULL LOAD AMPS*FLA* (A)	FLA*1.25 (A)	OCBP SIZE (A)	GROUND SIZE	CONDUCTOR SIZE	75°C AMPACITY (A)	AMPACITY CHECK #1	AMBIENT TEMP. (°C)	TOTAL CC CONDUCTORS IN RACEWAY
STRINGS 1	JUNCTION BOX	300	15.00	18.75	20	1/4" BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2
STRINGS 2	JUNCTION BOX	300	15.00	18.75	20	1/4" BARE COPPER #6 AWG	CU #10 AWG	35	PASS	38	2
JUNCTION BOX	INVERTER	300	15.00	18.75	20	CU #10 AWG	CU #10 AWG	35	PASS	38	4
Sizing 1 Voltage Drop											
Sizing 2 Voltage Drop											
0.245											
0.245											

AC FEEDER CALCULATIONS											
CIRCUIT ORIGIN	CIRCUIT DESTINATION	VOLTAGE (V)	FULL LOAD AMPS*FLA* (A)	FLA*1.25 (A)	OCBP SIZE (A)	NEUTRAL SIZE	GROUND SIZE	CONDUCTOR SIZE	75°C AMPACITY (A)	AMPACITY CHECK #1	AMBIENT TEMP. (°C)
INVERTER	AC DISCONNECT	240	24	30	30	CU #6 AWG	CU #6 AWG	CU #6 AWG	65	PASS	38
AC DISCONNECT	POI	240	24	30	30	CU #6 AWG	N/A	CU #6 AWG	65	PASS	38
Sizing 1 Voltage Drop											
Sizing 2 Voltage Drop											
0.245											
0.245											

CUMULATIVE VOLTAGE DROP 0.098

ELECTRICAL NOTES

- ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL, AND LABELED FOR ITS APPLICATION.
- ALL CONDUCTORS SHALL BE RATED UP TO 600V FOR RESIDENTIAL AND 1000V FOR COMMERCIAL AND 90 DEGREE C WET ENVIRONMENT.
- CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP, OR VALLEY.
- WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- WHERE SIZES OF JUNCTION BOX, RACEWAYS, AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
- ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
- MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR ILSCO GBL-4DBT LAY-IN LUG.
- TEMPERATURE RATINGS OF ALL CONDUCTORS, TERMINATIONS, BREAKERS, OR OTHER DEVICES ASSOCIATED WITH THE SOLAR PV SYSTEM SHALL BE RATED FOR AT LEAST 75 DEGREE C.

PROJECT NAME & ADDRESS
JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

DRAWN BY
ESR

SHEET NAME
WIRING CALCULATIONS

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-7

PHOTOVOLTAIC POWER SOURCE

EVERY 10' ON CONDUIT & ENCLOSURES

LABEL-1:
LABEL LOCATION:
DUEANT CONDUIT RACEWAY
SOLA DECK / JUNCTION BOX
CODE REF: NEC 690.31 (D)(2)



WARNING

ELECTRIC SHOCK HAZARD

TERMINALS ON THE LINE AND LOAD SIDES MAY
BE ENERGIZED IN THE OPEN POSITION

LABEL-2:
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.13(B)



WARNING

DUAL POWER SUPPLY

SOURCE: UTILITY GRID AND
PV SOLAR ELECTRIC SYSTEM

LABEL-3:
LABEL LOCATION:
MAIN SERVICE PANEL
CODE REF: NEC 705.12(C) & NEC 690.59

SOLAR PV BREAKER:
BREAKER IS BACKFED
DO NOT RELOCATE


LABEL-4:
LABEL LOCATION:
MAIN SERVICE PANEL
CODE REF: NEC 705.12(C) & NEC 690.59



POWER SOURCE OUTPUT
CONNECTION. DO NOT
RELOCATE THIS
OVERCURRENT DEVICE

LABEL-5:
LABEL LOCATION:
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
SUBPANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 705.12(B)(3)(2)

SOLAR PV SYSTEM EQUIPPED
WITH RAPID SHUTDOWN



LABEL-6:
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.55(C)(1)(A)

RAPID SHUTDOWN SWITCH
FOR SOLAR PV SYSTEM

LABEL-7:
LABEL LOCATION:
AC DISCONNECT
MAIN SERVICE PANEL (ONLY IF SOLAR IS BACK-FED)
CODE REF: NEC 690.55(C)(2)

DC DISCONNECT

LABEL-8:
LABEL LOCATION:
INVERTER
CODE REF: NEC 690.13(B)

AC DISCONNECT
PHOTOVOLTAIC SYSTEM
POWER SOURCE
NOMINAL OPERATING AC VOLTAGE
RATED AC OUTPUT CURRENT

LABEL-9:
LABEL LOCATION:
AC DISCONNECT
CODE REF: NEC 690.54

MAXIMUM VOLTAGE
MAXIMUM CIRCUIT CURRENT
MAXIMUM RATED OUTPUT
CURRENT OF THE CHARGE
CONTROLLER OR DC-TO-DC
CONVERTER (IF INSTALLED)

LABEL-10:
LABEL LOCATION:
ON THE RIGHT SIDE OF THE INVERTER (PRE-EXISTING ON THE INVERTER)
CODE REF: NEC 690.53

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2811,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/02/2025	

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME

LABELS

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-8

Harvest the Sunshine

DEEP BLUE 3.0 Light

405W MBB
Half-cell Black Module
JAM54S31 380-405/MR

Mono

Introduction

Assembled with 1180 PERC cells, the half-cell configuration of the modules offers the advantages of higher power output, lower temperature-dependent performance, reduced shading effect, and the empty space between the cells is 2mm, which is not all technologies have reached a new level in 2022.

-  Higher output power
-  Lower LOCE
-  Less shading and lower resistive loss
-  Better mechanical loading tolerance

Superior Warranty

- 25-year product warranty
- 25-year linear power output warranty

Comprehensive Certificates

- IEC 61215, IEC 61730, UL 61215, UL 61730
- ISO 9001: 2015 Quality management systems
- ISO 14001: 2015 Environmental management systems
- ISO 45001: 2018 Occupational health and safety management systems
- IEC TS 62941: 2016 Terrestrial photovoltaic (PV) modules - Guidelines for increased confidence in PV module design qualification and type approval

New linear power warranty ■ Standard module linear power warranty

JA SOLAR




www.jasolar.com
JA Solar reserves the right to amend the information without notice.

JA SOLAR

JAM54S31 380-405/MR

MECHANICAL DIAGRAMS



SPECIFICATIONS

Cell	Mono
Weight	21.5kg±0.5%
Dimensions	1722±2mm×1134±2mm×30±1mm
Cable Cross Section Size	4mm ² IEC: 12 AWG (UL)
No. of cells	108 (6×18)
Junction Box	IP68, 3 diodes
Connector	MC4-EVO2 (1500V)
Cable Length (Including Connector)	Female: 300mm±40mm (UL) Male: 1200mm±40mm (UL)
Packaging Configuration	38pcs/Pallet, 864pcs/40 Container

ELECTRICAL PARAMETERS AT STC

TYPE	JAM54S31-380MR	JAM54S31-405MR	JAM54S31-425MR	JAM54S31-450MR
Rated Maximum Power (P _{max}) [W]	380	405	425	450
Open Circuit Voltage (V _{oc}) [V]	36.58	36.71	36.85	37.02
Maximum Power Voltage (V _{mp}) [V]	31.22	30.48	30.64	31.01
Short Circuit Current (I _{sc}) [A]	13.44	13.52	13.61	13.79
Maximum Power Current (I _{mp}) [A]	12.55	12.64	12.81	12.90
Module Efficiency [%]	20.5	20.7	20.8	20.9

Power Tolerance	±3%
Temperature Coefficient of V _{oc} [1/°C]	-0.04%/°C
Temperature Coefficient of V _{mp} [1/°C]	-0.275%/°C
Temperature Coefficient of P _{max} [1/°C]	-0.350%/°C


Remark: Electrical data in this catalog do not refer to a single module and they are not part of the data sheet. They only serve for comparison among different module types.

ELECTRICAL PARAMETERS AT NOCT

TYPE	JAM54S31-380MR	JAM54S31-405MR	JAM54S31-425MR	JAM54S31-450MR
Rated Max Power (P _{max}) [W]	336	354	368	386
Open Circuit Voltage (V _{oc}) [V]	34.36	34.48	34.75	35.12
Max Power Voltage (V _{mp}) [V]	28.51	28.65	29.06	29.47
Short Circuit Current (I _{sc}) [A]	10.75	10.82	10.89	11.03
Max Power Current (I _{mp}) [A]	10.04	10.11	10.19	10.36

NOCT: Irradiance 800W/m², ambient temperature 20°C, wind speed 1 m/s, AM1.5G, UL Type 1

CHARACTERISTICS



Premium Cells, Premium Modules

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST.
ERWIN, NC 28339

PROJECT NAME & ADDRESS

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-9

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2811,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	DATE	REV
DESCRIPTION	INITIAL DESIGN	06/30/2025



This document is the property of Intertek Testing Services and is not transferable. The certification mark(s) may be employed only at the location of the Party Authorized To Apply Mark.

Country:	P. R. China
Country:	Vietnam

Party Authorized To Apply Mark: Same as Manufacturer
Report Issuing Office: Intertek Testing Services Shanghai Limited

Control Number: 5020189
Authorized by: _____
for L. Matthew Snyder, Certification Manager[illegible]

3435 East Argonne Road, Niles, Illinois 60057
Telephone 800-345-3851 or 847-439-5867 Fax 312-283-1072

Catalytic (CV) Modules - Design Qualification And Type App

Terrestrial Photovoltaic (PV) Modules - Design Qualification And Type Approval - Part 1-1: Special Requirements For Testing Of Crystalline Silicon Photovoltaic (PV) Modules [UL 61245-1-1:2017 Ed.1]

Photovoltaic (PV) Module Safety Qualification - Part 1: Requirements For Construction [UL 61730-1:2017 Ed.1]

Photovoltaic (PV) Module Safety Qualification - Part 1: Requirements for Construction [CSA C22.2#61730-1:2019 Ed.2]

ATM Issued: 12-Jun-2024
ED 16.3.15 (1-Jul-2022) Microbiology

Page 11 of 16

ATM for Report 190900406SHA-001

Page 12 of 16

ATM Issued: 12~Jun-2024
ED 18.3.15 (1-Jul-2022) Mandatory

intertek
Total Quality Assured.

AUTHORIZATION TO MARK



TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/30/2025	

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339


DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-10

POWER OPTIMIZER



✓ Specifically designed to work with SolarEdge residential inverters	✓ Faster installations with simplified wire management and easy assembly using a single bolt
✓ Detects abnormal PV connector behavior, preventing potential safety issues	✓ Flexible system design for maximum space utilization
✓ Module-level voltage shutdown for installer and firefighter safety	✓ Compatible with bifacial PV modules
✓ Superior efficiency (99.5%)	✓ Meets NEC requirements for arc fault protection (AFCI) and Photovoltaic Rapid Shutdown System (PVRSS)
✓ Mitigates all types of module mismatch loss, from manufacturing tolerance to partial shading	

solar edge

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/09/2025	

INPUT		5440	5500S	5850S
Rated Input DC Power		400 W	500 W	850 W
Alternate Maximum Input Voltage Range		40 V	125 V	175 V
Input Operating Range		8-60 V	10.5-105 V	15-85 V
Minimum Input Current (Maximum of Connected Modules)		34.5	15	
Maximum Input Short-Circuit Current ¹			18.75	40
Minimum Efficiency			93.5	95
Weighted Efficiency			96.6	96
Overload Capacity				96

OUTPUT DURING OPERATION (POWER OPTIMIZER CONNECTED TO OPERATING SOLAREDGE INVERTER)

Maximum Output Current	15	AK
Maximum Output Voltage	60	Vdc
Output During Standby (Power Optimizer Disconnected from SolarEdge Inverter or Inverter Off)	80	Vdc
Standby Output Voltage and Power Converter	1 ± 0.1	Vdc

STANDARD COMPLIANCE

Photocatalytic Rapid Shutdown System

[illegible]

Maximum Allowed System Voltage

Dimensions (W x H x D)	129 x 155 x 38 / 5.07 x 6.10 x 1.50	129 x 163 x 45 / 5.07 x 6.40 x 1.77	mm / in.
Weight	720 g / 1.6	790 g / 1.74	g / lb
*Fiber Connector		MC4	
*Input Wire Length		0.170 ±2	m / ft
*Output Connector		MC4	

Churn Rate Length	Churn Rate	Churn Rate Length	Churn Rate
0-100	0.0000	0-100	0.0000
100-200	0.0000	100-200	0.0000
200-300	0.0000	200-300	0.0000
300-400	0.0000	300-400	0.0000
400-500	0.0000	400-500	0.0000
500-600	0.0000	500-600	0.0000
600-700	0.0000	600-700	0.0000
700-800	0.0000	700-800	0.0000
800-900	0.0000	800-900	0.0000
900-1000	0.0000	900-1000	0.0000
1000-1100	0.0000	1000-1100	0.0000
1100-1200	0.0000	1100-1200	0.0000
1200-1300	0.0000	1200-1300	0.0000
1300-1400	0.0000	1300-1400	0.0000
1400-1500	0.0000	1400-1500	0.0000
1500-1600	0.0000	1500-1600	0.0000
1600-1700	0.0000	1600-1700	0.0000
1700-1800	0.0000	1700-1800	0.0000
1800-1900	0.0000	1800-1900	0.0000
1900-2000	0.0000	1900-2000	0.0000
2000-2100	0.0000	2000-2100	0.0000
2100-2200	0.0000	2100-2200	0.0000
2200-2300	0.0000	2200-2300	0.0000
2300-2400	0.0000	2300-2400	0.0000
2400-2500	0.0000	2400-2500	0.0000
2500-2600	0.0000	2500-2600	0.0000
2600-2700	0.0000	2600-2700	0.0000
2700-2800	0.0000	2700-2800	0.0000
2800-2900	0.0000	2800-2900	0.0000
2900-3000	0.0000	2900-3000	0.0000
3000-3100	0.0000	3000-3100	0.0000
3100-3200	0.0000	3100-3200	0.0000
3200-3300	0.0000	3200-3300	0.0000
3300-3400	0.0000	3300-3400	0.0000
3400-3500	0.0000	3400-3500	0.0000
3500-3600	0.0000	3500-3600	0.0000
3600-3700	0.0000	3600-3700	0.0000
3700-3800	0.0000	3700-3800	0.0000
3800-3900	0.0000	3800-3900	0.0000
3900-4000	0.0000	3900-4000	0.0000
4000-4100	0.0000	4000-4100	0.0000
4100-4200	0.0000	4100-4200	0.0000
4200-4300	0.0000	4200-4300	0.0000
4300-4400	0.0000	4300-4400	0.0000
4400-4500	0.0000	4400-4500	0.0000
4500-4600	0.0000	4500-4600	0.0000
4600-4700	0.0000	4600-4700	0.0000
4700-4800	0.0000	4700-4800	0.0000
4800-4900	0.0000	4800-4900	0.0000
4900-5000	0.0000	4900-5000	0.0000
5000-5100	0.0000	5000-5100	0.0000
5100-5200	0.0000	5100-5200	0.0000
5200-5300	0.0000	5200-5300	0.0000
5300-5400	0.0000	5300-5400	0.0000
5400-5500	0.0000	5400-5500	0.0000
5500-5600	0.0000	5500-5600	0.0000
5600-5700	0.0000	5600-5700	0.0000
5700-5800	0.0000	5700-5800	0.0000
5800-5900	0.0000	5800-5900	0.0000
5900-6000	0.0000	5900-6000	0.0000
6000-6100	0.0000	6000-6100	0.0000
6100-6200	0.0000	6100-6200	0.0000
6200-6300	0.0000	6200-6300	0.0000
6300-6400	0.0000	6300-6400	0.0000
6400-6500	0.0000	6400-6500	0.0000
6500-6600	0.0000	6500-6600	0.0000
6600-6700	0.0000	6600-6700	0.00

PV System Design Using a Solar Edge Inverter		SolarEdge String Wire/Hub Sample #		Price: Phase Ia 277V 4-Wire (cont)	
		A	B	A	B
Minimum String Length (Power)	5440				
Maximum String Length (Power)	51000 / 54400				
Maximum String Length (Power Observation)	51000	0	43	0	29
Maximum String Length (Power Observation)	51000	530		6000	12,150
Maximum String Power (Power Observation)	Per the inverter, maximum per AC Power = 5.7/700W				
Maximum Allowed Connected Power per String ⁽¹⁾	Inverters with Rated AC Power of 4000W	530			
Maximum Allowed Connected Power per String ⁽²⁾	Inverters with Rated AC Power of 5000W	530			
Maximum Allowed Connected Power per String ⁽³⁾	Inverters with Rated AC Power of 7000W	530			
Parallel Strings of Different Lengths or Orientations	Yes				
	6000 only when connected to 277V 4-Wire (cont)				
	One string 7200 Two strings or more 7800				
					15,000

21. It is not allowed to make a phone and a second Power Opportunity in the same entry.
(7) A winning entry that has 30 competitors does not meet NEC, and unknown requirements, likely voltage will be above the 50V requirement.
(8) Please see the www.5000watt.com/5000watt.asp section page for details.
(9) For the 200V and 10V maximum is permitted only when the difference in connected power between 200V and 1000V is less than 100W.
(10) For the 200V and 277-480V grid, the maximum is permitted only when the difference in connected power between 200V and 277V is less than 100W.

[illegible]

PROJECT NAME & ADDRESS

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"

SHEET NUMBER
PV-11

HOME BACKUP

12-25
YEAR
WARRANTY



- * *For more information, contact the author at carol@carolmccall.com*

solar edge

SE3800H-US / SE5700H-US / SE7600H-US / SE10000H-US / SE11400H-US

[illegible]

© Sciencelife Technologies, LLC. All rights reserved. SCIENCElife, the Sciencelife logo, OPTIMIZED BY SCIENCElife, the Sciencelife logo, and trademarks are trademarks of Sciencelife Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: February 18, 2024 05:00:22Z NA04. Subject to change without notice.



REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/30/2025	

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

ANSI B 11" X 17" SHEET SIZE

SHEET NUMBER
PV-12

SE3800H-US / SE5700H-US / SE7600H-US / SE10000H-US / SE11400H-US

(8) Discharge power is limited up to the inverter's rated AC power for on-grid and stand-alone applications, as well as up to the installed batteries' rating.

© SpherLogic Technologies, Ltd. All rights reserved. SpherLogic, the SpherLogic logo, OPTIMIZED BY SpherLogic are trademarks or registered trademarks of SpherLogic Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: February 19, 2024. D5-000-629-00-01. Subject to change without notice.






XR Rail® Family

Tech Brief

Solar is Not Always Sunny

Over their lifetime, solar panels experience countless extreme weather events. Not just the worst storms in years, but the worst storms in 40 years. High winds capable of ripping panels from a roof, and snowfalls weighing enough to buckle a panel frame.

XR Rails® are the structural backbone preventing these results. They resist uplift, protect against buckling and safely and efficiently transfer loads into the building structure. Their superior spanning capability requires fewer roof attachments, reducing the number of roof penetrations and the amount of installation time.



Force-Stabilizing Curve

Sloped roofs generate both vertical and lateral loads on mounting rails which can cause them to buckle and pull away from the roof. XR Rail® is specifically designed to increase strength in both directions while resisting the twisting. This unique feature ensures greater security during extreme weather and a longer system lifetime.

Compatible with Flat & Pitched Roofs

XR Rails® are compatible with Flat-Roof® and other pitched roof attachments.



Corrosion-Resistant Materials

All XR Rails® are made of 6000-series aluminum alloy, then protected with an anodized finish. Anodizing prevents surface and structural corrosion, while also providing a more attractive appearance.



XR Rail® Family

Tech Brief

The XR Rail® Family offers the strength of a curved rail in three targeted sizes. Each size supports specific design loads, while minimizing material costs. Depending on your location, there is an XR Rail® to match.



XR10

XR10 is a sleek, low-profile mounting rail. Designed for use in residential applications, it features a 6" span and a 10" height. It is compatible with most solar panels and is available in black or silver.

- 6" spanning capability
- Moderate load capacity
- Black or silver anodized finish
- Internal splices available



XR100

XR100 is a medium-profile mounting rail. Designed for use in commercial applications, it features a 10" span and a 10" height. It is compatible with most solar panels and is available in black or silver.

- 10" spanning capability
- Heavy load capacity
- Black or silver anodized finish
- Internal splices available



XR1000

XR1000 is a heavyweight mounting rail. Designed for use in commercial applications, it features a 12" span and a 12" height. It is compatible with most solar panels and is available in black or silver.

- 12" spanning capability
- Extreme load capacity
- Black or silver anodized finish
- Internal splices available

Rail Selection

The table below was prepared in compliance with applicable engineering codes and standards.* Values are based on the following criteria: ASCE 7-16, Gable Roof Flush Mount, Roof Zones 1 & 2; Exposure B, Roof Slope of 8 to 20 degrees and Mean Building Height of 30 ft. Visit IronRidge.com for detailed certification letters.

Load	Rail Span						
	3'-0"	4'-0"	5'-4"	6'-0"	8'-0"	10'-0"	12'-0"
Shallow (30°)							
Wind (140 mph)							
None	90						
	120						
	140						
	180						
	90						
20	120						
	140						
	160						
	90						
30	120						
	140						
	160						
	90						
40	120						
	140						
	160						
	90						
80	120						
	140						
	160						
	90						
120	120						
	140						
	160						
	90						

*Table is meant to be a simplified guide only for conveying general rail capabilities. Use approved certification letters for actual design guidance.

TOP TIER SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2811,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	06/07/2025	

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME

EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B

11" X 17"

SHEET NUMBER

PV-14




UFO® Family of Components

Simplified Grounding for Every Application


The UFO® family of components eliminates the need for separate grounding hardware by bonding solar modules directly to IronRidge® XR Rails®. All system types that feature the UFO® family—Flush Mount®, Tilt Mount®, and Ground Mount®—are fully listed to the UL 2703 standard.

UFO® hardware forms secure electrical bonds with both the module and the rail, resulting in many parallel grounding paths throughout the system. This leads to safer and more reliable installations.

Only for installation and use with IronRidge products in accord with written instructions. See IronRidge.com/UFO



Universal Fastening Object (UFO)
The UFO® securely bonds solar modules to XR Rails®. It can be used in any orientation and can fit a wide range of module heights.



Stopper Sleeve
This sleeve secures the rail into the UFO® connecting it into a bonded end clamp.


BOSS® Splice
Bonded Structural Splice connects rails with built-in bonding tooth. No tools or hardware needed.

Grounding Lug
A single Grounding Lug connects an entire row of PV modules to the grounding conductor.

Bonded Attachments
The bonding bolt attaches end and bonds the L-locks to the rail. It is installed with the rail and is bonded to the rail of the system.

Tech Brief

System Diagram



○ UFO ● Stopper Sleeve ● Grounding Lug □ BOSS® Splice — Ground Wire

Approved Enphase microinverters can provide equipment grounding of IronRidge systems, eliminating the need for grounding lugs and field installed equipment ground conductors (EGC). A minimum of two microinverters mounted to the same rail and connected to the same Engage cable is required. Refer to installation manuals for additional details.

UL Certification

The IronRidge® Flush Mount®, Tilt Mount®, and Ground Mount Systems have been listed to UL 2703 by Intertek Group plc.

UL 2703 is the standard for evaluating solar mounting systems. It ensures these devices will maintain strong electrical and mechanical connections over an extended period of time in extreme outdoor environments.

Go to IronRidge.com/UFO

Cross-System Compatibility

Feature	Flush Mount	Tilt Mount	Ground Mount
XR Rails®	✓	✓	XR100 & XR1000
UFO®/Stopper	✓	✓	✓
BOSS® Splice	✓	✓	N/A
Grounding Lugs	1 per Row	1 per Row	1 per Array
Microinverters & Power Optimizers	Compatible with most MLPE manufacturers. Refer to system installation manual.		
Fire Rating	Class A	Class A	N/A
Modules	Tested or Evaluated with over 400 Framed Modules. Refer to installation manuals for a detailed list.		

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS	DATE	REV
DESCRIPTION	INITIAL DESIGN	06/30/2005

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST.
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B
14" X 17"

SHEET NUMBER

PV-15



QuickMount® Halo UltraGrip

Cut Sheet

Release Liner shown for reference

RD STRUCTURAL SCREW FN RD-1430-01-M1
SOLD SEPARATELY
SHOWN FOR REFERENCE

ITEM NO	DESCRIPTION	QTY IN KIT
1	QM Halo UltraGrip (Mill or Black)	1

PART NUMBER	DESCRIPTION
QM-HUG-01-M1	Halo UltraGrip - Mill
QM-HUG-01-B1	Halo UltraGrip - Black

© 2022 IronRidge, Inc. All rights reserved. Visit www.ironridge.com for product information. QM-HUG-01-B1 or QM-HUG-01-M1 Cut Sheet Rev 1.0

Cut Sheet

1. Halo UltraGrip

Dimensions: .38, 3.35, 3.83, 1.63, .40, 2.99, 1.56, $\phi .26$

Property	Value
Material	3000 Series Aluminum
Finish	Mill or Black

© 2022 IronRidge, Inc. All rights reserved. Visit www.ironridge.com for product information. QM-HUG-01-B1 or QM-HUG-01-M1 Cut Sheet Rev 1.0



TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/07/2025	

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST,
ERWIN, NC 28339

PROJECT NAME & ADDRESS

DRAWN BY
ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE
ANSI B
11" X 17"


SHEET NUMBER
PV-16



IRONRIDGE

QuickMount® RD Structural Screw


Cut Sheet



ITEM NO	DESCRIPTION	QTY IN KIT
1	Self Drilling Screw, #14, Wood Tip	1
2	Washer, EPDM Backed	1

PART NUMBER	DESCRIPTION
RD-1430-01-M1	RD Structural Screw

1. Self Drilling Screw, #14, Wood Tip



Property	Value
Material	300 Series Stainless Steel
Finish	Clear

2. Washer, EPDM Backed



Property	Value
Material	300 Series Stainless Steel
Finish	Clear

© 2022 IronRidge, Inc. All rights reserved. Visit www.ironridge.com for patent information. QM-RD-1430-01-M1 Cut Sheet Rev. 1.0

TOP TIER
SOLAR SOLUTIONS

TOP TIER SOLAR SOLUTIONS
1530 CENTER PARK DR #2911,
CHARLOTTE, NC 28217,
UNITED STATES

REVISIONS		
DESCRIPTION	DATE	REV
INITIAL DESIGN	06/30/2025	

PROJECT NAME & ADDRESS

JENNIFER LAMPLEY
RESIDENCE
501 S 11TH ST.
ERWIN, NC 28339

DRAWN BY

ESR

SHEET NAME
EQUIPMENT
SPECIFICATION

SHEET SIZE

ANSI B
11" X 17"



SHEET NUMBER

PV-17

ITEM NO.	PART NUMBER	DESCRIPTION	QTY
1	JB-12 BODY	POLYCARBONATE WITH UV INHIBITORS	1
2	JB-12 LID	POLYCARBONATE WITH UV INHIBITORS	1
3	#10 X 1-1/4" PHILLIPS PAN HEAD SCREW		6
4	#8 X 3/4" PHILLIPS PAN HEAD SCREW		6

SIZE	DWG NO.	REV
B	JB-12	
SCALE: 1:2	WEIGHT: 1.45 LBS	SHEET 1 OF 3
TORME SPECIFICATION		
15-20 LBS		
UL 1741, NEMA 3R		
CSA C22.2 NO. 290		
WEIGHT: 1.45 LBS		

SIZE	DWG NO.	REV
B	JB-12	
SCALE: 1:2	WEIGHT: 1.45 LBS	SHEET 2 OF 3



PROPRIETARY AND CONFIDENTIAL: THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF EZ SOLAR. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF EZ SOLAR IS PROHIBITED.



PROPRIETARY AND CONFIDENTIAL: THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF EZ SOLAR. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF EZ SOLAR IS PROHIBITED.

REVISIONS	DESCRIPTION	DATE	REV
INITIAL DESIGN	06/05/2025		