

TIME RECEIVED
October 11, 2018 10:35:27 AM EDT

REMOTE CSID

DURATION
43

PAGES
1

STATUS
Received

Oct. 11. 2018 10:32AM

No. 0270 P. 1

910-237-1423 Pat Godwin Coals Farmers Day Oct 12/13

ALL VENDORS SHOULD CHECK IN WITH CHAMBER STAFF (EVENT STAFF) WHO WILL BE LOCATED ON MAIN STREET FOR FINAL APPROVAL OF VENDOR LOCATION. YOU WILL BE ESCORTED TO YOUR BOOTH SPACE. **ONE FREE PARKING VOUCHER PER VENDOR.**

79		79	Bye STAGE	80		80
77		77		X		X
75		75		76		76
12' 73		73		74		74
71		71	Tables	72		72
69		69	Tables	70		70
67	T 10X10	67	Tables	68	TRAILOR	68
65		65		66	T 10X10	66
63	T 10X10	63		X 64	T- 20X10	X 64
61	T 10X10	61		X 62		X 62
12' 59	RAILROAD STREET	59	CHAMBER	60		60
X 57	TRAILOR	X 57		58	RAILROAD STREET	58
55		55		56	T 10X10	56
53	T 10X10	53		54	T 10X10	54
12' 51		51		52		52
X 49	T 10X10	X 49		50	KIDS PARK	50
X 47	TRAILOR	X 47		48	T 10X10	48
X 45		X 45		46	T 10X10	46
24' 43		43		44		44
41		41		42	T 10X10	42
39	T 10X10	39		40	T 10X10	40
37	T 10X10	37		38		38
X 35	T 10X10	X 35		X 36		X 36
X 33	T 10X10	X 33		X 34	T 10X10	X 34
31		31		32	T 10X10	32
29		29		30	T 10X10	30
27		27		28	T 10X10	28
12' 25		25		26	T 10X10	26
X 23	TRAILOR	X 23		X 24	T 10X10	X 24
X 21		X 21		22		22
19	T 10X10	19		20	T 10X10	20
17	T 10X10	17		X 18	T 10X10	X 18
X 15	T 10X10	X 15		X 16	TRAILOR	X 16
X 13	TRAILOR	X 13		X 14		X 14
11		11		12		12
9	T 10X10	9		10	T 10X10	10
7	T 10X10	7		8	T 10X10	8
5	T 10X10	5		6	T 10X10	6
3	T 10X10	3		4	T 10X10	4
X 1	T 10X10	X 1		2		2

Each number is 12'

X Power X Breaks
12 + 24'

TIME RECEIVED
October 11, 2018 10:36:09 AM EDT

REMOTE CSID

DURATION
27

PAGES
1

STATUS
Received

Oct. 11. 2018 10:33AM

No. 0271 P. 1/1

LEMON STREET					M A I N . S T R E E T
<u>DEPOT</u>					
91	89	87	85	83 & 81 91 X	
				TRAILER	
			94		
92	90	88	86 80	84 & 82 92 X	
			T 10X10	T 10X10	



Fire Marshal Division

October 11, 2018

Pat Godwin
147 South McKinley Street
Coats, NC. 27521

Coats Farmer's Day **Re: Application Number – FMFW1810-0006**

Ms. Godwin,

Thank you for submitting the plans for the Coats Farmer's Day event. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **Permits**
 - A permit will be issued for the special assembly that will include the event as a whole.
 - A permit may be issued for other tent areas if the individual tent exceeds 700 square feet or the aggregate area of multiple canopies placed side by side without a fire break clearance of 12'

- **Fire Extinguishers**
 - Portable fire extinguishers shall be provided within a 30-foot (9144 mm) travel distance of commercial-type cooking equipment. Cooking equipment involving vegetable or animal oils and fats shall be protected by a Class K rated portable extinguisher.
 - 2A-10B:C fire extinguisher shall be placed at tents/canopies with a travel distance not to exceed 100' from any fire extinguisher

- **2411.6 Outdoor cooking.**
 - Outdoor cooking that produces sparks or grease-laden vapors shall not be performed within 20 feet (6096 mm) from a tent, air-supported, air-inflated or tensioned membrane structure, temporary membrane structure or canopy



- **2411.5 Cooking tents.**
 - Tents where cooking is performed shall be separated from other tents, air-supported, air-inflated or tensioned membrane structures, temporary membrane structures or canopies by a minimum of 20 feet (6096 mm).

- **2415 Generators**
 - Generators and other internal combustion power sources shall be separated from tents, air-supported, air-inflated or tensioned membrane structures, temporary membrane structures or canopies by a minimum of 20 feet (6096 mm) and shall be isolated from contact with the public by fencing, enclosure or other approved means.

- **2413.3 Refueling.**
 - Refueling shall be performed in an approved location not less than 20 feet (6096 mm) from tents, air-supported, air-inflated or tensioned membrane structures, temporary membrane structures or canopies.

- **Permits**
 - Final inspection will be conducted the day of the event and the permit will be issued after inspection.

Thank you again for submitting the plans for the Coats Farmer's Day event. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Sincerely,



D. Banks Wallace
Chief Deputy Fire Marshal