



**1 ELECTRICAL DEMOLITION PLAN**  
 E2 3/32=1'-0"

- KEYED NOTES:**
- 1 EC SHALL REMOVE LIGHTS THIS AREA.
  - 2 EXISTING LIGHTS SHALL REMAIN THIS AREA.
  - 3 REMOVE 240V. DISCONNECTS, CONDUIT AND WIRE THIS LOCATION.
  - 4 REMOVE 240V., 1PH. PANEL, TO BE REPLACED WITH NEW 240V., 1PH. PANEL.
  - 5 REMOVE 240V., 1PH. PANEL, CONDUIT AND WIRE BACK TO SOURCE.
  - 6 REMOVE EXISTING FACP AND FIRE ALARM DEVICES.
  - 7 REMOVE EXISTING DISCONNECT, CONDUIT AND WIRE FEEDING EXISTING WATER HEATER BACK TO SOURCE.

- DEMOLITION NOTES:**
1. ANY ITEMS REMOVED SHALL BE OFFERED TO THE OWNER. THE OWNER MAY RETAIN ANY ITEM REMOVED. ANY ITEM THAT THE OWNER DOES NOT RETAIN BECOMES THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE.
  2. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR PATCHING ANY HOLES IN REMAINING WALLS RESULTING FROM THE REMOVAL OF ELECTRICAL DEVICES.
  3. WHERE CONDUITS ARE CONCEALED IN EXISTING WALLS OR FLOORS NOT SUBJECT TO REMOVAL, THE CONTRACTOR MAY ABANDON THE CONDUIT BUT SHALL REMOVE ALL EQUIPMENT AND WIRING. PROVIDE BLANK STAINLESS STEEL FACEPLATES TO COVER EMPTY JUNCTION BOXES.
  4. REMOVE ALL ELECTRICAL DEVICES, WHETHER SHOWN ON PLANS OR NOT, WHICH ARE LOCATED IN WALLS SUBJECT TO REMOVAL OR IN AREAS SPECIFICALLY REFERRED TO IN NOTES.
  5. THE ELECTRICAL CONTRACTOR SHALL MAINTAIN ALL CIRCUIT CONTINUITY TO ALL REMAINING CIRCUITS IN AREAS WHERE PART, BUT NOT ALL, OF THE CIRCUIT IS BEING REMOVED.
  6. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR VISITING THE SITE PRIOR TO THE BID TO DETERMINE FIELD CONDITIONS AND TO FIELD VERIFY THE EXTENT OF THE DEMOLITION WORK.

REVISIONS	
No.	DATE
1	3/7/19

A RENOVATION FOR:  
**SHAWTOWN SCHOOL**  
 HARNETT COUNTY  
 695 SHAWTOWN ROAD  
 LILLINGTON, NORTH CAROLINA

Project No:  
 2018-009  
 Scale:  
 Date Drawn: 1/29/19  
 Sheet Title

ELECTRICAL DEMOLITION PLAN