



Permit Reviews

Harnett County

Permit Number: **FMFW2106-0002**

Description: **Tank Installations**

Applied: **6/3/2021**

Approved:

Site Address: **2201 NC 24-87**

Issued:

Finalized:

City, State Zip Code: **CAMERON, NC 28326**

Status: **RECEIVED**

Applicant: **Commercial Permit Expediting LLC**

Parent Permit: **BCOM2103-0004**

Owner: **PTM LP**

Parent Project:

Contractor: **Guardian Fueling Technologies**

Details:

LIST OF REVIEWS

SENT DATE	RETURNED DATE	DUE DATE	TYPE	CONTACT	STATUS	REMARKS
Review Group: AUTO						
6/3/2021	6/7/2021	6/13/2021	FIRE MARSHAL	Leslie Jackson	DISAPPROVED	See Notes

Notes:

1 -Sets of plans shall be submitted for review. Plans shall indicate the following:

- a. Site plan indicating the exact placement of tank(s) with setbacks from buildings and lot lines.
- b. Indicate the type of product that will be stored in the tank(s).
- c. Description and specs on tank that notes their UL listing and containment type.
- d. Description and spec sheets on all piping and appurtenances attached to the tank(s).
- e. A copy of the appropriate NCDENR forms and information for the engineer of record shall be included with the storage tank submittal.

2. Storage Tank Inspections - Before being covered, the following inspections are required to be conducted by a fire code official:

- a. Witness of tank/secondary containment pressure test
- b. Witness of piping system pressure test.
- c. Visual inspection of tank anchoring methods.
- d. Visual inspection of fill material surrounding tank(s).
- e. The tank(s) and piping system shall not be covered unless it has been approved.
- f. The dispensing equipment and leak detection system will be inspected during the final inspection of the occupancy.

