


KEYNOTES

- 1 PROGRAMMABLE THERMOSTAT WITH REMOTE TEMPERATURE AND HUMIDITY SENSORS. REF ENERGY MANAGEMENT SYSTEM DRAWING.
- 2 ROUTE ALL DUCTWORK WITHIN THE JOISTS UNLESS OTHERWISE SPECIFIED (TYPICAL).
- 3 PROVIDE CO2 DETECTOR AND ALARM. MOUNT 12" AFF. SEE SHEET M1.5 FOR DETAIL OF CO2 DETECTOR AND ALARM.
- 4 ROUTE 10"x10" DUCT UP TO ROOF MOUNTED EXHAUST FAN. ROOF OPENING SHALL BE 12.5"x12.5". SEE MECHANICAL - SCHEDULES SHEET FOR EXHAUST FAN INFO
- 5 12" EXHAUST DUCT UP THRU ROOF TO EXHAUST FAN.
- 6 PROVIDE COPPER DRAIN LINES FROM COOLER/FREEZER EVAPORATORS. VERIFY LOCATIONS WITH REFRIGERATION PLANS (EVAPORATORS PROVIDED BY C/O OTHERS.)
- 7 REMOTE TEMPERATURE SENSOR IN RETURN AIR DUCT.
- 8 SMOKE DETECTOR FOR UNIT SHUT-DOWN TO BE FACTORY INSTALLED BY MANUFACTURER.
- 9 FULL SIZE SUPPLY & RETURN AIR DUCTS DOWN THRU ROOF FROM ROOFTOP PACKAGE UNIT.
- 10 CO2 LOUVRED CABINET. SEE SHEET M1.4 FOR DETAIL.
- 11 CONDENSING UNIT FOR REFRIGERATION EQUIPMENT BY VENDOR SHOWN FOR REFERENCE ONLY. MOUNTED ON COOLER ROOF OR GROUND AS SHOWN.
- 12 COPPER DRAIN LINE FROM COOLERS AND FREEZER EVAPORATORS THRU WALL AT 12" AFF TO ADJACENT GREENSPACE. PROVIDE HEAT TAPE TO CONDENSATE LINES EXPOSED TO FREEZING. PROVIDE RUNNING TRAP INSIDE TO PROTECT FROM PEST ENTRY
- 13 EXTERIOR ROOF ACCESS.

GENERAL NOTES

- A. EQUIPMENT SHALL COMPLY WITH ASHRAE STANDARDS.
- B. ALL WORK SHALL COMPLY WITH ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, LAWS, ACTS, AND AUTHORITIES HAVING JURISDICTION.
- C. THE COMPLETED INSTALLATION SHALL BE IN ACCORDANCE WITH ALL APPLICABLE INDUSTRY STANDARD OF GOOD PRACTICE AND SAFETY, AND THE MANUFACTURER'S STRICTEST RECOMMENDATIONS FOR EQUIPMENT AND PRODUCT APPLICATION AND INSTALLATION.
- D. ALL WORK SHALL BE LOCATED TO PROVIDE ADEQUATE CLEARANCE FOR ARCHITECTURAL DESIGN AND PROPER OPERATION AND SERVICE OF EQUIPMENT.
- E. ALL WORK SHALL BE LOCATED TO AVOID CONFLICTS WITH OTHER TRADES. CLOSELY COORDINATE ALL WORK WITH ALL OTHER TRADES. FAILURE OF THE CONTRACTOR TO COORDINATE WITH ALL OTHER TRADES SHALL RELIEVE THE OWNER/ENGINEER FROM ANY ADDED COSTS.



MECHANICAL FLOOR PLAN | 1
3/16" = 1'-0"



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ ISSUE	DATE
OTP	02/15/23

PROFESSIONAL IN


JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA
PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTCYCLE# R1.2 12/XX/22



CIRCLE K STORE
PROJECT NUMBER: 22130

MECHANICAL - FLOOR PLAN

M1.1

GENERAL NOTES

- A. EQUIPMENT SHALL COMPLY WITH ASHRAE STANDARDS.
- B. ALL WORK SHALL COMPLY WITH ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, LAWS, ACTS, AND AUTHORITIES HAVING JURISDICTION.
- C. THE COMPLETED INSTALLATION SHALL BE IN ACCORDANCE WITH ALL APPLICABLE INDUSTRY STANDARD OF GOOD PRACTICE AND SAFETY, AND THE MANUFACTURER'S STRICTEST RECOMMENDATIONS FOR EQUIPMENT AND PRODUCT APPLICATION AND INSTALLATION.
- D. ALL WORK SHALL BE LOCATED TO PROVIDE ADEQUATE CLEARANCE FOR ARCHITECTURAL DESIGN AND PROPER OPERATION AND SERVICE OF EQUIPMENT.
- E. ALL WORK SHALL BE LOCATED TO AVOID CONFLICTS WITH OTHER TRADES. CLOSELY COORDINATE ALL WORK WITH ALL OTHER TRADES. FAILURE OF THE CONTRACTOR TO COORDINATE WITH ALL OTHER TRADES SHALL RELIEVE THE OWNER/ENGINEER FROM ANY ADDED COSTS.

KEYNOTES

- 1 ROOFTOP EXHAUST FAN INSTALLED ON FACTORY CURB ON ROOF.
- 2 SATELLITE DISH SHOWN FOR REFERENCE ONLY. REFER TO ARCHITECTURAL DRAWINGS FOR INFO.
- 3 EXTERIOR ROOF ACCESS SHOWN FOR REFERENCE ONLY. REFER TO ARCHITECTURAL DRAWINGS FOR MORE INFORMATION.
- 4 PROVIDE MINIMUM 10'-0" SEPARATION FROM OUTSIDE AIR INTAKES ON HVAC UNITS.
- 5 ROOFTOP HVAC UNIT INSTALLED ON FACTORY CURB ON ROOF.
- 6 VTR'S SHOWN FOR REFERENCE ONLY. REFER TO PLUMBING DRAWINGS FOR MORE INFORMATION. PROVIDE MINIMUM 10'-0" SEPARATION FROM OUTSIDE AIR INTAKES ON HVAC UNITS.
- 7 ROOF HOSE BIB REFERENCE PLUMBING SHEETS.

rdc.

11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional


PROFESSIONAL

Jason M. Scates
P.E.

SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

△ ISSUE	DATE
OTP	02/15/23



MECHANICAL ROOF PLAN | 1
3/16" = 1'-0"

PROFESSIONAL IN

JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA


PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC


PROTCYCLE# R1.2 12/XX/22



CIRCLE K STORE
PROJECT NUMBER: 22130


MECHANICAL - ROOF PLAN

M1.1.1




BRACKETS ARE FURNISHED WITH RTU BRACKET CONSTRUCTION, QUANTITIES, AND SPACING SHOWN ON THIS DETAIL IS FOR GENERAL COORDINATION ONLY. INSTALL BRACKETS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS. COORDINATE FINAL BRACKET LOCATIONS WITH EQUIPMENT. DO NOT OBSTRUCT OPENINGS OR UTILITY CONNECTIONS.

RTU ANCHOR BRACKET DETAIL | 9
N.T.S.



REFER TO SMACNA HVAC DUCT CONSTRUCTION STANDARDS TABLE 4-1 FOR "RECTANGULAR DUCT HANGERS MINIMUM SIZE".


RECTANGULAR DUCT HANGER DETAIL | 6
N.T.S.



NOTES:

- CONDENSATE DRAIN LINES SHALL BE GRADED CONTINUOUSLY AND UNIFORMLY TO POINT OF DISCHARGE. MINIMUM OF 1/8" PER FOOT.
- CONDENSATE DRAIN LINES SHALL BE TYPE "M" HARD DRAWN COPPER TUBING ASTM B-88, UNO.
- GENERAL CONTRACTOR TO SUPPLY AND INSTALL ALL CONDENSATE DRAINS PER MANUFACTURER'S RECOMMENDATIONS.
- INSULATE PRIMARY COIL CONDENSATE INSIDE BUILDING IN ACCORDANCE WITH SHEET SPECIFICATIONS


CONDENSATE DRAIN TRAP DETAIL | 3
N.T.S.



NOTES:


- "LOW FLOW" TYPE DUCT SMOKE DETECTOR MOUNTED ON THE RETURN AIR DUCT WHERE SHOWN. FURNISHED, INSTALLED, AND CONTROL WIRING BY MECHANICAL CONTRACTOR. POWER WIRING BY ELECTRICAL/FIRE ALARM CONTRACTOR. SEE PLANS FOR ALL LOCATIONS. PROVIDE REMOTE VISIBLE AND AN AUDIBLE SIGNAL ALONG WITH LED BELOW CEILING AS REQUIRED PER 2018 NC MECH CODE AND NFPA.
- MECHANICAL CONTRACTOR SHALL FURNISH, INSTALL, AND PROVIDE WIRING TO HVAC UNIT TO SHUT DOWN UNIT UPON DETECTION OF SMOKE. MECHANICAL CONTRACTOR SHALL PROVIDE ALL NECESSARY RELAYS, CONTRACTORS, POWER MODULES, ETC. AS NECESSARY TO PROVIDE A COMPLETE OPERATIONAL SYSTEM. COORDINATE WITH ELECTRICAL/FIRE ALARM CONTRACTOR TO VERIFY VOLTAGE REQUIREMENTS, LOCATIONS, ETC.
- ELECTRICAL/FIRE ALARM CONTRACTOR SHALL PROVIDE WIRING IF FIRE DETECTION OR ALARM SYSTEMS ARE PROVIDED FOR THE BUILDING, THE SMOKE DETECTORS SHALL BE SUPERVISED BY SUCH SYSTEMS.
- SMOKE DETECTORS REQUIRED BY 2018 NCMC SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 72. DUCT SMOKE DETECTORS REQUIRE A REMOTE LED INDICATOR THRU THE CEILING LEVEL. NFPA 72 5-8.3. DUCT SMOKE DETECTORS SHALL ACTIVATE A VISIBLE AND AUDIBLE SIGNAL AT A NORMALLY OCCUPIED LOCATION AND SHALL BE MONITORED BY THE FACP AND REPORT AS A SUPERVISORY SIGNAL PER NFPA 72 AND THE 2018 NC MECH CODE. DUCT SMOKE DETECTORS TO PROVIDE SHUTDOWN IN 30 SECONDS OR LESS.

DUCT SMOKE DETECTOR CONNECTION DETAIL | 2
N.T.S.




NOTE:
1. FABRICATE PER SMACNA DUCT CONSTRUCTION STANDARDS FIGURE #2-8.
2. DO NOT USE EXTRACTORS IN BRANCH DUCTWORK.

DUCT CONNECTION | 8
N.T.S.




NOTE: RADIUS ELBOWS WITH MITERED THROAT ARE NOT ALLOWED

DUCT ELBOW DETAILS | 5
N.T.S.




REFER TO SMACNA HVAC DUCT CONSTRUCTION STANDARDS TABLE 4-2 FOR "MINIMUM HANGER SIZES FOR ROUND DUCT".

ROUND DUCT HANGER DETAIL | 7
N.T.S.



NOTE: INSTALL EQUIPMENT PER MANUFACTURERS RECOMMENDATIONS

POWER ROOF EXHAUSTER DETAIL | 4
N.T.S.



ROOF-TOP PACKAGE UNIT DETAIL | 1
N.T.S.



COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ	ISSUE	DATE
OTF		02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA

PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTCYCLE# R1.2 12/XX/22




CIRCLE K STORE


PROJECT NUMBER: 22130

MECHANICAL -
DETAILS (2 OF 2)

M1.2.1



DIFFUSER/GRILLE CONNECTION DETAIL | 2
N.T.S.



REFRIGERANT LINE GOOSENECK DETAIL | 1
N.T.S.



OUTSIDE AIR CALCULATION									
OUTSIDE AIR REQUIREMENTS PER TABLE 403.3 AND 403.3.1.2, 2018 NCMC									
NAME	AREA	# PEOPLE/ 1000 FT²	NUMBER OF PEOPLE	OUTDOOR AIR PER PERSON	OUTDOOR AIR PER AREA	PEOPLE LOAD REQUIRED (PLR) OSA	BUILDING LOAD REQUIRED (BLR) OSA	SYSTEM EFFICIENCY VALUE	TOTAL OSA REQUIRED [(PLR+BLR)/SYSTEM EFFICIENCY]
RTU1									
CASHIER	201 SF	15	3	7.5 CFM	0.12 CFM/SF	23 CFM	24 CFM	0.8	58 CFM
HALLWAY	60 SF	9	1	0.0 CFM	0.06 CFM/SF	0 CFM	4 CFM	0.8	5 CFM
MEN'S RESTROOM	131 SF		0	0.0 CFM	0.00 CFM/SF	0 CFM	0 CFM	0.8	0 CFM
SALES FLOOR-1	959 SF	15	14	7.5 CFM	0.12 CFM/SF	108 CFM	115 CFM	0.8	279 CFM
WOMEN'S RESTROOM	133 SF		0	0.0 CFM	0.00 CFM/SF	0 CFM	0 CFM	0.8	0 CFM
	1483 SF		18			130 CFM	143 CFM		341 CFM
RTU2									
BACK ROOM	279 SF	15	4	7.5 CFM	0.12 CFM/SF	31 CFM	33 CFM	0.8	81 CFM
PREP AREA	161 SF	15	2	7.5 CFM	0.12 CFM/SF	18 CFM	19 CFM	0.8	47 CFM
SALES FLOOR-2	979 SF	15	15	7.5 CFM	0.12 CFM/SF	110 CFM	117 CFM	0.8	284 CFM
	1418 SF		21			160 CFM	170 CFM		412 CFM
TOTALS	2902 SF		39			290 CFM	313 CFM		754 CFM

AIR BALANCE SCHEDULE				
MARK	O.A.	E.A.	PRESSURE	
EF 1	0	250 CFM	-250 CFM	
EF 2	0	400 CFM	-400 CFM	
RTU1	350	0 CFM	350 CFM	
RTU2	425	0 CFM	425 CFM	
TOTAL EXHAUST	775	650 CFM	125 CFM	

2018 NCECC LOAD SUMMARY				
AREA	COOLING LOAD CALCULATION (MBH)		PROVIDED EQUIPMENT COOLING CAPACITY (MBH)	
	SENSIBLE	TOTAL	SENSIBLE	TOTAL
RTU1	29.6	47.8	31.7	47.3
RTU2	30.2	47.5	41.3	59.9

- NOTES:
- CALCULATIONS WERE PERFORMED WITH REVIT MODEL SOFTWARE PROGRAM IN COMPLIANCE WITH ASHRAE FUNDAMENTALS.
 - EQUIPMENT SIZING MEETS THE IECC 403.2.2 REQUIREMENTS
 - ALL MECHANICAL AIR CONDITIONING EQUIPMENT TO HAVE MINIMUM EFFICIENCY RATING PER 2018 NCECC, TABLE C403.2.3. SUBMIT MECHANICAL AC EQUIPMENT TO OWNER OR ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ORDER.

ROOFTOP UNIT SCHEDULE																	
MARK	MANUFACTURER	MODEL	SUPPLY FAN			COOLING CAPACITY	COOLING ENTERING DRY BULB TEMPERATURE	COOLING ENTERING WET BULB TEMPERATURE	OUTSIDE AIR CFM	WEIGHT	ELECTRICAL DATA				ELEC HEAT		
			CFM	ESP (IN.)	HP						VOLTS	PH	HZ	MCA	MOC	KW	STAGES
RTU1	CARRIER	50GC	1,200	0.75	1.06	4.0 ton	80 °F	67 °F	350	555 lbf	208	3	60 Hz	48	50	12.0	2
RTU2	CARRIER	50GC	1,500	0.75	1.06	5.0 ton	80 °F	67 °F	425	736 lbf	208	3	60 Hz	39	45	7.9	2

- NOTES:
- SIZE ALL UNITS ON SUMMER AMBIENT TEMPERATURE: 95° F.
 - VERIFY VOLTAGE/PHASE WITH ELECTRICAL CONTRACTOR PRIOR TO ORDERING.
 - COOLING CAPACITY, MINIMUM HEAT CAPACITY AND CFM ARE MINIMUM OUTPUT REQUIRED. ALL UNITS SHALL HAVE NO LESS THAN 98% OF THESE CAPACITIES. COOLING CAPACITY IS GROSS COIL CAPACITY REQUIRED (FAN HEAT NOT DEDUCTED).
 - UNITS TO BE FURNISHED WITH FACTORY INSTALLED RETURN AIR SMOKE DETECTORS FOR THE ROOM OR SPACE IN WHICH THE SMOKE IS GENERATED PER IMC SECTION 606.2.
 - PROVIDE 14" ROOF MOUNTING CURB, FILTERS AND FILTER RACK SIZED AT 500 FPM VELOCITY. VERIFY INSULATION HEIGHT.
 - PROVIDE WITH PROGRAMMABLE HUMIDISTAT AND THERMOSTAT WITH REMOTE SENSOR FOR RTU1 AND RTU2.
 - PROVIDE RTU1 & RTU2 WITH AUXILIARY HEATER.
 - PROVIDE WITH HAIL GUARDS.
 - PROVIDE FACTORY INSTALLED DISCONNECT.
 - PROVIDE WITH UNPOWERED GFCI CONVENIENCE OUTLET.
 - PROVIDE HUMIDI-MIZER OPTION.
 - PROVIDE CONDENSATE OVERFLOW SHUTDOWN SWITCH.

AIR DEVICE SCHEDULE					
MARK	DESCRIPTION	MANUFACTURER	MODEL	FRAME	MATERIAL-MODULE
A	SA	TITUS	TMSA	LAY-IN	STEEL 24X24
B	EA	TITUS	23R	LAY-IN	STEEL 24X24
C	SA	TITUS	TDC	SURFACE MOUNT	STEEL12X12
E		RUSKIN	CDP-16	LAY-IN	ALUM 24X48
F	EA	TITUS	23R	SURFACE MOUNT	STEEL12X12
G	TA	TITUS	23R	LAY-IN	STEEL 24X24

- NOTE:
- FIELD PAINT ALL DIFFUSERS AND GRILLES - COLOR WHITE
 - SA=SUPPLY AIR
 - EA=EXHAUST AIR
 - RA=RETURN AIR
 - TA=TRANSFER AIR
 - NO DESCRIPTION = CONCENTRIC DIFFUSER
 - SUPPLY AND RETURN CONNECTIONS MATCH NECK SIZE.
 - PROVIDE VOLUME / BALANCE DAMPERS.
 - ROUND (MANUFACTURER / MODEL): RUSKIN / MDRS25, DAYTON / 2TF (OR EQUIVALENT)
 - RECTANGULAR (MANUFACTURER / MODEL): RUSKIN / MD25, DAYTON / 22CV (OR EQUIVALENT)
 - PROVIDE DIFFUSER TO DUCT CONNECTION TRANSITION AS REQUIRED.

EXHAUST FAN SCHEDULE											
Mark	AREA SERVED	MANUFACTURER	MODEL	FLOW	ESP	MOTOR				WEIGHT	DRIVE
						POWER	VOLTAGE	PH	HZ		
EF 1	RESTROOMS	GREENHECK	G-090-E	250 CFM	0.20 in-wg	0.040 hp	120 V	1	60 Hz	22.00 lb	DIRECT
EF 2	PREP AREA	GREENHECK	CUE-080-E	400 CFM	0.25 in-wg	0.100 hp	120 V	1	60 Hz	33.00 lb	DIRECT

- NOTES:
- EF 1 SHALL BE PROVIDED WITH BACKDRAFT DAMPER, FACTORY ROOF CURB.
 - EF 2 SHALL PROVIDED WITH BACKDRAFT DAMPER, FACTORY ROOF CURB, SPEED CONTROLLER. FAN SHALL BE UL LISTED. INSTALL FAN LEVEL. FAN CONTROLLED FROM LINE VOLTAGE THERMOSTAT PROVIDED BY ELECTRICAL. COORDINATE TEMPERATURE SETTING WITH OWNERS REPRESENTATIVE

rdc.

11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL

Jason M. Scates
P.E.

SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

△ ISSUE DATE

OTP 02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA


PROJECT

CIRCLE K
STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH
ROAD,
ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE

PROJECT NUMBER: 22130

MECHANICAL -
SCHEDULES

M1.2.2


ABBREVIATIONS	
ABBR	DESCRIPTION
AC	AIR CONDITIONING UNIT
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
AL	ACOUSTICAL LINING
AMP	AMPERE (AMPS)
AP	ACCESS PANEL
BF	BELOW FLOOR
BHP	BRAKE HORSE POWER
BOD	BOTTOM OF DUCT
BOP	BOTTOM OF PIPE
BTU	BRITISH THERMAL UNIT
BTUH	BTU PER HOUR
BD	BACKDRAFT DAMPER
C	CELSIUS
CI	CAST IRON
CFM	CUBIC FEET PER MINUTE
CO	CLEANOUT
CONT.	CONTINUATION
D	DRAIN
Db	DECIBEL
DB	DRY BULB
DBT	DRY BULB TEMPERATURE
DIA.	DIAMETER
DX	DIRECT EXPANSION
EFF	EFFICIENCY
ENT	ENTERING
EXH	EXHAUST
EMS	ENERGY MANAGEMENT SYSTEM
F	DEGREES FAHRENHEIT
FB	FLAT BOTTOM
FCO	FLOOR CLEANOUT
FCU	FAN COIL UNIT
FD	FLOOR DRAIN
FD	FIRE DAMPER
F.G.	FILTER GAUGE
FLEX	FLEXIBLE
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FS	FLOOR SINK
FT	FLAT TOP
FT.	FEET
FSD	FIRE/SMOKE DAMPER
GA	GAUGE
GAL	GALLONS
GPM	GALLONS PER MINUTE
GPH	GALLONS PER HOUR
HB	HOSE BIBB
HD	HAND DAMPER (VOLUME DAMPER)
HORZ	HORIZONTAL
HP	HORSEPOWER
HR	HOUR(S)
IN	INCHES
KVA	KILOVOLT-AMPERE
KW	KILOWATT
KWH	KILOWATT HOUR
LBS	POUNDS
MAX	MAXIMUM
MA	MAIN AIR (CONTROLS)
MCC	MOTOR CONTROL CENTER
MIN	MINIMUM
N/A	NOT APPLICABLE
NC	NOISE CRITERIA
NC	NOT IN CONTRACT
#,NO.	NUMBER (QUANTITY)
NO	NORMALLY OPEN
NC	NORMALLY CLOSED
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OBD	OPPOSED BLADE DAMPER
PRV	PRESSURE REDUCING VALVE
PSI	POUNDS PER SQUARE INCH
PSIG	POUNDS PER SQUARE INCH GAUGE
PD	PRESSURE DROP
QTY	QUANTITY
QUAD	QUADRANT
RA	RETURN AIR
REQ	REQUIRED
RH	RELATIVE HUMIDITY
RM	ROOM
RPM	REVOLUTIONS PER MINUTE
SA	SUPPLY AIR
SCD	SMOKE CONTROL DAMPER
S.DPR.	SMOKE DAMPER
SP	STATIC PRESSURE (INCHES OF WATER)
SPEC	SPECIFICATION
SQ	SQUARE
SDVV	SINGLE DUCT VARIABLE VOLUME
ST	SOUND TRAP
TEMP	TEMPERATURE
TSTAT	THERMOSTAT
TP	TOTAL PRESSURE (INCHES OF WATER)
TYP	TYPICAL
UC	UNDERCUT
UNO	UNLESS NOTED OTHERWISE
V	VOLTS
VAC	VOLTS, ALTERNATING CURRENT
VAV	VARIABLE AIR VOLUME
VEL	VELOCITY
VERT	VERTICAL
VTR	VENT THRU ROOF
WB	WET BULB
WCO	WALL CLEANOUT


ABBREVIATIONS	
ABBR	DESCRIPTION
WH	WALL HYDRANT
Z	ZONE
PIPING FLOWSTREAM ID	
SYMBOL	DESCRIPTION
D	DRAIN LINE
CD	CONDENSATE DRAIN
SCD	SECONDARY CONDENSATE DRAIN
PIPE FITTING SYMBOLS	
SYMBOL	DESCRIPTION
X	ANCHOR
ANCHOR WALL	ANCHOR, WALL
BLIND FLANGE	BLIND FLANGE
DROP AT END	DROP AT END
DROP AT MID	DROP AT MID
TOP CONNECTION, 45° OR 90°	TOP CONNECTION, 45° OR 90°
BOTTOM CONNECTION, 45° OR 90°	BOTTOM CONNECTION, 45° OR 90°
TEE CONNECTION	TEE CONNECTION
CAPPED OUTLET	CAPPED OUTLET
PIPE CAP	PIPE CAP
RISE IN PIPE	RISE IN PIPE
PIPE GUIDES	PIPE GUIDES
PIPE PLUG	PIPE PLUG
FLEX CONNECTION	FLEX CONNECTION
FLEX PIPE	FLEX PIPE
PRESSURE GAGE W/O COCK	PRESSURE GAGE W/O COCK
PRESSURE GAUGE W/ COCK	PRESSURE GAUGE W/ COCK
REDUCER OR INCREASER	REDUCER OR INCREASER
ECCENTRIC REDUCER	ECCENTRIC REDUCER
STRAINER	STRAINER
STRAINER, FLANGED	STRAINER, FLANGED
SWITCH, FLOW	SWITCH, FLOW
SWITCH, PRESSURE	SWITCH, PRESSURE
SWITCH, TEMPERATURE	SWITCH, TEMPERATURE
TEST & PRESSURE (T&P) FITTING	TEST & PRESSURE (T&P) FITTING
THERMOMETER	THERMOMETER
UNION	UNION
ORIFICE UNION	ORIFICE UNION
FLANGED UNION	FLANGED UNION
SLOPE IN DIRECTION SHOWN (DOWN)	SLOPE IN DIRECTION SHOWN (DOWN)
DIRECTION OF FLOW	DIRECTION OF FLOW
NEW PIPING	NEW PIPING
EXISTING PIPING TO REMAIN	EXISTING PIPING TO REMAIN
EXISTING PIPING TO BE REMOVED	EXISTING PIPING TO BE REMOVED
NEW PIPE CONNECTION TO EXISTING PIPING	NEW PIPE CONNECTION TO EXISTING PIPING
POINT OF NEW CONNECTION TO EXISTING	POINT OF NEW CONNECTION TO EXISTING
ANNOTATION SYMBOLS	
SYMBOL	DESCRIPTION
KEYED NOTE	KEYED NOTE
ROOM NUMBER	ROOM NUMBER
SYMBOL INDICATES NEW EQUIPMENT NUMBER REFERS TO SPECIFIC EQUIPMENT OUTSIDE AIR CFM REQUIRED	SYMBOL INDICATES NEW EQUIPMENT NUMBER REFERS TO SPECIFIC EQUIPMENT OUTSIDE AIR CFM REQUIRED
HEX SYMBOL INDICATES NEW EQUIPMENT NUMBER REFERS TO SPECIFIC EQUIPMENT IDENTIFIED IN EQUIPMENT SCHEDULE	HEX SYMBOL INDICATES NEW EQUIPMENT NUMBER REFERS TO SPECIFIC EQUIPMENT IDENTIFIED IN EQUIPMENT SCHEDULE
REVISION TRIANGLE REVISION NUMBER	REVISION TRIANGLE REVISION NUMBER
DETAIL NUMBER DETAIL SYMBOL DRAWING WHERE DETAIL APPEARS	DETAIL NUMBER DETAIL SYMBOL DRAWING WHERE DETAIL APPEARS
SECTION LETTER SECTION CUT SYMBOL	SECTION LETTER SECTION CUT SYMBOL
SECTION LETTER SECTION CUT SYMBOL DRAWING WHERE SECTION APPEARS	SECTION LETTER SECTION CUT SYMBOL DRAWING WHERE SECTION APPEARS
NORTH ARROW	NORTH ARROW
POINT OF NEW CONNECTION TO EXISTING	POINT OF NEW CONNECTION TO EXISTING
FLOW ARROWS	FLOW ARROWS
VALVE SYMBOL INDICATES A CONTROL VALVE V NUMBER REFERS TO A SPECIFIC VALVE IDENTIFIED IN THE CONTROL VALVE SCHEDULE	VALVE SYMBOL INDICATES A CONTROL VALVE V NUMBER REFERS TO A SPECIFIC VALVE IDENTIFIED IN THE CONTROL VALVE SCHEDULE

DUCTWORK SYMBOLS	
SYMBOL	DESCRIPTION
12x8	RECTANGULAR DUCT, WIDTH x DEPTH (INCHES)
120	ROUND DUCT (INCHES)
12x80	OVAL DUCT (INCHES)
12x8 W/1"AL	FLEXIBLE DUCT
ACOUSTICAL DUCT LINING	ACOUSTICAL DUCT LINING
FLEXIBLE CONNECTION	FLEXIBLE CONNECTION
SUPPLY DUCT - SECTION/ END VIEW	SUPPLY DUCT - SECTION/ END VIEW
RETURN DUCT - SECTION/ END VIEW	RETURN DUCT - SECTION/ END VIEW
EXHAUST DUCT - SECTION/ END VIEW	EXHAUST DUCT - SECTION/ END VIEW
CROSS SECTION THROUGH ROUND DUCT	CROSS SECTION THROUGH ROUND DUCT
VANED ELBOW (PROVIDE ALL SQUARE OR RECTANGULAR ELBOWS WITH VANES EXCEPT TRANSFER AIR SOUND ELBOW)	VANED ELBOW (PROVIDE ALL SQUARE OR RECTANGULAR ELBOWS WITH VANES EXCEPT TRANSFER AIR SOUND ELBOW)
LARGE RADIUS ELBOW	LARGE RADIUS ELBOW
SMALL RADIUS ELBOW	SMALL RADIUS ELBOW
RETURN AIR CEILING GRILLE AND RETURN AIR CEILING GRILLE WITH SOUND BOOT	RETURN AIR CEILING GRILLE AND RETURN AIR CEILING GRILLE WITH SOUND BOOT
CEILING DIFFUSERS (ARROWS DENOTE THROW PATTERN IF THROW IS SOMETHING OTHER THAN 4-WAY)	CEILING DIFFUSERS (ARROWS DENOTE THROW PATTERN IF THROW IS SOMETHING OTHER THAN 4-WAY)
EXHAUST CEILING REGISTER OR GRILLE	EXHAUST CEILING REGISTER OR GRILLE
LINEAR DIFFUSER	LINEAR DIFFUSER
ROUND DIFFUSER	ROUND DIFFUSER
SIDEWALL EXHAUST OR RETURN AIR GRILLE	SIDEWALL EXHAUST OR RETURN AIR GRILLE
SIDEWALL SUPPLY REGISTER	SIDEWALL SUPPLY REGISTER
DIFFUSER UNDER DUCT	DIFFUSER UNDER DUCT
POINT OF NEW CONNECTION TO EXISTING	POINT OF NEW CONNECTION TO EXISTING
ROOM THERMOSTAT	ROOM THERMOSTAT
ROOM TEMPERATURE SENSOR	ROOM TEMPERATURE SENSOR
DUCT SMOKE DETECTOR (DS)	DUCT SMOKE DETECTOR (DS)
ACCESS DOOR	ACCESS DOOR
MANUAL VOLUME DAMPER (VD)	MANUAL VOLUME DAMPER (VD)
FIRE DAMPER (FD) THROUGH WALL/ FLOOR	FIRE DAMPER (FD) THROUGH WALL/ FLOOR
FIRE/SMOKE DAMPER (FSD) THROUGH WALL/ FLOOR	FIRE/SMOKE DAMPER (FSD) THROUGH WALL/ FLOOR
MOTOR OPERATED DAMPER	MOTOR OPERATED DAMPER
CONNECT NEW DUCT TO EXISTING DUCT	CONNECT NEW DUCT TO EXISTING DUCT
EXISTING DUCT	EXISTING DUCT
EXISTING DUCT TO BE REMOVED	EXISTING DUCT TO BE REMOVED
30° RISE(R)/DROP(D) IN DUCTWORK IN DIRECTION OF ARROW	30° RISE(R)/DROP(D) IN DUCTWORK IN DIRECTION OF ARROW
CONCENTRIC DUCT REDUCER	CONCENTRIC DUCT REDUCER
ECCENTRIC DUCT REDUCER	ECCENTRIC DUCT REDUCER
DUCT TRANSITION FROM RECTANGULAR TO ROUND	DUCT TRANSITION FROM RECTANGULAR TO ROUND
CONICAL TAP FITTING	CONICAL TAP FITTING
SHOE TAP FITTING	SHOE TAP FITTING
DUCT OVER/UNDER ANOTHER DUCT	DUCT OVER/UNDER ANOTHER DUCT
SINGLE LINE DUCTWORK	
SYMBOL	DESCRIPTION
N	NEW
E	EXISTING
R	RELOCATED
NFW/RELOCATED SUPPLY DIFFUSER, NECK SIZE, AND BALANCE AIR AS INDICATED (MATCH EXISTING)	NFW/RELOCATED SUPPLY DIFFUSER, NECK SIZE, AND BALANCE AIR AS INDICATED (MATCH EXISTING)
NFW/RELOCATED RETURN GRILLE WITH BOOT (MATCH EXISTING)	NFW/RELOCATED RETURN GRILLE WITH BOOT (MATCH EXISTING)
EXISTING SUPPLY DIFFUSER	EXISTING SUPPLY DIFFUSER
EXISTING RETURN GRILLE WITH BOOT	EXISTING RETURN GRILLE WITH BOOT
RELOCATED EXISTING GRILLE OR DIFFUSER	RELOCATED EXISTING GRILLE OR DIFFUSER
RELOCATED ROOM THERMOSTAT, ELECTRIC	RELOCATED ROOM THERMOSTAT, ELECTRIC
EXISTING ROOM THERMOSTAT, ELECTRIC	EXISTING ROOM THERMOSTAT, ELECTRIC
1-1/2 X BRANCH DUCT FROM SIDE OF MAIN	1-1/2 X BRANCH DUCT FROM SIDE OF MAIN
SQUARE ELBOW WITH TURNING VANES	SQUARE ELBOW WITH TURNING VANES
RADIUS TYPE 90° ELBOW	RADIUS TYPE 90° ELBOW
DUCT TRANSITION	DUCT TRANSITION
ACCESS PANEL (AP)	ACCESS PANEL (AP)
EXISTING DUCTWORK	EXISTING DUCTWORK
EXISTING DUCT TO BE REMOVED	EXISTING DUCT TO BE REMOVED
FLEXIBLE DUCT	FLEXIBLE DUCT
AIR TERMINAL SYMBOLS	
SYMBOL	DESCRIPTION
MARK (AS SHOWN ON SCHEDULE)	MARK (AS SHOWN ON SCHEDULE)
NECK SIZE (Ø DIA. OR H" x W" RECTANG.)	NECK SIZE (Ø DIA. OR H" x W" RECTANG.)
CFM	CFM
TYP	TYPICAL OF NUMBER SHOWN ON SYSTEM, OR INSTALL NOTE.

GENERAL NOTES	
A.	ALL PIPING AND DUCTS IN FINISHED ROOMS OR SPACES SHALL BE CONCEALED IN FURRED CHASES OR SUSPENDED CEILINGS, UNLESS OTHERWISE NOTED.
B.	PROVIDE ACCESS PANELS OR DOORS IN UNACCESSIBLE CEILINGS AND/OR CHASES FOR ALL VALVES, TRAPS, DAMPERS, CLEANOUTS, COILS, FANS, CONTROLS, ETC. ACCESS DOOR RATING SHALL MATCH CLASSIFICATION OF WALL AND CEILING FIRE RATING.
C.	COORDINATE THE LOCATION OF ALL DIFFUSERS, GRILLES, REGISTERS, ACCESS DOORS, ETC., WITH THE ARCHITECTURAL REFLECTED CEILING PLAN(S).
D.	ALL ROUND RUNOUTS AND DROPS TO DIFFUSERS SHALL BE THE SAME NOMINAL SIZE AS THE SCHEDULED DIFFUSER NECK SIZE.
E.	THE FIRST FIGURE OF DUCT SIZE INDICATES DIMENSION OF FACE SHOWN OR INDICATED. ALL DUCT SIZES SHOWN ON DRAWINGS ARE NET INSIDE DIMENSIONS.
F.	PROVIDE TURNING VANES IN ALL SQUARE ELBOWS. EXCEPT TRANSFER AIR SOUND ELBOWS.
G.	THE CFM OF EACH DIFFUSER, REGISTER, ETC., IS INDICATED IN THE SYMBOL DESIGNATION ON THE DRAWINGS.
H.	REFER TO THE ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL FIRE RATED AND/OR SMOKE RATED WALLS AND ASSEMBLIES. PROVIDE APPROVED FIRE AND FIRE/SMOKE DAMPERS IN ALL REQUIRED PENETRATIONS FOR DUCTWORK, GRILLES, REGISTERS AND DIFFUSERS. ALL PIPE AND DUCTWORK PENETRATIONS OF FIRE, SMOKE AND FULL HEIGHT WALLS SHALL BE CAULKED AIRTIGHT TO THE ADJACENT STRUCTURE BY MEANS OF U.L. APPROVED FIRE PROOF CAULKING MATERIAL.
I.	CONTRACTOR SHALL COORDINATE ALL DUCTWORK, PIPING, PLUMBING AND FIRE PROTECTION PIPING WITH STRUCTURAL AND ELECTRICAL SYSTEMS AND SHALL PROVIDE NECESSARY OFFSETS TO AVOID CONFLICTS AND TO MAINTAIN EQUIPMENT ACCESS AND SERVICEABILITY.
J.	CONTRACTOR SHALL FURNISH ALL NECESSARY STRUCTURES, INSERTS, SLEEVES, AND HANGING DEVICES FOR INSTALLATION OF MECHANICAL AND PLUMBING EQUIPMENT, DUCTWORK AND PIPING, ETC. CONTRACTOR SHALL COORDINATE WITH GENERAL CONTRACTOR AND ALL BUILDING TRADES TO AVOID CONFLICTS AND TO MAINTAIN EQUIPMENT ACCESS AND SERVICEABILITY.
K.	CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY MISCELLANEOUS ANGLES, CHANNELS, UNISTRUT, ETC., AS MAY BE REQUIRED TO ADEQUATELY SUPPORT THE MECHANICAL PIPING, DUCTWORK, AND EQUIPMENT IN A MANNER APPROVED BY THE ARCHITECT WHICH WILL NOT OVERLOAD THE BUILDING STRUCTURAL SYSTEM.
L.	CONTRACTOR SHALL PROVIDE RETURN AIR OR TRANSFER AIR OPENINGS IN FULL HEIGHT WALLS SIZED AT 500 FPM (UNLESS OTHERWISE SPECIFICALLY SHOWN ON THE DRAWINGS) TO CREATE AND/OR MAINTAIN A RETURN AIR PATH AS REQUIRED. FIRE DAMPERS AND/OR SMOKE DAMPERS SHALL BE PROVIDED IN SUCH OPENINGS WHERE REQUIRED BY NOTE "H".
M.	SEAL ALL TRANSVERSE JOINTS, LONGITUDINAL SEAMS, DUCT WALL PENETRATIONS AND FITTING CONNECTIONS ON ALL DUCT SYSTEMS.
CODE INFORMATION	
2018 NORTH CAROLINA BUILDING CODE (NCBC), 2018 NORTH CAROLINA MECHANICAL CODE (NCMC), 2018 NORTH CAROLINA ENERGY CONSERVATION CODE (NCECC) AND 2018 NORTH CAROLINA PLUMBING CODE (NCPCL).	
ALL SYSTEMS SHALL BE IN COMPLIANCE WITH THE ABOVE CODES AS ADOPTED BY THE CITY OF ANGLIER, NC.	
OUTDOOR AIR VENTILATION PROVIDED AND BASED ON CHAPTER 4, SECTION 403.2 AND TABLE 403.3.	
SEE SHEET M1.2.2 FOR VENTILATION CALCULATIONS.	
ALL ROOFTOP EQUIPMENT SHALL BE PERMANENTLY IDENTIFIED AS TO THE AREA SERVED WITH A RUST-PROOF METAL NAMEPLATE PER 2018 NCMC.	
DUCT SMOKE DETECTORS REQUIRED BY 2018 NCMC SECTION 606 SHALL BE INSTALLED IN THE RETURN DUCTWORK AS SHOWN ON THE PLANS PER NCMC 606.2.1, 606.2.2, 606.3, AND NFPA 72. IF A FIRE ALARM SYSTEM IS AVAILABLE, THAT THE DUCT SMOKE DETECTOR(S) SHALL BE CONNECTED TO THE FIRE ALARM SYSTEM (NCMC 606.4.1) AND IF A FIRE ALARM SYSTEM IS NOT AVAILABLE, PROVIDE A VISIBLE AND AUDIBLE SUPERVISORY SIGNAL AT A CONSTANTLY SUPERVISED LOCATION TRIGGERED BY THE ACTIVATION OF A DUCT SMOKE DETECTOR. INCLUDE THE AIR DUCT DETECTOR TROUBLE INDICATOR (LED AT THE CEILING BELOW THE DUCT DETECTOR) AS REQUIRED BY 2018 NCMC 606.4.1, EXCEPTION 2.	
EQUIPMENT AND APPLIANCES SHALL BE INSTALLED AS REQUIRED BY THE TERMS OF THEIR APPROVAL, IN ACCORDANCE WITH THE CONDITIONS OF THE LISTING. THE MANUFACTURERS INSTALLATION INSTRUCTIONS AND THIS CODE. MANUFACTURERS INSTALLATION INSTRUCTIONS SHALL BE AVAILABLE ON THE JOB SITE AT THE TIME OF INSPECTION PER 2018 NCMC SECTION 304.1.	
ACCESS TO ROOF MOUNTED EQUIPMENT COMPLIES WITH 2018 NCMC. SEE ARCHITECTURAL DRAWINGS FOR ROOF ACCESS DETAILS.	
SYMBOLS LIST NOTES	
1. SYMBOLS LISTS, NOTES, ABBREVIATIONS, ETC. ARE FOR GENERAL REFERENCE ONLY. THE PRESENCE OF SYMBOLS, NOTES, ABBREVIATIONS, ETC. DOES NOT IMPLY ITS USE ON THIS PROJECT. REFER TO DRAWINGS FOR SPECIFIC SYMBOLS, NOTES, ABBREVIATIONS, ETC. USED.	
VENTILATION VERIFICATION	
AN AIR BALANCE REPORT SHOWING FRESH AIR COMPLIANCE IS REQUIRED BY THE MECHANICAL INSPECTOR FOR FINAL INSPECTION APPROVAL. VENTILATION SYSTEMS SHALL BE BALANCED BY AN APPROVED METHOD. A BALANCE REPORT SHALL VERIFY THAT THE VENTILATION SYSTEM IS CAPABLE OF SUPPLYING AIRFLOW RATES REQUIRED BY SECTION 403 (2018) NCMC SECTION 403.3).	

2018 NCECC COMPLIANCE NOTES	
A.	DESIGN HEATING AND COOLING LOADS FOR THE BUILDING HAVE BEEN CALCULATED USING CARRIER HAP USING PROCEDURES RECOMMENDED BY ASHRAE.
B.	ALL EQUIPMENT AND SYSTEMS HAVE BEEN SIZED TO BE NO GREATER THAN NEEDED TO MEET CALCULATED LOADS.
C.	HUMIDIFICATION SYSTEMS HAVE NOT BEEN PROVIDED ON THIS PROJECT.
D.	EACH HEATING OR COOLING SYSTEM ZONE HAS BEEN PROVIDED WITH ITS OWN TEMPERATURE CONTROL DEVICE.
E.	THE PROGRAMMABLE THERMOSTATS SHALL BE CAPABLE OF SETTING BACK TEMPERATURE TO 55 DEGREES F DURING HEATING AND SETTING UP TO 86 DEGREES F DURING COOLING, CAPABLE OF AUTOMATICALLY SETTING BACK OR SHUTTING DOWN SYSTEMS DURING UNOCCUPIED HOURS USING 7-DIFFERENT DAY SCHEDULES. HAVE A ACCESSIBLE MANUAL 2-HOUR OVERRIDE THAT ALLOWS TEMPORARY OPERATION OF THE SYSTEM FOR UP TO 2 HOURS, HAVE A BATTERY BACK-UP CAPABLE OF MAINTAINING PROGRAMMED SETTINGS FOR AT LEAST 10 HOURS WITHOUT POWER. A SETBACK OR SHUTOFF CONTROL IS NOT REQUIRED ON THERMOSTATS THAT CONTROL SYSTEMS SERVING AREAS THAT OPERATE CONTINUOUSLY SUCH AS THE ELEVATOR EQUIPMENT ROOM AND ELECTRICAL ROOMS IF APPLICABLE.
F.	OUTDOOR-AIR SUPPLY SYSTEMS WITH DESIGN AIRFLOW RATES GREATER THAN 3000 CFM AND ALL EXHAUST SYSTEMS MUST HAVE DAMPERS THAT ARE AUTOMATICALLY CLOSED WHILE EQUIPMENT IS NOT OPERATING IF APPLICABLE.
G.	OUTSIDE VENTILATION HAS BEEN DESIGNED PER 20XX IMC.
H.	ALL SUPPLY AND RETURN AIR DUCTS MUST BE INSULATED WITH A MINIMUM OF R-6 (2" MINIMUM THICKNESS DUCT WRAP OR 1-1/2" WHEN DUCT IS LINED). ALL DUCTS LOCATED OUTSIDE THE BUILDING MUST BE INSULATED WITH A MINIMUM OF R-8.
I.	ALL JOINTS, LONGITUDINAL AND TRANSVERSE SEAMS, AND CONNECTIONS IN DUCTWORK MUST BE SECURELY SEALED USING WELDMENTS, MECHANICAL FASTENERS WITH SEALS, GASKETS, OR MASTICS, MESH AND MASTIC SEALING SYSTEMS, OR TAPES, TAPES AND MASTICS MUST BE LISTED AND LABELED IN ACCORDANCE WITH UL 181A OR UL 181B.
J.	MECHANICAL FASTENERS AND SEALS, MASTICS, OR GASKETS MUST BE USED WHEN CONNECTING DUCTS TO FANS AND OTHER AIR DISTRIBUTION EQUIPMENT, INCLUDING MULTIPLE-ZONE TERMINAL UNITS.
K.	OPERATOR AND MAINTENANCE DOCUMENTATION MUST BE PROVIDED TO THE OWNER THAT INCLUDES EQUIPMENT INPUT AND OUTPUT CAPACITY AND REQUIRED MAINTENANCE ACTIONS, EQUIPMENT OPERATION AND MAINTENANCE MANUALS, HVAC SYSTEM CONTROL MAINTENANCE AND CALIBRATION INFORMATION, INCLUDING WIRING DIAGRAMS, SCHEMATICS, AND CONTROL SEQUENCE DESCRIPTIONS. DESIRED OR FIELD DETERMINED SET POINTS MUST BE PERMANENTLY RECORDED ON THE CONTROL DRAWINGS, AT CONTROL DEVICES, OR FOR DIGITAL CONTROL SYSTEMS, IN PROGRAMMING COMMENTS. A COMPLETE NARRATIVE OF HOW EACH SYSTEM IS INTENDED TO OPERATE.
L.	EACH SUPPLY AIR OUTLET OR DIFFUSER MUST HAVE ITS OWN BALANCING DEVICE. ACCEPTABLE BALANCING DEVICES INCLUDE ADJUSTABLE DAMPERS LOCATED WITHIN THE DUCTWORK AND SUPPLY AIR DIFFUSERS.
M.	WATER-HEATING EQUIPMENT AND HOT WATER STORAGE TANKS SHALL MEET THE REQUIREMENTS OF TABLE 404.2 OF THE 2018 NCECC. THE EFFICIENCY SHALL BE VERIFIED THROUGH DATA FURNISHED BY THE MANUFACTURER OR THROUGH CERTIFICATION UNDER AN APPROVED CERTIFICATION PROGRAM.
N.	SERVICE WATER-HEATING EQUIPMENT MUST BE PROVIDED WITH CONTROLS THAT ALLOW THE USER TO SET WATER TEMPERATURE TO 100 DEGREES F FOR DWELLING UNITS AND 90 DEGREES F FOR OTHER OCCUPANCIES. CONTROL MUST LIMIT OUTPUT TEMPERATURES OF LAVATORIES IN PUBLIC FACILITY REST ROOMS TO 110 DEGREES F.
O.	WATER-HEATING EQUIPMENT NOT PROVIDED WITH INTEGRAL HEAT TRAPS AND SERVING NON-CIRCULATING SYSTEMS SHALL BE PROVIDED WITH HEAT TRAPS ON THE SUPPLY AND DISCHARGE PIPING ASSOCIATED WITH THE EQUIPMENT.
P.	FOR AUTOMATIC-CIRCULATING HOT WATER SYSTEMS, PIPING SHALL BE INSULATED WITH 1" OF INSULATION HAVING A CONDUCTIVITY NOT EXCEEDING 0.27 BTU-IN/(H x FT2 x F). THE FIRST 8" OF PIPING IN NON-CIRCULATING WATER HEATING SYSTEMS SERVED BY EQUIPMENT WITHOUT INTEGRAL HEAT TRAPS SHALL BE INSULATED WITH 1/2" PIPE INSULATION OF MATERIAL HAVING CONDUCTIVITY NOT EXCEEDING 0.27 BTU-IN/(H x FT2 x F).
DUCT SMOKE DETECTOR TESTING	
<u>TESTING AND INSPECTION OF SMOKE CONTROL DEVICES</u>	
A. PRIOR TO TESTING SMOKE CONTROL DEVICES:	
1. VERIFY PROPER OPERATION OF EACH EXISTING SMOKE DETECTOR. ACTIVATION TESTING SHALL BE PERFORMED USING "CANNED SMOKE" ACCEPTABLE TO THE AUTHORITIES HAVING JURISDICTION.	
2. VERIFY ACTIVATION OF THE EXISTING SMOKE DETECTOR SHUTS DOWN THE APPROPRIATE AIR-MOVING SYSTEM(S). VERIFY ACTIVATION OF THE SMOKE DETECTOR IS SHOWN ON THE FIRE ALARM SYSTEM WHERE MONITORING IS REQUIRED.	
B. INSPECTION & TESTING OF SMOKE CONTROL DEVICES:	
1. TESTING OF FIRE/SMOKE DAMPERS AND SMOKE DETECTORS SHALL BE ACCOMPANIED BY THE ELECTRICIAN AND/OR THE CONTROLS SYSTEM SUPPLIER. IF THE BUILDING HAS A FIRE ALARM SYSTEM, A REPRESENTATIVE OF THE MANUFACTURER MUST BE PRESENT DURING THE TESTING.	





11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL

Jason M. Scates
Professional Engineer
Seal No. 065196
Suite 5274, 1805 N 2ND ST, ROGERS, AR 72716
479-636-9004
JOB NO.:
DESIGNED BY:

REVISION

Δ	ISSUE	DATE
OTF		02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA


PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE

PROJECT NUMBER: 22130

MECHANICAL - NOTES

M1.2.3

GENERAL EMS NOTES

1. REFERENCE MECHANICAL NOTES SHEET AND MECHANICAL SPECIFICATIONS FOR CONTROLS INFORMATION.
2. TERMINATIONS SHALL BE MADE IN ACCORDANCE WITH EMS SUPPLIER INSTRUCTIONS. NO FOIL OR UNUSED WIRE(S) SHALL BE EXPOSED AFTER APPLICATION OF HEAT SHRINK.
3. MINOR CHANGES IN MATERIALS OR TERMINATION POINTS SHALL NOT INCREASE CONTRACT COST.
4. ROUTE EMS CONDUITS CONCEALED IN SALES AREA.



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ ISSUE	DATE
OTP	02/15/23



PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA

PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTCYCLE# R1.2 12/XX/22




CIRCLE K STORE

PROJECT NUMBER: 22130

**ENERGY
MANAGMENT
SYSTEM**

M1.2.4



SPACE HUMIDITY
SENSORS
PER RTU MANUFACTURER
AND T-STAT
REQUIREMENTS.
COORDINATE LOCATION
WITH OWNER.
AS APPLICABLE

SUPPLY
SENSORS


- WALK-IN COOLER SENSOR → R
- BEER CAVE SENSOR → R
- WALK-IN DAIRY SENSOR → R
- WALK-IN FREEZER SENSOR → R
- REAR FREEZER SENSOR → R

EMS CABLE SPECIFICATIONS
18/2 TSP - WINDY CITY #002352-S OR EQUAL
22/2 TSP - WINDY CITY #043004AL OR EQUAL

NOTE: ALL WIRING TO BE CONTINUOUS, WITH
NO SPLICES AND LABELED ON BOTH ENDS.

EMS RISER | 1
N.T.S.

SECTION	MECHANICAL SPECIFICATIONS
15010 BASIC MECHANICAL REQUIREMENTS	<ol style="list-style-type: none"> ALL WORK TO BE DONE AND MATERIALS FURNISHED COMPLYING WITH APPLICABLE LAWS, AND RESOLUTIONS, INCLUDING THE CURRENTLY ENFORCED VERSIONS OF THE INTERNATIONAL MECHANICAL CODE (I.M.C.), INTERNATIONAL PLUMBING CODE (I.P.C.), INTERNATIONAL BUILDING CODE (I.B.C.), AND LOCAL, STATE, AND FEDERAL FIRE SAFETY CODES (NFPA). ALL MATERIALS USED SHALL BE NEW AND UNDAMAGED. ALL WORK PERFORMED SHALL BE IN ACCORDANCE WITH CURRENT CONSTRUCTION INDUSTRY STANDARDS AND WORKMANSHIP. PRIOR TO SUBMITTING A PROPOSAL, THE CONTRACTOR SHALL VISIT THE SITE AND THOROUGHLY INSPECT ALL EXISTING CONDITIONS TO ENSURE THAT THE WORK REPRESENTED ON THE DRAWINGS AND THESE SPECIFICATIONS CAN BE INSTALLED AS INDICATED. AT SUBSTANTIAL COMPLETION OF THE CONSTRUCTION, FURNISH AS-BUILT PLANS TO ARCH/ENGINEER FOR APPROVAL BEFORE THEY ARE TURNED OVER TO OWNER ALL MANUFACTURED EQUIPMENT, ACCESSORIES AND MATERIALS SHALL BE USED AS INTENDED BY THE MANUFACTURER, IN STRICT ACCORDANCE WITH THE MANUFACTURERS WRITTEN INSTALLATION, OPERATION AND MAINTENANCE INSTRUCTIONS. THE MECHANICAL CONTRACTOR SHALL PROVIDE, IN ADDITION TO ANY OTHER WARRANTIES SPECIFIED, A ONE(1) YEAR FULL LABOR AND MATERIAL WARRANTY ON ALL WORKMANSHIP, MATERIAL AND EQUIPMENT FURNISHED FOR THIS PROJECT. THE CONTRACTOR SHALL REPLACE ALL DEFECTIVE WORKMANSHIP, EQUIPMENT, AND MATERIALS WITHOUT ADDITIONAL CHARGES, INCLUDING ALL REFRIGERANT CAUSED TO BE LOST BY REPAIR OF DEFECTIVE WORK OR MATERIALS. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR INSTRUCTING THE OWNER IN PROPER OPERATION AND MAINTENANCE OF THE EQUIPMENT. A WIRING DIAGRAM WITH INSTRUCTIONS FOR THE OPERATION, INSTALLER'S NAME, PHONE NUMBER, MODEL, AND MAKE OF EQUIPMENT PROVIDED, ETC., SHALL BE FURNISHED TO OWNER, AT A TIME DESIGNATED, PROVIDE AN ENGINEER OR MECHANIC TO GO OVER SYSTEM WITH OWNER'S REPRESENTATIVE TO THOROUGHLY FAMILIARIZE HIM WITH THE OPERATION AND MAINTENANCE OF THE SYSTEM. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL OPENINGS AND REQUIRED LINTELS NEEDED FOR GENERAL CONTRACTOR FOR THE INSTALLATION OF MECHANICAL EQUIPMENT. SAWCUTS, LINTELS, HEADERS, AND STRUCTURAL MODIFICATIONS TO THE BUILDING STRUCTURE NEEDED FOR THE INSTALLATION OF MECHANICAL EQUIPMENT SHALL BE APPROVED BY THE GENERAL CONTRACTOR, BEFORE INSTALLATION. IN GENERAL, OPENINGS AND REQUIRED LINTELS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING DETAILS AND TEMPLATES OF ALL OPENINGS NECESSARY FOR MECHANICAL EQUIPMENT INSTALLATION INCLUDING: HOUSING, ACCESS DOORS, INSPECTION DOORS, AND PASSAGE WAYS FOR MECHANICAL EQUIPMENT. THE MECHANICAL CONTRACTOR IS RESPONSIBLE FOR SEALING CRACKS AND FINISHING ROUGH EDGES LEFT FOLLOWING MECHANICAL INSTALLATION. THE USE OF THE MECHANICAL EQUIPMENT FOR HEATING, COOLING, OR DRYING DURING CONSTRUCTION IS PROHIBITED, UNLESS APPROVED BY WRITTEN DOCUMENTATION BY THE OWNER. ALL OTHER MANUFACTURERS BESIDES THE SPECIFIED PRODUCT MUST BE PRE-APPROVED PRIOR TO BIDDING. SUBMIT DETAILED EQUIPMENT CUT-SHEETS AND CLEARLY IDENTIFY ANY DIFFERENCES FROM THE SPECIFIED PRODUCT. ANY EQUIPMENT SUBMITTED DURING THE REGULAR SUBMITTAL PROCESS THAT WAS NOT PRE-APPROVED WILL BE AUTOMATICALLY BE REJECTED. PERMITS AND INSPECTIONS: MECHANICAL CONTRACTOR IS RESPONSIBLE TO OBTAIN AND PAY FOR ALL REQUIRED PERMITS AND LICENSES. WHEN REQUIRED BY CODE, ALL WORK MUST BE INSPECTED AND APPROVED BY LOCAL AUTHORITIES. PRIOR TO FINAL APPROVAL, FURNISH THE ARCHITECT/OWNER WITH CERTIFICATES OF INSPECTION AND APPROVALS BY LOCAL AUTHORITIES. PRIOR TO SUBMITTING BID, THE MECHANICAL CONTRACTOR SHALL CAREFULLY EXAMINE THE PLANS FOR THE PROPER FITTING OF THE MATERIAL AND APPARATUS INTO THE BUILDING. ARRANGE WORK SCHEDULE FOR MINIMUM INTERFERENCE WITH THE WORK OF OTHER TRADES. SHOULD THE PARTICULAR EQUIPMENT PROPOSED FOR INSTALLATION REQUIRE OTHER ARCHITECTURAL, STRUCTURAL, PLUMBING, OR ELECTRICAL CONDITIONS THAT THOSE SHOWN, ARRANGE FOR SUCH SPACE BEFORE SUBMITTING BID. ALL CHANGES NECESSITATED BY THE FAILURE TO COMPLY WITH THIS CLAUSE, SHALL BE MADE AT NO ADDED EXPENSE TO THE OWNER. WITHIN 10 DAYS AFTER AWARD OF CONTRACT, SUBMIT (4) COPIES OF A COMPLETE WRITTEN LIST OF ALL MAJOR ITEMS OF EQUIPMENT AND MATERIALS AS WELL AS ADDITIONAL COPIES, THAT THE CONTRACTOR MAY NEED RETURNED. THE SUBMITTAL SHALL DEFINITELY AND CLEARLY STATE WHERE SUBMITTED EQUIPMENT DOES NOT AGREE WITH THE CONTRACT DOCUMENTS, AND LIST DEVIATIONS IN COLOR OTHER THAN RED. SUBMIT ALL ITEMS AT ONE TIME AND IN A NEAT AND ORDERLY MANNER. PARTIAL LISTS WILL NOT BE ACCEPTABLE. SUBMITTALS SHALL INCLUDE MANUFACTURER'S SPECIFICATIONS, PHYSICAL DIMENSIONS AND RATINGS OF ALL EQUIPMENT SUBMITTED. SUBMITTALS SHALL BE INDEXED, SEPARATED BY DIVIDERS, AND BOUND IN LOOSE LEAF RING BINDERS.
15140 SUPPORTS AND ANCHORS	<ol style="list-style-type: none"> FURNISH PIPE AND DUCT HANGERS, WHERE REQUIRED, FIRMLY SUPPORTED FROM BUILDING STEEL, CONCRETE OR MASONRY STRUCTURE. SUPPORT PIPING SYSTEMS SECURELY WHILE ALLOWING FOR PIPE AND BUILDING EXPANSION AND CONTRACTION. PROVIDE COPPER PLATED HANGERS FOR COPPER PIPE. USE ADJUSTABLE STEEL BAND HANGERS. MAXIMUM SPACING SHALL BE 5' FOR 1/2" PIPING, 7' FOR 3/4" TO 1-1/4" PIPING, AND 9' FOR 1-1/2" PIPING. FURNISH MECHANICAL EQUIPMENT SUPPORTS AS DETAILED OR AS REQUIRED TO SAFELY AND PERMANENTLY CARRY THE WEIGHT OF THE EQUIPMENT.
15250 MECHANICAL INSULATION	<ol style="list-style-type: none"> INSULATE ALL METAL SUPPLY AND RETURN DUCTWORK WITH 2" FOIL BACKED FIBERGLASS INSULATION. IN UNHEATED ATTICS OR IN AREAS LOCATED ABOVE THE LINE OF BUILDING INSULATION, INSULATE ALL DUCTWORK, INCLUDING RETURN AIR AND EXHAUST AIR DUCTWORK, WITH 3" FOIL-BACKED INSULATION, AND REQUEST THAT GENERAL CONTRACTOR BLOW ATTIC INSULATION OVER THE TOP OF THE INSULATED DUCTWORK, EXPOSED SPIRAL DUCTWORK, OR DUCTWORK LOCATED WITHIN A HEATED SPACE DOES NOT REQUIRE INSULATION. LINE ALL SUPPLY AND RETURN DUCTWORK WITHIN FIFTEEN (15) FEET OF SUPPLY FAN WITH 1/2" DUCT LINER TO REDUCE SOUND. ALL INSULATION MATERIALS TO HAVE A FLAME SPREAD RATING OF 25 OR LESS AND SMOKE DEVELOPMENT RATING OF 50 OR LESS AS TESTED BY ASTM E-84, UL-723, NFPA 90A-90-B.
15782 ROOF-TOP UNITS	<ol style="list-style-type: none"> THE OWNER SHALL FURNISH AND GENERAL CONTRACTOR SHALL INSTALL PACKAGED ROOF-TOP UNIT(S) AS SHOWN AND SCHEDULED. THE UNIT(S) SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS, AND SHALL PERFORM AT THE CONDITIONS SCHEDULED. THE MECHANICAL CONTRACTOR SHALL PROVIDE TWO (2) SETS OF FILTERS FOR EACH UNIT AND SHALL BE RESPONSIBLE FOR CHANGING FILTERS WITHIN TWO (2) WEEKS OF START-UP. THE MECHANICAL CONTRACTOR SHALL PROVIDE A SINGLE POWER SOURCE CONNECTION DISCONNECT AND A 15 AMP DUPLEX, WEATHERPROOF CONVENIENCE OUTLET BOX FOR EACH ROOF TOP UNIT INSTALLED.
15783 CONDENSATE AND COOLER DRAINS	<ol style="list-style-type: none"> CONDENSATE DRAIN PIPING SHALL BE ASTM B-88, TYPE "M" HARD DRAWN COPPER WITH WROT COPPER FITTINGS AND SOLDERED JOINTS, 50/50 SOLDER. INSULATE WITH 1/2" THICK FLEXIBLE CLOSED CELL FOAMED PLASTIC PIPE INSULATION, ARMSTRONG ARAMFLEX, OR EQUAL FOR ENTIRE LENGTH. FITTINGS FIELD FABRICATED OF NESTING SIZES, SECURED WITH ADHESIVE. REFRIGERANT SUCTION LINES SHALL BE INSULATED TO 1" THICKNESS. ALL PIPING SHALL CONFORM TO ASTM B88-72. FITTINGS SHALL WROUGHT COPPER, DRAINAGE TYPE FOR LINES 1-1/4" AND LARGER. SOLDER WITH 50/50 SOLDER.



SECTION	MECHANICAL SPECIFICATIONS
15853 POWERED VENTILATORS	<ol style="list-style-type: none"> THE MECHANICAL CONTRACTOR SHALL FURNISH AND INSTALL VENTILATOR(S) AND/OR EXHAUST FAN(S) AS SHOWN AND SCHEDULED. THE UNIT(S) SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS, AND SHALL PERFORM AT THE CONDITIONS SCHEDULED. INSTALL VENTILATOR(S) AND/OR EXHAUST FAN(S) WITH CLEARANCES FOR SERVICE AND MAINTENANCE. THE MECHANICAL CONTRACTOR SHALL PROVIDE ONE (1) BACKDRAFT DAMPER FOR EACH VENTILATOR AND/OR EXHAUST FAN OR SHALL VERIFY A BACKDRAFT DAMPER HAS BEEN FACTORY INSTALLED. THE MECHANICAL CONTRACTOR SHALL ADJUST DAMPER LINKAGES FOR PROPER OPERATION.
15891 METAL DUCTWORK SYSTEMS	<ol style="list-style-type: none"> ALL DUCTWORK SHALL BE CONSTRUCTED FROM HOT NEW DIPPED GALVANIZED SHEET IRON OR STEEL, ASTM A-120, IN COMPLIANCE WITH 20XX I.M.C. CHAPTER 6, AND SMACNA HVAC DUCT CONSTRUCTION STANDARDS FOR GAGE AND REINFORCEMENT. ALL DUCTWORK SHALL BE SEALED AND INSULATED IN ACCORDANCE WITH ASHRAE 90.1 2007. ALL LOW VELOCITY AIR CONDITIONING SUPPLY AIR AND RETURN AIR DUCTWORK SHALL BE 2-INCH DUCT CONSTRUCTION. CONSTRUCT AND ERECT DUCTWORK IN ACCORDANCE WITH THE CURRENT ISSUES OF THE IMC, SMACNA STANDARDS AND ASHRAE HANDBOOKS. DUCTS SHALL CONFORM TO DIMENSIONS ON THE DRAWINGS UNLESS LOCATION OF STRUCTURAL MEMBERS PROHIBITS. IN CASE OF CHANGE IN DIMENSIONS, CROSS SECTIONAL AREAS SHALL BE MAINTAINED. ROUND FLEX DUCT SHALL BE USED FOR DIFFUSER-GRILL CONNECTIONS ABOVE LAY-IN CEILINGS. FLEXDUCT MAY BE USED IN OTHER AREAS WHERE THE DUCT AND GRILLE ARE PERMANENTLY AND REASONABLY ACCESSIBLE. MAXIMUM FLEX DUCT LENGTH IS 5'-0" AND THE DUCTWORK SHALL BE PRE-LINED WITH 1" INSULATION. PERFORMANCE OF FLEXIBLE DUCT SHALL MEET OR EXCEED THE RIGID DUCTWORK. FLEXIBLE DUCTS SHALL BE THERMAFLEX II TYPE M-KE, FACTORY FABRICATED ASSEMBLY, SPIRAL CONSTRUCTION, FIBERGLASS BLANKET INSULATION (R=6.0), AND MYLAR SHEATH. FLEXIBLE DUCTS UL LISTED FOR CLASS 0 DUCT AND COMPLY WITH NFPA-90A. PAINT ALL DUCTWORK, TURNING VANES, INSULATION ECT., THAT IS VISIBLE THROUGH GRILLES, REGISTERS, OR CEILING DIFFUSERS FLAT BLACK. TAPE ALL JOINTS IN SHEET METAL DUCTWORK WITH ARABOL AND CANVAS OR EQUAL ADHESIVE. FLEXIBLE CONNECTIONS SHALL BE 30 OUNCE, CLOSELY WOVEN, NEOPRENE COATED GLASS FABRIC THAT IS FIRE RETARDANT, WEATHERPROOF AND AIR TIGHT, A MINIMUM OF 6" WIDTH. FABRICATE ALL SHEET METAL DUCTS OF PRIME GRADE, LOCKING FORMING QUALITY GALVANIZED STEEL SHEETS USING GAUGES OF METAL AND REINFORCING BETWEEN JOINTS AS FOLLOWS <ol style="list-style-type: none"> 12" AND SMALLER (LONGEST SIDE)-24 GAUGE 13"-18" (LONGEST SIDE) - 24 GAUGE. 19"-30" (LONGEST SIDE) - 24 GAUGE, WITH 1"x1"x1/8" ANGLES AT 5 FT. ON CENTER 31"-42" (LONGEST SIDE) - 22 GAUGE, WITH 1"x1"x1/8" ANGLES AT 5 FT. ON CENTER DUCT LINER SHALL HAVE A FLAME SPREAD AND SMOKE DEVELOPMENT 25 OR LESS AND 50 OR LESS WHEN TESTED BY ASTM E-84 (NFPA 255) METHOD. INSULATE THE FIRST 10 FEET OF ALL RECTANGULAR SUPPLY AIR AND ALL RECTANGULAR RETURN AIR SHEET METAL DUCTWORK INTERNALLY WITH JOHNS-MANVILLE LINACOUSTIC PC FIBERGLASS DUCT LINER WITH REINFORCED COATING SYSTEM, THICKNESS 1" (R=6.0) AND DENSITY 1-1/2 PCF. ALL OTHER RECTANGULAR SUPPLY AIR AND RIGID ROUND DUCTWORK SHALL BE INSULATED WITH 2" THICK (R=6.0) JOHNS-MANVILLE MICROLITE DUCT WRAP WITH FSK VAPOR BARRIER.
15910 DUCT ACCESSORIES	<ol style="list-style-type: none"> THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING VOLUME DAMPERS, TURNING VANES, ACCESS DOORS, VIBRATION ISOLATORS, ETC. THE ACCESSORIES SHALL BE INSTALLED IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS.
15975 TEMPERATURE CONTROLS	<ol style="list-style-type: none"> THE OWNER SHALL FURNISH OR CONTRACT A TEMPERATURE CONTROL CONTRACTOR TO FURNISH ALL MOTORS, DRIVES, CONTROLLERS INTEGRAL TO THE MECHANICAL EQUIPMENT SYSTEM, AND FACTORY MOUNTED CONTROLS FOR ALL MECHANICAL EQUIPMENT. THE MECHANICAL CONTRACTOR OR CONTRACTED TEMPERATURE CONTROL CONTRACTOR SHALL FURNISH AND INSTALL ALL SWITCHES, FIRE STATS, FREEZE STATS, THERMOSTATS, TIMERS, CONTROL CABINETS, AND OTHER SPECIALIZED EQUIPMENT PERTAINING TO MECHANICAL CONTROL. THE ROOF MOUNTED UNITS (RTU) SHALL BE CONTROLLED BY A REMOTE TEMPERATURE SENSOR LOCATED IN THE RETURN AIR DUCT AND AN ELECTRIC THERMOSTAT. <ol style="list-style-type: none"> THE TEMPERATURE CONTROLS SHALL BE ELECTRIC, 7-DAY PROGRAMMABLE, WITH FUNCTION: AUTO, MANUAL, AND FAN ONLY, UNLESS SPECIFICALLY REQUESTED BY THE GENERAL CONTRACTOR AND OWNER, AND SHALL BE PROVIDED BY THE MECHANICAL CONTRACTOR OR CONTRACTED TEMPERATURE CONTROL CONTRACTOR. PROVIDE A HUMIDITY SENSOR IN THE RETURN AIR CONNECTED TO THE CONTROLLER FOR MONITORING HUMIDITY. ALL CONTROL WIRING SHALL BE IN CONDUIT. CONDUIT SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR. THE MECHANICAL CONTRACTOR SHALL COORDINATE WITH THE ELECTRICAL CONTRACTOR FOR LOCATION FOR CONDUITS. THE CONTRACTOR RESPONSIBLE TO INSTALL THE CONTROLS SHALL BE RESPONSIBLE TO PULL THE CONTROL WIRE. THE ROOF TOP UNIT SHALL UTILIZE TEMPERATURE CONTROLS SYSTEM FURNISHED AS PART OF THE UNIT, OR SPECIFIED TO BE PROVIDED AS OPTIONS OR ACCESSORIES BY THE MANUFACTURER BY OF THE UNIT. ALL WIRING WILL BE DONE IN ACCORDANCE WITH APPROVED SHOP DRAWINGS FURNISHED BY THE MANUFACTURER. ELECTRICAL WIRING: ALL WIRING AND STARTERS ARE INCLUDED IN THE ELECTRICAL DIVISION OF THIS PROJECT, BUT ALL CONTROLS, RELAYS, ETC., ARE INCLUDED UNDER THIS DIVISION. ROOM THERMOSTATS AND CONTROL SWITCHES SHALL BE LOCATED AS SHOWN OR DIRECTED, AND ALL CONTROLS, RELAYS, STARTERS AND WIRING SHALL CONFORM TO THE CURRENTLY ENFORCED VERSION OF THE NATIONAL ELECTRICAL CODE (NEC). ALL CONTROLS SHALL BE FURNISHED AND PROPERLY IDENTIFIED, WITH INSTRUCTIONS FOR PROPER ELECTRICAL CONNECTIONS. RESPONSIBILITY FOR PROPER CONNECTIONS AND OPERATION IS INCLUDED HEREIN.
15990 TESTING, ADJUSTING, AND BALANCING	<ol style="list-style-type: none"> THE MECHANICAL CONTRACTOR SHALL SUBCONTRACT AN AIR BALANCER TO BALANCE THE SYSTEMS DESCRIBED BELOW. THE BALANCING SHALL BE COMPLETED BY AN INDEPENDENT AIR BALANCER WHO IS NOT AN EMPLOYEE OF THE MECHANICAL CONTRACTOR. THE BALANCING SHALL BE DONE BY A QUALIFIED AIR BALANCER THAT HAS AT LEAST (3) YEARS OF DOCUMENTED AIR BALANCING EXPERIENCE. PER COMPLIANCE WITH ASHRAE 90.1-2007, THE BALANCER SHALL SUBMIT AN AIR BALANCE REPORT TO THE ENGINEER AND CITY INSPECTOR. THE BALANCE REPORT SHALL SHOW PROOF THAT THE SYSTEM HAS BEEN BALANCED TO +/- 10% OF THE DESIGNED AIRFLOW. IT IS THE MECHANICAL CONTRACTOR AND AIR BALANCER'S DUTY TO PROVIDE ACCURATE DATA, SO AREAS OF INCORRECT FLOW MAY BE DISCLOSED TO THE ENGINEER, INSPECTOR, AND OWNER. ALL AIRSIDE SYSTEMS, COMPONENTS, ETC. INCLUDING SUPPLY, RETURN, OUTDOOR, AND EXHAUST AIR SYSTEMS SHALL BE BALANCED. THE BALANCER SHALL PROVIDE SHEAVES AND BELTS AS NEEDED TO PROPERLY BALANCE EQUIPMENT TO +/- 10% OF THE DESIGNED AIRFLOWS. ALL DIFFUSERS, REGISTERS, GRILLES, AND LOUVERS SHALL BE INDIVIDUALLY BALANCED AND LISTED IN THE BALANCE REPORT. ALL AIRSIDE EQUIPMENT, SUPPLY, RETURN, AND OUTDOOR AIR FLOWRATES SHALL BE LISTED IN THE BALANCE REPORT.



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ ISSUE	DATE
OTP	02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA


PROJECT

CIRCLE K
STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH
ROAD,
ANGIER, NC

PROTOCOL# R1.2 12/XX/22




CIRCLE K STORE

PROJECT NUMBER: 22130

MECHANICAL -
SPECIFICATIONS

M1.3



NOTES

- PRESSURED RELIEF DEVICES SHALL BE PIPED TO THE OUTDOORS WHERE THE DISCHARGE WILL NOT IMPINGE ON THE STRUCTURE, PERSONNEL, OR MEANS OF EGRESS AND WILL NOT CREATE A HAZARDOUS CONCENTRATION OF CARBON DIOXIDE. (NFPA 55, 13.1.2.) THE TERMINATION OF THE PRESSURE RELIEF VENT DISCHARGE PIPING SHALL BE OUT DOORS AND A MINIMUM OF 10 FEET FROM THE OPENING INTO THE BUILDING.
- CONTAINERS, CYLINDERS, AND TANKS SHALL BE PROVIDED WITH A PRESSURE GAUGE AND A LEVEL GAUGE OR DEVICE FOR INDICATING THE QUANTITY OF LIQUID CARBON DIOXIDE. (NFPA 55, 13.1.2.1)
- ROOMS OR AREAS WHERE CONTAINER SYSTEMS ARE FILLED AND USED INDOORS OR IN ENCLOSED OUTDOOR LOCATIONS SHALL BE PROVIDED WITH A GAS DETECTION AND ALARM SYSTEM THAT IS CAPABLE OF DETECTING AND NOTIFYING THE BUILDING OCCUPANTS OF A GAS RELEASE THAT CREATES CARBON DIOXIDE VAPORS IN EXCESS OF ITS PEL. (NFPA 55, 13.2.2)
- CARBON DIOXIDE GAS DETECTION SHALL BE AS FOLLOWS:
 - PRE-ALARM (1500 PPM) NOTIFYING AY INCLUDE, BUT NOT LIMITED TO THE BUILDING OWNER, WORKING SUPERVISOR, OR MAINTENANCE COMPANY.
 - ALARM (30,000 PPM) NOTIFICATION SHALL INCLUDE THE COMPLETE AREA, OR BUILDING EVACUATION AND ACTIVATION OF THE 911 SYSTEM, TO NOTIFY THE ANGIER FIRE DEPARTMENT OF A CARBON DIOXIDE GAS DETECTION ALARM. (PFD POLICY CARBON DIOXIDE 1.1)
- CARBON DIOXIDE DETECTION SHALL BE LOCATED AT ALL POINTS OF USE LOCATIONS INSIDE THE BUILDING. (R3000.1)
 - NOTE: THE DETECTION SHOULD BE PLACED AT A LEVEL ACCEPTABLE BASED ON THE PROPERTIES OF THE GAS (HEAVIER OR LIGHTER THAN AIR) 12-18 INCHES AFF OR BFC
- ACTIVATION OF THE GAS DETECTION SYSTEM SHALL INITIATE AN AUDIBLE ALARM WITHIN THE ROOM OR AREA IN WHICH THE SYSTEM IS INSTALLED (NFPA 55, 13.2.2.1)
- A WARNING SIGN SHALL BE POSTED AT THE ENTRANCE TO THE BUILDING, ROOM, ENCLOSURE, OR CONFINED AREA WHERE THE CONTAINER IS LOCATED. (NFPA 55, 13.2.3)
- THE WARNING SIGN SHALL BE AT LEAST 8 IN. (200 MM) WIDE AND 6 IN. (150MM) HIGH AND STATE THE FOLLOWING:
 - CAUTION: CARBON DIOXIDE GAS: VENTILATE THE AREA BEFORE ENTERING. A HIGH CARBON DIOXIDE (CO2) GAS CONCENTRATION IN THIS AREA CAN CAUSE SUFFOCATION. (NFPA 55, 13.2.3.1)
- PROVIDE MINIMUM OF TWO NOTIFICATION DEVICES, ONE NEAR THE AREA/ROOM WHERE CYLINDER IS LOCATED, ON IN COMMON AREA WHERE THE PUBLIC GATHERS. DEVICES SHALL BE RATED AT 100 CD FOR VISUAL EFFECT AND 75 DB FOR AUDIBLE EFFECT UNLESS FULL FIRE ALARM IS PRESENT. (R3000.1)
 - *NOTE - IF THE BUILDING IS EQUIPPED WITH A FIRE ALARM NOTIFICATION SYSTEM; THE USE OF THE SYSTEM IS ACCEPTABLE, PROVIDED THE GAS DETECTION HAS AUDIBLE AND VISIBLE CLEAR INDICATORS IN THE HAZARD AREA UPON BOTH THE WARNING LEVEL AND ALARM LEVEL OF THE GAS.
- GAS DETECTION SYSTEM SHALL BE TIED INTO THE MONITORING SYSTEM IF PROVIDED (R3000.1)
- PROVIDE LABEL ON PIPING TO INDICATE EXACT CONTENTS AND DIRECTION OF FLOW. THESE LABELS SHALL BE PLACED EVERY 20 FEET, MAJOR CHANGE IN DIRECTION AND WHERE PIPING ENTERS AND LEAVING WALLS.

LEGEND

- SHUT OFF VALVE LOCATION
- CO2 TANK TUBING



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL

Jason M. Scates
P.E.
SUITE 5274 1805 N 2ND ST ROGERS, AR 72756
478-636-9004
JOB NO.:
DESIGNED BY:

REVISION

ISSUE	DATE
OTF	02/15/23

PROFESSIONAL IN

JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA
PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD, ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE
PROJECT NUMBER: 22130

CO2 LAYOUT PLAN AND NOTES

M1.4

- (B603) - POINT OF USE (BAG IN THE BOX)
 - (B501) - CO2 TANK
 - (B503) - DETECTION DEVICE
 - (B503-D) - NOTIFICATION DEVICE (REPEATER)
 - (B504) - CO2 SIGN, SEE DETAIL 2/A9.1
 - (B502) - CO2 TANK
- NOTE: SEE ALSO SHEET A1.5 & A3.2 FOR ADDITIONAL INFORMATION

CO2 LAYOUT PLAN (FOR REFERENCE ONLY) 1

3/16" = 1'-0"



CO2 CABINET



SPECIFICATIONS	Carbo-Mizer® 400
Dimensions	
Diameter	20 in (50.8 cm)
Height (with legs)	68 in (172.7 cm)
Weight	
Empty Weight	305 lb (138 kg)
Full Weight	750 lb (340.2 kg)
Design criteria	
Code *	ASME
MAWP	300 psig (20.7 barg)
Insulation Type †	SI
Capacity	
Gross Volume	46.2301 gal (175 ltr)
Storage Capacity at 125 psig	400 lb (182 kg)
Performance	
Evaporation Rate‡	2.5 lb/day
CO2 Gas Delivery (Continuous)§	5.5 lb/hr
Peak Flow Rate §	10 lb/hr
Components	
ASME Relief Valve Setting	300 psig (20.7 barg)
Secondary RV Setting	450 psig (31 barg)
Sure-Fill™ RV Setting	N/A
Gas Use Connection	1/4 in 45° Flare
Fill Line Connection	5/8 in Male 45° Flare
Vent Connection	1/2 in OD Tubing
Construction	
Inner Vessel Material	Stainless Steel
Outer Vessel Material	Stainless Steel
Vaporizer Coil	N/A
Liquid Level Gauge	Differential Pressure



Royston's Outdoor CO2 Cabinet allows you to securely store your bulk CO2 tanks

SAFE AND SECURE STORAGE
Our attractive, aluminum CO2 Cabinet allows you to store and protect your bulk CO2 tanks in outdoor installations safely and securely. The cabinet features a lockable, piano-hinged door with key-only access for employees. Anchor points on all four legs allow secure attachment to concrete. Pre-punched penetrations for lines allow for easy access, and a louvered door and sides provide natural cross ventilation. The cabinet is finished in a neutral, exterior-grade powder coat paint but can be custom-colored to blend with any surrounding environment. For uninterrupted fountain drink service, keep your CO2 tanks properly protected.



Royston quality, a one-year warranty and a 20- to 30-year life expectancy make this the go-to CO2 Cabinet nationwide.

STANDARD FEATURES

- Lockable door
- Full-length, stainless steel, piano-hinged door for easy access
- Anchor points at all four legs for secure installation
- Pre-punched penetrations for lines
- Louvered door and sides for natural cross ventilation
- Formed, pitched roof to allow for drainage

UPGRADES

- Custom color options include dark grey, black, blue, red or white to blend with surrounding environment



NUCO Specifications for Phoenix, Arizona: Fill, Vent and Supply Line Materials for NuCO₂ Micro Bulk Tank Installations Item ID #: PFD-01 Revision#: 3.0

1. **Purpose:** Provide the specification for the Fill, Vent and Supply Line Materials for Micro Bulk Tank Installations completed by NuCO₂ in Phoenix, AZ.

2. **Process Owner:** Director Product Engineering, CO₂ Solutions

3. **Responsibility:** PHX Service Technicians, PHX Supervisor, District 9 Manager, Safety, Engineering, Supply Chain.

4. **Part Specifications**

Gas Vent Line

Material/Part	Material/Part
PHD req'd for 1000 lb capacity - 7.50CM & backpressure $\le 186\text{ psig}$ set	Working Pressure: 120 psig minimum
pressure for 0.375" ID $\le 100\text{ psig}$ backpressure <math>< 15\text{ psig}</math> ($\le 58\text{ of } 200\text{ psig PHD}$)	Burst Pressure Rating: 480 psig minimum (must be > 4X Working Pressure)
Rated operating temperatures and pressures in Vent Line during filling:	Temperature Rating: -50°F to +125°F or higher
Manual Vent Fill - 30" and 120 psig	Inside Diameter = 0.375" nominal
Auto-Fill Vent Fill (Chart Industries) - 30" and 120 psig	Outside Diameter = 0.500" nominal

Author: Mark Novak - 1 - Revision Date: 3/23/2012
 Process Owner: Director Product Engineering, CO₂ Solutions Effective Date: 3/23/2012

NUCO Specifications for Phoenix, Arizona: Fill, Vent and Supply Line Materials for NuCO₂ Micro Bulk Tank Installations Item ID #: PFD-01 Revision#: 3.0

Material/Part	Material/Part
Pressures during filling are between 120 and 200 psig	Working Pressure: 120 psig minimum
Liquid temperatures during filling are between -34°F and +12°F	Burst Pressure Rating: 480 psig minimum (must be > 4X Working Pressure)
	Temperature Rating: -40°F to +125°F or higher
	FDA 21 CFR 177 Food Compliant and NSF/ANSI Food Equipment Materials

NuCO₂ Specifications for Metallic Copper Vent and Fill Line:

- Material Specification: ASTM B280 Type ACR A (annealed) Copper Tube

Nominal Tube Size, inches	Outside Diameter, inches	Inside Diameter, inches	Wall Thickness, inches	Calculated Minimum Burst Pressure, psi	Working Pressure, 5x4900 psi 100°F
1/2	0.590	0.436	0.032	4097	727

Author: Mark Novak - 3 - Revision Date: 3/23/2012
 Process Owner: Director Product Engineering, CO₂ Solutions Effective Date: 3/23/2012

NUCO Specifications for Phoenix, Arizona: Fill, Vent and Supply Line Materials for NuCO₂ Micro Bulk Tank Installations Item ID #: PFD-01 Revision#: 3.0

Gas Supply Line

Material/Part	Material/Part
Micro Bulk Tank regulated outlet supply gas pressure requirements are between 90 psig for PepsiCo and 120 psig for Coca Cola	Working Pressure: 120 psig minimum
	Burst Pressure Rating: 480 psig minimum (must be > 4X Working Pressure)
	Temperature Rating: 0°F to +125 psig
	SDCO: 0.250"/0.420" and 0.375"/0.535" nominal
	FDA 21 CFR 177 Food Compliant and NSF/ANSI Food Equipment Materials
	Low permeability

NuCO₂ Specifications for Non-Metallic Gas Supply Line material:

- Working Pressure: 125 psig minimum (requirements for Supply Pressure Regulator setting 90 psig for Pepsi and 120 psig Coca-Cola)
- Burst Pressure Rating: 580 psig minimum (4x Working)
- Operating Temperature: -30°F or lower to +125°F (Chart Industries testing demonstrates outlet gas temperature approximately +50°F)
- ID/OD = 0.250"/0.420" and 0.375"/0.535 nominal
- Color: natural
- FDA 21 CFR 177 Food Compliant and NSF/ANSI 51 Food Equipment Materials
- Low permeability

Author: Mark Novak - 4 - Revision Date: 3/23/2012
 Process Owner: Director Product Engineering, CO₂ Solutions Effective Date: 3/23/2012

NUCO Specifications for Phoenix, Arizona: Fill, Vent and Supply Line Materials for NuCO₂ Micro Bulk Tank Installations Item ID #: PFD-01 Revision#: 3.0

NuCO₂ Non-Metallic CO₂ gas beverage supply material example:

FLEX-TECH HOSE & TUBING, INC.
 FEB FDA/NSF-51 POLYETHYLENE BEVERAGE HOSE

Hose is made from premium grade FDA and NSF listed materials. The combination of the EVA cover and the Polyethylene tube material have been carefully selected for low taste and odor properties, superior flexibility, clarity and high environmental stress cracking resistance.

Applications:

- Selt drink fountain machines for retail and commercial dispensing
- Other beverage dispensing to include but not limited to the following:
 - Fruit juice, tea, coffee and coffee related product disp.
 - Water service (sanitized both pre- and non-sterilized)
 - Dairy product dispensing machines

Construction:

- Tube:** extruded from FDA approved (Regulation 21 CFR 177.1520) and NSF-51 listed Polyethylene. Material has been carefully selected for its low taste and odor properties, superior flexibility, clarity and high environmental stress cracking resistance.
- Reinforcement:** Synthetic, high tensile textile cord for improved coupling resistance, higher pressure ratings and longer lasting overall product integrity and durability.
- Connectors:** FDA approved (Regulations 21 CFR 177.1530 and 175.105) Polyethylene Vinyl Acetate (PEVA) Copolymer specially formulated for clarity and added flexibility.
- All materials used in the construction of this product are NSF compliant.**

Specifications:

- Temperature Range: -40°F to +125°F (86-51°C)
- Standard Sizes: 1/4", 3/8", 1/2"
- Rated Working Pressure: 120 psig (8.3 barg) (not to be exceeded)
- SDS units based on drink wrapped in plastic and labeled, 500' or 100' rolls only or equivalent weight
- Available based on redistribution upon request

*Various brand labeling and trace yarn color coding available - minimum order quantities may apply.

Part Number	Size	Length	Weight	Material	Material
PHD10000101	1/2"	100'	100 lbs	PEVA	PEVA
PHD10000102	3/8"	100'	50 lbs	PEVA	PEVA
PHD10000103	1/4"	100'	25 lbs	PEVA	PEVA

Author: Mark Novak - 5 - Revision Date: 3/23/2012
 Process Owner: Director Product Engineering, CO₂ Solutions Effective Date: 3/23/2012

LOGICO₂ CO₂ Alarm Sensor Mk9 Quick Guide

Installation Height
 CO₂ is a heavy gas that accumulates in the lowest areas filling an area from the floor and up. Therefore it is our recommendation to mount the CO₂ Alarm Sensor at 12 inches /30 centimeters from the floor. This way the awareness of a leak is made as early as possible insuring time to deal with the leak as well as avoiding unnecessary loss of CO₂. This also harmonizes with existing code. The Horn/Strobe has to be able to be seen by everybody and mounted 80" to 96" above the floor as per the NFPA 72.

CO₂ detection distance
 The CO₂ Alarm Sensor must be mounted within a 5 meter/ 15 feet radius of the CO₂ distribution point. If a specific distribution point cannot be defined, install the sensor in the most appropriate location to cover a 78 square meter / 840 square foot area to be monitored.

Corridors
 In areas where the CO₂ is stored in the end of a corridor, it is paramount to place an extra Horn Strobe at the entrance of the corridor. This to give early warning in case of a CO₂ leakage.

Lower floor/basement
 In areas where the CO₂ is stored or distributed in Below Grade locations such as Lower Floors and Basements, it is essential to have Horn Strobes before the entrance to the area.

Enclosed Spaces
 In enclosed spaces Horn Strobes must be placed outside of each entrance.

System Installation

Installation Schematics:



11921 Freedom Drive #1110
 Reston, Va 20190
 t 703.668.0086
 rdcollaborative.com

COPYRIGHT NOTICE
 This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL

REVISION	DATE
△ ISSUE	02/15/23
OTP	


PROFESSIONAL IN
 JMS
 PROJECT
 SAG
 QUALITY
 JMS
 DRAWN
 JBA
 PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
 ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE
 PROJECT NUMBER: 22130

CO₂ CUT SHEETS

M1.5

KEYNOTES

- 1 SATELLITE DISH LOCATION. REFERENCE THE ARCH ROOF PLAN FOR EXACT LOCATION.
- 2 EXTERIOR ROOF ACCESS SHOWN FOR REFERENCE ONLY. REFER TO ARCHITECTURAL DRAWINGS FOR MORE INFORMATION.
- 3 ROOF DRAINAGE WITH 4" LEADER. SEE DETAIL 9/A8.3. REFER TO ROOF DRAIN CALCULATION FOR SIZING INFO.

rdc.

11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ ISSUE	DATE
OTP	02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA



PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTCYCLE# R1.2 12/XX/22




CIRCLE K STORE

PROJECT NUMBER: 22130


PLUMBING -
ROOF PLAN

P1.1

ROOF DRAIN CALCULATIONS						
0.0104 = CONVERSION FACTOR - GPM/SQFT FOR 1"/HR RAINFALL.						
AREA NAME	AREA (A1)	PARAPET AREA	1/2 PARAPET WALL AREA (A2)	RAIN FALL RATE (R IN INCHES)	GPM=0.0104 x R x (A1+A2), [EQ 11-1 IPC 1106.2.1]	2018 NORTH CAROLINA PLUMBING CODE: MINIMUM VERTICAL PRIMARY DRAIN SIZE PER TABLE 1106.3
LEFT ROOF	1978 ft²	334 ft²	167 ft²	3.75	84	3"
RIGHT ROOF	1859 ft²	351 ft²	176 ft²	3.75	79	3"
	3838 ft²		343 ft²			




FREEZELESS ROOF HYDRANT | 2
N.T.S.




PLUMBING ROOF PLAN | 1
3/16" = 1'-0"

KEYNOTES

- 1 PVC REFRIGERATION CHASE PROVIDED BY MECHANICAL CONTRACTOR, REF 1-M1.1
- 2 CONTRACTOR TO COORDINATE UNDERGROUND SEWER LINE TO AVOID COLUMN FOOTING.
- 3 PROVIDE 3-COMPARTMENT SINK DRAIN LINES WITH FLOW CONTROL DEVICE AND RUN TO FLOOR SINK ABOVE GRADE. PROVIDE (3) 1 1/2" INDIRECT WASTE, 1 FOR EACH COMPARTMENT OF SINK.
- 4 AIR GAP TO BE TWICE THE EFFECTIVE OPENING OF THE INDIRECT WASTE PIPE.
- 5 REFER TO DETAIL 2/P1.1.1 FOR TYPICAL HUB DRAIN INSTALLATION.
- 6 FLOOR SINK TO BE MINIMUM 50% EXPOSED WITHOUT HAVING TO MOVE ANY EQUIPMENT AND OPEN CABINETS TO GAIN ACCESS.
- 7 DRAIN EQUIPMENT INDIRECTLY TO THE NEAREST FLOOR SINK UNDER CABINET. AIR GAP TO BE TWICE THE EFFECTIVE OPENING. TYPICAL FOR ALL BEVERAGE EQUIPMENT. DRAIN LINE TO MAINTAIN A MINIMUM SLOPE 2% FROM EQUIPMENT TO FLOOR SINK.



HUB DRAIN DETAIL | 2
N.T.S.



PLUMBING FLOOR PLAN - WASTE AND VENT | 1
3/16" = 1'-0"



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE
This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 478-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

Δ ISSUE	DATE
OTP	02/15/23


PROFESSIONAL IN
JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA
PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTOCOL# R1.2 12/XX/22





CIRCLE K STORE
PROJECT NUMBER: 22130

PLUMBING FLOOR PLAN - WASTE AND VENT

P1.1.1

KEYNOTES	
1	3/4" CW DOWN IN WALL EXPOSED TO HB SHALL BE PROVIDED WITH HEAT TAPE AND INSULATION.
2	SHUT-OFF (BALL VALVE) ABOVE CEILING. PROVIDE ACCESS (TYPICAL).
3	THE HEATED WATER SUPPLY PIPING SHALL BE ROUTED TO WITHIN THE LENGTH SPECIFIED FROM THE HEATED WATER SOURCE IN ACCORDANCE WITH THE IECC CH. C404.5.1.
4	PROVIDE TMV PER AHJ REQUIREMENTS, TYP.
5	ROUTE FILTER WATER LINES DOWN WALL AND OVER HORIZONTALLY UNDER CABINET.
6	CO2 LINE TO RUN UP WALL THEN OVERHEAD TO CONNECT TO CARBONATORS. INSTALL PER MANUFACTURERS' INSTALLATION INSTRUCTIONS.
7	MAIN WATER SUPPLY LINE UP IN WALL TO ABOVE CEILING. COORDINATE EXACT LOCATION.
8	FILTERED WATER ABOVE CEILING.

PLUMBING SYMBOLS	
SS	SANITARY SEWER
GW	GREASE WASTE
OW	OIL WASTE
ST	STORM SEWER
RD	ROOF DRAIN LINE
ORD	OVERFLOW ROOF DRAIN LINE
- - -	DOMESTIC COLD WATER
- - -	DOMESTIC HOT WATER
- - -	DOMESTIC HOT WATER RETURN
IW	IRRIGATION WATER
T	110°F TEMPERED WATER
FW	FILTERED WATER
G	NATURAL GAS
A	COMPRESSED AIR
CD	CONDENSATE DRAIN
RO	REVERSE OSMOSIS WATER
V	PLUMBING VENT
VAC	PLUMBING VACUUM
U	UNION
GR	GAS PRESSURE REGULATOR
GC	GAS COCK
ED	ELBOW - TURNED DOWN
EU	ELBOW - TURNED UP
TD	TEE - TURNED DOWN
TU	TEE - TURNED UP
BV	BALL VALVE (BV)
BNC	BYPASS NORMALLY CLOSED (BNC)
PV	PLUG VALVE
CV	CHECK VALVE
SV	SHUT-OFF VALVE IN VERTICAL LINE
BPF	BACKFLOW PREVENTER
M	WATER METER
WHA	WATER HAMMER ARRESTOR
TMV	THERMOMETER
TRV	T & P RELIEF VALVE
TMV	THERMOSTATIC MIXING VALVE
FD	FLOOR DRAIN
RD	ROOF DRAIN/OVERFLOW ROOF DRAIN
FS	FLOOR SINK
FCO	FLOOR CLEANOUT
YCO	YARD CLEANOUT
FPWH	FREEZE PROOF WALL HYDRANT
HB	HOSE BIBB
WCO	WALL CLEANOUT
CE	CONNECT TO EXISTING
ETR	EXISTING TO REMAIN
UNO	UNLESS NOTED OTHERWISE
WHA	WATER HAMMER ARRESTOR
VBF	VENT BELOW FLOOR
?	KEYNOTE CALLOUT SYMBOL (? = NUMBER)
?	PLUMBING FIXTURE CALLOUT SYMBOL



PLUMBING FLOOR PLAN HOT AND COLD WATER | 1
3/16" = 1'-0"

GENERAL NOTES

IF POST MIX IS INSTALLED A STAINLESS R.P.B.A. MUST BE USED OR WILKINS 375X1 WITH NO COPPER INSTALLED DOWNSTREAM OF R.P.B.A.



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL

Jason M. Scates
P.E.
SUITE 5274 1805 N 2ND ST ROGERS, AR 72756
478-636-9004
JOB NO.:
DESIGNED BY:

REVISION	
ISSUE	DATE
OTF	02/15/23


PROFESSIONAL IN
JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA
PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD, ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE
PROJECT NUMBER: 22130


PLUMBING FLOOR PLAN-DOMESTIC WATER

P1.1.2



NOTES:

1. PROVIDE IAPMO APPROVED BACKFLOW PREVENTER IN-LINE TO EACH "NON-CARBONATED" KITCHEN BEVERAGES EQUIPMENT.
2. PROVIDE IAPMO APPROVED REDUCED PRESSURE BACKFLOW PREVENTER TO EACH "CARBONATED" KITCHEN BEVERAGES EQUIPMENT (STAINLESS STEEL)
3. BEVERAGES LINES OF "CARBONATORS" SHALL NOT HAVE ANY COPPER LINES DOWNSTREAM OF REDUCED PRESSURE BACKFLOW PREVENTER.
4. BACKFLOW PREVENTERS SHALL HAVE PROPER DRAINS AND ACCESSIBLE FOR MAINTENANCE.



HOT AND COLD WATER RISER | 2
N.T.S.

WASTE AND VENT PLUMBING RISER | 1
N.T.S.

SITE LOCATION:	ANGIER, NC - KENNEBEC CHURCH RD. AND FALCON CREST CIR.
STATIC PRESSURE:	59 PSI AS PER TEST TAKEN ON 06/15/2022
TOTAL WATER SUPPLY FIXTURE UNIT:	86.75 (PREDOMINANTLY FLUSH VALVES) PER 2018 NCPC
GPM:	38.875
WATER MAIN:	2" (VERIFY WITH WATER COMPANY)
	59.0 PSI (PRESSURE IN MAIN) -8.3 PSI (LOSS THROUGH 2" METER) -2 PSI (LOSS THROUGH TAP) -25 PSI (FIXTURE LOSS AT END, FLUSH VALVE) -7 PSI (14 DROP FOR ELEVATION, 0.5 PSI LOSS PER FT) -12 PSI (BACKFLOW PREVENTER) 4.7 PSI (AVAILABLE PRESSURE)
	PIPE LENGTH (TAP TO METER) 18 FT PIPE LENGTH (METER TO BUILDING) 263 FT PIPE LENGTH (BUILDING TO LAST FIXTURE) 93 FT VERTICAL LENGTH 14 FT EQUIVALENT LENGTH OF FITTINGS 45 FT TOTAL DEVELOPED LENGTH 433 FT
MAX ALLOWABLE LOSS (PER 100 FT OF PIPE):	PRESSURE AVAILABLE 4.7 X 100 = 1.08 PSI/100 FT TOTAL LENGTH 433
SIZE PIPES PER 7 FT/SEC.	
A PRESSURE TEST IS TO BE PERFORMED IMMEDIATELY AFTER AWARDED OF BID. IF PRESSURE IS LOWER THAN LISTED ABOVE, NOTIFY ENGINEER IMMEDIATELY.	


WATER SUPPLY CALCULATION | 3
N.T.S.

GREASE INTERCEPTOR CALCULATION					
VOL = F x R x S					
TAG	FLOW RATE (F)	RETENTION TIME (R MINUTES)	STORAGE FACTOR (S)	GREASE INTERCEPTOR OPERATING VOLUME	COMMENTS
P412	19 GPM	2	0.8	40 gal	GREASE TRAP PROVIDED = 50 GPM/272.7 LBS


GREASE INTERCEPTOR DEMAND					
TAG	DESCRIPTION	VOLUME	COUNT	DRAINAGE TOTAL	GPM
P001	3-COMPARTMENT SINK W/ (2) 18" DRAIN BOARDS	37.4	1	37.4	18.7
Grand total			1	37.4	18.7

2 MINUTE DRAIN TIME


PLUMBING LOADS										
TAG	DESCRIPTION	CWFU	HWFU	DRAINAGE PER (DFU)	COUNT	CW TOTAL (CWFU)	HW TOTAL (HWFU)	DRAINAGE TOTAL (DFU)	TOTAL WATER (WSFU)	TOTAL WATER GPM
P001	3-COMPARTMENT SINK W/ (2) 18" DRAIN BOARDS	3	3	37.4	1	3	3	37.4	6	3
P101	TOILET	10	0	10	3	30	0	30	30	15
P103	URINAL	10	0	4	1	10	0	4	10	5
P107	WALL MOUNTED HAND SINK	2.25	2.25	2	2	4.5	4.5	4	9	4.5
P201	MOP SERVICE SINK	3	3	2	1	3	3	2	6	3
P203	WALL MOUNTED HAND SINK	2.25	2.25	2	1	2.25	2.25	2	4.5	2.25
P204	DROP-IN HAND SINK	2.25	2.25	3	2	4.5	4.5	6	9	4.5
P402	WATER FILTER	1	0	0	1	0	0	0	0	0
P403	FLOOR SINK	0	0	0.5	4	0	0	2	0	0
P404	FLOOR DRAIN WITH TRAP PRIMER	0	0	4	5	0	0	20	0	0
P411	HOSE BIBB	1	0	0	2	2	0	0	2	1
P413	DRINKING FOUNTAIN	0.25	0	0.25	1	0.25	0	0.25	0.25	0.125
P417	FREEZELESS ROOF HYDRANT	1	0	0	1	1	0	0	1	0.5
Grand total					25	60.5	17.25	107.65	77.75	38.875




TRAP PRIMER ASSEMBLY | 1
N.T.S.



2-WAY CLEANOUT DIAGRAM | 3
N.T.S.



EVERPURE WATER FILTER SYSTEM | 2
N.T.S.



WALL MOUNTED ELECTRIC WATER HEATER | 4
N.T.S.

GENERAL NOTES

- FURNISH ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, FEES, PERMITS, CERTIFICATE OF INSPECTION, ETC. NECESSARY OR REASONABLE, REQUIRED FOR THE COMPLETE INSTALLATION OF ALL PLUMBING WORK.
- WORK SHALL COMPLY WITH ALL FEDERAL, STATE, AND LOCAL CODES, LAWS, ACTS, ORDINANCES, REGULATIONS AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
- THE COMPLETED INSTALLATION SHALL BE IN ACCORDANCE WITH ALL THE APPLICABLE INDUSTRY STANDARDS OF GOOD PRACTICE, SAFETY, AND THE MANUFACTURERS STRICTEST RECOMMENDATIONS FOR EQUIPMENT AND PRODUCT APPLICATION AND INSTALLATION.
- THESE DRAWINGS ARE DIAGRAMMATIC ONLY. CONTRACTOR SHALL MAKE MODIFICATIONS INCLUDING OFFSETS, TURNS, AND RE-ROUTING REQUIRED TO COMPLETE THE INSTALLATION. DO NOT SCALE LOCATION OF EQUIPMENT OR PIPING.
- COORDINATE ALL PLUMBING WORK, INCLUDING EQUIPMENT AND PIPING, WITH OTHER TRADES PRIOR TO WORK.
- CONTRACTOR TO VERIFY LOCATION OF ALL EXISTING EQUIPMENT SO THAT NO INTERFERENCES ARE ENCOUNTERED WITH OTHER EQUIPMENT OR WITH STRUCTURAL ELEMENTS.
- ALL PLUMBING WORK IS TO RUN IN A NEAT AND PROFESSIONAL MANNER, WITH THE AESTHETICS OF THE FACILITY OF PARAMOUNT IMPORTANCE. ALL ROUGH-IN WORK TO BE HIDDEN WITHIN WALLS AND ABOVE CEILING UNLESS OTHERWISE NOTED.
- ALL WORK SHALL BE LOCATED TO AVOID CONFLICTS WITH OTHER TRADES. CLOSELY COORDINATE ALL WORK WITH ALL OTHER TRADES. FAILURE OF THE CONTRACTOR TO COORDINATE WITH ALL OTHER TRADES SHALL RELIEVE THE OWNER FROM ANY ADDED COSTS.
- THE CONTRACTOR SHALL DO ALL NECESSARY CUTTING OF WALLS AND CEILING. PATCH AROUND ALL OPENINGS TO MATCH EXISTING CONSTRUCTION. NO STRUCTURAL MEMBER SHALL BE CUT WITHOUT PERMISSION FROM THE ENGINEER.
- VENT SIZES NOT SHOWN IN THE PLAN VIEW OR RISER VIEW SHALL BE 1 1/2\".
- EXACT LOCATION OF PLUMBING FIXTURES SHALL BE DETERMINED FROM ARCHITECTURAL DRAWINGS. CONTRACTOR SHALL VERIFY INVERT ELEVATIONS OF SEWERS TO WHICH NEW WASTE LINES ARE TO BE CONNECTED BEFORE MAKING UP OR INSTALLATION OF NEW WASTE SYSTEM.



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 479-636-9004
1805 N 2ND ST JOB NO.:
ROGERS, AR 72756 DESIGNED BY:

REVISION

ISSUE DATE

OTF 02/15/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA


PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTOCOL# R1.2 12/XX/22



CIRCLE K STORE

PROJECT NUMBER: 22130

PLUMBING-SCHEDULES AND DETAILS

P1.3

PLUMBING FIXTURE SCHEDULE

TAG	DESCRIPTION	MFG.	MODEL	ROUGH-IN SIZE				COUNT	TRIM/REMARKS
				CW	HW	FW	SAN		
B001	FOUNTAIN DRINK DISPENSER	CORNELIUS	ED-300	0"	0"	1/2"	3/4"	2	
B101	ICE MAKER	FOLLETT	HCD1810RH	0"	0"	3/8"	0"	1	19" FOLLETT REMOTE CHEWBLET
B102	1 FOUNTAIN AND/OR BAGGER	MANITOWOC	IYF-1800C-161	0"	0"	3/8"	3/4"	1	30" MANITOWOC REMOTE ICE MAKER (1825LB)
B104	OPTIONAL MULTIPLEX	MULTIPLEX	TS905046G-263	0"	0"	1/2"	0"	1	
B301	FOUR BARREL COUNTERTOP FCB	CORNELIUS	VIPER ELITE-4B	0"	0"	1/2"	0"	2	
B308	FREAL BLENDER AND BLENDING BAR FREEZER	FREAL	B6	0"	0"	1/2"	3/4"	1	
B603	3 WIDE BIB RACK PACKAGE	CORNELIUS	3BIFJ	0"	0"	0"	0"	3	
C001	3-HOPPER BEAN TO CUP BREWER	SCHAERER	040381-00058 EUS	0"	0"	0"	0"	3	
C002	5-HD CAPPUCCINO	WILBURT CURTIS	PCGT5	0"	0"	0"	0"	1	
C201	SMALL COUNTERTOP ICE MAKER	FOLLETT	15CI00A-NW-NF-ST-RD	0"	0"	0"	1/2"	1	

HD	PVC HUB DRAIN	---	---						4	SIZING PER P1.1.1
M102	WATER DISPENSER	GLACIER	G21B	0"	0"	0"	0"	2		(1) 1/2" WATER LINE PER (3) MACHINES 15 PSI MINIMUM. EACH UNIT TO HAVE DEDICATED BALL VALVE SHUTOFF. INDIRECT DRAIN.
P001	3-COMPARTMENT SINK W/ (2) 18" DRAIN BOARDS	ADVANCE TABCO	9-3-54-18RL	1/2"	1/2"	0"	2"	1		GC TO SUPPLY AND INSTALL SINK
P101	TOILET	AMERICAN STANDARD	3043.001	1"			4"	3		VALVE, SLOAN 111 ESS-1.25-TMO-HW WATER CONSERVATION 1.28 GALLONS PER FLUSH, OPEN FRONT SEAT - OLSONITE #10CC.
P103	URINAL	AMERICAN STANDARD	6590.001	3/4"			2"	1		URINAL FLUSH VALVE SLONE 186-ESS-0.5-TMO-HW AUTOMATIC HARD WIRED. WALL BRACKET SUPPORT SET AT ELEV. TO MEET ADA
P107	WALL MOUNTED HAND SINK	KOHLER	K-2005	1/2"	1/2"	0"	1"	2		FAUCET: TOTO TEL3LS-10 - 0.5 GPM SENSOR OPERATED SELF-GENERATING POWER SYSTEM, STANDARD SPOUT, 4" COVER PLATE, GRID STRAINER WITH TAILPIECE, P-TRAP WITH CLEANOUT, STOP VALVES, SS BRAIDED WATER SUPPLIES AND ESCUTOCHONS. CARRIER: JOSAM 17100, WADE W-520, LAVATORY ENCLOSURE: TRUEBRO LAV-SHIELD 2018, PROVIDE P108, ASSE 1070 TMV SET TO 110F.
P108	THERMOSTATIC MIXING VALVE	ZURN	ZW3870XLTf	0"	0"			2		PROVIDE ASSE 1070 CERTIFIED MIXING VALVE SET TO 110°F AT ALL HAND SINKS PER AHJ
P201	MOP SERVICE SINK	MUSTEE	63M	3/4"	3/4"		3"	1		AMERICAN STANDARD #6344.111 WALL MOUNT FAUCET TOP BRACE, VACUUM BREAK, STOPS
P203	WALL MOUNTED HAND SINK	ADVANCE TABCO	7-PS-60	1/2"	1/2"	0"	1 1/2"	1		PROVIDE P108, ASSE 1070 TMV SET TO 110F.
P204	DROP-IN HAND SINK	ELKAY OR EQUAL	K11515	1/2"	1/2"	0"	2"	2		FAUCET BY G.C. CHROME STOPS 1/4 TURN SUPPLIES AND P-TRAP. PROVIDE P108, ASSE 1070 TMV SET TO 110F.
P400	FIXED BLADDER TYPE EXPANSION TANK	AMTROL FLEXCON WATTS WILKINS	ST-12 WH-18 PLT-12 XT-18	0"				1		4.4 GALLON MINIMUM TOTAL CAPACITY, FACTORY STANDARD PRECHARGE CAPACITY.
P401	ELECTRIC WATER HEATER	A.O. SMITH	DRE-52-24	1 1/4"	1 1/4"			1		3/4" P & T RELIEF VALVE. 52 GAL STORAGE. ELECTRICAL, 24 KW, 208V, 3PH.
P402	WATER FILTER	EVERPURE	EV9437-10	3/4"		3/4"	3/4"	1		
P403	FLOOR SINK	ZURN	Z1901					4		1/2" GRATE WITH 12"x12" (6" DEEP) PORCELAIN SEDIMENT BUCKET
P404	FLOOR DRAIN WITH TRAP PRIMER	WADE	1000-S-TD6.1					5		SATIN STRAINER
P405	FLOOR CLEANOUT	J.R. SMITH	4100 SERIES					3		ADJUSTABLE FLOOR CLEANOUT, 5 IN ROUND NICKEL BRONZE TOP, 4 IN PIPE, GAS TIGHT GASKETED BRASS PLUG, NO HUB OUTLET, MD LOAD RATING.
P406	TRAP PRIMER	SIoux CHIEF	SERIES 695	1/2"				3		OR APPROVED EQUIVALENT. AMOUNTS AS REQUIRED
P409	RECIRCULATION PUMP	TACO	T003-BC4	1/2"	0"	0"	0"	1		FLOW RANGE: 0 - 52 GPM, HEAD RANGE (FT): 0 - 32', HP: 1/40 - 1/6, CONNECTION SIZES: 3/4" - 1/2" FLANGED, 3/4" SWEAT, NPT OR UNION
P411	HOSE BIBB	MIFAB	MHY-35	3/4"				2		ANTI-SIPHON VACUUM BREAKER PROTECTED, VANDAL RESISTANT VACUUM BREAKER.
P412	40 GALLON PORTABLE GREASE INTERCEPTOR	SCHIER	GB3					1		ABOVE GROUND INSTALL
P413	DRINKING FOUNTAIN	OASIS	PG8ACSLTM	3/8"	0"	0"	1 1/4"	1		
P415	DUAL CHECK VALVE ATMOSPHERIC PORT & STRAINER FOR CARBONATED BEVERAGE MACHINES	WATTS	SD-3	3/8"				12		STAINLESS STEEL BODY CONSTRUCTION WITH INTERNAL RUBBER COMPONENTS AND IS DESIGNED FOR CONTINUOUS OR INTERMITTENT PRESSURE APPLICATIONS. WITH A WYE PATTERN STRAINER. MAXIMUM WORKING PRESSURE: 150PSI (10 BAR)
P417	FREEZELESS ROOF HYDRANT	WOODFORD	RHY2-MS	3/4"				1		PROVIDE MOUNTING SYSTEM AND DRAIN. ROUTE 1/8" DRAIN LINE TO NEAREST APPROVED DRAIN WITH AIR GAP. HYDRANT TO BE PROVIDED WITH A DOUBLE CHECK BACKFLOW PREVENTER.



SECTION	PLUMBING SPECIFICATIONS	SECTION	PLUMBING SPECIFICATIONS
15010 BASIC MECHANICAL REQUIREMENTS	1. ALL WORK TO BE DONE AND MATERIALS FURNISHED COMPLYING WITH APPLICABLE LAWS AND REGULATIONS, INCLUDING THE STATE OF XXXX MECHANICAL, PLUMBING AND FIRE SAFETY CODES. OBTAIN AND PAY FOR REQUIRED PERMITS AND FEES. 2. ALL MATERIALS USED SHALL BE NEW AND UNDAMAGED. 3. ALL WORK PERFORMED SHALL BE IN ACCORDANCE WITH CURRENT CONSTRUCTION INDUSTRY STANDARDS AND WORKMANSHIP. 4. FURNISH SHOP DRAWINGS TO ARCH/ENGINEER FOR APPROVAL PRIOR TO PLACING DELIVERY ORDERS. PROVIDE SHOP DRAWINGS OF ALL MANUFACTURED EQUIPMENT AND MATERIALS EXCEPT PIPE, PIPE FITTINGS AND GALVANIZED DUCTWORK. 5. FURNISH ACCESS DOORS (RATED OR NON-RATED AS REQUIRED) WHERE VALVES OR EQUIPMENT ARE CONCEALED BEHIND A NON ACCESSIBLE CEILING OR WALL. FURNISH ACCESS DOORS TO GENERAL CONTRACTOR FOR INSTALLATION. 6. FURNISH STEEL PIPE SLEEVES WHERE PIPES PENETRATE RATED WALLS. PROVIDE FIRESTOPPING MATERIALS AND SYSTEM TO MAINTAIN THE REQUIRED RATING OF THE WALL PENETRATED. PROVIDE SHOP DRAWINGS SHOWING LISTING AND RATING OF FIRESTOPPING MATERIALS. 7. ALL MANUFACTURED EQUIPMENT, ACCESSORIES AND MATERIALS SHALL BE USED AS INTENDED BY THE MANUFACTURER IN STRICT ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTALLATION, OPERATION AND MAINTENANCE INSTRUCTIONS. 8. CONTRACTOR SHALL PROVIDE IN ADDITION TO ANY OTHER WARRANTIES SPECIFIED, A ONE YEAR FULL LABOR AND MATERIAL WARRANTY ON ALL WORKMANSHIP, MATERIAL AND EQUIPMENT FURNISHED FOR THIS PROJECT. 9. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL OPENINGS AND REQUIRED LINTELS NEEDED FOR THE GENERAL CONTRACTOR FOR THE INSTALLATION OF MECHANICAL EQUIPMENT. 10. SAWCUTS, LINTELS, HEADERS, AND STRUCTURAL MODIFICATIONS TO THE BUILDING STRUCTURE NEEDED FOR THE INSTALLATION OF MECHANICAL EQUIPMENT SHALL BE APPROVED BY THE GENERAL CONTRACTOR, BEFORE INSTALLATION. 11. IN GENERAL, OPENINGS AND REQUIRED LINTELS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR PROVIDING DETAILS AND TEMPLATES OF ALL OPENINGS NECESSARY FOR MECHANICAL EQUIPMENT INSTALLATION INCLUDING: HOUSING, ACCESS DOORS, INSPECTION DOORS, AND PASSAGEWAYS FOR MECHANICAL EQUIPMENT. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR SEALING CRACKS AND FINISHING ROUGH EDGES LEFT FOLLOWING MECHANICAL INSTALLATION. 12. APPROVAL EQUALS: PLUMBING ITEMS MANUFACTURED BY A COMPANY OTHER THAN THAT WHICH WAS SPECIFIED IN THE SCHEDULE MAY BE SUBSTITUTED BY APPROVED SHOP DRAWINGS CONTINGENT UPON MEETING THE DESIGN, APPEARANCE, AND FUNCTIONAL STANDARDS ESTABLISHED BY THE ORIGINALLY SPECIFIED ITEM(S). THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING DIMENSIONS, CLEARANCES, ASSEMBLY, FIT, ETC. OF THE APPROVED EQUAL(S), AND THEIR AFFECT ON OTHER EQUIPMENT FIT AND OPERATION. THE CONTRACTOR IS LIABLE FOR ANY ADDED COSTS TO HIMSELF OR OTHERS CAUSED BY THE APPROVED EQUALS.	15100 VALVES	1. BALL VALVES SHALL BE CLASS 125 FOR WATER WITH ENDS AND MATERIALS TO MATCH PIPING SYSTEMS. 2. BALL VALVES 2" AND SMALLER SHALL HAVE BRONZE BODY, STAINLESS STEEL BALL, TEFLON SEATS, AND STUFFING BOX RING, LEVER HANDLE AND BALANCING STOPS, ENDS TO MATCH PIPING SYSTEM.
		15140 SUPPORTS & ANCHORS	1. FURNISH PIPE AND DUCT HANGERS, WHERE REQUIRED, FIRMLY SUPPORTED FROM BUILDING STEEL, CONCRETE OR MASONRY STRUCTURE. SUPPORT PIPING SYSTEMS SECURELY WHILE ALLOWING FOR PIPE AND BUILDING EXPANSION AND CONTRACTION. PROVIDE COPPER PLATED HANGERS, FOR COPPER PIPE. USE ADJUSTABLE CLEVIS HANGERS OR ADJUSTABLE STEEL BAND HANGERS. MAXIMUM SPACING SHALL BE 5' FOR 1/2" PIPING, 7' FOR 3/4" TO 1" PIPING, 9' FOR 1-1/2" TO 2" PIPING. FURNISH PLUMBING EQUIPMENT SUPPORTS AS DETAILED OR AS REQUIRED TO SAFELY AND PERMANENTLY CARRY THE WEIGHT OF THE EQUIPMENT.
		15250 PLUMBING INSULATION	1. INSULATE ABOVE FLOOR WATER PIPING WITH ELASTOMERIC PLASTIC PERFORMED PIPE INSULATION WITHOUT JACKETING. ALL INSULATING MATERIALS TO HAVE FLAME SPREAD RATING OF 25 OR LESS AND SMOKE DEVELOPMENT RATING OF 50 OR LESS AS TESTED BY ANSIASTM E 84 (NFPA 233) METHOD. INSULATE ALL PIPING WITH SURFACE TEMPERATURES BELOW 75 DEGREE F WITH 1/2" INSULATION. INSULATE ALL PIPING WITH SURFACE TEMPERATURES 75 DEGREES F AND HIGHER WITH 1" THICK INSULATION. INSTALL MINIMUM 1" INSULATION ON ALL HOT WATER PIPING AND THE FIRST 8' OF COLD WATER PIPING AT THE TANK. JOINTS IN INSULATION SHALL BE GLUED, NOT TAPED. WHERE PIPES ARE EXPOSED AND LESS THAN 8' ABOVE FLOOR, PROVIDE HEAVY DUTY METAL JACKETING OVER INSULATION. INSULATE ABOVE FLOOR HORIZONTAL STORM PIPING WITH 1" FIBERGLASS PERFORMED PIPE INSULATION WITH FACTORY APPLIED ALL PURPOSE COVER.
		15411 WATER DISTRIBUTION SYSTEM	1. ABOVE GRADE: WATER PIPING SHALL BE CROSSLINKED PE (PEX) TUBING: PEX TUBE SHALL BE TESTED AND CERTIFIED FOR POTABLE WATER SYSTEMS, AND SHALL COMPLY WITH ANSINSF STANDARD 14, ANSINSF STANDARD 61, AND ASTM F876 AND/OR ASTM F877. TUBE SHALL BE LABELED WITH THE ABOVE CERTIFICATIONS. PROVIDE PEX TUBING SYSTEM BY ONE OF THE FOLLOWING: UPONOR, OR APPROVED PEX ALTERNATIVE. FITTINGS AND CONNECTORS SHALL BE BY THE SAME MANUFACTURER AND ASSEMBLED WITH THE MANUFACTURER'S APPROVED TOOLS. THE SAME CONNECTION METHOD SHALL BE USED THROUGHOUT THE INSTALLATION. a. AT CONTRACTOR'S OPTION, IN LIEU OF PEX PIPING SYSTEM AS SPECIFIED ABOVE TYPE L COPPER ASTM B 75, ASTM B 88, ASTM 251, ASTM B 447 WITH WROUGHT COPPER SOLDER-JOINT FITTINGS ASME B 16. 2. BELOW GRADE: WATER PIPING SHALL BE PEX PIPING SYSTEM IN COMPLIANCE WITH THE UPONOR PLUMBING DESIGN ASSISTANCE MANUAL (PDAM), CURRENT EDITION AND THE UPONOR PIPING SYSTEMS INSTALLATION GUIDE, CURRENT EDITION (OR APPROVED ALTERNATIVE), CROSSLINKED PE (PEX) TUBING, ASTM F876 WITHOUT JOINTS BENEATH THE SLAB. a. AT CONTRACTOR'S OPTION, IN LIEU OF PEX PIPING TYPE K COPPER WITH WROUGHT COPPER SOLDER-JOINT FITTINGS. SOLDER SHALL BE 9596-396 TIN-ANTIMONY ANSIASTM B 32 FOR HEATING SYSTEM PIPING. 3. THOROUGHLY FLUSH AND CLEAN ALL NEW AND EXISTING WATER PIPING SYSTEMS. TEST ALL PIPING SYSTEMS PER REGULATIONS IN ITEM NO.1 OR AT 225 PSI FOR A MINIMUM OF 2 HOURS WITH NO PRESSURE DROP INDICATED PRIOR TO INSULATING. STERILIZE ALL DOMESTIC WATER PIPING PRE REQUIREMENTS OF LOCAL HEALTH DEPARTMENT.
	15420 DRAINAGE & VENT SYSTEMS	1. WITHIN BUILDING, SCHEDULE 40 PVC, DWV TYPE PIPE AND SOLVENT WELDED PIPE FITTINGS, SCHEDULE 30 PVC PIPE MAY BE USED FOR VENT PIPING WHERE PERMITTED BY CODE. HORIZONTAL PIPE SHALL BE SUPPORTED BY ADJUSTABLE RING HANGERS EQUAL TO ITT-GRINNEL FIG. 97. VERTICAL PIPING SHALL BE SUPPORTED AT EACH FLOOR OR ATTIC LEVEL BY RISER.	
	15440 PLUMBING FIXTURES	1. PROVIDE AIR CHAMBERS AT EACH FIXTURE CONNECTION. AIR CHAMBERS SHALL BE ONE SIZE LARGER THAN SUPPLY PIPE AND SHALL BE 12" LONG, WHERE REQUIRED BY PLUMBING CODE. FURNISH AND INSTALL MANUFACTURED WATER HAMMER ARRESTORS. 2. PLUMBING FIXTURES SHALL BE INSTALLED WHERE SHOWN ON THE ARCHITECTURAL DRAWINGS. INSTALL FIXTURES LEVEL AND PLUMB. FURNISH TRAPS WHERE REQUIRED. FIXTURES SHALL BE EASILY REMOVABLE FOR SERVICE AND CLEANING. 3. PROVIDE CHROME PLATED RIGID OR FLEXIBLE SUPPLIES TO FIXTURES WITH STOP VALVES. CHROME PLATED 17 GAUGE BRASS TRAPS WITH CHROME PLATED ESCUTCHEONS. 4. SEAL ALL FIXTURES TO WALL AND FLOOR USING SILICONE SEALANT. MATCH SEALANT COLOR TO FIXTURE COLOR. 5. FIXTURES DESIGNATED BARRIER FREE SHALL BE INSTALLED IN COMPLIANCE WITH AMERICAN'S WITH DISABILITIES ACT. 6. ALL CLEANOUT COVERS TO BE STAINLESS STEEL.	

rdc.

11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT NOTICE

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional

PROFESSIONAL



SUITE 5274 1805 N 2ND ST ROEGERS, AR 72756 478-636-9004 JOB NO.: DESIGNED BY:

REVISION

△ ISSUE DATE

REVISION	DATE

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA


PROJECT

CIRCLE K STORES, INC.

ANGIER, NC

9706 KENNEBEC CHURCH ROAD, ANGIER, NC

PROTOCOL# R1.2 12/XX/22




CIRCLE K STORE

PROJECT NUMBER: 22130

PLUMBING-SPECIFICATIONS

P1.4



ANNOTATION SYMBOLS	
SYMBOL	DESCRIPTION
⊙	KEYED NOTE
Room name	ROOM NAME
101	ROOM NUMBER
EF 3	HEX SYMBOL INDICATES NEW EQUIPMENT NUMBER REFERS TO SPECIFIC EQUIPMENT IDENTIFIED IN EQUIPMENT SCHEDULE
XX	REVISION TRIANGLE REVISION NUMBER
1 A101	DETAIL NUMBER DETAIL SYMBOL DRAWING WHERE DETAIL APPEARS
1 11 TYP	FIXTURE TAG SCHEDULE CALLOUT TYP OF NUMBER IN SYSTEM
1 SIM	DETAIL NUMBER SECTION CUT SYMBOL DRAWING WHERE DETAIL APPEARS
MECHANICAL SYMBOLS	
SYMBOL	DESCRIPTION
1" G	PIPE SIZE AND GAS PIPING SYSTEM
●	FULL PORT BALL VALVE
⊙	THERMOSTAT
SYMBOLS LIST NOTES	
1. SYMBOLS LISTS, NOTES, ABBREVIATIONS, ETC. ARE FOR GENERAL REFERENCE ONLY. THE PRESENCE OF SYMBOLS, NOTES, ABBREVIATIONS, ETC. DOES NOT IMPLY ITS USE ON THIS PROJECT. REFER TO DRAWINGS FOR SPECIFIC SYMBOLS, NOTES, ABBREVIATIONS, ETC. USED.	


ABBREVIATIONS			
AC	AIR CONDITIONING UNIT	IN	INCHES
AD	ACCESS DOOR	KVA	KILOVOLT-AMPERE
AF	ABOVE FINISHED FLOOR	KW	KILOWATT
AL	ACOUSTICAL LINING	KWH	KILOWATT HOUR
AMP	AMPERE (AMPS)	LB	POUNDS
AP	ACCESS PANEL	MAX	MAXIMUM
BF	BELOW FLOOR	MA	MAIN AIR (CONTROLS)
BHP	BRAKE HORSE POWER	MCC	MOTOR CONTROL CENTER
BOD	BOTTOM OF DUCT	MIN	MINIMUM
BOP	BOTTOM OF PIPE	NA	NOT APPLICABLE
BTU	BRITISH THERMAL UNIT	NC	NOISE CRITERIA
BTUH	BTU PER HOUR	NIC	NOT IN CONTRACT
BD	BACKDRAFT DAMPER	#.NO.	NUMBER (QUANTITY)
C	CELSIUS	NO	NORMALLY OPEN
CI	CAST IRON	NC	NORMALLY CLOSED
CFM	CUBIC FEET PER MINUTE	NTS	NOT TO SCALE
CO	CLEANOUT	OA	OUTSIDE AIR
CONT.	CONTINUATION	ORB	OPPOSED BLADE DAMPER
D	DRAIN	PRV	PRESSURE REDUCING VALVE
Db	DECIBEL	PSI	POUNDS PER SQUARE INCH
DB	DRY BULB	PSIG	POUNDS PER SQUARE INCH GAUGE
DBT	DRY BULB TEMPERATURE	PD	PRESSURE DROP
DIA.	DIAMETER	QTY	QUANTITY
DX	DIRECT EXPANSION	QUAD	QUADRANT
EFF	EFFICIENCY	RA	RETURN AIR
ENT	ENTERING	REQ	REQUIRED
EXH	EXHAUST	RH	RELATIVE HUMIDITY
EMS	ENERGY MANAGEMENT SYSTEM	RM	ROOM
°F	DEGREES FAHRENHEIT	RPM	REVOLUTIONS PER MINUTE
FB	FLAT BOTTOM	SA	SUPPLY AIR
FCO	FLOOR CLEANOUT	SCD	SMOKE CONTROL DAMPER
FCU	FAN COIL UNIT	S.DPR	SMOKE DAMPER
FD	FLOOR DRAIN	SP	STATIC PRESSURE (INCHES OF WATER)
FD	FIRE DAMPER	SPEC	SPECIFICATION
FG	FILTER GAUGE	SO	SQUARE
FLEX	FLEXIBLE	SDVV	SINGLE DUCT VARIABLE VOLUME
FPM	FEET PER MINUTE	ST	SOUND TRAP
FPS	FEET PER SECOND	TEMP	TEMPERATURE
FS	FLOOR SINK	TSTAT	THERMOSTAT
FT	FEET	TP	TOTAL PRESSURE (INCHES OF WATER)
FSD	FIRE/SMOKE DAMPER	TYP	TYPICAL
GAL	GALLONS	UC	UNDERCUT
GAL	GALLONS PER MINUTE	V	VOLTS
GPM	GALLONS PER MINUTE	VAC	VOLTS, ALTERNATING CURRENT
GPH	GALLONS PER HOUR	VAV	VARIABLE AIR VOLUME
GPR	GAS PRESSURE REGULATOR	VEL	VELOCITY
HB	HOSE BIBB	VERT	VERTICAL
HD	HAND DAMPER (VOLUME DAMPER)	VTR	VENT THRU ROOF
HORZ	HORIZONTAL	WB	WET BULB
HP	HORSEPOWER	WCO	WALL CLEANOUT
HR	HOUR(S)	WH	WALL HYDRANT
		Z	ZONE

INSTALLATION NOTES	
ALL MECHANICAL EQUIPMENT SHALL BE ANCHORED TO RESIST SEISMIC FORCES. THE SEISMIC BRACING / ANCHORAGE OF DUCTWORK AND EQUIPMENT SHALL BE IN ACCORDANCE WITH, "GUIDELINES FOR SEISMIC RESTRAINTS OF MECHANICAL AND PLUMBING SYSTEMS", PUBLISHED BY S.M.A.C.N.A. AND P.P.I.C., APPROVED BY O.S.A., AND ALL LOCAL AND I.B.C. CODES AND STANDARDS.	

UNIT HEATER SCHEDULE											
MARK	LOCATION	MANUFACTURER	MODEL	CFM	MOTOR					WEIGHT	NOTES
					POWER	VOLTAGE	PH	HZ	MCA		
UH 1	WASH BAY	REZNOR	EWHB	700	7.5 kW	208 V	1	60 Hz	14.00 A	70 lb	
UH 2	EQUIPMENT ROOM	REZNOR	EGW	300	3.75 kW	208 V	1	60 Hz	14.00 A	20 lb	

NOTE:

- PROVIDE WITH REMOTE THERMOSTAT AND SPARK IGNITION.
- MOUNT BOTTOM OF UNIT HEATER 11'-0" AFF.
- HEATERS ARE INTENDED ONLY FOR FREEZE PROTECTION



GENERAL NOTES	
<p>A. PROVIDE ALL HEATING, ITEMS INDICATED ON THE DRAWINGS, DESCRIBED IN THIS SPECIFICATION, OR REQUIRED FOR A COMPLETE AND PROPER INSTALLATION. HVAC WORK INCLUDES THE FOLLOWING:</p> <ol style="list-style-type: none"> UNIT AND RADIANT HEATERS DUCTS, FILTERS, DAMPERS, GRILLES, REGISTERS, DIFFUSERS; CONTROLS, INCLUDING 24 VOLT CONTROL WIRING AND 120/24 VOLT TRANSFORMERS; CONDUIT FOR LOW VOLTAGE WIRING; <p>B. FURNISH, WITHOUT EXTRA CHARGE, ANY ADDITIONAL MATERIAL AND LABOR REQUIRED TO COMPLY WITH THE ABOVE CODES AND STANDARDS, EVEN THOUGH THE WORK MAY NOT BE DESCRIBED IN THE CONTRACT DOCUMENTS. WHERE THE REQUIREMENTS OF THE CONTRACT DOCUMENTS EXCEED THE REQUIREMENTS OF THE ABOVE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE.</p> <p>C. AFTER AWARD OF CONTRACT AND BEFORE COMMENCING WORK, IF REQUESTED BY CIRCLE K PROJECT ENGINEER, SUBMIT SIX COPIES OF THE FOLLOWING TO THE ARCHITECT FOR APPROVAL. SUBMITTALS SHALL BE IN BROCHURE FORM WITH INDEX AND SELECTED ITEMS CLEARLY DESIGNATED AND REFERENCED TO THE APPROPRIATE EQUIPMENT TAG NUMBER:</p> <ol style="list-style-type: none"> COMPLETE MATERIALS LIST OF ALL ITEMS PROPOSED TO BE FURNISHED AND INSTALLED UNDER THIS SECTION; CATALOG CUTS AND OTHER DATA REQUIRED TO DEMONSTRATE COMPLIANCE WITH THE CONTRACT DOCUMENTS. <p>D. COOPERATE WITH OTHER TRADES IN ORDER THAT ALL SYSTEMS IN THE WORK MAY BE INSTALLED IN THE BEST ARRANGEMENT.</p> <p>E. EXAMINE THE AREAS AND CONDITIONS UNDER WHICH WORK OF THIS SECTION WILL BE INSTALLED. CORRECT CONDITIONS DETRIMENTAL TO THE PROPER AND TIMELY COMPLETION OF THE WORK. NOTIFY ARCHITECT OF ANY DISCREPANCIES. DO NOT PROCEED UNTIL UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED.</p> <p>F. AVOID INTERFERENCE WITH STRUCTURE, AND WITH WORK OF OTHER TRADES. INSTALL ALL EQUIPMENT PER MANUFACTURER'S INSTRUCTIONS. INSTALL ACCESSIBLE PARTS, INCLUDING EQUIPMENT, COILS, VALVES, DAMPERS, CONTROLS, AND FILTERS WITH ADEQUATE CLEARANCE FOR INSPECTION, ADJUSTMENTS, REPAIR, AND REPLACEMENT.</p> <p>G. ALL OTHER MATERIALS, NOT SPECIFICALLY DESCRIBED BUT REQUIRED FOR A COMPLETE AND PROPER INSTALLATION, SHALL BE AS SELECTED BY THE CONTRACTOR SUBJECT TO ACCEPTANCE BY THE ENGINEER.</p> <p>H. DO NOT CUT INTO OR REDUCE THE SIZE OF ANY STRUCTURAL MEMBER WITHOUT THE PERMISSION OF THE ARCHITECT.</p> <p>I. CONTRACTOR SHALL FURNISH ALL NECESSARY STRUCTURES, INSERTS, SLEEVES, AND HANGING DEVICES FOR INSTALLATION OF MECHANICAL AND PLUMBING EQUIPMENT, DUCTWORK AND PIPING, ETC. CONTRACTOR SHALL COORDINATE WITH GENERAL CONTRACTOR AND ALL BUILDING TRADES TO AVOID CONFLICTS AND TO MAINTAIN EQUIPMENT ACCESS AND SERVICEABILITY.</p> <p>J. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY MISCELLANEOUS ANGLES, CHANNELS, UNISTRUT, ETC., AS MAY BE REQUIRED TO ADEQUATELY SUPPORT THE MECHANICAL PIPING, DUCTWORK, AND EQUIPMENT IN A MANNER APPROVED BY THE ARCHITECT WHICH WILL NOT OVERLOAD THE BUILDING STRUCTURAL SYSTEM.</p> <p>K. NOTIFY CIRCLE K PROJECT ENGINEER AT LEAST 24 HOURS PRIOR TO COVERING OR ENCLOSING WORK. DO NOT ALLOW OR CAUSE ANY OF THE WORK OF THIS SECTION TO BE COVERED UP OR ENCLOSED UNTIL IT HAS BEEN OBSERVED AND ACCEPTED BY THE CIRCLE PROJECT ENGINEER AND BY ALL OTHER AUTHORITIES HAVING JURISDICTION.</p> <p>L. THE ENTIRE SYSTEM SHALL BE WARRANTED FOR A PERIOD OF ONE (1) YEAR BEGINNING WITH OWNER'S ACCEPTANCE OF THE WORK. ALL LABOR AND MATERIALS NECESSARY TO REPAIR OR REPLACE THE SYSTEM, OR PORTIONS THEREOF, DURING THAT TIME SHALL BE WARRANTED FOR A PERIOD OF ONE (1) YEAR FROM THE REPAIR OR REPLACEMENT.</p> <p>M. INSTRUCT OWNER'S REPRESENTATIVE IN THE OPERATION OF THE SYSTEMS.</p> <p>N. PROVIDE ONE REPRODUCIBLE AS-BUILT DRAWING AND AN OPERATION AND MAINTENANCE MANUAL. AS A MINIMUM, THE MANUAL SHALL CONTAIN:</p> <ol style="list-style-type: none"> A COMPLETE LIST OF ALL EQUIPMENT AND APPURTENANCES WITH EQUIPMENT DESIGNATIONS (PER DRAWINGS), MANUFACTURERS, AND CATALOG NUMBERS. COPIES OF MANUFACTURERS' BROCHURES AND INSTRUCTIONS FOR OPERATION AND MAINTENANCE OF ALL MECHANICAL EQUIPMENT, INCLUDING REPLACEMENT PARTS LISTS. TYPED SYSTEM OPERATION AND MAINTENANCE INSTRUCTIONS, INCLUDING INSPECTION, LUBRICATION, AND SERVICE INSTRUCTIONS AND SCHEDULES. LIST OF NAMES, ADDRESSES AND PHONE NUMBERS OF DISTRIBUTORS OF ALL EQUIPMENT AND APPURTENANCES. MANUFACTURERS' WARRANTIES. 	

CODE INFORMATION	
<p>A. 2018 NORTH CAROLINA BUILDING CODE (2018 NBC), 2018 NPC, 2018 NCMG, AND 2018 NCECC.</p> <ul style="list-style-type: none"> ALL SYSTEMS SHALL BE IN COMPLIANCE WITH THE ABOVE CODES AS ADOPTED BY THE CITY OF ANGIER. <p>B. EQUIPMENT AND APPLIANCES SHALL BE INSTALLED AS REQUIRED BY THE TERMS OF THEIR APPROVAL, IN ACCORDANCE WITH THE CONDITIONS OF THE LISTING, THE MANUFACTURERS INSTALLATION INSTRUCTIONS AND THIS CODE. MANUFACTURERS INSTALLATION INSTRUCTIONS SHALL BE AVAILABLE ON THE JOB SITE AT THE TIME OF INSPECTION PER IMC SECTION 304.1.</p>	

MATERIALS SPECIFICATIONS	
<ol style="list-style-type: none"> INSTALL ALL EQUIPMENT IN ACCORDANCE WITH MANUFACTURERS' INSTRUCTIONS AND RECOMMENDATIONS. PROVIDE WEATHER-PROOF FLASHINGS AT ALL PIPE PENETRATIONS THROUGH THE BUILDING WALLS AND ROOF. AS A MINIMUM, FLASHINGS SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH SMACNA STANDARDS. FLASHINGS SHALL BE GUARANTEED WEATHERPROOF FOR THE DURATION OF THE GUARANTEE. SUPPORT ALL HVAC UNITS, PIPING AND OTHER APPURTENANCES. DO NOT SCREW OR DRIVE FASTENERS INTO NON-STRUCTURAL COMPONENTS SUCH AS ROOF DECKS OR WALLS. THOROUGHLY CLEAN ALL COMPONENTS AND REMOVE ALL DIRT, SCALE, OIL, AND OTHER FOREIGN SUBSTANCES. PROVIDE CLEAN AIR FILTERS FOR ALL EQUIPMENT. FURNISH ACCESS DOORS AND PANELS AT WALLS, AND CEILINGS FOR ACCESS TO HARDWARE, CONTROLS, OPERATOR, DRIVE MECHANISMS AND VOLUME DAMPERS. 	



KEYNOTES

- 1 T-STAT. SET TO 40°F.
- 2 LOCATE 3'-4" ABOVE FINISHED FLOOR ON EXTERIOR WALL.

rdc.

11921 Freedom Drive #1110
 Reston, Va 20190
 t 703.668.0086
 rdcollaborative.com

COPYRIGHT

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional.


PROFESSIONAL



SUITE 5274 479-638-5004
 1605 N 2ND ST JOB NO.: 23894
 ROGERS, AR 72756 DESIGNED BY: JBA

REVISION

ISSUE	DATE
OTP	02/10/23



MECHANICAL FLOOR PLAN | 1
 1/4" = 1'-0"



PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN


JBA

PROJECT

CIRCLE K STORES, INC.
DET CW
ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
 ANGIER, NC

PROTOTYPE CYCLE # R3.2 12/19/22



CIRCLE K STORE


PROJECT NUMBER: 22130

CW MECHANICAL FLOOR PLAN

M2.0-CW

KEYNOTES


- 1 DOWN IN WALL TO DISCHARGE TO STORM DRAIN.
- 3 TIE INTO EXISTING 6" SAN. LINE ON SITE AS REQUIRED. PROVIDE WITH BACKWATER VALVE DOWNSTREAM OF RECLAIM TANK.
- 4 INTERCEPTOR SYSTEM PER MARK VII LOCATE PER CIVIL PLANS.
- 5 RO MACHINE AND WATER SOFTENER TO DRAIN IN TO TRENCH DRAIN.
- 6 2" SCHD 80 PVC SUCTION LINES TO RECOVERY SYSTEM. ONE LINE USED AS SPARE.
- 7 1" SCH 80 PVC LINE TO SERVE AS A CONDUIT FOR (4) 14 GAUGE WIRES (TWO ARE SPARES) TERMINATED IN A WATER TIGHT JUNCTION BOX ABOVE THE WATER LINE TO PURWATER RECLAIM SYSTEM FOR FLOAT CONTROLS
- 8 1" SCH 80 PVC LINE FOR OZONE RETURN IN RECLAIM TANK.
- 9 1" LINE FOR BACKWASH/SEPARATOR RETURN LINE.
- 10 1 1/2" LINE SUPPLY FEED TO WASH MANIFOLD.
- 11 3" VENT FOR OS1. COORDINATE WITH LADDER TO ROOF LOCATION.
- 12 VALVE AND CAP LINE FOR CARWASH INSTALLER FUTURE CONNECTION.
- 14 2" DOM. WATER LINE AND 2" METER AND REDUCED PRESSURE BACKFLOW PREVENTER ARE LOCATED EXTERIOR OF BUILDING. REFER TO CIVIL UTILITY PLAN FOR EXACT LOCATION.
- 15 PROVIDE MAIN SHUT-OFF VALVE 18" AFF.



WATER SUPPLY CALCULATIONS

SITE LOCATION:	ANGIER, NC - KENNEBEC CHURCH RD AND FALCON CREST CIR.
STATIC PRESSURE:	59 PSI - NOTIFY ENGINEER IF STATIC PRESSURE IS LOWER THAN STATED.
GPM:	30
WATER MAIN:	2" (VERIFY WITH WATER COMPANY)
	59.0 PSI PRESSURE IN MAIN -3.5 PSI 7' DROP FOR ELEVATION, 0.5 PSI PER FT -8.3 PSI LOSS THROUGH 2" METER -2 PSI LOSS THROUGH TAP -30 PSI PRESSURE REQ'D FOR CAR WASH EQUIPMENT -12 PSI BACKFLOW PREVENTER 3.2 PSI RESIDUAL PRESSURE
	PIPE LENGTH (CURB STOP TO METER) 18 FT PIPE LENGTH (METER TO LAST FIXTURE) 561 FT VERTICAL LENGTH 14 FT EQUIVALENT LENGTH OF FITTINGS 55 FT TOTAL DEVELOPED LENGTH 646 FT
MAX ALLOWABLE LOSS (PER 100 FT OF PIPE):	RESIDUAL PRESSURE: $3.2 \times 100 = 0.49$ PSI/100 FT TOTAL LENGTH: 646
SIZE PIPES PER 7 FT/SEC.	

PLUMBING SUPPLY PLAN | 2
1/4" = 1'-0"



PLUMBING DRAINAGE PLAN | 1
1/4" = 1'-0"



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional
PROFESSIONAL



SUITE 5274 479-638-5004
1805 N 2ND ST JOB NO.: 23894
ROGERS, AR 72756 DESIGNED BY: JBA


REVISION

Δ ISSUE	DATE
OTP	02/10/23

PROFESSIONAL IN
JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA
PROJECT

CIRCLE K STORES, INC.
DET CW
ANGIER, NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC
PROTOTYPE CYCLE # R3.2 12/19/22



CIRCLE K STORE
PROJECT NUMBER: 22130

CW PLUMBING FLOOR PLAN

P2.0-CW

SECTION	PLUMBING SPECIFICATIONS	PLUMBING PROJECT NOTES
15010 BASIC MECHANICAL REQUIREMENTS	<ol style="list-style-type: none"> ALL WORK TO BE DONE AND MATERIALS FURNISHED COMPLYING WITH APPLICABLE LAWS AND REGULATIONS, INCLUDING THE STATE OF XXXX MECHANICAL, PLUMBING AND FIRE SAFETY CODES. OBTAIN AND PAY FOR REQUIRED PERMITS AND FEES. ALL MATERIALS USED SHALL BE NEW AND UNDAMAGED. ALL WORK PERFORMED SHALL BE IN ACCORDANCE WITH CURRENT CONSTRUCTION INDUSTRY STANDARDS AND WORKMANSHIP. FURNISH SHOP DRAWINGS TO ARCH/ENGINEER FOR APPROVAL PRIOR TO PLACING DELIVERY ORDERS. PROVIDE SHOP DRAWINGS OF ALL MANUFACTURED EQUIPMENT AND MATERIALS EXCEPT PIPE, PIPE FITTINGS AND GALVANIZED DUCTWORK. FURNISH ACCESS DOORS (RATED OR NON-RATED AS REQUIRED) WHERE VALVES OR EQUIPMENT ARE CONCEALED BEHIND A NON ACCESSIBLE CEILING OR WALL. FURNISH ACCESS DOORS TO GENERAL CONTRACTOR FOR INSTALLATION. FURNISH STEEL PIPE SLEEVES WHERE PIPES PENETRATE RATED WALLS. PROVIDE FIRESTOPPING MATERIALS AND SYSTEM TO MAINTAIN THE REQUIRED RATING OF THE WALL PENETRATED. PROVIDE SHOP DRAWINGS SHOWING LISTING AND RATING OF FIRESTOPPING MATERIALS. ALL MANUFACTURED EQUIPMENT, ACCESSORIES AND MATERIALS SHALL BE USED AS INTENDED BY THE MANUFACTURER IN STRICT ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTALLATION, OPERATION AND MAINTENANCE INSTRUCTIONS. CONTRACTOR SHALL PROVIDE IN ADDITION TO ANY OTHER WARRANTIES SPECIFIED, A ONE YEAR FULL LABOR AND MATERIAL WARRANTY ON ALL WORKMANSHIP, MATERIAL AND EQUIPMENT FURNISHED FOR THIS PROJECT. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL OPENINGS AND REQUIRED LINTELS NEEDED FOR THE GENERAL CONTRACTOR FOR THE INSTALLATION OF MECHANICAL EQUIPMENT. SAWCUTS, LINTELS, HEADERS, AND STRUCTURAL MODIFICATIONS TO THE BUILDING STRUCTURE NECESSARY FOR THE INSTALLATION OF MECHANICAL EQUIPMENT SHALL BE APPROVED BY THE GENERAL CONTRACTOR, BEFORE INSTALLATION. IN GENERAL, OPENINGS AND REQUIRED LINTELS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR PROVIDING DETAILS AND TEMPLATES OF ALL OPENINGS NECESSARY FOR MECHANICAL EQUIPMENT INSTALLATION INCLUDING: HOUSING, ACCESS DOORS, INSPECTION DOORS, AND PASSAGEWAYS FOR MECHANICAL EQUIPMENT. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR SEALING CRACKS AND FINISHING ROUGH EDGES LEFT FOLLOWING MECHANICAL INSTALLATION. APPROVAL EQUALS: PLUMBING ITEMS MANUFACTURED BY A COMPANY OTHER THAN THAT WHICH WAS SPECIFIED IN THE SCHEDULE MAY BE SUBSTITUTED BY APPROVED SHOP DRAWINGS CONTINGENT UPON MEETING THE DESIGN, APPEARANCE, AND FUNCTIONAL STANDARDS ESTABLISHED BY THE ORIGINALLY SPECIFIED ITEM(S). THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING DIMENSIONS, CLEARANCES, ASSEMBLY, FIT, ETC. OF THE APPROVED EQUAL(S), AND THEIR AFFECT ON OTHER EQUIPMENT FIT AND OPERATION. THE CONTRACTOR IS LIABLE FOR ANY ADDED COSTS TO HIMSELF OR OTHERS CAUSED BY THE APPROVED EQUALS. 	<ol style="list-style-type: none"> FURNISH ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, FEES, PERMITS, CERTIFICATE OF INSPECTION, ETC. NECESSARY OR REASONABLE, REQUIRED FOR THE COMPLETE INSTALLATION OF ALL PLUMBING WORK. ALL MATERIALS USED SHALL BE NEW AND UNDAMAGED. FEDERAL, STATE, AND LOCAL CODES, LAWS, ACTS, ORDINANCES, REGULATIONS AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION. THE COMPLETED INSTALLATION SHALL BE IN ACCORDANCE WITH ALL THE APPLICABLE INDUSTRY STANDARDS OF GOOD PRACTICE, SAFETY, AND THE MANUFACTURERS STRICTEST RECOMMENDATIONS FOR EQUIPMENT AND PRODUCT APPLICATION AND INSTALLATION. THESE DRAWINGS ARE DIAGRAMMATIC ONLY. CONTRACTOR SHALL MAKE MODIFICATIONS INCLUDING OFFSETS, TURNS, AND RE-ROUTING REQUIRED TO COMPLETE THE INSTALLATION. DO NOT SCALE LOCATION OF EQUIPMENT OR PIPING. BEFORE COMMENCEMENT OF WORK, THE CONTRACTOR SHALL VERIFY EXACT LOCATIONS, ELEVATIONS AND CHARACTERISTICS OF UTILITIES AND PIPING AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT & ENGINEER OF ANY DISCREPANCIES. COORDINATE ALL PLUMBING WORK, INCLUDING EQUIPMENT AND PIPING, WITH OTHER TRADES PRIOR TO WORK. CONTRACTOR TO VERIFY LOCATION OF ALL EXISTING EQUIPMENT SO THAT NO INTERFERENCES ARE ENCOUNTERED WITH OTHER EQUIPMENT OR WITH STRUCTURAL ELEMENTS. THE GENERAL CONTRACTOR SHALL MAKE ALL ARRANGEMENTS WITH UTILITY COMPANIES FOR SERVICE, CONNECTIONS AND METERS. ALL PLUMBING WORK IS TO RUN IN A NEAT AND PROFESSIONAL MANNER, WITH THE AESTHETICS OF THE FACILITY OF PARAMOUNT IMPORTANCE. ALL ROUGH-IN WORK TO BE HIDDEN WITHIN WALLS AND ABOVE CEILING UNLESS OTHERWISE NOTED. ALL WORK SHALL BE LOCATED TO AVOID CONFLICTS WITH OTHER TRADES. CLOSELY COORDINATE ALL WORK WITH ALL OTHER TRADES. FAILURE OF THE CONTRACTOR TO COORDINATE WITH ALL OTHER TRADES SHALL RELIEVE THE ARCHITECT/ENGINEER/OWNER FROM ANY ADDED COSTS. THE CONTRACTOR SHALL DO ALL NECESSARY CUTTING OF WALLS AND CEILING. PATCH AROUND ALL OPENINGS TO MATCH EXISTING CONSTRUCTION. NO STRUCTURAL MEMBER SHALL BE CUT WITHOUT PERMISSION FROM THE ENGINEER. THESE DRAWINGS ARE DIAGRAMMATIC ONLY. DO NOT SCALE LOCATIONS OF FIXTURES, EQUIPMENT, LINES, ETC. COORDINATE ALL DOCUMENTS AS TO PROPER LOCATIONS OF ALL EQUIPMENT AND MATERIALS. EXACT LOCATION AND MOUNTING HEIGHTS OF PLUMBING FIXTURES NOT SPECIFIED IN THESE PLANS SHALL BE VERIFIED WITH CIRCLE K REPRESENTATIVE. CONTRACTOR SHALL VERIFY INVERT ELEVATIONS OF SEWERS TO WHICH NEW WASTE LINES ARE TO BE CONNECTED BEFORE MAKING UP OR INSTALLATION OF NEW WASTE SYSTEM. NO PIPING OR EQUIPMENT SHALL BE INSTALLED ABOVE ELECTRICAL EQUIPMENT OR INSTALLED IN ELECTRICAL ROOMS. ALL VALVES, UNIONS, ETC. SHALL BE SAME SIZE AS LINE SIZE UNLESS OTHERWISE INDICATED ON DRAWINGS. SEE ARCHITECTURAL DRAWINGS FOR HANDICAP FIXTURE LOCATIONS AND MOUNTING HEIGHTS. INSTALL ALL EXPOSED HOT WATER AND DRAIN PIPING BELOW HANDICAP LAVATORIES AND SINKS WITH ARMSTRONG "ARMOFLEX" OR EQUAL. THE GENERAL CONTRACTOR SHALL PROVIDE ALL FAUCETS, TRAPS, STOPS, GATE VALVES, GAS SINKS, WATER HAMMER ARRESTORS, CLEANOUT COVERS AND INDIRECT WASTE UNLESS OTHERWISE NOTED ON PLANS. WASTE AND SOIL PIPING SHALL BE SLOPED AT 1/4" PER FOOT UNLESS OTHERWISE NOTED ON PLANS. DO NOT SUSPEND ANY PIPING, ACCESSORIES, OR ANY OTHER ITEMS FROM STEEL ROOF DECK ITSELF. ALL SUPPORTS SHALL CONFORM TO TRUSS MANUFACTURERS RECOMMENDATIONS. THE CONTRACTOR SHALL RECORD ON AS-BUILT DRAWINGS ALL SIZES, LOCATIONS, AND MATERIALS OF EXISTING PIPING ENCOUNTERED DURING EXCAVATION AND NEW PIPING INSTALLED. SUBMIT ACCURATE "AS-BUILT" DRAWINGS TO OWNER UPON PROJECT COMPLETION. PROVIDE A READY-TO-USE SYSTEM WITH ALL WORK GUARANTEED IN WRITING AGAINST DEFECTIVE WORKMANSHIP AND MATERIALS FOR A PERIOD OF ONE YEAR MINIMUM FROM OWNER OCCUPANCY UNLESS ARCHITECT SPECIFIES A LONGER WARRANTY TERM. FINISHED SURFACES ARE TO BE PATCHED AND FINISHED TO MATCH EXISTING SURFACES WHEN ROUGH-IN PIPING AND FIXTURES ARE REMOVED AND/OR RELOCATED. UPON COMPLETION OF JOB, THE CONTRACTOR SHALL INSPECT ALL EXPOSED PORTIONS OF THE PLUMBING INSTALLATION AND COMPLETELY REMOVE ALL EXPOSED LABELS, SOILS, MARKINGS, AND FOREIGN MATERIAL EXCEPT PRODUCT LABELS AND THOSE REQUIRED BY LAW. SUBMIT SIX COPIES OF SHOP DRAWINGS AND MATERIAL DATA SUBMITTALS TO THE CIRCLE K PROJECT ENGINEER, IF REQUESTED, FOR APPROVAL BEFORE INSTALLATION. NO SUBSTITUTIONS SHALL BE ALLOWED WITHOUT PRIOR APPROVAL BY THE ENGINEER. ALL LINES UNDERGROUND SHALL BE LOCATED AWAY FROM BEARING FOOTINGS OR AS INSTRUCTED UNDER STRUCTURAL ENGINEERED DRAWINGS.

SECTION	PLUMBING SPECIFICATIONS
15100 VALVES	<ol style="list-style-type: none"> BALL VALVES SHALL BE CLASS 125 FOR WATER WITH ENDS AND MATERIALS TO MATCH PIPING SYSTEMS. BALL VALVES 2" AND SMALLER SHALL HAVE BRONZE BODY, STAINLESS STEEL BALL, TEFLON SEATS, AND STUFFING BOX RING, LEVER HANDLE AND BALANCING STOPS, ENDS TO MATCH PIPING SYSTEM.
15140 SUPPORTS & ANCHORS	<ol style="list-style-type: none"> FURNISH PIPE AND DUCT HANGERS, WHERE REQUIRED, FIRMLY SUPPORTED FROM BUILDING STEEL, CONCRETE OR MASONRY STRUCTURE. SUPPORT PIPING SYSTEMS SECURELY WHILE ALLOWING FOR PIPE AND BUILDING EXPANSION AND CONTRACTION. PROVIDE COPPER PLATED HANGERS, FOR COPPER PIPE. USE ADJUSTABLE CLEVIS HANGERS OR ADJUSTABLE STEEL BAND HANGERS. MAXIMUM SPACING SHALL BE 8' FOR 1/2" PIPING, 7' FOR 3/4" TO 1" PIPING, 9' FOR 1-1/2" TO 2" PIPING. FURNISH PLUMBING EQUIPMENT SUPPORTS AS DETAILED OR AS REQUIRED TO SAFELY AND PERMANENTLY CARRY THE WEIGHT OF THE EQUIPMENT.
15250 PLUMBING INSULATION	<ol style="list-style-type: none"> INSULATE ABOVE FLOOR WATER PIPING WITH ELASTOMERIC PLASTIC PERFORMED PIPE INSULATION WITHOUT JACKETING. ALL INSULATING MATERIALS TO HAVE FLAME SPREAD RATING OF 25 OR LESS AND SMOKE DEVELOPMENT RATING OF 50 OR LESS AS TESTED BY ANSIA/ASTM E 84 (NFPA 233) METHOD. INSULATE ALL PIPING WITH SURFACE TEMPERATURES BELOW 75 DEGREE F WITH 1/2" INSULATION. INSULATE ALL PIPING WITH SURFACE TEMPERATURES 75 DEGREES F AND HIGHER WITH 1" THICK INSULATION. INSTALL MINIMUM 1" INSULATION ON ALL HOT WATER PIPING AND THE FIRST 8' OF COLD WATER PIPING AT THE TANK. JOINTS IN INSULATION SHALL BE GLUED, NOT TAPED, WHERE PIPES ARE EXPOSED AND LESS THAN 8' ABOVE FLOOR, PROVIDE HEAVY DUTY METAL JACKETING OVER INSULATION. INSULATE ABOVE FLOOR HORIZONTAL STORM PIPING WITH 1" FIBERGLASS PERFORMED PIPE INSULATION WITH FACTORY APPLIED ALL PURPOSE COVER.
15411 WATER DISTRIBUTION SYSTEM	<ol style="list-style-type: none"> ABOVE GRADE: WATER PIPING SHALL BE CROSSLINKED PE (PEX) TUBING; PEX TUBE SHALL BE TESTED AND CERTIFIED FOR POTABLE WATER SYSTEMS, AND SHALL COMPLY WITH ANSINSF STANDARD 14, ANSINSF STANDARD 61, AND ASTM F876 AND/OR ASTM F877. TUBE SHALL BE LABELED WITH THE ABOVE CERTIFICATIONS. PROVIDE PEX TUBING SYSTEM BY ONE OF THE FOLLOWING: UPONOR, OR APPROVED PEX ALTERNATIVE FITTINGS AND CONNECTORS SHALL BE BY THE SAME MANUFACTURER AND ASSEMBLED WITH THE MANUFACTURER'S APPROVED TOOLS. THE SAME CONNECTION METHOD SHALL BE USED THROUGHOUT THE INSTALLATION. <ol style="list-style-type: none"> AT CONTRACTOR'S OPTION, IN LIEU OF PEX PIPING SYSTEM AS SPECIFIED ABOVE TYPE L COPPER ASTM B 75, ASTM B 88, ASTM B 251, ASTM B 447 WITH WROUGHT COPPER SOLDER-JOINT FITTINGS SAE B 16 BELOW GRADE: WATER PIPING SHALL BE PEX PIPING SYSTEM IN COMPLIANCE WITH THE UPONOR PLUMBING DESIGN ASSISTANCE MANUAL (PDAM), CURRENT EDITION AND THE UPONOR PIPING SYSTEMS INSTALLATION GUIDE, CURRENT EDITION (OR APPROVED ALTERNATIVE). CROSSLINKED PE (PEX) TUBING, ASTM F876 WITHOUT JOINTS BENEATH THE SLAB. <ol style="list-style-type: none"> AT CONTRACTOR'S OPTION, IN LIEU OF PEX PIPING TYPE K COPPER WITH WROUGHT COPPER SOLDER-JOINT FITTINGS. SOLDER SHALL BE 9596-396 TIN-ANTIMONY ANSIA/ASTM B 32 FOR HEATING SYSTEM PIPING. THOROUGHLY FLUSH AND CLEAN ALL NEW AND EXISTING WATER PIPING SYSTEMS. TEST ALL PIPING SYSTEMS PER REGULATIONS IN ITEM NO.1 OR AT 225 PSI FOR A MINIMUM OF 2 HOURS WITH NO PRESSURE DROP INDICATED PRIOR TO INSULATING. STERILIZE ALL DOMESTIC WATER PIPING PRE REQUIREMENTS OF LOCAL HEALTH DEPARTMENT.
15420 DRAINAGE & VENT SYSTEMS	<ol style="list-style-type: none"> WITHIN BUILDING, SCHEDULE 40 PVC, DWV TYPE PIPE AND SOLVENT WELDED PIPE FITTINGS. SCHEDULE 30 PVC PIPE MAY BE USED FOR VENT PIPING WHERE PERMITTED BY CODE. HORIZONTAL PIPE SHALL BE SUPPORTED BY ADJUSTABLE RING HANGERS EQUAL TO ITT-GRINNEL FIG. 97. VERTICAL PIPING SHALL BE SUPPORTED AT EACH FLOOR OR ATTIC LEVEL BY RISER.
15440 PLUMBING FIXTURES	<ol style="list-style-type: none"> PROVIDE AIR CHAMBERS AT EACH FIXTURE CONNECTION. AIR CHAMBERS SHALL BE ONE SIZE LARGER THAN SUPPLY PIPE AND SHALL BE 12" LONG. WHERE REQUIRED BY PLUMBING CODE, FURNISH AND INSTALL MANUFACTURED WATER HAMMER ARRESTORS. PLUMBING FIXTURES SHALL BE INSTALLED WHERE SHOWN ON THE ARCHITECTURAL DRAWINGS. INSTALL FIXTURES LEVEL AND PLUMB. FURNISH TRAPS WHERE REQUIRED. FIXTURES SHALL BE EASILY REMOVABLE FOR SERVICE AND CLEANING. PROVIDE CHROME PLATED RIGID OR FLEXIBLE SUPPLIES TO FIXTURES WITH STOP VALVES, CHROME PLATED 17 GAUGE BRASS TRAPS WITH CHROME PLATED ESCUTCHEONS. SEAL ALL FIXTURES TO WALL AND FLOOR USING SILICONE SEALANT. MATCH SEALANT COLOR TO FIXTURE COLOR. FIXTURES DESIGNATED BARRIER FREE SHALL BE INSTALLED IN COMPLIANCE WITH AMERICANS WITH DISABILITIES ACT. ALL CLEANOUT COVERS TO BE STAINLESS STEEL.


GENERAL PLUMBING NOTES

- PROVIDE CLEAN-OUTS ON ALL HORIZONTAL DRAINS. CLEAN-OUTS CAN BE OMITTED ON DRAIN LINES LESS WHICH ARE LESS THAN 5'-0" UNLESS IT SERVES A SINK OR URINAL.
- SLOPE ALL SEWER AND WASTE LINES @ 1/4" PER FOOT.
- AVOID COLUMNS AND WALL FOOTING FOUNDATION.
- REFER TO PLUMBING RISERS FOR ALL PIPE SIZING.
- RAINWATER SHALL SHEET FLOW FROM CARWASH ROOF TO CONVENIENCE STORE ROOF. REFER TO CS PLUMBING DRG PIPINGS FOR ROOF DRAIN SIZE AND CALCULATIONS.
- UNDERGROUND SEWER LINE TO AVOID COLUMN FOOTING.
- PLUMBING CONTRACTOR TO PROVIDE BALL TYP SHUT-OFF VALVES FOR ALL WATER LINES TO EQUIPMENT.

TAG	DESCRIPTION	MFG.	MODEL	ROUGH-IN SIZE					COUNT	TRIM/REMARKS
				CW	HW	SAN	VENT	VENT		
BV1	WATER BALL VALVE	UPONOR	LFC48						8	PEX-TO-PEX, LEAD-FREE (LF) BRASS BALL VALVES (1/2 INCH (13 MM) THROUGH 2 INCH (50 MM) NOMINAL PIPE SIZE)
FCO	FLOOR CLEANOUT	WATTS	CO-204-R						1	ADJUSTABLE FLOOR CLEANOUT, 5 IN ROUND NICKEL BRONZE TOP, 4 IN PIPE, GAS TIGHT GASKETED BRASS PLUG, NO HUB OUTLET, MD LOAD RATING.
HB	HOSE BIBB	MIFAB	MHY-206-K	3/4"					2	WITH INTEGRAL VACUUM BREAKER. ENCASED TYPE NON-FREEZE.
OS1	SAND/OIL INTERCEPTOR	STRIEM	OS-75			6"	3"		1	SEE STRIEM MANUFACTURERS SPECIFICATION SHEET FOR DETAILS.
RD1	ROOF DRAIN (PRIMARY)	JOSAM	21500			4"			1	COATED CAST IRON BODY, BOTTOM OUTLET, NO-HUB ROOF DRAIN WITH CAST OR DUCTILE IRON DOME, MEMBRANE CLAMP, ADJUSTABLE EXTENSION (OR EXTENSION SIZED FOR ROOF INSULATION), SUMP RECEIVER, 2" EXTERNAL WATER DAM, AND UNDERDECK CLAMP. ADJUSTABLE EXTENSION NOT PERMITTED FOR JOSAM ROOF DRAINS. UNDERDECK CLAMP AND SUMP RECEIVER NOT REQUIRED FOR ZURN TOP-SET INSTALLATION.
RD2	ROOF DRAIN (SECONDARY)	JOSAM	21500			4"			1	COATED CAST IRON BODY, BOTTOM OUTLET, NO-HUB ROOF DRAIN WITH CAST OR DUCTILE IRON DOME, MEMBRANE CLAMP, ADJUSTABLE EXTENSION (OR EXTENSION SIZED FOR ROOF INSULATION), SUMP RECEIVER, 2" EXTERNAL WATER DAM, AND UNDERDECK CLAMP. ADJUSTABLE EXTENSION NOT PERMITTED FOR JOSAM ROOF DRAINS. UNDERDECK CLAMP AND SUMP RECEIVER NOT REQUIRED FOR ZURN TOP-SET INSTALLATION.
RT	RECLAIM TANK 1 AND 2	MARK VII	JP1500SO			6"			2	1500 GALLON WATER RECLAIM TANKS SEE RECLAIM SYSTEM DESIGN (BY MARK VII) DETAIL.
TD1	DRAIN PIT	---	---			6"			1	2' X 30" DRAIN PIT BASIN, PROVIDE WITH TYPE 15 VALVE GRATE. REF ARCH/STRUCT DWGS.
TD3	EQUIPMENT ROOM TRENCH DRAIN	SMITH/ACO ZURN	9931/9870-425-GHD/9936 Z886-HD/RF/GZ-887-HD			4"	2"		1	POLYPROPYLENE OR HDPE TRENCH DRAIN WITH HEAVY DUTY SLOTTED GALVANIZED STEEL GRATE AND FRAME ASSEMBLY. PROVIDE CATCH BASIN WHERE INDICATED ON PLAN. MODEL#: TRENCH/GRATE/CATCH BASIN
TP	TRAP PRIMER	PPP	P2-500	1/2"					2	PRECISION PLUMBING PRODUCTS; PRESSURE ACTUATED. LOCATE IN WALL MOUNTED ACCESSIBLE BOX W/ COVER @ 24" AFF.
YCO	YARD CLEANOUT	WATTS	CO-300-MF/CO-380						4	CAST IRON FERRULE AND PLUG. DURA-COATED CAST IRON, DOUBLE-FLANGED HOUSING, AND EXTRA HEAVY DUTY SCORRIATED CAST IRON COVER WITH LIFTING DEVICE, VANDAL-PROOF SCREWS. DOUBLE YCO(S) INDICATES A 2-WAY CLEANOUT.



ROOF DRAIN CALCULATIONS						
0.0104 = CONVERSION FACTOR - GPM/SQFT FOR 17"HR RAINFALL.						
		2021 INTERNATIONAL PLUMBING CODE:		MINIMUM HORIZONTAL DRAIN SIZE SLOPED AT 1/4" PER FOOT. PER TABLE		
AREA NAME	AREA (A1)	PARAPET AREA	1/2 PARAPET WALL AREA (A2)	RAIN FALL RATE (R IN INCHES)	GPM=0.0104 x R x (A1+A2), [EQ 11-1 IPC 1106.2.1]	MINIMUM VERTICAL PRIMARY DRAIN SIZE PER TABLE 1106.2
CARWASH ROOF	1364 ft²	498 ft²	249 ft²	3.75	63	3"
	1364 ft²		249 ft²			3"



PLUMBING ROOF PLAN | 2

1/4" = 1'-0"

PLUMBING SYMBOLS	
SS	SANITARY SEWER
GW	GREASE WASTE
OW	OIL WASTE
ST	STORM SEWER
RD	ROOF DRAIN LINE
ORD	OVERFLOW ROOF DRAIN LINE
---	DOMESTIC COLD WATER
---	DOMESTIC HOT WATER
---	DOMESTIC HOT WATER RETURN
IW	IRRIGATION WATER
T	110°F TEMPERED WATER
FW	FILTERED WATER
G	NATURAL GAS
A	COMPRESSED AIR
CD	CONDENSATE DRAIN
RO	REVERSE OSMOSIS WATER
V	PLUMBING VENT
VAC	PLUMBING VACUUM
U	UNION
R	GAS PRESSURE REGULATOR
C	GAS COCK
E	ELBOW - TURNED DOWN
O	ELBOW - TURNED UP
T	TEE - TURNED DOWN
T	TEE - TURNED UP
B	BALL VALVE (BV)
F	FLOW CONTROL VALVE
P	PLUG VALVE
C	CHECK VALVE
S	SHUT-OFF VALVE IN VERTICAL LINE
B	BACKFLOW PREVENTER
M	WATER METER
W	WATER HAMMER ARRESTOR
T	THERMOMETER
R	T & P RELIEF VALVE
TMV	THERMOSTATIC MIXING VALVE
FD	FLOOR DRAIN
RD	ROOF DRAIN/OVERFLOW ROOF DRAIN
FS	FLOOR SINK
FCO	FLOOR CLEANOUT
YCO	YARD CLEANOUT
FPWH	FREEZE PROOF WALL HYDRANT
HB	HOSE BIBB
WCO	WALL CLEANOUT
C	CONNECT TO EXISTING
ETR	EXISTING TO REMAIN
D	DEMO PIPE
X	AREA OF SLAB CUT
VBF	VENT BELOW FLOOR
?	KEYNOTE CALLOUT SYMBOL (? = NUMBER)
11 TYP	PLUMBING FIXTURE CALLOUT SYMBOL (WITH TYP OF NUMBER IN SYSTEM)

SYMBOLS LIST NOTES

- SYMBOLS LISTS, NOTES, ABBREVIATIONS, ETC. ARE FOR GENERAL REFERENCE ONLY. THE PRESENCE OF SYMBOLS, NOTES, ABBREVIATIONS, ETC. DOES NOT IMPLY ITS USE ON THIS PROJECT. REFER TO DRAWINGS FOR SPECIFIC SYMBOLS, NOTES, ABBREVIATIONS, ETC. USED.



11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional PROFESSIONAL



SUITE 5274 479-638-5004
105 N 2ND ST JOB NO.: 23594
ROGERS, AR 72756 DESIGNED BY: JBA

REVISION

ISSUE	DATE
OTF	02/10/23

PROFESSIONAL IN


JMS
PROJECT
SAG
QUALITY
JMS
DRAWN
JBA

PROJECT

CIRCLE K
STORES, INC.
DET CW
ANGIER,
NC

9706 KENNEBEC CHURCH
ROAD,
ANGIER, NC

PROTOTYPE CYCLE # R3.2 12/19/22



CIRCLE K STORE

PROJECT NUMBER: 22130

CW PLUMBING
SPECIFICATIONS
& DETAILS

P2.1-CW

SPECIFICATIONS:

1. MAX FLOW RATE: 75 GPM
2. CAPACITIES: LIQUID: 110 GAL. (14.7 CU. FT.); OIL: 93 GAL.; SAND: 11 GAL.
3. UNIT WEIGHT: 188 LBS.
4. MAXIMUM OPERATING TEMPERATURE 140°F CONTINUOUS.
5. H2O RATED PICKABLE CAST IRON COVER: 16,000 LB. CAPACITY.

Additional Options

- SS - Slick Stick; Oil Level Monitoring System*
- AK-1 - High Water Anchor Kit
- *Monitoring system will raise covers by 2-1/2".

NOTES:

- A. SNAP-IN FLOW CONTROL (SHIPS WITH UNIT).
- B. FOR GRAVITY DRAINAGE APPLICATIONS ONLY. DO NOT USE FOR PRESSURE APPLICATIONS.
- C. SEAMLESS MEDIUM DENSITY POLYETHYLENE TANK.
- D. UNIT SUPPLIED WITH BUILT-IN ADAPTER FOR UP TO 6" OF ADJUSTABILITY. ADDITIONAL RISER(S) AVAILABLE FOR DEEPER BURIAL DEPTH.
- E. COVER PLACEMENT ALLOWS FULL ACCESS TO TANK FOR PROPER MAINTENANCE.
- F. ENGINEERED INLET AND OUTLET DIFFUSERS ARE REMOVABLE TO INSPECT/CLEAN PIPING.

DIFFUSION FLOW TECHNOLOGY:


THE INLET DIFFUSER SPLITS INFLUENT INTO THREE PATHS, CREATING LAMINAR FLOW AND UTILIZING THE ENTIRE LIQUID VOLUME OF THE TANK FOR EFFICIENT OIL SEPARATION. THE CALIBRATED OPENINGS GREATLY REDUCE INFLUENT TURBULENCE. THE INFLUENT ENTERS THE MAIN CHAMBER WITHOUT DISTURBING THE EXISTING OIL OR SAND LAYERS. THE BOTTOM OF THE OUTLET DIFFUSER ALLOWS ONLY EFFLUENT THAT IS FREE OF OIL TO EXIT THE TANK.

ENGINEER SPECIFICATION GUIDE:

STRIEM OIL RESERVE OIL/SAND SEPARATOR MODEL OS-75-113-JCW SHALL BE LIFETIME GUARANTEED AND MADE IN USA OF SEAMLESS, ROTATIONALLY-MOLDED POLYETHYLENE. SEPARATOR SHALL BE FURNISHED FOR BELOW GRADE INSTALLATION, WITH FIELD ADJUSTABLE RISER SYSTEM, SNAP-IN FLOW CONTROL AND (2) VENT CONNECTIONS. SEPARATOR FLOW RATE SHALL BE 75 GPM. SEPARATOR OIL CAPACITY SHALL BE 93 GALLONS. SAND CAPACITY SHALL BE 11 GALLONS. COVERS SHALL PROVIDE WATER/GAS-TIGHT SEAL AND HAVE A MAXIMUM 16,000 LBS LOAD CAPACITY.

THIRD PARTY STRUCTURAL ANALYSIS:

THE OS-75-113-JCW HAS BEEN STRUCTURALLY ANALYZED IN ACCORDANCE WITH THE REQUIREMENTS OF IBC 2012/2015 AND ASCE 7 FOR DIRECT BURIAL. THE MAXIMUM BURIAL DEPTH AND BACKFILL MATERIAL ARE SPECIFIED IN OUR INSTALLATION INSTRUCTIONS. THE STRUCTURAL DESIGN HAS BEEN REVIEWED AND SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF CALIFORNIA. A SEALED STRUCTURAL ANALYSIS REPORT IS AVAILABLE UPON REQUEST.



MODEL NUMBER: OS-75-113-JCW

SPECIFICATION SHEET

DESCRIPTION:

POLYETHYLENE OIL SEPARATOR 75 GPM 110 GALLON CAPACITY

PROPRIETARY AND CONFIDENTIAL:
THE INFORMATION CONTAINED IN THIS DRAWING IS THE DOLE PROPERTY OF STRIEM, LLC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF STRIEM, LLC. IS PROHIBITED.


DWG BY: DATE: 07/16/2020 REV: 0

Striem

3100 Brinkerhoff
Kansas City, KS 66115
Tel: 913-222-1500
Fax: 913-291-0457
www.striemco.com
Made in the U.S.A

SAND/OIL INTERCEPTOR | 7

N.T.S.




SECTION-CARWASH TRENCH | 6

N.T.S.

2 TANK CONFIGURATION FOR 5 MICRON PUR-WATER RECOVERY SYSTEMS

THIS IS THE SUGGESTED IDEAL CONFIGURATION FOR A 30 GPM LOW VOLUME 5 MICRON PUR-WATER SYSTEM. PUR-WATER RECOGNIZES THE FACT THAT SEPTIC TANKS ARE A LOCAL BUSINESS AND NOT ALL AREAS WILL HAVE THESE CONFIGURATIONS. THIS DRAWING IS OFFERED AS A GUIDELINE ONLY. IF YOU HAVE ANY QUESTIONS ABOUT A SIZE OR CONFIGURATION OF TANKS IN YOUR AREA, PLEASE CONTACT PUR-WATER AT 800-882-8854



KEYED NOTES:(X)


1. TO PUR-WATER RECOVERY SYSTEM (2) 2" SCH 80 PVC LINES, ONE TO SERVE AS A SPARE. LINES ARE STRAPPED TO THE TANK WALL. INSTALL SCH 80 UNIONS ABOVE THE WATERLINE TO ALLOW SERVICING OF EACH SUCTION LINE. TERMINATE SUCTION LINES W/ FULL FLOW FLAPPER CHECK VALVES (PUR-WATER SUPPLIED) NO SPRING LOADED FOOT VALVES
2. PURWATER PROVIDED (1) LOW-LOW SAFETY LEVEL FLOAT SHOULD BE MOUNTED SO THAT IT WILL BE IN THE DOWN POSITION 8" ABOVE THE BOTTOM OF THE FLAPPER CHECK. THIS FLOAT CONTROLS THE SAFETY FUNCTION TO PROTECT THE PUMP FROM A LOW WATER SITUATION.
3. (1) 1" SCH 80 AIR SPARGER OR OZONE RECIRCULATION LINE. FOR AIR SPARGER SYSTEMS, ALLOW THE SPARGER TO BE 6-12" ABOVE THE WATER LINE. MOUNT IN THE MANWAY, IF POSSIBLE, TO ALLOW ACCESS FOR MAINTENANCE. FOR OZONE SYSTEMS, PLUMB THE LINE WITH A TEE, ON THE WET END, 24" UP FROM THE BOTTOM OF THE TANK.
4. (1) 1" SCH 80 PVC LINE TO SERVE AS A CONDUIT FOR (4) 14 GAUGE WIRES (TWO ARE SPARES) TERMINATED IN A WATER TIGHT JUNCTION BOX ABOVE THE WATER LINE TO PUR-WATER RECLAIM SYSTEM FOR FLOAT CONTROLS.
5. (1) 1" SCH 80 UNDERFLOW LINE FROM THE BOTTOM OF THE RECLAIM SYSTEM CYCLONE SEPARATOR. THIS LINE SHOULD BE LEVEL, OR PREFERABLY, SLOPE FROM THE RECLAIM SYSTEM TO THE CAR WASH SYSTEM CATCH BASIN OR THE FIRST COMPARTMENT OF TANK 1.
6. USE 6" PIPE AS INTERCONNECT PIPING BETWEEN COMPARTMENTS AND BETWEEN TANKS. ELEVATIONS DIMENSIONS ARE TO PIPE INVERTS.
7. (1) 4" SCH 80 PIPE TO BE ROUTED TO SEWER OR OIL WATER SEPARATOR. NOTE: BACK FLOW PREVENTION FROM THE SEWER IS REQUIRED. CONSULT WITH LOCAL AUTHORITIES ON WHETHER FURTHER TREATMENT (i.e. OIL/WATER SEPARATION IS REQUIRED TO MEET DISCHARGE PERMIT).

GENERAL NOTES:

- A. DRAWING IS FOR REFERENCE ONLY AND IS TO BE USED FOR PLUMBING REFERENCE. CONSULT WITH TANK MANUFACTURER FOR TANK LOADS.
- B. SEAL ALL TANK PENETRATIONS TO PROVIDE WATER TIGHT SEAL TO PREVENT TANK LEAKAGE INTO SOIL.
- C. LINE TO SEWER TO HAVE BACK FLOW PREVENTION. CONSULT WITH LOCAL AUTHORITIES ON WHETHER FURTHER TREATMENT (i.e. OIL/WATER SEPARATOR IS REQUIRED TO MEET DISCHARGE PERMIT).
- D. APPROXIMATE TANK VOLUME IS 1500 GALLONS PER TANK, EACH TANK IS DIVIDED BY INTERNAL BAFLE. TOTAL WATER STORAGE IS APPROXIMATELY 3000 GALLONS.
- E. RECLAIM EQUIPMENT SHALL BE PROVIDED AND INSTALLED BY GENERAL CONTRACTOR.


RECLAIM SYSTEM DESIGN (BY MARK VII) | 5

N.T.S.




VENT THRU ROOF (VTR) | 3

N.T.S.



SUPPLY WATER RISER | 2

N.T.S.



WASTE AND VENT RISER | 1

N.T.S.

rdc.

11921 Freedom Drive #1110
Reston, Va 20190
t 703.668.0086
rdcollaborative.com

COPYRIGHT

This drawings is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the professional PROFESSIONAL

Jason M. Scates
P.E.

SUITE 5274 479-638-5004
1805 N 2ND ST JOB NO.: 23894
ROGERS, AR 72756 DESIGNED BY: JBA

REVISION

ISSUE	DATE
OTP	02/10/23

PROFESSIONAL IN

JMS

PROJECT

SAG

QUALITY

JMS

DRAWN

JBA

PROJECT

CIRCLE K STORES, INC.
DET CW
ANGIER,
NC

9706 KENNEBEC CHURCH ROAD,
ANGIER, NC

PROTOTYPE CYCLE # R3.2 12/19/22




CIRCLE K STORE

PROJECT NUMBER: 22130


PLUMBING
RISERS AND
DETAILS

P2.2-CW



DESIGNER NOTE: REPLACE DETAIL ON SHEET WITH PROPER DETAIL IF CARWASH IS ATTACHED LEFT OR RIGHT.

THE INFORMATION CONTAINED IN THIS DOCUMENT IS DESIGNED AND INTENDED FOR PRELIMINARY EDUCATION AND PLANNING PURPOSES ONLY. THESE DRAWINGS IN NO WAY REPRESENT FINAL ARCHITECTURAL OR STRUCTURAL DRAWINGS OR PLANS. MARK VII EQUIPMENT IS NOT RESPONSIBLE FOR THE ACTUAL RESULTS OF EFFORTS IMPLEMENTED DUE TO THE INFORMATION CONTAINED IN THIS DOCUMENT. EQUIPMENT LOCATION ONLY



INSTALLER'S RESPONSIBILITY: --- CHEM --- CHEM ---
GENERAL CONTRACTORS RESPONSIBILITY: _____

--- CWL --- CWL --- CWL ---	CITY WATER LINE
--- AIR --- AIR --- AIR ---	COMPRESSED AIR LINE
--- RO --- RO --- RO ---	RO WATER LINE
--- RW --- RW --- RW ---	RECLAIM LINES
--- SW --- SW --- SW ---	SOFTWATER LINES
--- CHEM --- CHEM --- CHEM ---	CHEMICAL LINES, BY MARK VII

- HARD PLUMBING OF WATER AND AIR LINES FROM SUPPLY SOURCE TO BALL VALVES TO BE PERFORMED BY CONTRACTOR. TERMINATING WITH A FULL PORT BALL VALVE WITH FEMALE THREAD. SOFT PLUMBING FROM BALL VALVES TO EQUIPMENT TO BE PERFORMED BY CAR WASH SUPPLIER/INSTALLER.
- PLUMBING SHOULD CONFORM TO ALL LOCAL BUILDING CODES.
- MAIN WATER LINE SHOULD BE SIZED; BY OTHERS, TO SUPPLY ADEQUATE WATER PRESSURE AND FLOW TO THE GANTRY & HIGH PRESSURE PUMPING PLANT.
- WATER LINE DROPS ARE RECOMMENDED 1" DROPS, MAIN WATER "TRUNK" LINE TO BE SIZED BY OTHERS.
- AIR SUPPLY LINES ARE TO BE TERMINATED WITH AIR BALL VALVES WITH FEMALE THREAD (REC 1/2" DROPS). INCOMING CITY WATER SHOULD COME THROUGH A BACKFLOW PREVENTOR, PRESSURE REDUCER, AND Y-STRAINER.
- HARD PIPE FROM PUMP TO UNDERCARRIAGE BY GC AND RECOMMENDED 3/4" STAINLESS STEEL HIGH PRESSURE TUBING AND FITTINGS. FINAL CONNECTION TO PUMP STAND TO BE HP HOSE BY MARK VII.
- WASH BAY MUST BE PROTECTED FROM FREEZING CONDITIONS.
- AIR REGULATOR (SUPPLIED BY OTHERS) SHOULD BE SET FOR A MAXIMUM PRESSURE OF 120 PSI. CAR WASH COMPONENTS CAN BE DAMAGED BY PRESSURE HIGHER THAN 120 PSI.
- NUMBER OF CHEMICAL LINES MAY VARY PER OPTIONS SELECTED.

EQUIPMENT ROOM ELEVATION - STORE OR EXTERIOR WALL

