95%

CIVIL SITE PLANS
FOR
SAMET
HARNETT COUNTY 1

DUNN, NORTH CAROLINA
HARNETT COUNTY

SHEET LIST

SHEET #	TITLE
C0.0	COVER SHEET
C1.0	SITE PLAN
C1.1	GENERAL NOTES
C1.2	EXISTING CONDITIONS
C2.0	OVERALL STORMWATER
C2.1	DRAINAGE AREAS
C2.2	POND PROFILE
C2.3	DRAINAGE DETAIL
C3.0	OVERALL SITE GRADING
C4.0	OVERALL WATER AND SEWER
C4.1	SANITARY SEWER PROFILE
C5.0	CONSTRUCTION DETAILS
C5.1	CONSTRUCTION DETAILS
C5.2	CONSTRUCTION DETAILS
C5.3	CONSTRUCTION DETAILS
C5.4	CONSTRUCTION DETAILS
C5.5	CONSTRUCTION DETAILS
C5.6	CONSTRUCTION DETAILS
C5.7	CONSTRUCTION DETAILS
C5.8	CONSTRUCTION DETAILS
C5.9	CONSTRUCTION DETAILS
C5.10	CONSTRUCTION DETAILS
C5.11	CONSTRUCTION DETAILS
C5.12	CONSTRUCTION DETAILS
E.03	LIGHTING PLAN
LA	LANDSCAPE PLAN
EC	SEDIMENTATION AND EROSION CONTROL PLANS
	ARCHITECTURAL ELEVATIONS

UTILITY OWNER:
POWER:
WATER AND SEWER: HARNETT COUNTY WATER AND SEWER

PRELIMINARY

RIVER BASIN: CAPE FEAR
RECEIVING STREAM: CAPE FEAR RIVER (ULTIMATE)
CLASSIFICATION: SC

SAFETY IS IN YOUR HANDS. EVERY DIG. EVERY TIME.

TC² ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO. | REVISION | DATE

SAMET HARNETT COUNTY 1

COVER SHEET

NORTH CAROLINA PROFESSIONAL SEAL 038734 ENGINEER BRIAN P. ENSIG

DATE: JULY 2025
SCALE NTS
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C0.0

0 25 50 100 Feet
1:50

NOTES:
1. NO GENERATION OF DUST, ODORS, NOISE, VIBRATION OR ELECTRICAL INTERFERENCE OR FLUCTUATION SHALL BE PERCEPTIBLE BEYOND THE PROPERTY LINES.
2. ALL ESTABLISHMENTS SHALL BE MAINTAINED SO AS NOT TO CREATE ENVIRONMENTAL HAZARDS (SUCH AS OIL OR GAS LEAKS OR SPILLS) THAT POSE A THREAT TO GROUND OR SURFACE WATER QUALITY, AIR QUALITY, WILDLIFE AND/OR HUMANS.

LOCATION MAP N.T.S.

SITE

EXISTING SPOT ELEVATIONS
EXISTING CONTOURS
FUTURE DEVELOPMENT
CONNECTION TO FUTURE PHASE
FUTURE STORMWATER POND
APPROXIMATE LOCATION 175,000 GALLON WATER TANK
APPROXIMATE PHASE LIMITS (16 ACRES +/-)
EX. PROPERTY LINE
4' SIDEWALK
ELECTRIC SERVICE AND CONDUIT BY CONTRACTOR
ELECTRIC SERVICE BY OWNER
PROPOSED SETBACK
FUTURE UNDREGROUND GAS, FIBER OPTIC AND ELECTRIC SERVICES
PROPOSED 12" WATER MAIN
24" CURB AND GUTTER
TELECOM HANDHOLE BY BY OWNER UTILITY CONTRACTOR
TELECOM BY OWNER UTILITY CONTRACTOR
HEAVY DUTY ASPHALT
1-IN 2-OUT DRIVEWAY
TRUCK LOADING AREA
PROPOSED DUMPSTER LOCATION
PROPOSED FIRE HYDRANT ASSEMBLY (TYP.)
8" FIRE MAIN
HEAVY DUTY ASPHALT
HEAVY DUTY CONCRETE
VEHICLE RAMP-HEAVY DUTY CONCRETE
8" FIRE MAIN
3" DOMESTIC WATER LINE
PROPOSED FDC
PRELIMINARY TRANSFORMER LOCATION
TELECOM HANDHOLE BY ELECTRICAL CONTRACTOR
TELECOM BY ELECTRICAL CONTRACTOR-DIRECT BURY OR CONDUIT
FIRE DEPT ACCESS
175,500 SF BUILDING (OFFICE SPACE 2,994 SF TOTAL)
WAREHOUSE 100
OFFICE AREA 101 20'
STANDARD DUTY ASPHALT
PROPOSED SANITARY SEWER MANHOLE
PROPOSED TURNDOWN STYLE CURB, SEE DETAIL SHEETS
6' SIDEWALK
5' SIDEWALK
PROPERTY LINE
DRIVEWAY 2
PROPOSED SETBACK
PROPOSED FIRE HYDRANT ASSEMBLY
STANDARD DUTY ASPHALT PARKING LOT AREA: 44,774 SF
PROPOSED 8" SANITARY SEWER MAIN
8' LANDSCAPE BUFFER
EXISTING HYDRANT
STORMWATER POND FENCE
EXISTING 12" WATER MAIN
ARROWHEAD ROAD
PROPOSED SANITARY SEWER CONNECTION TO EXISTING MANHOLE
APPROXIMATE STORMWATER POND
APPROXIMATE PHASE LIMITS (14 ACRES +/-)
EX. PROPERTY LINE
EXISTING HYDRANT
1-IN 2-OUT DRIVEWAY
PROPOSED V-CURB
DRIVEWAY 2
PROPOSED FIRE HYDRANT ASSEMBLY (TYP.)
TRUCK TRAILER LOADING SPACE (TYP.)
VEHICLE RAMP-HEAVY DUTY CONCRETE
FIRE DEPT ACCESS
PROPOSED SETBACK
FIRE ACCESS LANE (HEAVY DUTY ASPHALT)
PROPOSED SANITARY SEWER MANHOLE
US 301 S.
SAMET HARNETT COUNTY 1
SITE PLAN

SITE DATA TABLE-Samet Harnett County Site 1

PARCEL ID	215050123	
PARCEL OWNERSHIP	SAM Harnett I LLC	
CURRENT ZONING	I-100	
EXISTING BUILDING (TO BE REMOVED) SF	N/A	
TOTAL SITE AREA (AC)	13.47	
DISTURBED/TOTAL PROJECT AREA (SF)	696,960 SF	16.00 AC
BUILDING DATA-CONSTRUCTION TYPE: II-B		
BUILDING USE:	LIGHT INDUSTRIAL/WAREHOUSE	
# OF BUILDINGS (1)	AREA (SF)	
BUILDING AREA (EACH)	175,500	
BUILDING HEIGHT / # OF STORIES	45' AGL (1 STORYS)	
OFFICE AREA	2,994	
BUILDING AREA (OTHER USES)	172,506	
BUILDING SETBACKS		
	REQUIRED	PROPOSED
SETBACK OFF HIGHWAYS & THOUROUGHFARES	50'	94'
Front Setback	50'	99'
Side Setback	30'	75'
Rear Setback	50'	151'
PARKING SPACES		
REQUIRED	REQUIRED	PROPOSED
1/2,000 SF	87.75	138
Bicycle	EXEMPT	
ADA (Including Van-Accessible) 2% OF TOTAL PARKING	3	6
Off-Street Loading	5	>10
PARKING SQUARE FOOTAGE	42,101	
IMPERVIOUS COVERAGE		
STATE REQUIREMENT:	<70% IMPERVIOUS	
TYPE	PROPOSED (SF)	PERCENT OF IMPERVIOUS
ASPHALT	132,374	38.1%
SIDEWALK/CONCRETE	39,705	11.4%
BUILDINGS	175,500	50.5%
TOTAL	347,579	59.2%
OPEN SPACE REQUIREMENTS		
EXEMPT		

SEE CIVIL DESIGN SHEETS FOR, MORE CONCISE WATER AND SEWER, GRADING AND STORMDRAIN PLANS

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER COMMENTS	7/16/15

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET: C1.0

CONTRACTOR NOTES:

1. THE CONTRACTOR IS REQUIRED TO OBTAIN ANY/ALL PERMITS REQUIRED FOR CONSTRUCTION OF THESE PLANS.
2. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH PERMITS ISSUED AND WITH TOWN OF LELAND, AND THE STATE OF NORTH CAROLINA.
3. THE CONTRACTOR IS TO ESTABLISH AND CHECK ALL HORIZONTAL AND VERTICAL CONTROLS TO BE USED WITH THE PROJECT. IN ADDITION, THE CONTRACTOR IS TO COMPUTE THE LAYOUT OF THE ENTIRE SITE PLAN IN ADVANCE OF BEGINNING ANY WORK ASSOCIATED WITH THE SUBJECT PLANS. CONTRACTOR SHALL EMPLOY A PROFESSIONAL SURVEYOR TO PERFORM SITE IMPROVEMENT STAKEOUT(S).
4. ANYTIME WORK IS PERFORMED OFF-SITE OR WITHIN AN EXISTING EASEMENT, THE CONTRACTOR IS TO NOTIFY THE HOLDER OF SAID EASEMENT AS TO THE NATURE OF PROPOSED WORK, AND TO FOLLOW ANY GUIDELINES OR STANDARDS WHICH ARE ASSOCIATED WITH OR REFERENCED IN THE RECORDED EASEMENT.
5. CONTRACTOR SHALL REFER TO ARCHITECTURAL DRAWINGS BY OTHERS FOR ALL BUILDING DIMENSIONS AND DETAILS.

GENERAL NOTES:

1. BOUNDARY AND EXISTING CONDITIONS SURVEY COMPLETED BY BATEMAN CIVIL SURVEYING, INC., AND TREE INVENTORY AND TOPOGRAPHIC SURVEY COMPLETED BY BATEMAN CIVIL SURVEYING, INC. THE SURVEY SHALL BE FIELD VERIFIED BY CONTRACTOR AND ANY DISCREPANCIES REPORTED TO THE OWNER AND ENGINEER.
2. REASONABLE CARE HAS BEEN EXERCISED IN SHOWING THE LOCATION OF EXISTING UTILITIES ON THE PLANS. THE EXACT LOCATION OF ALL EXISTING UTILITIES IS NOT KNOWN IN ALL CASES. THE CONTRACTOR SHALL EXPLORE THE AREA AHEAD OF DITCHING OPERATIONS BY OBSERVATIONS, ELECTRONIC DEVICES, HAND DIGGING AND BY PERSONAL CONTACT WITH THE UTILITY COMPANIES. IN ORDER TO LOCATE EXISTING UTILITIES IN ADVANCE OF TRENCHING OPERATIONS SO AS TO ELIMINATE OR MINIMIZE DAMAGE TO EXISTING UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS RESULTING FROM ANY DAMAGE TO THE EXISTING UTILITY LINES INCLUDING LOSS OF UTILITY REVENUES. CONTRACTOR SHALL ARRANGE FOR TEMPORARY SUPPORT OF EXISTING UTILITIES, SUCH AS POLES, CONDUITS, FIBER OPTIC CABLES, TELEPHONE CABLES, WATER LINES, ETC.
3. CONTRACTOR SHALL COMPLY WITH THE LATEST REVISIONS AND INTERPRETATIONS OF THE DEPARTMENT OF LABOR SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION PROMULGATED UNDER THE OCCUPATIONAL SAFETY AND HEALTH ACT.
4. CONTRACTOR SHALL PLAN AND CONSTRUCT WORK SO AS TO CAUSE MINIMUM INCONVENIENCE TO THE OWNER AND THE PUBLIC. THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN AT ALL TIMES DURING THE PROGRESS OR TEMPORARY SUSPENSION OF WORK, SUITABLE BARRIERS, FENCES, SIGNS OR OTHER ADEQUATE PROTECTION, INCLUDING FLAGMEN AND WATCHMEN AS NECESSARY TO INSURE THE SAFETY OF THE PUBLIC AS WELL AS THOSE ENGAGED IN THE CONSTRUCTION WORK. CONSTRUCTION SIGNING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF "CONSTRUCTION AND MAINTENANCE OPERATIONS SUPPLEMENT TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" BY THE USDOT.
5. ALL MATERIAL CLEARED OR DEMOLISHED BY THE CONTRACTOR IN ORDER TO CONSTRUCT THE WORK SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE PROPERLY DISPOSED OF OFF-SITE.
6. ALL WORK BY THE CONTRACTOR SHALL BE WARRANTED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR AFTER THE OWNER ACCEPTS THE WORK.
7. CONTRACTOR SHALL CALL THE NORTH CAROLINA ONE-CALL CENTER AT 811 AND ALLOW THE CENTER TO LOCATE EXISTING UTILITIES BEFORE DIGGING.
8. ANY DISCREPANCY IN THIS PLAN AND ACTUAL FIELD CONDITIONS SHALL BE REPORTED TO THE OWNER PRIOR TO START OF CONSTRUCTION. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS AND DIMENSIONS SHOWN HEREON BEFORE BEGINNING CONSTRUCTION.
9. CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND ADJOINING PROPERTY PROTECTED FROM DAMAGE.
10. ACCESS TO UTILITIES, FIRE HYDRANTS, STREET LIGHTING, ETC., SHALL REMAIN UNDISTURBED, UNLESS COORDINATED WITH THE ENGINEER AND RESPECTIVE UTILITY.
11. THE GENERAL CONTRACTOR SHALL REMOVE ALL DEBRIS FROM THE SITE UPON COMPLETION OF THE PROJECT AND AT LEAST ONCE A WEEK DURING CONSTRUCTION.
12. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE LOADS ON ALL DUMPTRUCKS AND REFUSE TRANSPORT VEHICLES, TARPS MUST BE UTILIZED. CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE STREET CLEAN AND FREE OF DEBRIS AT ALL TIMES.
13. THE CONTRACTOR SHALL KEEP THE AREA OUTSIDE THE "LIMITS OF DISTURBANCE" BROOM CLEAN AT ALL TIMES.
14. ALL STREET SURFACES, DRIVEWAYS, CULVERTS, CURB AND GUTTERS, ROADSIDE DRAINAGE DITCHES AND OTHER STRUCTURES THAT ARE DISTURBED OR DAMAGED IN ANY MANNER AS A RESULT OF CONSTRUCTION SHALL BE REPLACED OR REPAIRED IN ACCORDANCE WITH THE SPECIFICATIONS.
15. CONTRACTOR SHALL MAINTAIN AN "AS-BUILT" SET OF DRAWINGS TO RECORD THE EXACT LOCATION OF ALL PIPING PRIOR TO CONCEALMENT. DRAWINGS SHALL BE GIVEN TO THE OWNER UPON COMPLETION OF THE PROJECT WITH A COPY OF THE TRANSMITTAL LETTER TO THE ENGINEER.
16. IF DEPARTURES FROM THE SPECIFICATIONS OR DRAWINGS ARE DEEMED NECESSARY BY THE CONTRACTOR, DETAILS OF SUCH DEPARTURES AND REASONS THEREOF SHALL BE GIVEN TO THE OWNER FOR REVIEW, NO DEPARTURES FROM THE CONTRACT DOCUMENTS SHALL BE MADE WITHOUT THE PERMISSION OF THE OWNER, TOWN OF CAROLINA BEACH OR STATE OF NORTH CAROLINA, RESPECTIVELY.
17. CONTRACTOR SHALL VERIFY LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES. THE LOCATION OF ALL EXISTING UTILITIES ARE NOT NECESSARILY SHOWN ON PLANS AND WHERE SHOWN ARE ONLY APPROXIMATE. THE CONTRACTOR SHALL ON HIS INITIATIVE AND AT NO EXTRA COST HAVE LOCATED ALL UNDERGROUND LINES AND STRUCTURES AS NECESSARY. NO CLAIMS FOR DAMAGES OR EXTRA COMPENSATION SHALL ACCRUE TO THE CONTRACTOR FROM THE PRESENCE OF SUCH PIPE OTHER OBSTRUCTIONS OR FROM DELAY DUE TO REMOVAL OR REARRANGEMENT OF THE SAME. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND STRUCTURES. CONTACT NORTH CAROLINA ONE CALL" TOLL FREE 1-800-632-4949 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL NONSUBSCRIBING UTILITIES.
18. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ALL INSPECTIONS, CERTIFICATIONS, EQUIPMENT, ETC., THAT MAY BE REQUIRED.
19. THE ENGINEER AND/OR OWNER DISCLAIM ANY ROLE IN THE CONSTRUCTION MEANS AND METHODS ASSOCIATED WITH THE PROJECT AS SET FORTH IN THESE PLANS.
20. ALL LOT STRIPING AND DIRECTIONAL ARROWS TO BE REFLECTIVE MARKINGS AND SHALL CONFORM TO MUTCD. ALL PARKING STALL MARKINGS AND LANE ARROWS WITHIN THE PARKING AREAS SHALL BE WHITE.
21. LANDSCAPE PLANTINGS AT ENTRANCE/ EXITS WILL BE INSTALLED AND MAINTAINED SO AS NOT TO INTERFERE WITH SIGHT DISTANCE NEEDS OF DRIVERS IN THE PARKING AREA AND AT ENTRANCE/EXIT LOCATIONS PER LOCAL STANDARDS.
22. ALL DIMENSIONS AND RADII ARE TO OUTSIDE FACE OF BUILDING OR TO FACE OF CURB UNLESS OTHERWISE NOTED.

GENERAL DEMOLITION NOTES:

1. CONTRACTOR TO COORDINATE WITH THE OWNER TO PROPERLY MAINTAIN OR RELOCATE EXISTING SERVICE CONNECTIONS WHEN NECESSARY.
2. CONTRACTOR IS TO WALK THE SITE AND BECOME FAMILIAR WITH THE SCOPE OF DEMOLITION REQUIRED. ALL DEMOLITION WORK REQUIRED TO CONSTRUCT NEW SITE IMPROVEMENTS WILL BE PERFORMED BY THE CONTRACTOR AND WILL BE CONSIDERED UNCLASSIFIED EXCAVATION.
3. DEMOLITION SHALL INCLUDE BUT IS NOT LIMITED TO THE EXCAVATION, HAULING AND OFFSITE DISPOSAL OF CONCRETE PADS, CONCRETE DITCHES, FOUNDATIONS, SLABS, STEPS, AND STRUCTURES; ABANDONED UTILITIES, BUILDINGS, PAVEMENTS AND ALL MATERIALS CLEARED AND STRIPPED TO THE EXTENT NECESSARY AS DIRECTED BY THE GEOTECHNICAL ENGINEER FOR THE INSTALLATION OF THE NEW IMPROVEMENTS AND WITHIN THE LIMITS OF CLEARING AND GRADING AND AS SHOWN ON THESE PLANS.
4. THE CONTRACTOR SHALL PROTECT ALL ADJACENT PROPERTY, STRUCTURES AND UTILITIES ON THE PROPERTY NOT TO BE DEMOLISHED. DAMAGE TO PROPERTIES OF OTHERS DUE TO THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED IN KIND BY THE CONTRACTOR AT NO COST TO OWNER.
5. ELECTRIC, TELEPHONE, SANITARY SEWER, WATER AND STORM SEWER UTILITIES THAT SERVICE OFF-SITE PROPERTIES SHALL BE MAINTAINED DURING THE CONSTRUCTION PROCESS BY THE CONTRACTOR.
6. THE CONTRACTOR SHALL PRODUCE A PHOTOGRAPHIC RECORD (DIGITAL) OF DEVELOPMENT COMMENCING WITH A RECORD OF THE SITE AS IT APPEARS BEFORE DEMOLITION HAS BEGUN. AFTERWARDS, A PHOTOGRAPHIC RECORD SHALL BE MAINTAINED WEEKLY DURING CONSTRUCTION AND ENDING WITH A PHOTOGRAPHIC RECORD OF THE DEVELOPMENT AS IT APPEARS AFTER DEMOLITION. THIS RECORD SHALL BE DELIVERED TO THE OWNER.
7. EXISTING CURB AND GUTTER, LIGHTS, SIDEWALK, AND UTILITIES NOT INTENDED FOR DEMOLITION SHALL BE MAINTAINED, PROTECTED AND UNDISTURBED DURING DEMOLITION.
8. ALL EXISTING IMPROVEMENTS INDICATED OR REQUIRED TO BE DEMOLISHED SHALL INCLUDE REMOVAL FROM THE PROPERTY AND PROPER DISPOSAL.
9. CONTRACTOR SHALL COORDINATE RELOCATION OF ALL EXISTING OVERHEAD AND UNDERGROUND UTILITIES INCLUDING CABLE, GAS, TELEPHONE AND ELECTRIC AND ANY OTHER UTILITIES THROUGH THE SITE WITH THE RESPECTIVE COMPANIES.
10. CONTRACTOR SHALL MAINTAIN REQUIRED DISTANCES FROM HIGH VOLTAGE OVERHEAD LINES AND REMOVE TREES SO THEY DO NOT FALL TOWARDS OVERHEAD ELECTRICITY.
11. PROVIDE SMOOTH SAW CUT OF EXISTING PAVEMENTS, CURBS AND GUTTERS AND SIDEWALKS TO BE DEMOLISHED.
12. ALL DEMOLITION WORK SHALL BE DONE IN STRICT ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS AS WELL AS OSHA REGULATIONS.
13. EXISTING FIRE HYDRANTS ON OR NEAR THE SITE ARE TO REMAIN IN SERVICE.
14. INFORMATION CONCERNING UNDERGROUND UTILITIES WAS OBTAINED FROM AVAILABLE RECORDS, BUT THE CONTRACTOR MUST DETERMINE THE EXACT LOCATION AND ELEVATIONS.

GENERAL EROSION CONTROL NOTES:

1. THE EROSION CONTROL PLAN SHALL INCLUDE PROVISIONS FOR GROUNDCOVER ON ALL EXPOSED PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3:1 WITHIN 7 CALENDAR DAYS FROM THE LAST LAND DISTURBING ACTIVITY. GROUND COVER SHALL BE PROVIDED ON ALL OTHER DISTURBED AREAS WITHIN 14 CALENDAR DAYS FROM THE LAST LAND DISTURBING ACTIVITY.
2. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE NORTH CAROLINA EROSION AND SEDIMENT CONTROL HANDBOOK. (NO SEPARATE PAYMENT).
3. THE CONTRACTOR SHALL NOTIFY PLAN APPROVING AUTHORITY ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO FINAL INSPECTION.
4. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO CLEARING AND/OR LAND DISTURBANCE.
5. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN AND PERMIT SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
6. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO OFF-SITE BORROW OR WASTE AREAS STAGING OR STORAGE AREAS), THE CONTRACTOR SHALL PREPARE AND SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND TO TOWN OF LELAND FOR APPROVAL. CONTRACTOR SHALL PAY ALL FEES REQUIRED AND SHALL INSTALL NECESSARY MEASURES AT NO SEPARATE PAYMENT. THE CONTRACTOR SHALL PROVIDE THE OWNER AND THE ENGINEER A COPY OF THE AMENDED PERMIT.
7. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY EITHER THE REVIEWING AGENCY OR THE ENGINEER. (NO SEPARATE PAYMENT).
8. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
9. ALL AREAS DISTURBED BY CONSTRUCTION UNLESS OTHERWISE IMPROVED SHALL BE SODDED OR SEEDED AS INDICATED AND STABILIZED.
10. DURING DEWATERING OPERATIONS, WATER SHALL BE PUMPED INTO AN APPROVED FILTERING DEVICE PRIOR TO DISCHARGE TO RECEIVING OUTLET.
11. THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
12. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED BY CONTRACTOR ONCE STABILIZATION OR A SUFFICIENT GROUND COVER HAS BEEN ESTABLISHED OR AS DIRECTED BY THE ENGINEER. (NO SEPARATE PAYMENT). NCDEQ'S FINAL APPROVAL IS REQUIRED.
13. TEMPORARY GRAVEL CONSTRUCTION ENTRANCE SHALL BE REQUIRED AT ALL CONSTRUCTION STAGING AREAS AND SITE ENTRANCES.

EROSION CONTROL AND SEQUENCE OF CONSTRUCTION

THESE EROSION CONTROL AND SEQUENCE OF CONSTRUCTION NOTES ARE INTENDED FOR EACH "PHASE" OF CONSTRUCTION. THE ORDER AND STEPS TAKEN MUST BE IMPLEMENTED AS EACH PART OF THE PROJECT IS DEVELOPED; WHETHER AS A WHOLE OR IN PHASES. ANY EROSION CONTROL DEVICES/MEASURES MUST REMAIN IN PLACE UNTIL THE ENTIRE DISTURBANCE IS STABILIZED AND ALL IMPROVEMENTS WITHIN THE DISTURBANCE LIMITS ARE COMPLETE.

GENERAL EROSION CONTROL NOTES:

1. CONSTRUCT TEMPORARY GRAVEL CONSTRUCTION ENTRANCE(S), ESTABLISH THE LIMITS OF DISTURBANCE, TREE PROTECTION FENCING, AND TEMPORARY SILT FENCE.
2. CLEAR AND REMOVE FROM SITE TREES AS DESIGNATED, ROOTS, ROOT MAT, ETC. FROM THE AREA WITHIN THE DESIGNATED CLEARING LIMITS.
3. INSTALL REMAINING EROSION CONTROL MEASURES AS SHOWN ON THE PLANS WITHIN THE AREA DISTURBED. ALL EROSION CONTROL MEASURES MUST BE INSTALLED BEFORE COMMENCING CONSTRUCTION.
4. PLANT GRASS OVER ALL GRADED AREAS WITHIN 14 WORKING DAYS OF CEASE OF ANY GRADING ACTIVITY.
5. IMMEDIATELY UPON THE INSTALLATION OF ANY STORM DRAINAGE CATCH BASIN, DROP INLET, ETC., THE CONTRACTOR SHALL INSTALL INLET PROTECTION TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEM.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING AND RESTORING TO PRE-CONSTRUCTION CONDITIONS ANY AREAS OUTSIDE THE PROJECT LIMITS THAT MAY INADVERTENTLY BE DAMAGED DUE TO THE FAILURE OF THE EROSION CONTROL MEASURES.
7. DURING GRADING AND AFTER GRADING HAS BEEN COMPLETE, THE CONTRACTOR SHALL CONTINUE TO MAINTAIN PERMANENT AND TEMPORARY EROSION CONTROL MEASURES UNTIL FINAL APPROVAL BY ENGINEER OR EROSION CONTROL INSPECTOR.
8. UPON RECEIVING FINAL APPROVAL, THE CONTRACTOR CAN REMOVE TEMPORARY EROSION CONTROL MEASURES.
9. THE CONTRACTOR SHALL CONTINUE TO WATER, FERTILIZE, MOW AND MAINTAIN GRASS & PLANTED AREAS UNTIL ALL CONSTRUCTION IS COMPLETE.

GENERAL EROSION CONTROL NOTES:

1. ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF- PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK AND AFTER MAJOR RAIN EVENTS. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
2. ALL CONSTRUCTION ENTRANCES WILL BE PERIODICALLY TOP DRESSED WITH AN ADDITIONAL 2 INCHES OF #4 STONE TO MAINTAIN PROPER DEPTH. ANY SEDIMENT THAT IS TRACKED INTO THE STREET WILL BE IMMEDIATELY REMOVED.
3. SEDIMENT WILL BE REMOVED BEHIND THE SEDIMENT FENCE WHEN IT BECOMES 0.5 FEET DEEP AT THE FENCE. THE SEDIMENT FENCE WILL BE BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. SILT FENCE STAKES WILL BE SPACED 6 FEET APART UNLESS A WIRE BACKING IS USED WITH 8 FOOT STAKE SPACING.
4. ALL SEEDED AREAS WILL BE FERTILIZED, RESEEDED AS NECESSARY, AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER.
5. INLET PROTECTION – INSPECT WIRE AND ROCK INLET PROTECTION AT LEAST ONCE EVERY 7 DAYS AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE SEDIMENT STORAGE AREA TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE CONTAMINATED PART OF THE GRAVEL FACING.
6. SEDIMENT BASIN/SEDIMENT TRAPS – REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN IT ACCUMULATES TO WITHIN ONE HALF OF THE DESIGN DEPTH. PLACE SEDIMENT IN AREA WITH SEDIMENT CONTROLS. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, PIPING, AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE RISER AND POOL AREA.
7. SEDIMENT BASIN BAFFLES – BAFFLES WILL BE REPAIRED OR REPLACED IF THEY COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE. THEY WILL BE REPLACED PROMPTLY. SEDIMENT WILL BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE FIRST BAFFLE.
8. SKIMMER – INSPECT SKIMMER AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL TO MAKE SURE THAT THE INTAKE MECHANISM, ORIFICE, OR DISCHARGE PIPE IS NOT CLOGGED WITH TRASH OR SEDIMENT. IF THE BASIN IS DRY, MAKE SURE THAT ANY VEGETATION GROWING ON THE BOTTOM IS NOT HOLDING THE SKIMMER DOWN. TAKE SPECIAL PRECAUTION IN WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.
9. OUTLET PROTECTION – INSPECT RIP RAP OUTLET STRUCTURES WEEKLY AND AFTER SIGNIFICANT (21 INCH OR GREATER) RAINFALL EVENTS TO SEE IF ANY EROSION AROUND OR BELOW THE RIP RAP HAS TAKEN PLACE, OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.
10. EMERGENCY SPILLWAY / FOREBAY PROTECTION – AFTER EVERY HIGH-WATER EVENT INSPECT THE INTEGRITY OF THE LINED SPILLWAY AND THE ADJACENT EARTHEN BANKS. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE. REPAIR ANY VOIDS IN THE RIP RAP LINED APRONS, RE-ESTABLISH ANY LOOSE STONES, AND FIX GAPS IN THE ADJACENT VEGETATIVE COVER.
11. TEMPORARY DIVERSION DITCH – INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.
12. CHECK DAMS-EXCELSIOR OR RIP-RAP SEDIMENT SHALL BE REMOVED FROM THE CHECK DAM WHEN IT REACHES HALF FILLED. CHECK DAMS SHALL BE REPAIRED OR REPLACED WHEN THEY NO LONGER DRAIN AS DESIGNED OR ARE DISLODGED AND CHANNEL SHALL BE REPAIRED OR RUTS, PIPIING AND SETTLEMENT AROUND THE DAM AS NEEDED.
13. SEDIMENT FILTER BAG ON A TEMPORARY PUMP AROUND SYSTEM-INSPECT THE BAG AND ITS CONNECTION TO THE PUMPING APPARATUS TO ENSURE THERE IS NO LEAKAGE FOR THE DURATION OF DE-WATERING ACTIVITIES. IF THE SEDIMENT BAG TEARS OR IS DAMAGED IN ANY WAY DURING CONSTRUCTION OF THE CULVERT CROSSING OR DE-WATERING ACTIVITY, THE CONTRACTOR SHALL REPAIR OR REPLACE THE SEDIMENT BAG IMMEDIATELY.

NORTH CAROLINA ACCESSIBILITY NOTES:

1. SPECIAL ATTENTION SHALL BE GIVEN TO COMPLIANCE WITH AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NORTH CAROLINA BUILDING CODE/ANSI A117.1, AND APPLICABLE LOCAL LAWS & REGULATIONS.
2. IT IS ESSENTIAL THAT CONTRACTORS ARE AWARE OF THE SITE ACCESSIBILITY REQUIREMENTS. PARAMOUNTE ENGINEERING HAS DEVELOPED THESE NOTES AND DETAILS TO ASSURE THAT CONTRACTORS ARE AWARE OF THE REQUIREMENTS AT THE POINT IN TIME WHEN THEY ARE BIDDING THE PROJECT. IN ADDITION, PARAMOUNTE ENGINEERING HAS MADE A POINT IN THESE NOTES AND DETAILS, AS WELL AS IN OUR DRAWINGS, TO PROVIDE SLOPES / GRADES AND DIMENSIONS THAT COMPLY WITH THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NORTH CAROLINA BUILDING CODE/ANSI A117.1 AND APPLICABLE LOCAL LAWS & REGULATIONS. IF THESE SLOPES / GRADES AND DIMENSIONS ARE NOT ACHIEVABLE, THE CONTRACTOR IS REQUIRED TO CONTACT THE OWNER IMMEDIATELY AND BEFORE MOVING FORWARD WITH THE WORK.
3. THE CONTRACTOR SHALL NOTIFY PARAMOUNTE ENGINEERING IMMEDIATELY OF ANY CONFLICT BETWEEN THESE NOTES AND DETAILS AND OTHER PROJECT DRAWINGS, WHETHER BY PARAMOUNTE ENGINEERING OR OTHERS. THE CONTRACTOR SHALL NOT PROCEED WITH THE WORK FOR WHICH THE ALLEGED CONFLICT HAS BEEN DISCOVERED UNTIL SUCH ALLEGED CONFLICT HAS BEEN RESOLVED. NO CLAIM SHALL BE MADE BY THE CONTRACTOR FOR DELAY OR DAMAGES AS A RESULT OF RESOLUTION OF ANY SUCH CONFLICT(S).
4. THESE ACCESSIBILITY NOTES AND DETAILS ARE INTENDED TO DEPICT SLOPE AND DIMENSIONAL REQUIREMENTS ONLY. REFER TO SIDEWALK, CURBING, AND PAVEMENT DETAILS FOR ADDITIONAL INFORMATION.

GENERAL ACCESSIBLE ROUTE NOTES:

1. AT LEAST ONE ACCESSIBLE ROUTE SHALL BE PROVIDED WITHIN THE SITE FROM ACCESSIBLE PARKING SPACES AND ACCESSIBLE PASSENGER LOADING ZONES; PUBLIC STREETS OR SIDEWALKS; AND PUBLIC TRANSPORTATION STOPS TO THE ACCESSIBLE BUILDING OR FACILITY ENTRANCE THEY SERVE.
2. AT LEAST ONE ACCESSIBLE ROUTE SHALL CONNECT ACCESSIBLE BUILDINGS, ACCESSIBLE FACILITIES, ACCESSIBLE ELEMENTS, AND ACCESSIBLE SPACES THAT ARE ON THE SAME SITE.
3. WALKING SURFACES THAT ARE PART OF AN ACCESSIBLE ROUTE SHALL HAVE A MAXIMUM RUNNING SLOPE OF 5.0% AND A MAXIMUM CROSS SLOPE OF 2.0%.
4. ANY WALKING SURFACE THAT IS PART OF AN ACCESSIBLE ROUTE WITH A RUNNING SLOPE GREATER THAN 5.0% IS A RAMP AND SHALL COMPLY WITH THE GUIDELINES FOR RAMPS OR CURB RAMPS.
5. TRANSITIONS BETWEEN RAMPS, WALKS, LANDINGS, GUTTERS OR STREETS SHALL BE FLUSHAND FREE OF ABRUPT VERTICAL CHANGES (1/4 INCH MAXIMUM VERTICAL CHANGE IN LEVEL PERMITTED).
6. FLOOR SURFACES SHALL BE STABLE, FIRM AND SLIP RESISTANT.
7. THE MINIMUM CLEAR WIDTH OF EXTERIOR ACCESSIBLE ROUTES SHALL BE FORTY-EIGHT (48) INCHES MINIMUM MEASURED BETWEEN HANDRAILS WHERE HANDRAILS ARE PROVIDED (NC BUILDING CODE 1104.1 & 1104.2).
8. WHERE AN ACCESSIBLE ROUTE MAKES A 180 DEGREE TURN AROUND AN OBJECT THAT IS LESS THAN FORTY-EIGHT (48) INCHES IN WIDTH, CLEAR WIDTH SHALL BE FORTY-TWO (42) INCHES MINIMUM APPROACHING THE TURN, FORTY-EIGHT (48) INCHES MINIMUM DURING THE TURN, AND FORTY-TWO (42) INCHES MINIMUM LEAVING THE TURN. THE CLEAR WIDTH APPROACHING AND LEAVING THE TURN MAY BE THIRTY-SIX (36) INCHES MINIMUM WHEN THE CLEAR WIDTH AT THE TURN IS SIXTY (60) INCHES MINIMUM. .* SEE NOTE 7 ABOVE FOR NC CLEAR WIDTH OF EXTERIOR ACCESSIBLE ROUTES*
9. AN ACCESSIBLE ROUTE WITH A CLEAR WIDTH LESS THAN SIXTY (60) INCHES SHALLPROVIDE PASSING SPACES AT INTERVALS OF TWO HUNDRED (200) FEET MAXIMUM. PASSING SPACES SHALL BE EITHER A SIXTY (60) INCH MINIMUM BY SIXTY (60) INCH MINIMUM SPACE; OR AN INTERSECTION OF TWO (2) WALKING SURFACES THAT PROVIDE A COMPLIANT T-SHAPED TURNING SPACE, PROVIDED THE BASE AND ARMS OF THE T-SHAPED SPACE EXTEND FORTY-EIGHT (48) INCHES MINIMUM BEYOND THE INTERSECTION.
10. DOORS, DOORWAYS AND GATES THAT ARE PART OF AN ACCESSIBLE ROUTE SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NORTH CAROLINA BUILDING CODE/ ANSI A117.1, AND APPLICABLE LOCAL LAWS & REGULATIONS.
11. DIRECTIONAL SIGNAGE INDICATING THE ROUTE TO THE NEAREST ACCESSIBLE BUILDING ENTRANCE SHALL BE PROVIDED AT INACCESSIBLE BUILDING ENTRANCES.
12. WHERE POSSIBLE, DRAINAGE INLETS SHALL NOT BE LOCATED ON AN ACCESSIBLE ROUTE. IN THE EVENT THAT A DRAINAGE INLET MUST BE LOCATED ON AN ACCESSIBLE ROUTE, THE GRATE SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), A117.1, THE NC BUILDING CODE, AND APPLICABLE LOCAL LAWS & REGULATIONS

GENERAL ACCESSIBLE ROUTE NOTES:

1. ANY PART OF AN ACCESSIBLE ROUTE WITH A RUNNING SLOPE GREATER THAN 5% SHALL BE CONSIDERED A RAMP.
2. THE MAXIMUM RUNNING SLOPE FOR A RAMP SHALL BE 8.33% AND THE MAXIMUM CROSS SLOPE SHALL BE 2.0%.
3. THE CLEAR WIDTH OF AN EXTERIOR RAMP RUN SHALL BE FORTY EIGHT INCHES (NC BUILDING CODE 1104.1). WHERE HANDRAILS ARE PROVIDED ON THE RAMP RUN, THE CLEAR WIDTH SHALL BE MEASURED BETWEEN THE HANDRAILS.
4. THE RISE FOR ANY RAMP RUN SHALL BE THIRTY (30) INCHES MAXIMUM.
5. LANDINGS SHALL BE PROVIDED AT THE TOP AND BOTTOM OF RAMPS. LANDINGS SHALL HAVE A SLOPE NOT STEEPER THAN 2.0% IN ANY DIRECTION. THE LANDING CLEAR WIDTH SHALL BE AT LEAST AS WIDE AS THE WIDEST RAMP RUN LEADING TO THE LANDING. THE LANDING CLEAR LENGTH SHALL BE SIXTY (60)INCHES.
6. RAMP RUNS WITH A RISE GREATER THAN SIX (6) INCHES SHALL HAVE HANDRAILS ON BOTH SIDES COMPLYING WITH THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NC BUILDING CODE/ANSI A117.1, AND APPLICABLE LOCAL LAWS & REGULATIONS.
7. FLOOR SURFACES OF RAMPS AND LANDINGS SHALL BE STABLE, FIRM AND SLIP RESISTANT.
8. EDGE PROTECTION COMPLYING WITH AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NC BUILDING CODE/ANSI A117.1, AND APPLICABLE LOCAL LAWS & REGULATIONS SHALL BE PROVIDED ON EACH SIDE OF RAMP RUNS AND ON EACH SIDE OF RAMP LANDINGS.
9. WHERE DOORWAYS ARE LOCATED ADJACENT TO A RAMP LANDING, MANEUVERING CLEARANCES REQUIRED BY THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS), THE NC BUILDING CODE/ANSI A117.1 SHALL BE PERMITTED TO OVERLAP THE REQUIRED LANDING AREA. WHERE DOORS THAT ARE SUBJECT TO LOCKING ARE ADJACENT TO A RAMP LANDING, LANDINGS SHALL BE SIZED TO PROVIDE A COMPLIANT TURNING SPACE.

GENERAL CURB RAMP NOTES:

1. THE MAXIMUM RUNNING SLOPE OF A CURB RAMP SHALL BE 8.33% AND THE MAXIMUM CROSS SLOPE SHALL BE 2.0%.
2. COUNTER SLOPES OF ADJOINING GUTTERS AND ROAD SURFACES IMMEDIATELY ADJACENT TO THE CURB RAMP SHALL NOT BE STEEPER THAN 5%. THE ADJACENT SURFACES AT TRANSITIONS AT CURB RAMPS TO WALKS, GUTTERS AND STREETS SHALL BE AT THE SAME LEVEL.
3. THE CLEAR WIDTH OF A CURB RAMP SHALL BE 36 INCHES (36) MINIMUM, EXCLUSIVE OF FLARED SIDES, IF PROVIDED. *NOTE NC BUILDING CODE REQUIRES EXTERIOR ACCESSIBLE ROUTES TO BE 48 INCHES MINIMUM WIDE (1104.1 & 1104.2).*
4. LANDINGS SHALL BE PROVIDED AT THE TOP OF CURB RAMPS. THE CLEAR LENGTH OF THE LANDING SHALL BE THIRTY-SIX (36) INCHES MINIMUM. THE CLEAR WIDTH OF THE LANDING SHALL BE AT LEAST AS WIDE AS THE CURB RAMP, EXCLUDING FLARED SIDES, LEADING TO THE LANDING. LANDINGS SHALL HAVE A SLOPE NOT STEEPER THAN 2% IN ANY DIRECTION.
5. IF A CURB RAMP IS LOCATED WHERE PEDESTRIANS MUST WALK ACROSS THE RAMP, OR WHERE IT IS NOT PROTECTED BY HANDRAILS OR GUARDRAILS, IT SHALL HAVE FLARED SIDES.
6. WHERE PROVIDED, CURB RAMP FLARES SHALL NOT EXCEED 10%.
7. CURB RAMPS AND THE FLARED SIDES OF CURB RAMPS SHALL BE LOCATED SO THAT THEY DO NOT PROJECT INTO VEHICULAR TRAFFIC LANES, PARKING SPACES OR PARKING ACCESS AISLES. CURBS AT MARKED CROSSINGS SHALL BE WHOLLY CONTAINED WITHIN THE MARKINGS, EXCLUDING ANY FLARED SIDES.
8. CURB RAMPS SHALL BE LOCATED OR PROTECTED TO PREVENT THEIR OBSTRUCTION BY PARKED VEHICLES.
9. IT IS RECOMMENDED TO PROVIDE CURB RAMPS WITH A TWENTY-FOUR (24) INCH DEEP DETECTABLE WARNING COMPLYING WITH 406.12 A117.1, EXTENDING THE FULL WIDTH OF THE RAMP. REFERTO DETECTABLE WARNING DETAILS AND NOTES FOR PLACEMENT, ORIENTATION AND NOTES. THE NC BUILDING CODE DOES NOT CURRENTLY REQUIRE DETECTABLE WARNINGS AT CURB RAMPS, NOR DO THE 2010 ADA STANDARDS – HOWEVER US DOT ADA REGULATIONS DO REQUIRE THESE.
10. FLOOR SURFACES OF CURB RAMPS SHALL BE DEEP GROOVED, ½ INCH WIDE BY ¼ INCH DEEP, ONE (1) INCH CENTERS TRANSVERSE TO THE RAMP.
11. WHERE PROVIDED, STOP LINES SHALL BE LOCATED IN ADVANCE OF CURB RAMP.
12. WHERE PROVIDED, PEDESTRIAN ACTIVATED SIGNALS SHALL BE LOCATED ADJACENT TO THE SIDEWALK AND NOT ON THE SIDEWALK.
13. WHERE PROVIDED, DRAINAGE INLETS SHALL BE LOCATED UPSTREAM OF CURB RAMPS AND NOT IN THE RAMP AREA.
14. CURB RAMP TYPE AND LOCATION ARE PER PLAN.

NORTH CAROLINA ACCESSIBILITY NOTES CONTINUED:

PARKING SPACE NOTES

1. ACCESSIBLE PARKING SPACES SHALL BE LOCATED ON THE SHORTEST ACCESSIBLE ROUTES OF TRAVEL FROM ADJACENT PARKING TO AN ACCESSIBLE BUILDING ENTRANCE.
2. ACCESSIBLE PARKING SPACES SHALL BE AT LEAST NINETY-SIX (96) INCHES WIDE. ACCESS AISLES SHALL BE 60 INCHES WIDE. ONE OF SIX ACCESSIBLE SPACES SHOULD PROVIDE A VAN ACCESSIBLE AISLE. THE AISLE SHOULD BE 96 INCHES WIDE (OR ACCESSIBLE SPACE IS 11 FEET AND ACCESS AISLE IS FIVE FEET). WHERE PARKING SPACES AND ACCESS AISLES ARE MARKED WITH LINES, THE WIDTH MEASUREMENTS SHALL BE MADE FROM CENTERLINE OF THE MARKINGS. WHERE PARKING SPACES OR ACCESS AISLES ARE NOT ADJACENT TO ANOTHER PARKING SPACE OR ACCESS AISLES, MEASUREMENTS SHALL BE PERMITTED TO INCLUDE THE FULL WIDTH OF THE LINE DEFINING THE PARKING SPACE OR ACCESS AISLE.
3. PARKING ACCESS AISLES SHALL BE PART OF AN ACCESSIBLE ROUTE TO THE BUILDING OR FACILITY ENTRANCE AND SHALL COMPLY WITH PROVISIONS FOR ACCESSIBLE ROUTES. MARKED CROSSINGS SHALL BE PROVIDED WHERE THE ACCESSIBLE ROUTE MUST CROSS VEHICULAR TRAFFIC LANES. WHERE POSSIBLE, IT IS PREFERABLE THAT THE ACCESSIBLE ROUTE NOT PASS BEHIND PARKED VEHICLES.
4. TWO (2) ACCESSIBLE PARKING SPACES MAY SHARE A COMMON ACCESS AISLE.
5. ACCESS AISLES SHALL EXTEND THE FULL LENGTH OF THE PARKING SPACE THEY SERVE.
6. ACCESS AISLES SHALL BE MARKED SO AS TO DISCOURAGE PARKING IN THEM.
7. ACCESS AISLES SHALL NOT OVERLAP THE VEHICULAR WAY. ACCESS AISLES SHALL BE PERMITTED TO BE PLACED ON EITHER SIDE OF THE PARKING SPACE EXCEPT FOR ANGLED VAN PARKING SPACES WHICH SHALL HAVE ACCESS AISLES LOCATED ON THE PASSENGER SIDE OF THE PARKING SPACES.
8. FLOOR SURFACES OF PARKING SPACES AND ACCESS AISLES SERVING THEM SHALL BE STABLE, FIRM AND SLIP RESISTANT. ACCESS AISLES SHALL BE AT THE SAME LEVEL AS THE PARKING SPACES THEY SERVE. CHANGES IN LEVEL ARE NOT PERMITTED.
9. PARKING SPACES AND ACCESS AISLES SHALL BE LEVEL WITH SURFACE SLOPES NOT EXCEEDING 2.0% IN ALL DIRECTIONS.
10. PARKED VEHICLE OVERHANGS SHALL NOT REDUCE THE REQUIRED CLEAR WIDTH OF AN ACCESSIBLE ROUTE.
11. PARKING SPACES FOR VANS AND ACCESS AISLES AND VEHICULAR ROUTES SERVING THEM SHALL PROVIDE A VERTICAL CLEARANCE OF NINETY-EIGHT (98) INCHES MINIMUM. SIGNS SHALL BE PROVIDED AT ENTRANCES TO PARKING FACILITIES INFORMING DRIVERS OF CLEARANCES AND THE LOCATION OF VAN ACCESSIBLE PARKING SPACES.
12. EACH ACCESSIBLE PARKING SPACE SHALL BE PROVIDED WITH SIGNAGE DISPLAYING THE INTERNATIONAL SYMBOL OF ACCESSIBILITY. SIGNS SHALL BE INSTALLED AT A MINIMUM CLEAR HEIGHT OF SIXTY (60) INCHES ABOVE GRADE AND SHALL NOT INTERFERE WITH AN ACCESSIBLE ROUTE FROM AN ACCESS AISLE. SIGNS LOCATED WHERE THEY MAY BE HIT BY VEHICLES BEING PARKED SHALL BE INSTALLED WITH BOLLARD PROTECTION.
13. SIGNAGE AT ACCESSIBLE PARKING SPACES REQUIRED BY THE NC BUILDING CODE SECTION 1106.1 SHALL COMPLY WITH THE REQUIREMENTS OF NORTH CAROLINA GENERAL STATUTE 20-37.6 AND 136-30 AND THE NCDOT UNIFORM MANUAL ON TRAFFIC CONTROL DEVICES. A SEPARATE SIGN IS REQUIRED FOR EACH SPACE. SIGNS TO INDICATE THE MAXIMUM PENALTY MUST BE PROVIDED AT EACH ACCESSIBLE SPACE.
14. ACCESSIBLE PARKING SPACE, ACCESS AISLE STRIPING, AND INTERNATIONAL SYMBOL OF ACCESSIBILITY SHALL BE PAINTED BLUE (OR ANOTHER COLOR THAT CAN BE DISTINGUISHED FROM PAVEMENT).

PASSENGER LOADING ZONE NOTES:

1. PASSENGER LOADING ZONES SHALL PROVIDE VEHICULAR PULL-UP SPACE NINETY-SIX (96) INCHES WIDE MINIMUM AND TWENTY (20) FEET LONG MINIMUM.
2. PASSENGER LOADING ZONES SHALL PROVIDE A CLEARLY MARKED ACCESS AISLE THAT IS SIXTY (60) INCHES WIDE MINIMUM AND EXTENDS THE FULL LENGTH OF THE VEHICLE PULL-UP SPACE THEY SERVE.
3. ACCESS AISLE SHALL ADJOIN AN ACCESSIBLE ROUTE AND NOT OVERLAP THE VEHICULAR WAY.
4. VEHICLE PULL-UP SPACES AND ACCESS AISLES SERVING THEM SHALL BE LEVEL WITH SURFACE SLOPES NOT EXCEEDING 2.0% IN ALL DIRECTIONS. ACCESS AISLES SHALL BE AT THE SAME LEVEL AS THE VEHICLE PULL-UP SPACE THEY SERVE. CHANGES IN LEVEL ARE NOT PERMITTED.
5. FLOOR SURFACES OF VEHICLE PULL-UP SPACES AND ACCESS AISLES SERVING THEM SHALL BE STABLE, FIRM AND SLIP RESISTANT.
6. VEHICLE PULL-UP SPACES, ACCESS AISLES SERVING THEM AND A VEHICULAR ROUTE FROM AN ENTRANCE TO THE PASSENGER LOADING ZONE, AND FROM THE PASSENGER LOADING ZONE TO A VEHICULAR EXIT SERVING THEM, SHALL PROVIDE A VERTICAL CLEARANCE OF ONE HUNDRED FOURTEEN (114)INCHES MINIMUM.

ACCESSIBLE ENTRANCE NOTES:

1. ACCESSIBLE ENTRANCES SHALL BE PROVIDED AS REQUIRED BY THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS) AND THE NORTH CAROLINA BUILDING CODE, AND APPLICABLE LOCAL LAWS & REGULATIONS.
2. ENTRANCE DOORS, DOORWAYS AND GATES SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT (2010 ADA STANDARDS) THE NC BUILDING CODE/ANSI A117.1 AND SHALL BE ON AN ACCESSIBLE ROUTE.

GENERAL STORM SEWER NOTES:

1. ALL STORMDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH TOWN OF LELAND AND STATE OF NORTH CAROLINA REQUIREMENTS AS SPECIFIED ON THE DRAWINGS AND PROJECT SPECIFICATIONS.
2. BEDDING FOR ALL STORMDRAIN PIPE SHALL BE AS SPECIFIED ON THE DRAWINGS.
3. ALL STORMDRAIN PIPES SHOWN AS RCP ON THE PLANS SHALL BE REINFORCED CONCRETE PIPE CONFORMING TO ASTM C-76, UNLESS INDICATED OTHERWISE ON PLANS.

ROOF DRAIN NOTES:

1. PROPOSED BUILDINGS SHALL DIVERT ROOF DRAINAGE TO STORMWATER COLLECTION SYSTEMS.

EXISTING UTILITY NOTES:

1. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO VERIFY THE ACTUAL LOCATION AND AVAILABILITY OF ALL EXISTING AND PROPOSED UTILITIES IN THE FIELD PRIOR TO GROUND BREAKING.
2. EXISTING UTILITIES AND STRUCTURES SHOWN, BOTH UNDERGROUND AND ABOVE GROUND, ARE BASED ON A FIELD SURVEY AND THE BEST AVAILABLE RECORD DRAWINGS. THE CONTRACTOR SHALL FIELD VERIFY FIELD CONDITIONS PRIOR TO BEGINNING RELATED CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO THE OWNER'S REPRESENTATIVE IMMEDIATELY.

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

GENERAL NOTES

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET: C1.1

N/F
COUNTY OF HARNETT
DB 4253 PG 1200
PB 2024 PG 399 (NEW LOT 2)
PIN # 1515-08-4063

N/F
COUNTY OF HARNETT
DB 4253 PG 1200
PB 2024 PG 399 (NEW LOT 2)
PIN # 1515-08-4063

N/F
SAM HARNETT I LLC
DB 4253 PG 1280
PB 2024 PG 399 (NEW LOT 1)
PIN # 1515-06-6718
AREA: 13.471 AC. ±

S 57°45'21" E 704.10'

S 32°13'32" W 290.20'
[SURVEY TIE]

DIRT PATH

EXISTING PROPERTY LINE

N 32°14'39" E 413.91'

OLD DUNN-FAYETTEVILLE ROAD
PER DB 609 PG 816 & PB 1 PG 67
APPARENT 30' R/W
ROADWAY IMPROVEMENTS
NO LONGER PRESENT

EXISTING FIBER OPTIC HANDHOLE

EXISTING WATER VALVE

TBM: SSM #1109 (GCO NAIL SET)
ELEV: 186.33' (NAVD 88)

POWER POLE W/ GUY WIRES

135.30'

N 32°58'16" W 476.11' (TOTAL)

340.81'

ASPHALT ROAD

CONC. CURB (TYP.)

12" WATER MAIN

EXISTING FIRE HYDRANT

UNDERGROUND TELECOM

EXISTING CONTOUR

N 45°08'16" W 240.53'

C5

C6

C7

L4

L7

8" DIP GRAVITY SANITARY SEWER MAIN

198.77'

UNDERGROUND TELECOM

OVERHEAD ELECTRIC

WOODED AREA

EXISTING POWER POLE

EXISTING SANITARY SEWER MANHOLE

EXISTING STORMDRAIN PIPE

EXISTING POWER POLE

EXISTING POWER POLE

EXISTING SANITARY SEWER MANHOLE

EXISTING 18" RCP STORMDRAIN

UNDERGROUND ELECTRIC

APPROX. LOCATION OF BURIED STORM PIPE, SEE DRAWINGS

BURIED STORM PIPE

TOP OF BURIED STORM PIPE IS 17.37' BELOW GRADE

S 63°23'41" W 430.70'

RBF

DRAIN INLET
GRATE: 174.66
INVERTS:
UNOBTAINABLE
DEBRIS IN BOX

SSMH
RIM: 179.01
IN: 173.01

SSMH
RIM: 179.51
IN: 173.31
OUT: 173.39

SSMH
RIM: 180.59
IN: 174.11
OUT: 174.07

SSMH
RIM: 182.79
IN: 175.89
OUT: 175.79

SSMH
RIM: 187.28
IN: 180.28
OUT: 180.27

LOCATION MAP N.T.S.

SITE

0 25 50 100 Feet
1:50

LEGEND

- STORM WATER LINE
- SS — SANITARY SEWER LINE
- CO — SEWER CLEANOUT LINE
- OHW — OVERHEAD WIRES
- E — BURIED ELECTRIC LINE
- G — BURIED GAS LINE
- T — BURIED TELECOM. LINE
- W — BURIED WATER LINE
- FD — BURIED STEAM LINE
- UTILITY POLE
- LIGHT POLE
- ELEC. SERVICE/VAULT
- TELEPHONE PEDESTAL
- FIBER OPTIC WARNING POST
- WATER VALVE
- WATER VALVE MANHOLE
- FIRE HYDRANT
- SANITARY MANHOLE
- SANITARY CLEANOUT
- SIGN
- IPS — IRON PIPE SET

LINE TABLE

LINE	BEARING	DISTANCE
L1	S 48°52'53" E	15.0'
L2	S 41°22'29" E	380.15'
L3	N 39°51'24" W	313.32'
L4	S 69°17'28" E	109.37'
L5	S 20°23'14" W	123.32'
L6	N 69°36'46" W	15.0'
L7	S 77°37'29" W	88.33'
L8	N 32°58'16" W	70.43'
L9	S 43°30'47" E	15.07'

CURVE TABLE

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C1	138947.59'	313.34'	313.34'	N 31°19'21" E	0°07'45"
C2	285250.68'	474.35'	474.35'	N 31°18'20" E	0°05'43"
C3	10658.5'	217.13'	217.13'	N 31°58'12" E	1°10'02"
C4	151.73'	84.51'	83.42'	N 62°47'02" W	31°54'45"
C5	1869.86'	397.06'	396.31'	N 39°03'16" W	12°09'59"
C6	140.0'	41.59'	41.59'	N 40°47'14" E	17°00'59"
C7	125.0'	25.17'	25.12'	S 63°31'24" E	11°32'07"

EXISTING CONDITIONS SURVEY DATA FROM PRELIMINARY SURVEY BY SSM SURVEYING AND MAPPING, P.C. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UTILITY LOCATION AND SURVEY PRIOR TO COMMENCING CONSTRUCTION

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNET COUNTY 1

EXISTING CONDITIONS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C1.2

0 25 50 100 Feet

1:50

CATCH BASIN TABLE

Inlet	Elevation (Rim)(ft)	Elevation (Invert)(ft)
CI-1A	183.8	181.2
CI-1B	183.8	181.1
CI-2A	188.5	180.6
CI-2B	183.7	180.7
CI-3A	188.5	180.5
CI-3B	183.7	180.2
CI-4A	187.5	179.7
CI-4B	183.8	179.8
CI-5A	188.0	179.6
CI-5B	186.5	179.5
CI-6A	189.2	179.5
CI-6B	187.9	179.0
CI-7A	189.0	179.3
CI-7B	187.2	178.4
CI-8A	188.9	179.1
CI-8B	188.9	182.6
CI-9A	188.9	178.9
CI-9B	189.4	182.9
CI-10A	188.9	178.9
CI-10B	189.4	182.9
CI-11A	189.1	178.6
CI-11B	189.4	183.2
CI-12A	189.1	178.5
CI-12B	189.4	183.3
CI-14B	189.4	183.6
CI13B	189.4	183.6
MH1	184.2	178.1

SEE SHEETS C5.1–C5.11 FOR STANDARD DETAILS

NOTE

WET BASIN'S UTILIZED AS PART OF A SEDIMENTATION AND EROSION CONTROL PLAN SHALL BE CLEANED OUT TO INCLUDE REMOVAL OF ALL BAFFLES, SEDIMENT AND DEWATERING DEVICES. UPON COMPLETION OF CLEANOUT, POND SLOPES SHALL BE RE–ESTABLISHED AS PER THE PLANS. FOREBAYS SHALL BE INSTALLED AS SHOWN ON THIS SHEET BEFORE PONDS MAY BE UTILIZED FOR STORMWATER TREATMENT.

SEE SHEET C2.2 FOR POND CROSS SECTION AND STAGE STORAGE TABLES

LEGEND

- CURB INLET–SEE DETAIL SHEET C5.xxx
- SD — STORM DRAIN PIPE MATERIAL AS DESCRIBED
- HEAVY DUTY ASPHALT PAVEMENT
- HEAVY DUTY CONCRETE PAVEMENT
- STANDARD DUTY ASPHALT PAVEMENT

EXISTING SPOT ELEVATIONS

EXISTING CONTOURS

FUTURE DEVELOPMENT

DIVERSION/TRAP–SEE SEDIMENTATION AND EROSION CONTROL PLANS

DRIVEWAY 1

EX. PROPERTY LINE

PROPOSED CURB INLET (TYP.)

144 +/– LF 36" HDPE

88 +/– LF 36" RCP

152 +/– LF 36" HDPE

END TREATMENT PER DETAIL 1 SHEET C5.3

65 +/– LF 18" CLASS III RCP

PROPOSED CURB INLET (TYP.)

END TREATMENT PER DETAIL 1 SHEET C5.3

CI 1A CI 1B CI 2B CI 3B CI 4B CI 5B

175 +/– LF 24" RCP

154 +/– LF 36" HDPE

VEHICLE RAMP

8" PVC–OUTLET ROOF DRAINS TO RAMP–SEE DETAIL SHEET C5.6

PROPOSED V–CURB SEE DETAIL SHEET C

CI 3A CI 2A

PROPOSED CURB INLET (TYP.)

34 +/– LF 24" RCP

HEAVY DUTY CONCRETE

8" PVC–OUTLET ROOF DRAINS TO RAMP–SEE DETAIL SHEET C5.6

4' SIDEWALK

PUMP ROOM 105 ELEV 104

8" PVC–ROOF DRAIN LEADER

ROOF DRAINS SHALL OUTLET TO LOADING DOCK AND SHEET FLOW TO PROPOSED SD INLETS AS SHOWN

8" PVC–ROOF DRAIN LEADER

VEHICLE RAMP

US 301 S.

357 +/– LF 36" HDPE

255 +/– LF 24" RCP

24" CURB AND GUTTER

HEAVY DUTY ASPHALT

WAREHOUSE 100 FFE 191.0

CI 6B

357 +/– LF 36" HDPE

34 LF +/– 24" RCP

CI 4A

DRIVEWAY 2

CI 5A

38 LF +/– 24" HDPE

4' SIDEWALK

6' SIDEWALK

5' SIDEWALK

FIRE ACCESS LANE

PROPOSED CURB INLET (TYP.)

OFFICE AREA

CI 6A

38 LF +/– 24" HDPE

PROPERTY LINE

END TREATMENT PER DETAIL 1 SHEET C5.3

38 LF +/– 18"HDPE

CI 9A CI 12A CI 13B CI 14B CI 10A CI 11A CI 11B CI 12B CI 10B CI 8B CI 9B CI 7B

92 +/– LF 15" HDPE

93 +/– LF 15" HDPE

43 +/– LF 18" HDPE

85 +/– LF 36" HDPE

100 +/– LF 18" CLASS III RCP

END TREATMENT PER DETAIL 1 SHEET C5.3

CI 7A

13 LF +/– 24" HDPE

CI 8A

91 +/– LF 24" CLASS III RCP

82+/– LF 15" HDPE

MH1

26 +/– LF 36" CLASS III RCP

11 +/– LF 15" HDPE

13 +/– LF 15" HDPE

13 +/– LF 15" HDPE

11 +/– LF 24" HDPE

61 LF +/– 24" HDPE

91 +/– LF 24" HDPE

PROPOSED POND OUTLET STRUCTURE SEE DETAIL SHEET C2.2

FES 1 WITH RIP RAP APRON INVERT: 178 SEE DETAIL SHEET C2.3

FES 2 WITH RIP RAP APRON INVERT: 178 SEE DETAIL SHEET C2.3

ARROWHEAD ROAD

CONC. CURB (TYP.)

PROPOSED STORMWATER POND SEE POND SECTION SHEET C2.2

PROPOSED STORMWATER POND FENCE

85 +/– LF 18" CLASS III RCP

PROPOSED FES AND RIP RAP APRON INVERT:176.8

Q_f=CIA: 0.3 X 3.9 X 15 = 15.71 CFS (EXISTING)
Tc EXISTING: 15 MIN

Q_f=CIA: 0.55 X 5.24 X 7.98 = 22.9 CFS (PROPOSED POND B OUTFALL)
Tc PROPOSED: 5MINS POND OUTFALL

POND A ATTENUATED OUTFLOW (1YR 24HR): 0.03 CFS

TIME OF CONCENTRATION Tc FOR EXISTING CONDITION CALCULATED USING THE KIRPICH EQUATION.

EQUATION 2 – POND: VOLUME OF PERMANENT POOL: 339,123; SURFACE AREA: 46,484; AVERAGE DEPTH: 7.29'

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

DATE

REVISION

NO.

SAMET HARNETT COUNTY 1

PRELIMINARY OVERALL STORMDRAIN

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

C2.0

0 25 50 100 Feet
1:50

SEE SHEETS C5.1–C5.11 FOR STANDARD DETAILS

NOTE
WET BASIN'S UTILIZED AS PART OF A SEDIMENTATION AND EROSION CONTROL PLAN SHALL BE CLEANED OUT TO INCLUDE REMOVAL OF ALL BAFFLES, SEDIMENT AND DEWATERING DEVICES. UPON COMPLETION OF CLEANOUT, POND SLOPES SHALL BE RE-ESTABLISHED AS PER THE PLANS. FOREBAYS SHALL BE INSTALLED AS SHOWN ON THIS SHEET BEFORE PONDS MAY BE UTILIZED FOR STORMWATER TREATMENT.

SEE SHEET C2.2 FOR POND CROSS SECTION AND STAGE STORAGE TABLES

LEGEND
- CURB INLET–SEE DETAIL SHEET C5.xxx
- SD — STORM DRAIN PIPE MATERIAL AS DESCRIBED
- HEAVY DUTY ASPHALT PAVEMENT
- HEAVY DUTY CONCRETE PAVEMENT
- STANDARD DUTY ASPHALT PAVEMENT

EXISTING SPOT ELEVATIONS
EXISTING CONTOURS
FUTURE DEVELOPMENT
EX. PROPERTY LINE
PROPOSED CURB INLET (TYP.)
PROPOSED V-CURB
DRIVEWAY 1
APPROXIMATE PHASE LIMITS (16 ACRES +/–)
HEAVY DUTY CONCRETE
PROPOSED CURB INLET (TYP.)
APPROXIMATE STORMWATER POND
4' SIDEWALK
VEHICLE RAMP
24" CURB AND GUTTER
HEAVY DUTY ASPHALT
WAREHOUSE
100
PUMP ROOM
105
ELEC.
104
OFFICE AREA
101
FIRE ACCESS LANE
6' SIDEWALK
5' SIDEWALK
PROPOSED CURB INLET (TYP.)
DRIVEWAY 2
PROPERTY LINE
BENCHMARK
TBM #1 X MARK ON MAIL SET
ELEV. = 192.10' (NAVD 88)
ASPHALT ROAD
CONC. ISLAND
ARROWHEAD ROAD
CONC. CURB (TYP.)
PROPOSED STORMWATER POND
PROPOSED STORMWATER POND FENCE
PROPOSED POND OUTLET STRUCTURE
BURIED STORM PIPE
APPROX. LOCATION OF BURIED STORM PIPE AND MANHOLE
US 301 S.
SAMET HARNETT COUNTY 1
PRELIMINARY OVERALL STORMDRAIN

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

DATE
REVISION
NO.

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C2.1





POND PROFILE (NOT TO SCALE)

STAGE STORAGE TABLE						
ELEV	AREA (sq. ft.)	DEPTH (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)	CONIC INC. VOL. (cu. ft.)	CONIC TOTAL VOL. (cu. ft.)
166.00	12,910.49	N/A	N/A	0.00	N/A	0.00
167.00	14,977.94	1.00	13944.21	13944.21	13931.42	13931.42
168.00	17,189.00	1.00	16083.47	30027.69	16070.79	30002.22
169.00	19,543.67	1.00	18366.34	48394.03	18353.75	48355.96
170.00	22,041.95	1.00	20792.81	69186.84	20780.30	69136.26
171.00	24,683.84	1.00	23362.90	92549.74	23350.44	92486.70
172.00	27,469.34	1.00	26076.59	118626.33	26064.19	118550.89
173.00	30,398.45	1.00	28933.89	147560.22	28921.53	147472.42
174.00	33,470.93	1.00	31934.69	179494.91	31922.36	179394.78
175.00	36,639.54	1.00	35055.24	214550.15	35043.30	214438.08
176.00	39,864.71	1.00	38252.13	252802.28	38240.79	252678.87
177.00	43,146.44	1.00	41505.58	294307.85	41494.76	294173.63
178.00	46,484.74	1.00	44815.59	339123.44	44805.22	338978.85
179.00	49,879.59	1.00	48182.16	387305.60	48172.19	387151.05
180.00	53,331.00	1.00	51605.29	438910.90	51595.67	438746.72
181.00	60,403.51	1.00	56867.26	495778.15	56830.57	495577.29
182.00	64,024.61	1.00	62214.06	557992.21	62205.27	557782.57
183.00	67,702.26	1.00	65863.43	623855.65	65854.88	623637.44

PERMANENT POOL ELEVATION
TEMPORARY POOL ELEVATION

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

DATE

REVISION

NO.

SAMET HARNETT COUNTY 1

POND PROFILE

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C2.2



POND OUTLET STRUCTURE A
SCALE NTS



NOTE: MINIMUM H=2/3
PIPE DIAMETER

SECTION B–B

RIP RAP OUTLET PROTECTION

NOTES:

1. 5' W X 6' L, 9" THICK CLASS B RIP RAP.
2. RIPRAP SHOULD EXTEND UP BOTH SIDES OF THE APRON AND AROUND THE END OF THE PIPE OR CULVERT AT THE DISCHARGE OUTLET AT A MAXIMUM SLOPE OF 2:1 AND A HEIGHT NOT LESS THAN TWO THIRDS THE PIPE DIAMETER OR CULVERT HEIGHT.
3. THERE SHALL BE NO OVERFLOW FROM THE END OF THE APRON TO THE SURFACE OF THE RECEIVING CHANNEL. THE AREA TO BE PAVED OR RIPRAPPED SHALL BE UNDERCUT SO THAT THE INVERT OF THE APRON SHALL BE AT THE SAME GRADE (FLUSH) WITH THE SURFACE OF THE RECEIVING CHANNEL. THE APRON SHALL HAVE A CUTOFF OR TOE WALL AT THE DOWNSTREAM END.
4. THE WIDTH OF THE END OF THE APRON SHALL BE EQUAL TO THE BOTTOM WIDTH OF THE RECEIVING CHANNEL. MAXIMUM TAPER TO RECEIVING CHANNEL 5:1
5. ALL SUBGRADE FOR STRUCTURE TO BE COMPACTED TO 95% OR GREATER.
6. THE PLACING OF FILL, EITHER LOOSE OR COMPACTED IN THE RECEIVING CHANNEL SHALL NOT BE ALLOWED.
7. NO BENDS OR CURVES IN THE HORIZONTAL ALIGNMENT OF THE APRON WILL BE PERMITTED.
8. RIP RAP APRON SHALL BE EXTENDED AS POND EXCAVATION CONTINUES AND DEPTH INCREASES.

RIPRAP PIPE OUTLET PROTECTION
NOT TO SCALE



EMERGENCY SPILLWAY
NOT TO SCALE

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

DRAINAGE DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C2.3

0 25 50 100 Feet

1:50

EXISTING SPOT ELEVATIONS

EXISTING CONTOURS

FUTURE DEVELOPMENT

FUTURE DEVELOPMENT

DRIVEWAY 1

PROPOSED V-CURB

HEAVY DUTY ASPHALT

APPROXIMATE PHASE LIMITS (14 ACRES +/-)

EX. PROPERTY LINE

4' SIDEWALK

EXISTING SPOT ELEVATION

HEAVY DUTY CONCRETE

PUMP ROOM 105

ELEC 104

VEHICLE RAMP

VEHICLE RAMP

US 301 S.

EXISTING CONTOUR

EXISTING CONTOUR

175,500 SF BUILDING
FFE: 191'

WAREHOUSE 100

FIRE ACCESS LANE

24" CURB AND GUTTER

HEAVY DUTY ASPHALT

DRIVEWAY 2

4' SIDEWALK

6' SIDEWALK

5' SIDEWALK

OFFICE AREA 101

PROPERTY LINE

8' LANDSCAPE BUFFER

EX. PROPERTY LINE

APPROXIMATE STORMWATER POND

ARROWHEAD ROAD

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER COMMENT	7/25

SAMET HARNETT COUNTY 1

OVERALL GRADING PLAN

ORIGINAL MAP SIZE
24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

C3.0

0 25 50 100 Feet
1:50

UTILITY NOTES:
1. WATER MAINS SHALL BE LAID SO AS TO PROVIDE A MINIMUM HORIZONTAL SEPARATION OF 10 FEET FROM SEWERS. IF CONDITIONS EXIST SUCH THAT THIS SEPARATION CANNOT BE ACHIEVED, THE WATER MAIN CAN BE INSTALLED AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, EITHER IN A SEPARATE TRENCH, OR IN THE SAME TRENCH ON A BENCH OF UNDISTURBED EARTH.
2. WATER MAINS INSTALLED SIDE-BY-SIDE SHALL BE INSTALLED WITH A MINIMUM 5' HORIZONTAL SEPARATION BETWEEN PIPES.
3. WATER MAINS SHALL MAINTAIN A MINIMUM OF 30" OF COVER OVER PIPE.
4. WATER MAINS SHALL MAINTAIN A MINIMUM CLEARANCE OF 10' OF HORIZONTAL SEPARATION BETWEEN SANITARY SEWER PIPES AND A MINIMUM CLEARANCE OF 12" OF VERTICAL CLEARANCE BETWEEN STORM DRAIN LINES AT CROSSINGS.
5. WHEN A WATER MAIN CROSSES OVER A SEWER, THE WATER MAIN SHALL BE LAID AT LEAST 18 INCHES ABOVE THE SEWER. IF THIS SEPARATION CANNOT BE ACHIEVED, BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF DUCTILE IRON PIPE WITH JOINTS THAT MEET WATER MAIN STANDARDS. THE DUCTILE IRON PIPE SHALL EXTEND 10 FEET ON EACH SIDE OF THE CROSSING WITH A SECTION OF WATER MAIN PIPE CENTERED ON THE CROSSING.
6. WHEN A WATER MAIN CROSSES UNDER A SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND THE SEWER SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.
7. 18" OF VERTICAL CLEARANCE BETWEEN SANITARY SEWER AND STORM DRAIN LINES; WHEN VERTICAL CLEARANCE IS LESS THAN 18" BETWEEN SANITARY SEWER AND STORM DRAIN, SANITARY SEWER SHALL BE DUCTILE IRON PIPE FOR A MINIMUM OF 10' EITHER SIDE OF CROSSING AND STORM DRAIN SHALL BE RC PIPE.
8. WHERE VERTICAL CLEARANCE IS LESS THAT 12" BETWEEN WATER MAIN AND STORM DRAIN, WATER MAIN SHALL BE DUCTILE IRON PIPE FOR A MINIMUM OF 10' EITHER SIDE OF CROSSING AND STORM DRAIN SHALL BE RC PIPE.

FUTURE POND
FUTURE DEVELOPMENT
FUTURE UTILITY CONNECTION
PROPOSED HYDRANT ASSEMBLY
6" MJ GATE VALVE
8" MJ GATE VALVE
175,000 GALLON WATER SUPPLY
RPZ BACKFLOW PREVENTER-ABOVE GROUND-SEE DETAIL 600.21, SHEET C5.6
APPROXIMATE PHASE LIMITS (15 ACRES +/-)
EX. PROPERTY LINE
4' SIDEWALK
12" MJ GATE VALVE
12"-8" MJ REDUCING "T"
ELECTRIC SERVICE BY OWNER
ELECTRIC SERVICE AND CONDUIT BY CONTRACTOR
RPZ BACKFLOW PREVENTER-ABOVE GROUND-SEE DETAIL 600.21, SHEET C5.6
FUTURE UNDREGROUND GAS, FIBER OPTIC AND ELECTRIC SERVICES
PROPOSED 12" C900 DR18 WATER MAIN
TELECOM HANDHOLE BY BY OWNER UTILITY CONTRACTOR
TELECOM BY OWNER UTILITY CONTRACTOR
36'
12"45° MJ BEND
PROPERTY LINE
CONTRACTOR TO COORDINATE FUTURE UTILITY LOCATIONS/CONNECTIONS
MAKE CONNECTION TO EXISTING 12" WATER MAIN
DRIVEWAY 2
8" MJ "T"
8"-6" MJ REDUCING "T"
8" C900 DR18 FIRE MAIN
HEAVY DUTY ASPHALT
8"45° MJ BEND
8" FIRE SUPPLY TO FIRE RISER INSIDE BUILDING. SEE PLUMBING DETAILS FOR CONTINUATION
FDC TO BE LOCATED ON EXTERIOR WALL OF FIRE PUMP ROOM. SEE PLUMBING DETAILS FOR CONTINUATION
HEAVY DUTY CONCRETE
PUMP ROOM 105
ELECT 103
8" FIRE SERVICE
3" DOMESTIC WATER LINE
3" WATER METER
PROPOSED FDC
PROPOSED DUMPSTER LOCATION
PRELIMINARY TRANSFORMER LOCATION
SEE INSET
TELECOM BY ELECTRICAL CONTRACTOR-DIRECT BURY OR CONDUIT
TELECOM HANDHOLE BY ELECTRICAL CONTRACTOR
175,500 SF BUILDING
WAREHOUSE 100
OFFICE AREA 101
26'
99'
CLEANOUT TO BE LOCATED 5' OFF BUILDING. SEE PLUMBING DETAILS FOR CONTINUATION
6" C900 DR18 PVC LATERAL
5' SIDEWALK
6' SIDEWALK
8" C900 DR18 PVC
6" MJ GATE VALVE
6"45° MJ BEND
SANITARY SEWER MANHOLE SSMH-1
SANITARY SEWER MANHOLE SSMH-2
6" C900 DR18 FIRE MAIN
ASPHALT ROAD
DRIVEWAY 1
PROPOSED HYDRANT ASSEMBLY
8"-6" MJ REDUCING "T"
6" MJ GATE VALVE
8" C900 DR18 FIRE MAIN
8" MJ GATE VALVE
6"45° MJ BEND
US 301 S.
6" C900 DR18 FIRE MAIN
HOODED AREA
SSMH RIM 182.79 IN= 175.69 OUT= 175.74
APPROX. LOCATION OF BURIED STORM PIPE (UNKNOWN)
BURIED STORM PIPE
TOP OF BURIED STORM PIPE 177.17 (UNKNOWN)
FIRE ACCESS LANE
SANITARY SEWER MANHOLE SSMH-3
6" C900 DR18 PVC
SSMH RIM 180.59 IN= 174.14 OUT= 174.07
EX. PROPERTY LINE
APPROXIMATE STORMWATER POND
PROPOSED SANITARY SEWER CONNECTION TO EXISTING MANHOLE
EXISTING HYDRANT
EXISTING 12" WATER MAIN
ARROWHEAD ROAD
CONC. CURB (TYP.)
SSMH RIM 179.51 IN= 173.36 OUT= 173.30
INV. 178.81
INV. 178.91

UTILITY IN-SET
SCALE 1"=20'



GRAVITY SEWER NOTES:
1. MANHOLES LOCATED WITHIN THE 100-YEAR FLOOD PLAIN WHERE THE DESIGN RIM ELEVATION IS NOT 24 INCHES (2 FOOT) ABOVE THE 100-YEAR FLOOD ELEVATION SHALL CONFORM TO THE FOLLOWING:
1.1. MANHOLES SHALL BE WATERTIGHT AND VENTED 24 INCHES (2 FOOT) ABOVE THE 100-YEAR FLOOD ELEVATION.
1.2. MANHOLES SHALL BE VENTED EVERY 1,000 FEET OR EVERY OTHER MANHOLE, WHICHEVER IS GREATER.
1.3. PROVIDE WATERTIGHT, BOLTED RIM AND COVER.

GENERAL NOTES:
1. SEE PLUMBING PLANS FOR WATER AND SEWER CONNECTIONS AT BUILDINGS.
2. SEE SHEET C4.1 FOR SANITARY SEWER PROFILES.
3. ALL UTILITY WORK SHALL BE PERFORMED IN ACCORDANCE WITH PROJECT SPECIFICATIONS AND DETAILS.
4. ALL WATERLINES, TAPS, BENDS VALVES, METERS, HYDRANTS ETC. INSTALLED ON SITE SHALL MEET THE APPROPRIATE AWWA STANDARDS.
5. FIRE HYDRANTS SHALL BE INSTALLED PER CITY OF DUNN AND NC FIRE CODE STANDARD SPECIFICATIONS AND DETAILS.
6. ALL WATER AND SEWER SERVICE LINES SHALL BE C900 PVC UNLESS OTHERWISE NOTED.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER COMMENTS	7/16/15

SAMET HARNETT COUNTY 1

PRELIMINARY WATER AND SEWER LAYOUT

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C4.0



Sanitary Sewer PROFILE



TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1		

SAMET HARNETT COUNTY 1

SANITARY SEWER PROFILE

ORIGINAL MAP SIZE
24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

C4.1



NOTES:

1. USE NORMAL OR REVERSE CROWN TO MATCH DIRECTION OF PAVEMENT SLOPE.
2. EXPANSION JOINTS: 1/2" WIDE, FULL DEPTH, AT 50' INTERVALS, TRANSVERSELY, AT ABUTTING STRUCTURES AND AT DRIVEWAYS, TANGENT POINTS OF RADIUS RETURNS AND STREET INTERSECTIONS.
3. CONTRACTION JOINTS: 1" DEEP SAWCUTS ON 10 FT. CENTERS TRANSVERSLEY.

1 C-5.0 **24" CURB & GUTTER**
SCALE: N.T.S.



2 C-5.0 **HEADER CURB**
SCALE: N.T.S.



TYPE 2

1. *8.33% (12:1) MAX RAMP SLOPE*
2. *CROSS SLOPE: 2.00%*
3. *CURB RAMPS REQUIRE A (4'-0") MINIMUM LANDING WITH A MAXIMUM CROSS SLOPE AND LONGITUDINAL SLOPE OF 2.00% WHERE PEDESTRIANS PERFORM TURNING MANEUVERS. SLOPE TO DRAIN TO CURB.*

3 C-5.0 **NCDOT ADA RAMP TYPE 2**
SCALE: N.T.S.



SECTION IN EARTH AGGREGATE



SECTION IN CONCRETE PAVEMENTSECTION IN BITUMINOUS PAVEMENT

4 C-5.0 **BOLLARD DETAIL**
SCALE: N.T.S.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.0



HANDICAPPED PARKING SIGN
NOT TO SCALE



4 C-5.4 HANDICAP MARKING
SCALE: N.T.S.

NOTES:

1. PROVIDE ACCESSIBLE PARKING SIGN AT ALL HANDICAP SPACES.
2. PROVIDE "VAN ACCESSIBLE" SIGN AS REQUIRED ON PLANS.

1 C-5.1 HANDICAP PARKING SIGN
SCALE: N.T.S.



Label	Dimension	Angle 45	60	75	90
A	Stall Depth to Wall	17	18.5	19	18
B	Stall Depth Parallel to Vehicle	18	18	18	18
C	Aisle Width	12	16	22	25
D	Stall Depth to Interlock	15	17	18	18
E	Stall Depth Reduction due to Interlock	2	1.5	1	0
F	Stall Width (Parallel to Aisle)	12.7	10.4	9.3	9
G	Stall Width Perpendicular to Vehicle	9	9	9	9
I	Module Width Wall to Wall	46	54	60	61
J	Module Width Interlock to Interlock	42	51	58	61

2 C-5.1 PARKING DIMENSION DETAILS
SCALE: N.T.S.



NOTES
ALL CONCRETE SHALL BE N.D.O.T. CLASS "A"

A TWO (2) INCH LIFT (COMPACTED) OF DENSE GRADED AGGREGATE SHALL BE INSTALLED PRIOR TO PLACEMENT OF CONCRETE.

CONTRACTION JOINTS SHALL BE PLACED AT FIVE (5) FOOT INTERVALS.

EXPANSION JOINTS SHALL BE PLACED AT FIFTY (50) FOOT INTERVALS AND ALONG ALL EDGES BUTTED NEXT TO FIXED OBJECTS.

MAXIMUM SLOPE ACROSS SIDEWALK SHALL BE 1/4" PER FOOT TOWARD ROAD UNLESS OTHERWISE NOTED.

TURNDOWN SIDEWALK DETAIL
(TYPICAL SECTION)
(N.T.S)

3 C-5.1 SIDEWALK/CURB TURNDOWN DETAIL
SCALE: N.T.S.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO. | REVISION | DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.1



NOTE:

1. ALL SIDEWALKS SHALL HAVE A 1–2% CROSS SLOPE AND MAXIMUM 5% RUNNING SLOPE IN DIRECTION OF TRAVEL ALONG ADA ACCESSIBLE PATH. COORDINATE WITH ENGINEER PRIOR TO SIDEWALK CONSTRUCTION IF THERE IS ANY DISCREPANCY BETWEEN THIS REQUIREMENT AND THE GRADING PLAN/SPOT ELEVATIONS.
2. INSTALL EXPANSION JOINTS AT CONNECTION TO BUILDING FOUNDATIONS, SIDEWALKS, OR CURB AND GUTTERS. INSTALL CONTRACTION AND EXPANSION JOINTS PER SPECIFICATIONS.
3. CONTROL JOINTS SHALL BE EVERY 5 FEET
4. CONCRETE SHALL HAVE LIGHT BROOM FINISH
5. THIS SECTION SHALL BE USED ON THE CONCRETE TO BE USED AS A DUMPSTER PAD

1 / C-5.2 STANDARD DUTY CONCRETE
SCALE: N.T.S.



NOTE:
1. ALL SECTIONS PER GEOTECHNICAL REPORT PROVIDED BY ECS SOUTHEAST, LLP IN AUGUST 2021
2. PRIME COAT, NCDOT ITEM 600, IS TO BE APPLIED TO THE SURFACE OF THE 8" AGGREGATE BASE COURSE ONLY IF THE BASE COURSE IS TO BE LEFT EXPOSED FOR GREATER THAN 14 DAYS.

3 / C-5.2 HEAVY DUTY ASPHALT PAVING
SCALE: N.T.S.



MODEL	LENGTH	WEIGHT	WT. PER PALLET	No. PER PALLET
S-48	4'–0"	124 LBS.	3810 LBS.	36*
S-72	6'–0"	186 LBS.	3900 LBS.	24*

*SAVE ON PALLET QUANTITIES

5 / C-5.2 CURB STOP
SCALE: N.T.S.



2 / C-5.2 HEAVY DUTY CONCRETE PAVING
SCALE: N.T.S.



NOTE:
1. ALL SECTIONS PER GEOTECHNICAL REPORT PROVIDED BY ECS SOUTHEAST, LLP IN AUGUST 2021
2. PRIME COAT, NCDOT ITEM 600, IS TO BE APPLIED TO THE SURFACE OF THE 8" AGGREGATE BASE COURSE ONLY IF THE BASE COURSE IS TO BE LEFT EXPOSED FOR GREATER THAN 14 DAYS.

4 / C-5.2 LIGHT DUTY ASPHALT PAVING
SCALE: N.T.S.



6 / C-5.2 CURB INLETS CI-6B, 7B AND 8B
SCALE: N.T.S.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.2

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR

METHOD OF PIPE INSTALLATION

RIGID PIPE



GENERAL NOTES:

I.D. = THE MAXIMUM HORIZONTAL INSIDE DIAMETER DIMENSION.

O.D. = THE MAXIMUM HORIZONTAL OUTSIDE DIAMETER DIMENSION.

H = THE FILL HEIGHT MEASURED VERTICALLY AT ANY POINT ALONG THE PIPE FROM THE TOP OF THE PIPE TO THE TOP OF THE EMBANKMENT AT THAT POINT.

TAKE CARE TO FULLY COMPACT HAUNCH ZONE OF PIPE BACKFILL.

LOOSELY PLACED SELECT MATERIAL CLASS III OR CLASS II, TYPE 1 FOR PIPE BEDDING. LEAVE SECTION DIRECTLY BENEATH PIPE UNCOMPACTED AS PIPE SEATING AND BACKFILL WILL ACCOMPLISH COMPACTION.

DO NOT OPERATE HEAVY EQUIPMENT OVER ANY PIPE CULVERT UNTIL THE PIPE CULVERT HAS BEEN PROPERLY BACKFILLED AND COVERED WITH AT LEAST 3 FEET OF APPROVED MATERIAL.

SPRINGLINE OF PIPE

SELECT BACKFILL MATERIAL CLASS III OR CLASS II, BELOW SPRINGLINE.

APPROVED SUITABLE LOCAL MATERIAL ABOVE SPRINGLINE.

UNDISTURBED EARTH MATERIAL

SELECT MATERIAL CLASS V OR VI FOR FOUNDATION CONDITIONING. ENCAPSULATE WITH ENGINEERING FABRIC AS DIRECTED BY THE ENGINEER.

SHEET 2 OF 3

300.01

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR

METHOD OF PIPE INSTALLATION

RIGID PIPE

SHEET 3 OF 3

300.01



TRANSVERSE CONTRACTION JOINT



PLANNED TRANSVERSE CONSTRUCTION JOINT

GENERAL NOTES:
- FORM TRANSVERSE CONTRACTION JOINTS BY SAWING WITH APPROVED EQUIPMENT.
- SPACE TRANSVERSE CONTRACTION JOINTS AT INTERVALS OF 15'.
- USE A DOWEL ASSEMBLY OR OTHER APPROVED DOWEL INSERTION TECHNIQUE IN ALL TRANSVERSE CONTRACTION JOINTS. DOWEL ASSEMBLIES ARE COVERED IN DETAIL 700.03.
- PROVIDE SMOOTH DOWEL BARS. PROVIDE DEFORMED TIE BARS.
- WHEN UTILIZING AN EARLY ENTRY SAW, CUT THE JOINT TO A MINIMUM DEPTH OF 3".



DETAIL 'A'



DETAIL 'D'

TABLE I - DOWEL BARS		
SLAB THICKNESS	DOWEL BAR "D"	DOWEL LENGTH "L"
8" OR LESS	1"	14"
8½" TO 9½"	1⅛"	16"
10" TO 10½"	1¼"	18"
11" AND ABOVE	1½"	18"

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-18

ROADWAY STANDARD DRAWING FOR

CONCRETE PAVEMENT JOINTS

CONSTRUCTION AND CONTRACTION JOINTS

SHEET 1 OF 2

700.01



END TREATMENT DIMENSIONS							
D	L	W	T_s	T_b	T_e	A	B
15"	7'-6"	19"	4"	4"	6"	17¾"	20⅞"
18"	9'-0"	23"	4"	4"	6"	21¼"	25"
24"	12'-6"	30"	4"	4"	6"	27⅞"	32"

NOTES:
1. CONSTRUCT PIPE END SECTION USING #4 REBAR SPACED 9" EACH WAY AND MEET ALL REQUIREMENTS OF STD. SPEC. 310.
2. CHAMFER ALL EXPOSED CORNERS ¾".

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR

PARALLEL PIPE END SECTION

PRECAST CONCRETE SECTION FOR 15" TO 24" PIPE

SHEET 1 OF 1

310.02

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR

PARALLEL PIPE END SECTION

PRECAST CONCRETE SECTION FOR 15" TO 24" PIPE

SHEET 1 OF 1

310.02

1 C-5.3 NCDOT CULVERT DETAIL
SCALE: N.T.S.



LONGITUDINAL CONSTRUCTION JOINT



LONGITUDINAL JOINT



EMERGENCY TRANSVERSE CONSTRUCTION JOINT

GENERAL NOTES:
- CONSTRUCT TRANSVERSE CONSTRUCTION JOINTS AT THE END OF EACH DAY'S OPERATION (PLANNED JOINT) OR WHEN THE PLACING OF CONCRETE IS SUSPENDED FOR MORE THAN 30 MINUTES (EMERGENCY JOINT).
- USE AN APPROVED HEADER AT EMERGENCY JOINTS STD. DWG. 700.04 AND DESIGNED TO PERMIT THE PLACEMENT OF AND CORRECTLY HOLD IN PLACE TIE BARS.
- USE TIE BARS OF THE SAME DIAMETER AS DOWEL BARS FOR EMERGENCY TRANSVERSE CONSTRUCTION JOINTS.
- LOCATE PLANNED TRANSVERSE CONSTRUCTION JOINTS AT THE SPACING REQUIRED FOR CONTRACTION JOINTS. USE AN APPROVED METHOD OF INSTALLING DOWELS IN ALL PLANNED TRANSVERSE CONSTRUCTION JOINTS.
- DO NOT LOCATE EMERGENCY TRANSVERSE CONSTRUCTION JOINTS LESS THAN 6' FROM ANY CONTRACTION JOINT OR PLANNED CONSTRUCTION JOINT.
- DO NOT PLACE TIE BARS IN LONGITUDINAL JOINTS WITHIN 1'-4" OF A TRANSVERSE JOINT.
- WHEN UTILIZING AN EARLY ENTRY SAW, CUT THE JOINT TO A MINIMUM DEPTH OF 3".



DETAIL 'B'



DETAIL 'C'

TABLE II - LONGITUDINAL TIE BARS		
SLAB THICKNESS	TIE BAR DIA. "D"	TIE BAR LENGTH "L"
8½" OR LESS	½"	30"
9" OR ABOVE	⅝"	30"

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-18

ROADWAY STANDARD DRAWING FOR

CONCRETE PAVEMENT JOINTS

CONSTRUCTION AND CONTRACTION JOINTS

SHEET 2 OF 2

700.01

2 C-5.3 NCDOT CONCRETE JOINT DETAILS
SCALE: N.T.S.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

C5.3



GENERAL NOTES:
-JOIN PAVEMENTS AS SHOWN ON THIS DETAIL OR AS DIRECTED BY THE ENGINEER.
-PLACE TIE BARS (DEFORMED STEEL BARS) ALONG THE LONGITUDINAL JOINTS AT 30" ON CENTER. PLACE DOWEL BARS (SMOOTH STEEL BARS) ALONG THE TRANSVERSE JOINTS AT 12" ON CENTER. THE PLACEMENT AND/OR SPACING OF TIE OR DOWEL BARS MAY BE MODIFIED BY THE PLANS OR THE ENGINEER. MEASURE THE HOLES, TO ACCEPT THESE BARS, THE O.D. OF THE BAR PLUS 1/8" IN DIAMETER AND 1/2 THE LENGTH OF THE BAR PLUS 1" UNLESS OTHERWISE SPECIFIED BY THE MANUFACTURER OF THE ADHESIVE. USE RETAINING WASHERS (NYLON, PLACTIC OR COMPOSTIE) ON ALL BARS TO HOLD THE ADHESIVE MATERIAL IN PLACE. THE RETAINING WASHERS SHALL BE: I.D.=BAR O.D., O.D.=HOLE I.D. + 1/4" MIN., THICKNESS= 1/8" MIN. SEE STANDARD DRAWING 700.01 FOR BAR SIZES AND OTHER JOINT RELATED INFORMATION. PROVIDE ADHEVSIVE BONDING MATERIAL SPECIFICED BY SECTION 1081 OF THE STANDARD SPECIFICATIONS FOR TYPE 3 OR 3A ADHESIVES.
-SEE TYPICAL SECTIONS FOR PAVEMENT COMPOSITION, SUMMARY OF QUANTITIES AND FOR OTHER SPECIFIC INFORMATION.

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

1-18

ROADWAY STANDARD DRAWING FOR
TYING PROPOSED PAVEMENT TO EXISTING PAVEMENT

SHEET 1 OF 1
700.05

1 C-5.4 TYING PROPOSED PAVEMENT TO EXISTING PAVEMENT
SCALE: N.T.S.



NOTE: UPON COMPLETION OF FINAL SLAB, REMOVE DOWEL BARS AT SUCH TIME AS CONCRETE HAS CURED ENOUGH TO LEAVE A CAVITY FOR RESETTING AT A LATER DATE.

USE WOOD OR METAL FORM OF SUFFICIENT RIGIDITY TO ADEQUATELY SUPPORT THE EDGES OF THE SLAB.

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

1-18

ROADWAY STANDARD DRAWING FOR
CONCRETE PAVEMENT HEADER BOARD

SHEET 1 OF 1
700.04

2 C-5.4 CONCRETE FRAME/HEADER BOARD
SCALE: N.T.S.



3 C-5.4 PIPE INSTALLATION-FLEXIBLE PIPE
SCALE: N.T.S.



4 C-5.4 PIPE INSTALLATION-RIGID PIPE
SCALE: N.T.S.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.4

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR
METHOD OF PIPE INSTALLATION
FILL HEIGHT TABLES

SHEET 3 OF 3
300.01

FLEXIBLE PIPE

Round Corrugated Steel Pipe
2 2/3 x ½ corrugation **

Diameter (inches)	Minimum cover (inches)	(Ga)	Maximum Height of Cover (feet) 16	14	12	10	8
12	12		204	256			
15	12		162	204			
18	12		135	169	239		
21	12		115	145	204		
24	12		100	126	178		
30	12		79	100	142		
36	12		65	83	117	152	
42	12		55	70	100	130	160
48	12		48	61	87	113	139
54	12			54	77	100	123
60	12				69	90	111
66	12					81	100
72	12					74	91
78	12						81
84	12						69

Round Corrugated Aluminum Pipe
2 2/3 x ½ corrugation **

Diameter (inches)	Minimum cover (inches)	(Ga)	Maximum Height of Cover (feet) 16	14	12	10	8
12	12		123	155	216	281	344
15	12		98	123	174	224	275
18	12		81	102	144	187	228
21	12		69	87	123	160	195
24	12		60	76	108	139	171
27	12			67	95	123	151
30	12			60	85	111	136
36	12			50	71	92	113
42	12				60	78	96
48	12				52	68	84
54	12				46	50	74
60	12					50	62
66	12						51
72	12						41

** FOR DIFFERENT CORRUGATIONS AND ARCH PIPES REFER TO ROADWAY DESIGN MANUAL OR MANUFACTURERS SPECIFICATION.

HDPE - * (Minimum fill) 2' for pipe diameters ≥ 12" and ≤ 60"
* (Maximum fill) 20' for pipe diameters ≤ 24"
17' for pipe diameters ≥ 30" and ≤ 60"

PVC - * (Minimum fill) 2' for pipe diameters ≥ 12" and ≤ 36"
* (Maximum fill) 30' for pipe diameters ≥ 12" and ≤ 36"

* FILL HEIGHT IS MEASURED FROM THE TOP OF THE PIPE TO THE BOTTOM OF THE PAVEMENT STRUCTURE

REFER TO THE FOLLOWING FOR PIPE SPECIFICATIONS

CSP - AASHTO M36
CAAP - AASHTO M196
HDPE - AASHTO M294
PVC - ASTM F949 or AASHTO M304

NOTES: FILL HEIGHTS SHOWN WERE CALCULATED USING AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

1' MINIMUM COVER FOR ALL SIDE DRAIN PIPE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS

RIGID PIPE

RCP - * (Minimum fill) 1' for Class IV & CLASS V
2' for Class III & Class II

* (Maximum fill) 10' - Class II pipe
20' - Class III pipe
30' - Class IV pipe
40' - Class V pipe

(For fills > 40' & < 80' use LRFD Direct Design Method)

* FILL HEIGHT IS MEASURED FROM THE TOP OF THE PIPE TO THE BOTTOM OF THE PAVEMENT STRUCTURE

REFER TO THE FOLLOWING FOR PIPE SPECIFICATIONS

RCP - AASHTO M170

NOTES: FILL HEIGHTS SHOWN WERE CALCULATED USING AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

1' MINIMUM COVER FOR ALL SIDE DRAIN PIPE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

1-12

ENGLISH STANDARD DRAWING FOR
METHOD OF PIPE INSTALLATION
FILL HEIGHT TABLES

SHEET 3 OF 3
300.01

1 C-5.5 PIPE FILL HEIGHT
SCALE: N.T.S.



2 C-5.5 CONCRETE FLUME FOR ROOF DRAIN
SCALE: 1"=10'

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.5



WILKINS REGULATOR CO. MODEL 975 R
FOR THE FOLLOWING MAIN SIZES:
2 1/2", 3", 4", 6", 8", & 10"
WILKINS REGULATOR CO. MODEL 975 B
FOR THE FOLLOWING MAIN SIZES:
3/4", 1", 1 1/4", 1 1/2", & 2"
WILKINS REGULATOR CO. MODEL 575 R
FOR THE FOLLOWING MAIN SIZES:
2 1/2", 3", 4", 6", M8", & M10"
WILKINS REGULATOR CO. MODEL 975 AB
FOR THE FOLLOWING MAIN SIZES:
3/4", 1", 1 1/4", 1 1/2", & 2"

NOTES:
1. SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
2. ASSEMBLY SHALL BE HOUSED IN AN ALUMINUM INSULATED ENCLOSURE.
3. ALL PIPING SHALL BE STEEL OR DUCTILE IRON

north carolina DUNN city of dunn

REDUCED PRESSURE PRINCIPLE ASSEMBLY
ABOVE GROUND INSTALLATION ONLY

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.13
Sheet 1 of 1



NOTES:
1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS.
2. RESILIENT WEDGE GATE VALVE SHALL BE AS MANUFACTURED BY MUELLER CORP., AMERICAN DARLING OR CLOW CORP.
3. ALL VALVES SHALL HAVE 2" SQUARE OPERATING NUT AND SHALL OPEN COUNTERCLOCKWISE.
4. VALVE BODY, BONNET AND GATE SHALL BE IN ACCORDANCE WITH AWWA C-509/C-515 AND NSF61.
5. VALVE BODY AND BONNET SHALL BE COATED ON ALL INTERIOR AND EXTERIOR SURFACES WITH A FUSION BONDED EPOXY IN ACCORDANCE WITH AWWA C-550-90.
6. ALL VALVES 24" AND SMALLER SHALL HAVE A SAFE WORKING PRESSURE OF 250 PSI.
7. SEE VALVE BOX DETAIL FOR ADDITIONAL INFORMATION.
8. SEE VALVE BOX PROTECTOR RING DETAIL FOR ADDITIONAL INFORMATION.
9. VALVE BOX SECTIONS ARE REQUIRED. THE USE OF PIPE IN LIEU OF VALVE BOX SECTIONS SHALL NOT BE PERMITTED.

north carolina DUNN city of dunn

GATE VALVE

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.09
Sheet 1 of 1



north carolina DUNN city of dunn

PVC PIPE BACKFILL

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.13
Sheet 1 of 1

REQUIREMENTS FOR ABOVE GROUND INSTALLATIONS OF REDUCED PRESSURE PRINCIPLE AND DOUBLE CHECK VALVE ASSEMBLIES

1. THE BACKFLOW PREVENTOR MUST BE INSTALLED A MINIMUM DISTANCE OF 5 (5) FEET FROM THE METER SERVICE. INSTALLATION OF BACKFLOW PREVENTORS WITHIN THE RIGHT-OF-WAY WILL NOT BE APPROVED.
2. REDUCED PRESSURE PRINCIPLE ASSEMBLIES MUST BE INSTALLED IN A HORIZONTAL POSITION AND IN A LOCATION IN WHICH NO PORTION OF THE ASSEMBLY CAN BE SUBMERGED UNDER ANY CIRCUMSTANCES.
3. DOUBLE CHECK VALVE ASSEMBLIES MAY BE INSTALLED IN A VERTICAL POSITION PROVIDED IT CANNOT BE INSTALLED HORIZONTALLY AND THE FLOW OF WATER IS IN AN UPWARDS DIRECTION.
4. REDUCE PRESSURE PRINCIPLE BACKFLOW PREVENTORS MUST BE INSTALLED ABOVE GROUND.

   BACKFLOW PREVENTION ASSEMBLIES TWO AND ON-HALF (2 1/2) INCHES OR LARGER SHALL BE INSTALLED WITH DUCTILE IRON OR STEEL PIPE.
5. BACKFLOW PREVENTORS INSTALLED INSIDE MUST BE A MINIMUM DISTANCE OF TWELVE (12) INCHES ABOVE THE FLOOR, AND NO HIGHER THAN 4 (4) FEET ABOVE THE FLOOR, WITH ADEQUATE CLEARANCE AROUND THE BACKFLOW PREVENTOR FOR TESTING, AND/OR REPAIR. WHEREVER A REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTOR IS INSTALLED INSIDE A BUILDING, AN AIR GAP DRAIN LARGE ENOUGH TO CARRY OFF THE DISCHARGE OF WATER FROM THE RELIEF VALVE SHALL BE INSTALLED.
6. BACKFLOW PREVENTION ASSEMBLIES INSTALLED OUTSIDE, ABOVE GROUND MUST BE PROTECTED FROM FREEZING. THE BACKFLOW PREVENTION ASSEMBLY MUST BE INSTALLED A MINIMUM DISTANCE OF TWELVE (12) INCHES ABOVE GROUND, AND NO HIGHER THAN FOUR (4) FEET ABOVE GROUND. LANDSCAPING IS ALLOWED AROUND THE BACKFLOW PREVENTOR, BUT MUST NOT INTERFERE WITH THE REQUIRED ANNUAL TESTING AND/OR REPAIR.
7. SHOULD YOU HAVE ANY QUESTIONS CONCERNING THE REQUIREMENTS LISTED ABOVE CONTACT PUBLIC WORKS CROSS CONNECTION COORDINATOR, AT (910)890-5709, TO ASSIST YOU TO INSURE PROPER INSTALLATION.

north carolina DUNN city of dunn

BACKFLOW PREVENTION NOTES

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.12
Sheet 1 of 1



NOTES:
1. CONCRETE PROTECTOR RING SHALL BE 2500 P.S.I. PRECAST REINFORCED CONCRETE
2. VALVE BOX SHALL BE AT GRADE W/PROTECTOR RING EXTENDING 1/2" ABOVE GRADE
3. SEE GATE VALVE AND BOX DETAIL
4. VALVE BOX PROTECTOR RINGS SHALL BE INSTALLED AROUND VALVE BOX IN UNPAVED NON-TRAFFIC AREAS, AND SHALL NOT CREATE A HINDERANCE TO MOWING OPERATIONS.



SECTION A-A
N.T.S.



CUT AWAY VIEW

north carolina DUNN city of dunn

VALVE BOX PROTECTOR RING

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.11
Sheet 1 of 1





NOTES:
1. VALVE BOX SHALL BE 3 PART SLIP-TYPE MANUFACTURED BY ALABAMA PIPE CO., CHAPMAN VALVE CO., COLOMBIAN IRON WORKS, R.D. WOOD CO. OR APPROVED EQUAL.
2. VALVE BOX SHALL BE 3-PIECE CLOSE GRAINED CAST IRON SLIP-TYPE VALVE BOX WITH A MINIMUM THICKNESS OF 3/16".
3. VALVE BOX SHALL HAVE RAISED LETTERS "WATER" CAST INTO COVER.
4. VALVE BOX SHALL HAVE 3/8" HOLE DRILLED IN TOP SECTION THRU WHICH A 1/4"x1-1/2" GALVANIZED BOLT SHALL BE USED TO SECURE A MINIMUM 12 GAUGE, SINGLE STRAND, COATED COPPER TRACER WIRE FOR NON-FERROUS PIPE. A 1/2" WASHER SHALL BE USED BETWEEN NUT AND INSIDE OF BOX.TIGHTEN HAND TIGHT.
5. SCREW TYPE VALVE BOXES ARE NOT ACCEPTABLE.
6. DIMENSIONS SHOWN ARE FOR INFORMATION ONLY AND VARY BASED UPON THE MANUFACTURER.
7. VALVE BOX SECTIONS ARE REQUIRED. THE USE OF PIPE IN LIEU OF VALVE BOX SECTIONS SHALL NOT BE PERMITTED.
8. TRACING WIRE SHALL BE INSTALLED OUTSIDE OF BOX.

north carolina DUNN city of dunn

VALVE BOX

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.10
Sheet 1 of 1

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.6



GENERAL NOTES:

1. ALL CONCRETE BLOCKING SHALL BE 3000 P.S.I. MINIMUM.
2. ALL HYDRANT VALVES SHALL BE RODDED TO MAIN LINE.
3. HYDRANT TO BE LOCATED 10' FROM P.T. OR P.C. AT INTERSECTIONS.
4. THE HYDRANT PUMPER NOZZLE SHALL BE OF ONE-PIECE DESIGN.
5. THE NOZZLE SHALL BE AN INTEGRAL PART OF THE FIRE HYDRANT AND MUST BE FURNISHED BY THE MANUFACTURER OR AUTHORIZED DISTRIBUTOR. ADAPTERS WILL NOT BE ACCEPTED.

north carolina DUNN city of dunn

STANDARD FIRE HYDRANT

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.0
Sheet 1 of 1



north carolina DUNN city of dunn

BLOW-OFF ASSEMBLY

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.01
Sheet 1 of 1



SIGMA CORPORATION
(800) 824-4513
PO Box 519
Alexander City, AL 35011
(800) 736-2956
PO Box 1043
Rockingham, NC 28380

DRAWN BY: R.L. DATE: 6/29/2006

METER BOX (MBX-5A)

LOAD RATING: NON-TRAFFIC

MATERIAL SPECIFICATION: CAST IRON ASTM A 48 CLASS 30B

OPEN AREA - SQ. IN. N/A

CATALOG NUMBER
MB-2202

north carolina DUNN city of dunn

METER BOX for 1 1/2" & 2" WATER SERVICE

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.06
Sheet 2 of 2



NOTES:

1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS.
2. RAISED MALE FACE SHALL BE REQUIRED TO PROVIDE FOR PROPER ALIGNMENT OF THE TAPPING SLEEVE.
3. ALL VALVES SHALL HAVE 2" SQUARE OPERATING NUT AND SHALL OPEN COUNTERCLOCKWISE.
4. RESILIENT WEDGE GATE VALVE SHALL BE AS MANUFACTURED BY MUELLER CORP., AMERICAN DARLING OR CLOW CORP.
5. VALVE BODY, BONNET AND GATE SHALL BE IN ACCORDANCE WITH AWWA C-509/C-515 AND NSF61.
6. VALVE BODY AND BONNET SHALL BE COATED ON ALL INTERIOR AND EXTERIOR SURFACES WITH A FUSION BONDED EPOXY IN ACCORDANCE WITH AWWA C-550-90.
7. ALL VALVES 24" AND SMALLER SHALL HAVE A SAFE WORKING PRESSURE OF 250 PSI.
8. SEE TAPPING SLEEVE FOR ADDITIONAL INFORMATION.
9. DIMENSIONS SHOWN ARE FOR REFERENCE AND MAY VARY BASED UPON MANUFACTURER. VALVES SHALL BE SIMILAR IN NATURE TO THAT SHOWN AND SHALL NOT DEVIATE IN ESSENTIAL DETAILS.
10. ALL TAPPING SLEEVES SHALL BE HYDROSTATICALLY PRESSURE TESTED PRIOR TO THE TAP BEING ACCOMPLISHED. TEST SHALL BE APPROVED BY PWC PROJECT COORDINATOR PRIOR TO BEGINNING TAPPING PROCESS.

FOR USE WITH STANDARD M.J. PIPE

VALVE SIZE	A	B	C	D	E	F	G	H	J	K	L	M	N	R	S	T	TURNS TO OPEN	WEIGHT W/ACC
4	4-3/8	5-7/8	15/16	1-1/2	9	7-1/2	4-7/8	4-63/64	4-29/32	2-1/2	7-1/2	9	14-1/8	9	8-3/4	1/4	14	118
6	6-7/8	6-1/4	1	1-5/8	11	9-1/2	6-7/8	6-63/64	7	2-1/2	9-1/2	11	17-5/8	11-3/4	8-7/8	1/4	21	175
8	6-1/2	7-1/4	1-1/8	1-3/4	13-1/4	11-3/4	6-7/8	8-63/64	9-5/32	2-1/2	11-3/4	13-1/2	21	14-1/4	8-7/8	1/4	28	274
12	7	8-1/4	1-1/4	1-3/4	17-7/8	16-1/4	8-7/8	12-63/64	13-5/16	2-1/2	17	19	28-1/4	19-1/8	12-1	1/4	39	570
16	8-1/2	9-1/8	1-7/16	2-1/16	23	21	12-7/8	16-15/16	17-35/64	3-1/2	21-1/4	23-1/2	38-5/8	26-1/8	16-1	1/4	55	1140
24	10-1/2	14-1/4	1-7/8	2-1/2	31-3/4	30	16-7/8	24-15/16	25-15/16	3-1/2	29-1/2	32	54-5/8	37-5/8	20-1	3/8	5/16	79	3225

north carolina DUNN city of dunn

M.J. TAPPING VALVE

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.05
Sheet 2 of 4



north carolina DUNN city of dunn

VAULT COUPLING

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
600.08
Sheet 1 of 1

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.7



north carolina DUNN city of dunn

PRECAST 4' DIA SANITARY MANHOLE
FOR SEWER MAINS LESS THAN 18"
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.00
Sheet 1 of 1

NOTES

1. ALL PRE CAST CONCRETE MANHOLES SHALL CONFORM TO THE LATEST REVISION OF ASTM C478.
2. CONCRETE SHALL BE 4000 PSI AT 28 DAYS MINIMUM.
3. STEEL REINFORCEMENT SHALL BE GRADE 40 BILLET STEEL CONFORMING TO THE LATEST REVISION OF ASTM-A-185 FOR WALL REINFORCEMENT, AND THE LATEST REVISION OF ASTM-A615 FOR THE BASE REINFORCEMENT.
4. STANDARD JOINTS SHALL BE; SEALED WITH PUTTY TYPE PLASTIC CEMENT PER FED. SPEC. SS-C-153 OR AN O-RING TYPE JOINT CONFORMING TO THE LATEST REVISION OF ASTM-C443.
5. MANHOLE INLETS AND OUTLETS SHALL BE CAST IN PLACE FLEXIBLE RUBBER SLEEVES BOOTS PER THE LATEST REVISION OF ASTM-C923.
6. INVERTS TO BE CONSTRUCTED OF BRICK WITH A CONCRETE BENCH (DETAIL 700.02).
7. A STANDARD 0.20 FOOT DROP SHALL BE PROVIDED AT EACH MANHOLE. THE MAXIMUM SEPARATION OR INVERT IN TO INVERT OUT WITHIN A MANHOLE IS 24 INCHES. WHEN THE SEPARATION IS GREATER THAN 24 INCHES A DROP MANHOLE MUST BE USED.
8. MANHOLES GREATER THAN 20 FEET IN DEPTH SHALL HAVE AN INSIDE DIAMETER OR 5'-0". FOR SANITARY SEWER MAINS GREATER THAN EIGHTEEN INCHES (18") IN DIAMETER, MANHOLES SHALL BE A MINIMUM OF 5'-0" IN DIAMETER.
9. RIM ELEVATIONS SHALL BE AT GRADE IN STREETS & PARKING LOTS.
10. MANHOLES NOT LOCATED IN ROADWAYS SHALL HAVE A TOP ELEVATION A MINIMUM OF 12 INCHES ABOVE FINISH GRADE. MANHOLES LOCATED ALONG OUTFALLS SHALL HAVE A TOP ELEVATION A MINIMUM OF 24 INCHES ABOVE FINISHE GRADE OR 100 YEAR FLOOD PLAIN, OR 12 INCHES ABOVE 500 YEAR FLOOD PLAIN, WHICHEVER IS HIGHER. THE 100-YEAR FLOOD ELEVATION SHALL BE NOTED ON THE CONSTRUCTION DRAWINGS.

north carolina DUNN city of dunn

SANITARY MANHOLE NOTES
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.01
Sheet 1 of 1



NOTES:

1. INVERT MATERIAL SHALL BE CONCRETE CAST IN PLACE WITH A SMOOTH FINISH.
2. WIDTH OF INVERT SHALL MATCH INSIDE DIAMETER OF INCOMING AND OUTGOING PIPES.
3. BRICK INVERT SHALL BE FORMED AS SHOWN.
4. ALL INVERT ELEVATIONS SHALL BE AS SHOWN ON APPROVED CONSTRUCTION PLANS.
5. BENCHES TO BE BUILT OUT OF CONCRETE, MORTARED BLOCK OR BRICK. STONE IS NOT ACCEPTABLE.

north carolina DUNN city of dunn

SANITARY SEWER MANHOLE
INVERT
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.05
Sheet 1 of 1



NOTES:

1. THE MINIMUM SPACING FROM THE EDGE OF A CORE FOR A LATERAL TO THE EDGE OF THE NEXT CORE SHALL BE 6 INCHES.
2. SEWER LATERAL SHALL NOT ENTER A MANHOLE AT AN ANGLE LESS THAN 90° TO THE EFFLUENT PIPE.
3. ALL LATERALS TO BE INSTALLED AT THE TOP OF THE BENCH.
4. PROVIDE BRICK OR CONCRETE FOR INVERT.
5. INVERTS TO BE BUILT FROM LATERAL TO EFFLUENT PIPE.
6. THE MAXIMUM NUMBER OF LATERALS FOR ANY ONE MANHOLE IS FIVE (5).
7. ALL NEW LATERALS INTO MANHOLES MUST BE CORE DRILLED AND INSTALLED WITH A FLEXIBLE RUBBER BOOT.

north carolina DUNN city of dunn

SANITARY SEWER LATERAL
AT MANHOLE
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.06
Sheet 1 of 1



north carolina DUNN city of dunn

SANITARY SEWER DROP MANHOLE
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.07
Sheet 1 of 1



north carolina DUNN city of dunn

SANITARY SEWER MANHOLE VENT
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
700.08
Sheet 1 of 1

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
C5.8



PLAN



SECTION Y–Y



SECTION X–X

APPROVED HOOD DESIGNS

NOTES:

1. PRECAST DESIGN SPECIFICATIONS SHALL CONFORM TO THE LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTE WATER STRUCTURES", NCDOT AND THE CITY OF DUNN SPECIFICATIONS.
2. PRECAST STRUCTURES SHALL BE DESIGNED FOR H–20–44 LOADING.
3. PRECAST STRUCTURE SHALL HAVE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 4000 psi. IF THE BOTTOM CONCRETE SLAB IS POURED, IT SHALL BE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 3000 psi AND SHALL BE POURED INTO FORMS.
4. STEEL REINFORCING DESIGN SHALL CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE–BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH.
5. ADDITIONAL STEEL REINFORCEMENT SHALL BE INSTALLED AT ALL OPENINGS.
6. USE NCDOT STD NO. 840.03/CITY OF DUNN STD. 800.10 FRAME, GRATE AND HOOD UNLESS OTHERWISE INDICATED. USE TYPE "E", "I", OR "O" GRATES UNLESS OTHERWISE INDICATED.
7. FOR STRUCTURE HEIGHTS OVER 3'–6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO CITY OF DUNN STD. 700.03, OR AN APPROVED EQUAL.
8. OPTIONAL CONSTRUCTION – MONOLITHIC CLASS A PCC POUR. USE 2" KEYWAY OR #4 BAR DOWELS AT 12" CENTERS AT THE CONSTRUCTION JOINT.
9. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO FEDERAL SPECIFICATIONS SS–S–21A, ASSHTO M–198, TYPE B – BUTYL RUBBER.
10. PRECAST CATCH BASIN MINIMUM WALL THICKNESS (SOLID WALL AND BOTTOM SLAB):

HEIGHT OF STRUCTURE	WALL THICKNESS
0' TO 10'	6"
10' TO 16'	8"
OVER 16'	SPECIAL DESIGN

north carolina DUNN city of dunn

PRECAST CATCH BASIN
GRATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.09
Sheet 1 of 2



PLAN OVER–WIDTH



PLAN OVER–LENGTH



DETAIL SHOWING METHOD OF RISER CONSTRUCTION



SECTION J–J OVER–WIDTH



SECTION M–M OVER–LENGTH

NOTES (CONTINUED):

11. OVER–LENGTH, OVER–WIDTH, AND OVER–LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
12. THE EXTRA SLAB TO ACCOMMODATE OVER–LENGTH AND OVER–WIDTH PIPES, SHALL BE DESIGNED ACCORDING TO SHEET 2 OF 2 OF THE CURRENT NCDOT STD. NO. 840.02.
13. IT IS PREFERRED THAT THERE SHOULD BE A MINIMUM OF 6" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.

north carolina DUNN city of dunn

PRECAST CATCH BASIN
GRATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.09
Sheet 2 of 2









NOTES:

1. PRECAST DESIGN SPECIFICATIONS SHALL CONFORM TO THE LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTE WATER STRUCTURES", NCDOT AND THE CITY OF DUNN SPECIFICATIONS.
2. PRECAST STRUCTURES SHALL BE DESIGNED FOR H–20–44 LOADING.
3. PRECAST STRUCTURE SHALL HAVE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 4000 psi. IF THE BOTTOM CONCRETE SLAB IS POURED, IT SHALL BE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 3000 psi AND SHALL BE POURED INTO FORMS.
4. STEEL REINFORCING DESIGN SHALL CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE–BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH.
5. ADDITIONAL STEEL REINFORCEMENT SHALL BE INSTALLED AT ALL OPENINGS.
6. THE FRAME AND COVER SHALL BE CAST INTO THE PCC LID AND SHALL BE MANUFACTURED AS SPECIFIED IN CITY OF DUNN STD. 800.06.
7. FOR STRUCTURE HEIGHTS OVER 3'–6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO CITY OF DUNN STD. 700.03, OR AN APPROVED EQUAL.
8. GENERALLY, STEPS SHALL PLACED IN THE REAR WALL. IF THERE IS A CONFLICT WITH A PIPE ENTERING THE REAR WALL, THE STEPS SHALL BE MOVED TO A SIDE WALL WITH A CORRESPONDING SHIFT OF THE TOP, CAST IRON FRAME & COVER. THE LOCATION OF THE SHIFT STEPS AND FRAME & COVER SHALL BE APPROVED BY THE ENGINEER.
9. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO FEDERAL SPECIFICATIONS SS–S–21A, ASSHTO M–198, TYPE B – BUTYL RUBBER.
10. PRECAST CATCH BASIN MINIMUM WALL THICKNESS (SOLID WALL AND BOTTOM SLAB):

HEIGHT OF STRUCTURE	WALL THICKNESS
0' TO 10'	6"
10' TO 16'	8"
OVER 16'	SPECIAL DESIGN

north carolina DUNN city of dunn

PRECAST CATCH BASIN
THROATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.05
Sheet 1 of 2



NOTES (CONTINUED):

11. OVER–LENGTH, OVER–WIDTH, AND OVER–LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
12. THE PRECAST CONCRETE INLET LID FOR THE OVER–LENGTH INLET SHALL HAVE FOUR #5 BARS IN THE STREET FACE.
13. IF POSSIBLE, THERE SHOULD BE A MINIMUM OF 6" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.





north carolina DUNN city of dunn

PRECAST CATCH BASIN
THROATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.05
Sheet 2 of 2

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

C5.9



north carolina DUNN city of dunn

DROPPED CURB & GUTTER INLET

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.16
Sheet 1 of 2

NOTES:

1. BRICK MASONRY SHALL BE JUMBO BRICK, CONCRETE BRICK, OR SOLID CONCRETE BLOCKS WHICH MEETS THE SPECIFICATIONS OF SECTION 1040 OF THE LATEST EDITION OF THE NCDOT SPECIFICATIONS FOR ROADS AND STRUCTURES.
2. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO THE CITY STD. 700.03 OR APPROVED EQUAL.
3. CLASS A, 3000 psi CONCRETE SHALL BE USED THROUGHOUT.
4. CATCH BASIN BRICK MINIMUM WALL THICKNESS:

HEIGHT OF STRUCTURE	WALL THICKNESS
0' – 8'	8"
OVER 8' – 16'	*
OVER 16'	SPECIAL DESIGN

* OVER 8'-0" IN HEIGHT, USE 12" WALL FROM THE BOTTOM OF THE WALL TO 8'-0" FROM THE TOP OF THE WALL. USE 8" WALL FOR REMAINING 8'-0".

5. USE FORMS FOR CONSTRUCTION OF THE BOTTOM SLAB OR USE A PRECAST SLAB.
6. USE FRAME AND GRATE AS SPECIFIED ON CITY OF DUNN STD. 800.17.
7. THE EXTRA SLAB TO ACCOMMODATE OVER-LENGTH AND OVER-WIDTH PIPES, SHALL BE DESIGNED ACCORDING TO SHEET 2 OF 2 OF THE CURRENT NCDOT STD. NO. 840.01; UNLESS THE EXTENDED BOX WILL BE SUBJECT TO VEHICULAR TRAFFIC, THEN, THE EXTRA SLAB SHALL BE DESIGNED FOR H520 LOADING.
8. THE CONTRACTOR HAS THE OPTION OF FURNISHING A PRECAST PCC BOX. THE BOX SHALL MEET THE APPLICABLE SPECIFICATIONS OF THE CITY OF DUNN STD. 800.09.

north carolina DUNN city of dunn

DROPPED CURB & GUTTER INLET

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.16
Sheet 2 of 2



PIPE DIA.	W	E	G
12"	1-7/8"	2'-0"	2'-3 3/4"
15"	1-7/8"	2'-6"	2'-3 3/4"
18"	2"	3'-0"	3'-4"
24"	2-1/2"	4'-0"	4'-5"
30"	2-3/4"	5'-0"	5'-5 1/2"
36"	3"	6'-0"	6'-6"
42"	3-1/2"	6'-6"	7'-1"
48"	4"	7'-0"	7'-8"
54"	4-1/2"	7'-6"	8'-3"

NOTES:

1. END BLOCK SHALL BE PRECAST OR CAST-IN PLACE USING CLASS B CONCRETE, 2,500 psi.
2. THE PRECAST END BLOCK SHALL BE INSTALLED OR THE HOLE FOR THE POURED END BLOCK SHALL BE EXCAVATED, PRIOR TO THE INSTALLATION OF THE FLARED END SECTION.
3. THE END BLOCKS ARE MANDATORY FOR UPSTREAM F.E.S. AND REQUIRED, IF SPECIFIED IN THE PLANS, FOR DOWNSTREAM F.E.S. THE COST FOR THE END BLOCKS SHALL BE CONSIDERED INCIDENTAL TO THE COST OF F.E.S.

north carolina DUNN city of dunn

FLARED END SECTION
for 12" TO 54" PIPE

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.15
Sheet 1 of 1



NOTES:

1. FRAME AND COVER SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35B SPECIFICATIONS.
2. MINIMUM AVERAGE WEIGHT:
   COVER 75 lbs
   FRAME 61 lbs
   UNIT 137 lbs
3. FRAME AND COVER SHALL CONTAIN THE FOLLOWING INFORMATION:
   MANUFACTURER'S MARK
   LOCATION OF FOUNDRY (COUNTRY)
   MANUFACTURER'S CATALOG NUMBER
   (SEE COMPONENT DIAGRAMS FOR SPECIFICS)
4. APPROVED MANUFACTURERS:
   EAST JORDAN IRON WORKS, V-1887
   US FOUNDRY, USF 1162 RING AND LV COVER

north carolina DUNN city of dunn

FRAME AND COVER for
THROATED INLET

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 8/01/10
Scale: NTS
800.06
Sheet 1 of 1

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

C5.10



FRAME TOP VIEW

GRATE TOP VIEW



GRATE SECTION A-A



GRATE SECTION B-B



FRAME SECTION C-C



FRAME SECTION D-D

NOTES:

1. FRAMES, GRATE AND HOOD SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35B SPECIFICATIONS.
2. GRATE SHALL BE SUITABLE FOR BICYCLE TRAFFIC.
3. FRAME, GRATE AND HOOD SHALL CONTAIN THE FOLLOWING INFORMATION:
   MANUFACTURER'S MARK
   LOCATION OF FOUNDRY (COUNTRY)
   MANUFACTURER'S CATALOG NUMBER
   GRATE: "DUMP NO WASTE/ DRAINS TO WATERWAYS".
4. ESTIMATED TOTAL WEIGHT: 529 lbs.
5. APPROVED MANUFACTURERS:
   US FOUNDRY & MANUF. CORP
   ITEM NO. 5040223
   EAST JORDAN IRON WORKS, INC
   V-4510 (DIFFERENT DIMENSIONS)
6. OPEN AREA IS APPROXIMATELY 310 sq in.

north carolina DUNN city of dunn

FRAME & GRATE for GUTTER INLET
for DROPPED CURBING
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.17
Sheet 1 of 1



PLAN





SECTION A-A



SECTION B-B

APPROVED HOOD DESIGNS:



NOTES:

1. FRAMES, GRATE AND HOOD SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35 SPECIFICATIONS. IT SHALL ALSO MEET THE CURRENT NCDOT STD. NO. 840.03.
2. MINIMUM AVERAGE WEIGHT:
   GRATE 220 lbs
   BACK 140 lbs
   FRAME 215 lbs
   UNIT 575 lbs
3. FRAME, GRATE AND HOOD SHALL CONTAIN THE FOLLOWING INFORMATION:
   MANUFACTURER'S MARK
   LOCATION OF FOUNDRY (COUNTRY)
   MANUFACTURER'S CATALOG NUMBER
   NCDOT STD NO.
4. APPROVED MANUFACTURERS:
   EAST JORDAN IRON WORKS
   TYPE "E" V-4066-1
   TYPE "F" V-4066-3
   TYPE "G" V-4066-4
   US FOUNDRY & MANUF. CORP
   TYPE "E" USF 5181-6420
   TYPE "F" USF 5181-6425
   TYPE "G" USF 5181-6430
   OR APPROVED EQUAL.

north carolina DUNN city of dunn

FRAME, GRATE & HOOD
GRATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.10
Sheet 1 of 2



NOTES:

1. ALL PRECAST SEWER MANHOLE SECTIONS SHALL MEET THE REQUIREMENTS OF ASTM C-478 AND AASHTO M199. THE PRECAST CONCRETE COMPRESSIVE STRENGTH SHALL BE A MINIMUM OF 4000 psi.
2. ALL MANHOLE STEPS SHALL CONFORM TO CITY STD. 700.03 OR AN APPROVED EQUAL. STEPS SHALL BE INSTALLED IN LINE WITH THE VERTICAL SIDE OF THE CORE.
3. THE MANHOLE JOINTS SHALL BE SEALED BY A BUTYL RUBBER SEALANT. THE BUTYL RUBBER SEALANT SHALL BE 1" SQUARE AND SHALL CONFORM TO ASTM C-990 AND AASHTO M-198.
4. THE LIFT INSERT AND HOLES SHALL BE ACCORDING TO CITY SPECIFICATIONS. ALL LIFT HOLES SHALL BE COMPLETELY FILLED WITH NON-SHRINK GROUT AFTER MH INSTALLATION.
5. ALL PIPE ENTRANCES AND CONNECTIONS SHALL CONFORM TO SECTION 840 OF THE CURRENT EDITION OF THE NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
6. IF A FLAT TOP SECTION IS NECESSARY, IT SHALL BE APPROVED BY THE ENGINEER AND SHALL BE DESIGNED FOR HS-20 LOADING.
7. A REINFORCED CONCRETE FOOTING IS REQUIRED WHEN THE MANHOLE IS OVER 12' OR ON A POOR SOIL BASE. THE REINFORCED CONCRETE FOOTING MAY BE POURED OR PRECAST ACCORDING TO CURRENT NCDOT STD NO. 1525.01 SHEET 2 OF 2. THE CONTRACTOR HAS THE OPTION OF PROVIDING AL EXPANDED MANHOLE BASE SECTION AND SETTING THE BASE SECTION ON 12" MIN #57 STONE WITH NO EXTRA COST TO THE CITY.
8. ALL PIPE OPENINGS SHALL BE CAST TO ELEVATIONS SPECIFIED ON CONTRACT PLANS OR TO MEET JOB REQUIREMENTS.

north carolina DUNN city of dunn

PRECAST STORM MANHOLE – 4' DIA.
FOR STORM SEWER PIPES LESS THAN 21"
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.02
Sheet 1 of 1



SECTION B-B

MIN. FLOW AREA= 430 SQIN.

TYPE "E" GRATE

SECTION A-A



SIDE VIEW

MIN. FLOW AREA= 370 SQIN.

TYPE "G" GRATE

SECTION A-A



SIDE VIEW

SECTION A-A

MIN. FLOW AREA= 370 SQIN.

TYPE "F" GRATE



north carolina DUNN city of dunn

FRAME, GRATE & HOOD
GRATED INLET
CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS
800.10
Sheet 2 of 2

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

C5.11



SECTION OF FRAME
WEIGHT OF FRAME= 100 LBS.

PLAN OF FRAME



PLAN OF COVER
TOP VIEW

PLAN OF COVER
BOTTOM VIEW



SECTION OF COVER
WEIGHT OF COVER= 125 LBS.

NOTES:

1. ALL LETTERING SHALL BE CLEAN, CRISP AND CLEARLY LEGIBLE.
2. SEE CASTING SPECIFICATIONS.
3. CASTINGS SHALL RECEIVE ONE COAT OF KOPPERS SUPER SERVICE BITUMASTIC BLACK PAINT. PAINT SHALL BE KEPT OFF OF BOLT THREADS. SURFACE SHALL BE THOROUGHLY WIRE BRUSHED BEFORE PAINTING.

north carolina DUNN city of dunn	STORMWATER MANHOLE RING & COVER CITY of DUNN NORTH CAROLINA Department of Public Works	Revised: 1/28/11 Scale: NTS 800.00 Sheet 1 of 1



TRENCH WIDTH:

MIN W = Bc +16"
MAX W = Bc +4'

IF CONTRACTOR CHOOSES TO EXCAVATE PAST THE MAX W, THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS IN THE EXCAVATION BEYOND THE MAX W LIMITS.

BACKFILLING NOTES ACCORDING TO CURRENT EDITION OF NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES:

1. EXCAVATION, TRENCHING AND BACKFILLING SHALL BE DONE ACCORDING TO SECTION 300 AND ACCORDING TO NCDOT STD. NO. 300.01, METHOD OF PIPE INSTALLATION, METHOD A.
2. BACKFILLING SHALL ALSO BE IN ACCORDANCE WITH ARTICLE 300-7 AND COMPACTED TO 95% OF THE AASHTO T99 NCDOT MODIFIED PROCTOR.
3. THE LAST 8" OF BACKFILL BELOW THE FINISHED SURFACE OF THE SUBGRADE SHALL BE COMPACTED TO 100% OF THE AASHTO T99 NCDOT PROCTOR.

TYPICAL INSTALLATION:
1. UNLESS OTHERWISE SPECIED, A MODIFIED CLASS D FOUNDATION SHALL BE USED.
2. UNLESS OTHERWISE SPECIFIED, METHOD A SHALL BE USED.

north carolina DUNN city of dunn	STORM SEWER INSTALLATION CITY of DUNN NORTH CAROLINA Department of Public Works	Revised: 1/28/11 Scale: NTS 800.13 Sheet 1 of 1

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

CONSTRUCTION DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

C5.12



Statistics

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Boundary Line	+	0.0 fc	0.2 fc	0.0 fc	N/A	N/A
Load Dock Lot	+	1.0 fc	6.0 fc	0.0 fc	N/A	N/A
Parking Lot	+	1.5 fc	4.7 fc	0.4 fc	11.8:1	3.8:1

Luminaire Locations

No.	Label	Location X	Location Y	Location Z	MH	Orientation	Tilt	Aim X	Aim Y	Aim Z
1	A	624.24	-519.79	25.00	25.00	180.00	0.00	624.24	-520.99	0.00
2	A	300.07	-519.71	25.00	25.00	180.00	0.00	300.07	-520.90	0.00
3	A	408.45	-519.71	25.00	25.00	180.00	0.00	408.45	-520.90	0.00
4	A	846.78	-519.71	25.00	25.00	180.00	0.00	846.78	-520.90	0.00
5	A	178.15	-519.63	25.00	25.00	180.00	0.00	178.15	-520.82	0.00
6	A	527.23	-519.46	25.00	25.00	180.00	0.00	527.23	-520.65	0.00
7	A	733.02	-519.46	25.00	25.00	180.00	0.00	733.02	-520.65	0.00
8	B	863.16	-500.55	25.00	25.00	90.00	0.00	864.35	-500.55	0.00
9	B	160.53	-500.51	25.00	25.00	270.00	0.00	159.34	-500.51	0.00
10	B	160.39	-399.07	25.00	25.00	270.00	0.00	159.19	-399.07	0.00
12	B	863.13	-298.07	25.00	25.00	90.00	0.00	864.32	-298.07	0.00
13	B	160.21	-282.93	25.00	25.00	270.00	0.00	159.01	-282.93	0.00
14	A	175.75	-269.35	25.00	25.00	0.00	0.00	175.75	-268.16	0.00
15	A	472.00	-269.17	25.00	25.00	0.00	0.00	472.00	-267.97	0.00
16	A	753.96	-269.12	25.00	25.00	0.00	0.00	753.96	-267.93	0.00
17	A	279.29	-269.07	25.00	25.00	0.00	0.00	279.29	-267.88	0.00
18	A	374.41	-268.99	25.00	25.00	0.00	0.00	374.41	-267.79	0.00
19	A	658.46	-268.95	25.00	25.00	0.00	0.00	658.46	-267.76	0.00
20	A	854.92	-268.95	25.00	25.00	0.00	0.00	854.92	-267.76	0.00
21	A	564.01	-268.90	25.00	25.00	0.00	0.00	564.01	-267.71	0.00
22	B	863.16	-399.55	25.00	25.00	90.00	0.00	864.35	-399.55	0.00

RSX2 LED
Area Luminaire

Catalog Number
Notes
Type

The future is bound for the light you're at! www.acuitybrands.com

Introduction

The new RSX LED Area family delivers maximum value by providing significant energy savings, long life and outstanding photometric performance at an affordable price. The RSX2 delivers 11,000 to 31,000 lumens allowing it to replace 250W to 1000W HID luminaires.

The RSX features an integral universal mounting mechanism that allows the luminaire to be mounted on most existing drill hole patterns. This "no-drill" solution provides significant labor savings. An easy-access door on the bottom of mounting arm allows for wiring without opening the electrical compartment. A mast arm adaptor, adjustable integral slipfitter and other mounting configurations are available.

Specifications

EPA (ft²/60°): 0.69 ft² (0.06 m²)
Length: 29.3" (74.4 cm) (SPA mount)
Width: 13.4" (34.0 cm)
Height: 3.0" (7.6 cm) Main Body 7.2" (18.3 cm) Arm
Weight: (SPA mount) 30.0 lbs (13.6 kg)



Design Select options indicated by this color background.

design select

Items marked by a shaded background qualify for the Design Select program and ship in 15 days or less. To learn more about Design Select, visit www.acuitybrands.com/designselect. *See ordering tree for details

Ordering Information

EXAMPLE: RSX2 LED P6 40K R3 MVOLT SPA DDBXD

RSX2 LED

Series	Performance Package	Color Temperature	Distribution	Voltage	Mounting
RSX2 LED	P1 Performance Package P2 P3 P4 P5 P6	30K 3000K 40K 4000K 50K 5000K	R2 Type 2 Wide R3 Type 3 Wide R3S Type 3 Short R4 Type 4 Wide R4S Type 4 Short R5 Type 5 Wide * R5S Type 5 Short * AFR Automotive Front Row AFRRHQ Automotive Front Row Right Rotated AFRLHQ Automotive Front Row Left Rotated	MVOLT (120V-277V) * HVOLT (347V-480V) * XVOLT (277V-480V) * (use specific voltage for options as noted) 120 * 277 * 208 * 347 * 240 * 480 *	SPA Square pole mounting (3.5" min. SQ pole for 1 at 90°, 3.5" min. SQ pole for 2, 3, 4 at 90°) RPA Round pole mounting (3.2" min. dia. RND pole for 2, 3, 4 at 90°, 3.0" min. dia. RND pole for 1 at 90°, 2 at 180°, 3 at 120°) WA Mast arm adaptor (fits 2-3/8" OD horizontal tenon) IS Adjustable slipfitter (fits 2-3/8" OD tenons) * WBA Wall bracket * WBAXC Wall bracket with surface conduit box * AASP Adjustable tilt arm square pole mounting * AARP Adjustable tilt arm round pole mounting * AAWB Adjustable tilt arm with wall bracket * AAWXC Adjustable tilt arm wall bracket and surface conduit box *

Options		Finish	
Shipped Installed		DDBXD	Dark Bronze
HS House-side shield *		DBLXD	Black
PE Photocontrol, button style **		DNAXD	Natural Aluminum
PER7 Seven-wire twist-lock receptacle only (no controls) * **		DWHXD	White
SF Single fuse (120, 277, 347) *		DDBTXD	Textured Dark Bronze
DF Double fuse (208, 240, 480) *		DBLBXD	Textured Black
SPD20KV 20kV Surge pack (10kV standard)		DNATXD	Textured Natural Aluminum
FAO Field adjustable output *		DWHGXD	Textured White
DMG 0-10V dimming extend out back of housing for external control (control ordered separate) *			
DS Dual switching * **			
Shipped Installed			
*Standalone and Networked Sensors/Controls (factory default settings, see table page 9)			
NLSAU PIR9 nLight AIR generation 2, with Networked, Bi-Level motion/ambient sensor * **			
BAA Buy America(n) Act and/or Build America Buy America Qualified			
CCE Coastal Construction *			
*Note: NLSAU/PIR9 with nLight Air can be used as a standalone dimming sensor with out-of-box settings or as a wireless networked solution. See factory default settings table. Sensor coverage pattern is affected when luminaire is tilted.			
Shipped Separately (requires some field assembly)			
EGS External glare shield *			
EGFV External glare full visor (360° around light aperture) *			
BS Bird spikes *			

© 2011-2025 Acuity Brands Lighting, Inc. All rights reserved.

Performance Data

Lumen Output

Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of the configurations shown, within the tolerances allowed by Lighting Facts. Contact factory for performance data on any configurations not shown here.

Performance Package	System Watts	Distribution Type	30K (3000K, 70 CRI) Lumens	B	U	G	LPW	40K (4000K, 70 CRI) Lumens	B	U	G	LPW	50K (5000K, 70 CRI) Lumens	B	U	G	LPW
P1	77W	R2	10,040	2	0	1	129	11,031	2	0	1	133	11,031	2	0	1	133
		R3	10,005	2	0	2	141	10,992	2	0	2	155	10,992	2	0	2	155
		R3S	10,271	2	0	2	143	11,285	2	0	2	157	11,285	2	0	2	157
		R4	10,126	2	0	2	143	11,126	2	0	2	157	11,126	2	0	2	157
		R4S	9,779	2	0	2	138	10,744	2	0	2	151	10,744	2	0	2	151
		R5	10,272	4	0	2	145	11,285	4	0	2	159	11,285	4	0	2	159
		R5S	10,144	3	0	1	149	11,585	3	0	2	163	11,585	3	0	2	163
		AFR	10,026	2	0	1	141	11,016	2	0	1	155	11,016	2	0	1	155
		AFRRHQ	10,122	3	0	2	140	11,121	3	0	2	154	11,121	3	0	2	154
		AFRLHQ	10,164	3	0	2	141	11,167	3	0	2	155	11,167	3	0	2	155
P2	111W	R2	15,712	2	0	2	138	17,260	2	0	2	155	17,260	2	0	2	155
		R3	15,657	2	0	2	141	17,200	2	0	2	155	17,200	2	0	2	155
		R3S	16,077	2	0	2	145	17,661	2	0	2	159	17,661	2	0	2	159
		R4	15,847	2	0	2	143	17,409	2	0	2	157	17,409	2	0	2	157
		R4S	15,304	2	0	2	138	16,813	2	0	2	151	16,813	2	0	2	151
		R5	16,075	4	0	2	145	17,661	5	0	3	159	17,661	5	0	3	159
		R5S	16,502	4	0	2	149	18,138	4	0	2	163	18,138	4	0	2	163
		AFR	15,691	2	0	2	141	17,240	2	0	2	155	17,240	2	0	2	155
		AFRRHQ	15,841	3	0	3	139	17,404	4	0	3	153	17,404	4	0	3	153
		AFRLHQ	15,907	3	0	3	139	17,477	4	0	3	153	17,477	4	0	3	153
P3	147W	R2	19,855	3	0	2	132	21,814	3	0	2	145	21,814	3	0	2	145
		R3	19,785	3	0	3	135	21,737	3	0	4	148	21,737	3	0	4	148
		R3S	20,312	3	0	3	135	22,317	3	0	3	149	22,317	3	0	3	149
		R4	20,044	3	0	3	136	22,022	3	0	4	150	22,022	3	0	4	150
		R4S	19,359	3	0	3	132	21,267	3	0	3	145	21,267	3	0	3	145
		R5	20,313	5	0	3	138	22,317	5	0	3	152	22,317	5	0	3	152
		R5S	20,852	4	0	2	142	22,910	4	0	2	156	22,910	4	0	2	156
		AFR	19,828	3	0	2	135	21,785	3	0	2	148	21,785	3	0	2	148
		AFRRHQ	20,017	4	0	3	133	21,992	4	0	3	147	21,992	4	0	3	147
		AFRLHQ	20,101	4	0	3	134	22,084	4	0	3	147	22,084	4	0	3	147
P4	187W	R2	22,836	3	0	3	122	25,092	3	0	3	134	25,092	3	0	3	134
		R3	22,763	3	0	4	121	25,012	3	0	4	134	25,012	3	0	4	134
		R3S	23,369	3	0	3	123	25,668	3	0	3	137	25,668	3	0	3	137
		R4	23,054	3	0	4	123	25,329	3	0	4	135	25,329	3	0	4	135
		R4S	22,243	3	0	3	119	25,059	3	0	3	134	25,059	3	0	3	134
		R5	23,362	5	0	3	125	25,669	5	0	4	137	25,669	5	0	4	137
		R5S	23,983	4	0	2	128	26,350	4	0	2	141	26,350	4	0	2	140
		AFR	22,806	3	0	2	122	25,056	3	0	2	134	25,056	3	0	2	134
		AFRRHQ	23,023	4	0	3	121	25,295	4	0	3	133	25,295	4	0	3	133
		AFRLHQ	23,120	4	0	3	122	25,401	4	0	3	134	25,401	4	0	3	134
P5	210W	R2	26,141	3	0	2	122	28,721	3	0	2	135	28,721	3	0	2	135
		R3	26,049	3	0	4	124	28,620	3	0	4	136	28,620	3	0	4	136
		R3S	26,744	3	0	3	125	29,383	3	0	4	138	29,383	3	0	4	138
		R4	26,390	3	0	4	126	28,994	3	0	4	138	28,994	3	0	4	138
		R4S	25,462	3	0	3	121	27,974	3	0	3	133	27,974	3	0	3	133
		R5	26,744	5	0	4	127	29,383	5	0	4	140	29,329	5	0	4	140
		R5S	27,474	4	0	2	131	30,163	4	0	2	144	30,163	4	0	2	144
		AFR	26,106	3	0	2	124	28,682	3	0	2	137	28,682	3	0	2	137
		AFRRHQ	26,354	4	0	3	124	28,955	4	0	3	136	28,955	4	0	3	136
		AFRLHQ	26,471	4	0	3	125	29,083	5	0	3	138	29,083	5	0	3	138
P6	244W	R2	27,646	3	0	2	112	30,374	5	0	2	125	30,134	5	0	2	125
		R3	27,549	3	0	4	113	30,267	3	0	4	124	30,267	3	0	4	124
		R3S	28,261	3	0	3	115	31,073	3	0	4	126	31,073	3	0	4	126
		R4	27,909	3	0	4	114	30,663	3	0	4	126	30,663	3	0	4	126
		R4S	26,928	3	0	3	110	29,585	3	0	3	121	29,585	3	0	3	121
		R5	28,284	5	0	4	116	31,075	5	0	4	127	31,075	5	0	4	127
		R5S	29,035	4	0	2	119	31,900	5	0	3	131	31,900	5	0	3	131
		AFR	27,608	3	0	2	112	30,332	3	0	2	123	30,332	3	0	2	123
		AFRRHQ	27,872	4	0	3	113	30,622	5	0	3	124	30,622	5	0	3	124
		AFRLHQ	27,989	4	0	3	113	30,751	5	0	3	125	30,751	5	0	3	125

© 2011-2025 Acuity Brands Lighting, Inc. All rights reserved.

Plan View
Scale - 1" = 30ft

Schedule

Symbol	Label	Image	QTY	Catalog Number	Description	Lamp	Number Lamps	Lumens per Lamp	LLF	Wattage	Polar Plot
	A		15	RSX2 LED P3 40K R4	RSX Area Fixture Size 2 P3 Lumen Package 4000K CCT Type R4 Distribution		1	22020	1	149.98	Max: 12987cd
	B		6	RSX2 LED P3 40K R3	RSX Area Fixture Size 2 P3 Lumen Package 4000K CCT Type R3 Distribution		1	21736	1	149.98	Max: 15670cd

Harnett Site Lighting Photometric

Designer

Date
04/04/2025
Scale
Not to Scale
Drawing No.

Summary



CANOPY TREE PLANTING DETAIL

DECIDUOUS B&B TREE PLANTING DETAIL (TREES 3" CAL. OR LARGER)



UNDERSTORY PLANTING DETAIL



SHRUB & GROUNDCOVER DETAIL

SHRUB BED PLANTING DETAIL – B&B AND CONTAINER SHRUBS



LOCATION MAP N.T.S.



OVERALL PLANTING PLAN

0 25 50 100 Feet

1:50

PLANTING SPECIFICATIONS

NOTES: INCLUDE 12"x12"x4" RIVER ROCK AT DOWNSPOUTS OF CANOPIES. INSTALL PINE NEEDLE MULCH AS INDICATED IN PLANTING DETAILS ABOVE PROVIDE GRASS IN ALL OTHER DISTURBED AREAS

1. GRASS: TALL FESCUE MIX
   SCHEDULE: MARCH 1–NOVEMBER 1 (FESCUE/RYE MIX NOVEMBER 1–MARCH 1)
   RATE: 250 LBS. PER ACRE
   LIME: GROUND LIMESTONE
   RATE: 2,000 LBS. PER ACRE
   FERTILIZER: 10–20–20
   RATE: 500 LBS. PER ACRE
2. GRASS AREA PREPARATION: AREA SHALL BE AMENDED AND POWER TILLED TO 6" MINIMUM DEPTH. CULTIPAK OR ROLL SEED AREA.
   STRAW: 1 1/2 TONS PER ACRE
   TACK: 225 GAL. PER ACRE
3. MULCH: PINE NEEDLES; 3" DEPTH IN ALL PLANT BEDS.
4. SOIL REQUIREMENTS: MIX TOP SOIL, AMENDMENTS AND FERTILIZER WITH EXISTING SOIL IN A CLEAN LEVEL AREA ON SITE. PREPARE A LARGE ENOUGH QUANTITY OF PREPARED BACKFILL MATERIAL TO BACKFILL ALL TREE, SHRUB & GROUNDCOVER PLANTING AREAS AND PITS AS SHOWN ON THE PLANTING DETAILS.
5. PLANTING MIX: SHALL CONSIST OF 1 PART EXISTING SOIL, 1 PART IMPORTED TOP SOIL AND 1 PART PINE BARK SOIL CONDITIONER THOROUGHLY AND UNIFORMLY MIXED TOGETHER BLEND IN 2 POUNDS OF 10–10–10 COMMERCIAL FERTILIZER PER CUBIC YARD.
6. BED AREAS: SHALL BE RAISED 6" ABOVE GRADE WHEN COMPLETE.
7. NOTCH EDGE: ALL BED AREAS SHALL HAVE A 4" NOTCH EDGE WHEN ADJACENT TO GRASSED AREAS.
8. CONTINUOUS BEDS: ALL PLANTING BEDS SHALL BE CONTINUOUS UNDER SHRUBBERY.
9. TREE BEDS: ALL TREES SHALL HAVE A 6'–0" MIN. DIAMETER MULCH BED AT THEIR BASE.
10. WEED KILLER: APPLY PRE-EMERGENCE HERBICIDE TO ALL PLANTING BEDS, PER MANUFACTURER'S SPECIFICATIONS, PRIOR TO APPLICATION OF REQUIRED MULCH.

NORTH CAROLINA SEAL 44 REGISTERED LANDSCAPE ARCHITECT ROBERT J. GRILL
Robert J Grill
07-07-25

(336) 312-2939

SITE PLANS

PLANNING & LANDSCAPE ARCHITECTURE

4005 Brenvenue Drive, Greensboro, NC 27409

PLANT LIST

code	number	common name	botanical name	size	remarks
		TREES			
CM	18	CRAPE MYRTLE	LAGERSTROEMIA I. 'POWHATEN'	6'-7' TALL	MULTI-TRUNKED
LO	12	LAUREL OAK	QUERCUS LAURIFOLIA	MIN 2" CAL	
PO	14	PIN OAK	QUERCUS PALUSTRIS	MIN 2" CAL	
RM	24	RED MAPLE	ACER RUBRUM 'OCTOBER GLORY'	MIN 2" CAL	
RB	14	RIVER BIRCH	BETULA NIGRA	MIN 2" CAL	
SM	7	SOUTHERN MAGNLOIA	MAGNOLIA VIRGINIANA	MIN 2" CAL	
ZK	22	ZELKOVA	ZELKOVA SERRATA	MIN 2" CAL	
		SHRUBS			
AB	26	ABELIA	ABELIA GRANDIFLORA	MIN 30" SPREAD OR HT	
DB	28	DWARF BOXWOOD	BUXUS HARLANDI	MIN 30" SPREAD OR HT	
DYH	43	DWARF YAYPON HOLLY	ILEX VOMITORA 'NANA'	MIN 30" SPREAD OR HT	
IH	131	INDIAN HAWTHORN	RAPHOLEPSIS INDICA	MIN 30" SPREAD OR HT	
JP	112	JAPANESE PRIVET	LIGUSTRUM JAPONICUM	MIN 30" SPREAD OR HT	

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	1ST REVIEW COMMENTS	7725

SAMET HARNETT COUNTY 1

LANDSCAPE PLAN

PRELIMINARY

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET: LA1.0

r 070725

0 25 50 100 Feet

1:50

LEGEND

- EXISTING STORMDRAIN PIPE
- DRAIN AREA LIMITS
- 404 404 EXISTING 404 WETLAND LIMIT
- EXISTING DRAINAGE PATTERN
- PROPOSED SILT FENCE/LOD
- PROPOSED LIMITS OF DISTURBANCE
- TD FLOW DIRECTON

GENERAL NOTES:

1. CONTRACTOR SHALL INSTALL SILT FENCE PRIOR BEGINNING WORK ON SITE. STONE OUTLETS SHALL BE INSTALLED ALONG LENGTH OF SILT FENCE AT AN INTERVAL OF 1 STONE OUTLET PER 500 LF OF SILT FENCE OR IN LOW AREAS ALONG THE TRAVERSE, SEE DETAIL SHEET EC2.1.
2. SILT FENCE SHALL REMAIN IN PLACE DURING CURB INSTALLATION AND PAVING OPERATIONS UNLESS THE LOCATION OF THE SILT FENCE INTERFERES WITH THE WORK.
3. CONTRACTOR TO INSTALL/CONFIRM STABILIZED CONSTRUCTION ENTRANCE PRIOR TO BEGINNING WORK ON SITE.
4. SEE SHEET C1.2 FOR SURROUNDING PROPERTY OWNER INFORMATION.
5. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES BOTH UNDERGROUND AND ABOVE GROUND PRIOR TO COMMENCING WORK.
6. CONTRACTOR IS LIMITED TO DISTURBING LESS THAN 1 ACRE PRIOR TO CONSTRUCTION/EXCAVATION SEDIMENT BASINS/TRAPS AND TEMPORARY DIVERSIONS.
7. CONTRACTOR TO INSTALL INLET PROTECTION PRIOR TO COMMENCING PAVING OPERATIONS.
8. UPON COMPLETION OF PAVING OPERATIONS, INLET OPENINGS SHALL BE PROTECTED WITH COI BAFFLES OR SIMILAR MEASURE TO PREVENT SEDIMENT FROM ENTERING OPEN CURB OR DROP INLET.

NOTE

WET BASIN'S UTILIZED AS PART OF A SEDMENTATION AND EROSION CONTROL PLAN SHALL BE CLEANED OUT TO INCLUDE REMOVAL OF ALL BAFFLES, SEDIMENT AND DEWATERING DEVICES. UPON COMPLETION OF CLEANOUT, POND SLOPES SHALL BE RE-ESTABLISHED AS PER THE PLANS. FOREBAYS SHALL BE INSTALLED AS SHOWN ON THIS SHEET BEFORE PONDS MAY BE UTILIZED FOR STORMWATER TREATMENT.

SEE SHEET C2.2 FOR POND CROSS SECTION AND STAGE STORAGE TABLES

PROJECT LIMITS 16+/- ACRES

EX. PROPERTY LINE

AREA DISTURBED OWNED BY HARNETT COUNTY: 2.36AC

EXISTING SPOT ELEVATIONS

EXISTING CONTOURS

PROPERTY LINE

ASPHALT ROAD

ARROWHEAD ROAD

CONC. CURB (TYP.)

CONC. ISLAND

US 301 S.

WOODED AREA

BURIED STORM PIPE

ASPHALT TOOD

SSMH RIM 187.25 IN: 180.99 OUT: 180.87

SSMH RIM: 182.79 IN: 175.85 OUT: 175.75

SSMH RIM: 180.59 IN: 174.14 OT

SSMH RIM: 179.53 IN: 173.39 OUT: 173.29

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER DEQ COMMENT	7/17/25

SAMET HARNETT COUNTY 1

EROSION CONTROL SHEET EXISTING CONDITIONS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

EC1.0

0 25 50 100 Feet

1:50

LEGEND

- EXISTING STORMDRAIN PIPE
- DRAIN AREA LIMITS
- EXISTING DRAINAGE PATTERN
- PROPOSED SILT FENCE/LOD
- PROPOSED LIMITS OF DISTURBANCE
- TD FLOW DIRECTON

GENERAL NOTES:

1. CONTRACTOR SHALL INSTALL SILT FENCE PRIOR BEGINNING WORK ON SITE. STONE OUTLETS SHALL BE INSTALLED ALONG LENGTH OF SILT FENCE AT AN INTERVAL OF 1 STONE OUTLET PER 500 LF OF SILT FENCE OR IN LOW AREAS ALONG THE TRAVERSE, SEE DETAIL SHEET EC2.1.
2. SILT FENCE SHALL REMAIN IN PLACE DURING CURB INSTALLATION AND PAVING OPERATIONS UNLESS THE LOCATION OF THE SILT FENCE INTERFERES WITH THE WORK.
3. CONTRACTOR TO INSTALL/CONFIRM STABILIZED CONSTRUCTION ENTRANCE PRIOR TO BEGINNING WORK ON SITE.
4. SEE SHEET C1.2 FOR SURROUNDING PROPERTY OWNER INFORMATION.
5. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES BOTH UNDERGROUND AND ABOVE GROUND PRIOR TO COMMENCING WORK.
6. CONTRACTOR IS LIMITED TO DISTURBING LESS THAN 1 ACRE PRIOR TO CONSTRUCTION/EXCAVATION SEDIMENT BASINS/TRAPS AND TEMPORARY DIVERSIONS.
7. CONTRACTOR TO INSTALL INLET PROTECTION PRIOR TO COMMENCING PAVING OPERATIONS.
8. UPON COMPLETION OF PAVING OPERATIONS, INLET OPENINGS SHALL BE PROTECTED WITH COI BAFFLES OR SIMILAR MEASURE TO PREVENT SEDIMENT FROM ENTERING OPEN CURB OR DROP INLET.

SEQUENCE OF CONSTRUCTION PHASE 1

1. INSTALL STABILIZED CONSTRUCTION ENTRANCES AS SHOWN.
2. INSTALL SILT FENCE AS SHOWN
3. INSTALL SEDIMENT BASIN INCLUDING BAFFLES, SLOPE DRAINS, OUTLET STRUCTURE AND SKIMMER PER DETAIL ON SHEET EC 2.1.
4. INSTALL TEMPORARY DIVERSIONS A, B, C AND D TO DIRECT RUN-OFF TO BASIN.
5. BEGIN CLEARING AND GRADING WORK ON SITE.
6. IMMEDIATELY STABILIZE AREAS THAT WILL NOT BE IMPACTED WITH FUTURE CONSTRUCTION WITH TEMPORARY SEEDING AND MULCHING.
7. IMMEDIATELY INSTALL TEMPORARY SEED AND MULCH TO STABILIZE DISTURBED AREAS AS MEASURES ARE REMOVED AS PART OF PHASE 1 CLEARING/GRADING.
8. INSPECT SILT FENCE, AND STABILIZED CONSTRUCTION ENTRANCES.

SEE SHEETS C5.1–C5.11 FOR STANDARD DETAILS

NOTE

WET BASIN'S UTILIZED AS PART OF A SEDIMENTATION AND EROSION CONTROL PLAN SHALL BE CLEANED OUT TO INCLUDE REMOVAL OF ALL BAFFLES, SEDIMENT AND DEWATERING DEVICES. UPON COMPLETION OF CLEANOUT, POND SLOPES SHALL BE RE-ESTABLISHED AS PER THE PLANS. FOREBAYS SHALL BE INSTALLED AS SHOWN ON THIS SHEET BEFORE PONDS MAY BE UTILIZED FOR STORMWATER TREATMENT.

SEE SHEET C2.2 FOR POND CROSS SECTION AND STAGE STORAGE TABLES

EXISTING SPOT ELEVATIONS

FUTURE DEVELOPMENT

EXISTING CONTOURS

PROPOSED DIVERSION D
INSTALL RECP FABRIC MATTING ECC2 OR SIMILAR–SEE DETAIL SHEET EC2.0–2.1

TEMPORARY DIVERSION D TO HAVE RECP MATTING INSTALLED IMMEDIATELY UPON GRADING

INSTALL COIR FIBER WATTLE SEE DETAIL SHEET EC2.0

TEMPORARY ROCK DAM SEE DETAIL SHEET EC2.1

EX. PROPERTY LINE

APPROXIMATE PHASE LIMITS (16 ACRES +/–)

DRAINAGE AREA D (0.81 AC)

DRAINAGE AREA A (2.75 AC)

DRAINAGE AREA C (5.82 AC)

DRAINAGE AREA B (0.92 AC)

DRIVEWAY 1

CONSTRUCTION ENTRANCE SEE DETAIL SHEET EC2.0

CONSTRUCTION ENTRANCE SEE DETAIL SHEET EC2.0

US 301 S.

TEMPORARY DIVERSION A

ARMOR DIVERSION CORNER–USE CLASS B RIP–RAP

RELOCATED STAGING AREA IN PHASE 2

BUILDING PAD FFE 191'

INSTALL 8" DIAMETER COMPOST SOCK ENTIRE LENGTH, SEE DETAIL SHEET EC2.1. UPON STABILIZATION OF SLOPE, SOCK MAY BE CUT OPEN IN PLACE AND PERMANENT SEED AND MULCH SHALL BE INSTALLED.

TEMPORARY DIVERSION C TO BE REMOVED AS SITE PROPOSED SITE GRADES ARE ESTABLISHED

ARMOR DIVERSION CORNER–USE CLASS B RIP–RAP

CONSTRUCTION ENTRANCE SEE DETAIL SHEET EC2.0

PROPERTY LINE

DRIVEWAY 2

INSTALL SLOPE DRAIN SEE DETAIL SHEET EC2.0

INSTALL COIR FABRIC BAFFLES SEE DETAIL SHEET EC2.0

INSTALL SLOPE DRAIN SEE DETAIL SHEET EC2.0

INSTALL OUTLET STRUCTURE, SKIMMER AND RIP–RAP APRON–SEE DETAILS THIS SHEET AND SHEET EC2.0

PROPOSED STORMWATER POND/SEDIMENT BASIN SEE DETAIL SHEET EC1.3

ARROWHEAD ROAD

ASPHALT ROAD

CONC. CURB (TYP.)

BURIED STORM PIPE



SAMET-HARNETT COUNTY PHASE 1					
Name	Skimmer Size	Orifice Dia.	Orifice RAD	Required Basin Volume	Days to Drain
Basin A	2"	1 15/16"	15/16"	9828	3

GENERAL NOTES:

1. FAIRCLOTH SKIMMER® FLOW RATES WERE USED AS THE BASIS OF DESIGN WHEN DETERMINING DRAINAGE CALCULATIONS. UTILIZING A PRODUCT FROM AN ALTERNATIVE MANUFACTURER WILL CREATE A SIGNIFICANT DEVIATION TO THE DESIGN AND MUST BE APPROVED AND RECALCULATED BY THE DESIGN ENGINEER.
2. PROPER ORIFICE OPENING MUST BE SELECTED TO ENSURE POND DRAINS IN CORRECT AMOUNT OF TIME. MODIFICATIONS MAY BE REQUIRED IF FIELD CONDITIONS WARRANT A CHANGE.
3. BARREL PIPE SHOULD BE 1.4 X DEPTH OF THE BASIN TO ENSURE PROPER FUNCTION.

DRAWN BY T. R. EVANS 08/24

FAIRCLOTH SKIMMER® DISCHARGE SYSTEM WITH OUTLET STRUCTURE

FAIRCLOTH SKIMMER
WWW.FAIRCLOTHSKIMMER.COM
TELEPHONE: (910) 732-1244
FAX: (910) 732-1266
EMAIL: SALES@FAIRCLOTHSKIMMER.COM

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER DEQ COMMENT	7/17/25

SAMET HARNETT COUNTY 1

EROSION CONTROL SHEET PHASE–1

ORIGINAL MAP SIZE 24" X 36"

DRAWN: BPE

CHECKED: WPC

PROJECT NO.:

SHEET:

EC1.1

0 25 50 100 Feet

1:50

NOTE

WET BASIN'S UTILIZED AS PART OF A SEDIMENTATION AND EROSION CONTROL PLAN SHALL BE CLEANED OUT TO INCLUDE REMOVAL OF ALL BAFFLES, SEDIMENT AND DEWATERING DEVICES. UPON COMPLETION OF CLEANOUT, POND SLOPES SHALL BE RE-ESTABLISHED AS PER THE PLANS. FOREBAYS SHALL BE INSTALLED AS SHOWN ON THIS SHEET BEFORE PONDS MAY BE UTILIZED FOR STORMWATER TREATMENT.

SEE SHEETS C5.1–C5.11 FOR STANDARD DETAILS

SEE SHEET C2.2 FOR POND CROSS SECTION AND STAGE STORAGE TABLES

EXISTING SPOT ELEVATIONS

EXISTING CONTOURS

FUTURE DEVELOPMENT

ROCK CHECK DAM 1

EX. PROPERTY LINE

PROPOSED INLET PROTECTION SEE SHEET EC 2.0

PROPOSED CURB INLET (TYP.)

DRIVEWAY 1

APPROXIMATE PHASE LIMITS (16 ACRES +/-)

PROPOSED CURB INLET (TYP.)

4' SIDEWALK

PUMP ROOM 105

ELEC 104

PROPERTY LINE

WAREHOUSE 100

OFFICE AREA 101

INSTALL PERMANENT SEEDING IMMEDIATELY UPON REMOVAL OF TEMPORARY DIVERSION AND FINAL GRADING 1

US 301 S

PROPOSED INLET PROTECTION SEE SHEET EC 2.0

FIRE ACCESS LANE

PROPOSED CURB INLET (TYP.)

PROPERTY LINE

DRIVEWAY 2

ASPHALT ROAD

ARROWHEAD ROAD

CONC. ISLAND

CONC. CURB(TYP.)

PROPOSED POND OUTLET STRUCTURE SEE DETAIL SHEET C2.2

PROPOSED STORMWATER POND SEE POND SECTION SHEET C2.2

LEGEND

- CURB INLET–SEE DETAIL SHEET C5.2
- SD — STORM DRAIN PIPE MATERIAL AS DESCRIBED
- HEAVY DUTY ASPHALT PAVEMENT
- HEAVY DUTY CONCRETE PAVEMENT
- STANDARD DUTY ASPHALT PAVEMENT
- PROPOSED SILT FENCE/LOD
- PROPOSED LIMITS OF DISTURBANCE
- PROPOSED INLET PROTECTION

SEQUENCE OF CONSTRUCTION PHASE 2

1. FINALIZE BUILDING PAD INSTALLATION.
2. INSTALL STORMDRAIN INLETS AND PIPE SYSTEMS.
3. REMOVE SEDIMENT, BAFFLES AND SKIMMERS FROM POND AND INSTALL FOREBAY BERMS.
4. INSTALL STORMDRAIN INLET PROTECTION.
5. INSTALL PERMANENT SEED AND MULCH ALONG ALL SLOPES AND AREAS WHERE FINAL GRADING OPERATIONS HAVE BEEN COMPLETED.
6. INSTALL CURB AND GUTTER, SIDEWALKS, PARKING AND DRIVE LANES.
7. STABILIZE REMAINING AREAS AND INSTALL LANDSCAPING.
8. UPON STABILIZATION OF ENTIRE SITE, CONTACT NCDEQ FAYETTEVILLE OFFICE TO REQUEST SITE FINAL INSPECTION.
9. SEE SHEET C2.0–C2.3 FOR STORMDRAIN INSTALLATION.

1 INSTALL PERMANENT SEEDING AND MULCH IN ALL AREAS WHERE FINAL GRADING IS COMPLETE TO ENSURE SLOPES ARE STABILIZED.

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REVISED PER DEQ COMMENT	7/17/25

SAMET HARNETT COUNTY 1

EROSION CONTROL SHEET PHASE-2

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

EC1.2



POND/SEDIMENT BASIN PROFILE (NOT TO SCALE)

STAGE STORAGE TABLE

ELEV	AREA (sq. ft.)	DEPTH (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)	CONIC INC. VOL. (cu. ft.)	CONIC TOTAL VOL. (cu. ft.)
166.00	12,910.49	N/A	N/A	0.00	N/A	0.00
167.00	14,977.94	1.00	13944.21	13944.21	13931.42	13931.42
168.00	17,189.00	1.00	16083.47	30027.69	16070.79	30002.22
169.00	19,543.67	1.00	18366.34	48394.03	18353.75	48355.96
170.00	22,041.95	1.00	20792.81	69186.84	20780.30	69136.26
171.00	24,683.84	1.00	23362.90	92549.74	23350.44	92486.70
172.00	27,469.34	1.00	26076.59	118626.33	26064.19	118550.89
173.00	30,398.45	1.00	28933.89	147560.22	28921.53	147472.42
174.00	33,470.93	1.00	31934.69	179494.91	31922.36	179394.78
175.00	36,639.54	1.00	35055.24	214550.15	35043.30	214438.08
176.00	39,864.71	1.00	38252.13	252802.28	38240.79	252678.87
177.00	43,146.44	1.00	41505.58	294307.85	41494.76	294173.63
178.00	46,484.74	1.00	44815.59	339123.44	44805.22	338978.85
179.00	49,879.59	1.00	48182.16	387305.60	48172.19	387151.05
180.00	53,331.00	1.00	51605.29	438910.90	51595.67	438746.72
181.00	60,403.51	1.00	56867.26	495778.15	56830.57	495577.29
182.00	64,024.61	1.00	62214.06	557992.21	62205.27	557782.57
183.00	67,702.26	1.00	65863.43	623855.65	65854.88	623637.44



TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

POND PROFILE

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
EC1.3



EMERGENCY SPILLWAY
NOT TO SCALE



ELEVATION



EMBEDMENT AND POST DETAIL

GENERAL NOTES:

1. WIRE SHALL BE A MINIMUM OF 32 INCHES AND SHALL BE A MINIMUM OF 14 GAUGE WITH 6"x6" MESH SPACING.
2. FILTER FABRIC SHALL BE A MINIMUM OF 36" IN WIDTH AND SHALL BE FASTENED ADEQUATELY TO THE WIRE AND/OR POST IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATION.
3. STEEL POSTS SHALL BE 4'-0" IN HEIGHT AND BE OF THE SELF FASTENER ANGLE STEEL TYPE.

MAINTENANCE:
1. INSPECT ALL MEASURES AT LEAST WEEKLY AND AFTER EACH RAINFALL OF 1.0 INCH OR GREATER. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUTS.
4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

TEMPORARY SILT FENCE
NOT TO SCALE



SECTION VIEW

TEMPORARY CONSTRUCTION ENTRANCE
NOT TO SCALE

CONSTRUCTION SPECIFICATIONS:
1. CLEAR THE ENTRANCE AREA OF ALL VEGETATION, ROOTS, AND OTHER OBJECTIONABLE MATERIAL AND PROPERLY GRADE IT.
2. PLACE THE GRAVEL TO THE SPECIFIC GRADE AND DIMENSIONS SHOWN ON THE PLANS, AND SMOOTH IT OUT.
3. PROVIDE DRAINAGE TO CARRY WATER TO A SEDIMENT TRAP OR OTHER SUITABLE OUTLET.
4. USE GEOTEXTILE FABRICS IF SUBJECT TO SEEPAGE OR HIGH WATER TABLE.

MAINTENANCE:
1. MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOP-DRESSING WITH 2-INCHES OF #4 STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT IF NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.



TEMPORARY DIVERSION DITCH (TDD)
NOT TO SCALE

NOTES:

1. THE CONTRACTOR SHALL CONSTRUCT THE TEMPORARY DIVERSION DITCHES TO PROVIDE POSITIVE DRAINAGE OF THE DISTURBED AREAS TO THE TEMPORARY SEDIMENT BASINS, AND TO DIVERT DRAINAGE OF UNDISTURBED AREAS AROUND WORK ZONES AS INDICATED.
2. SEE SHEET EC2.1 FOR DETAIL ON EROSION CONTROL MATTING AND ASSOCIATED CALCULATIONS.

MAINTENANCE REQUIREMENTS:

1. INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE THE AREA.



1

FERTILIZER: FERTILIZER SHALL BE APPLIED AT THE RATE OF 500 LB/ACRE OF A 10-10-10 COMMERCIAL FERTILIZER. FERTILIZER SHALL BE APPLIED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION T-901 SEEDING OF THE PROJECT SPECIFICATIONS.

LIME: LIME SHALL BE APPLIED AT THE RATE OF 3,000 LBS/ACRE. LIME SHALL BE APPLIED IN ACCORDANCE WITH SECTION T-901 SEEDING OF THE PROJECT SPECIFICATIONS.

MULCH: MULCH MAY CONSIST OF HAY, STRAW, OR MANUFACTURED MULCH. MULCH SHALL BE EVENLY APPLIED AT THE RATE OF 2 TO 3 TONS PER ACRE TO PROVIDE A LOOSE DEPTH OF 1 ½"-3". MANUFACTURED MULCH SHALL BE APPLIED AT THE RATE AS RECOMMENDED BY THE MANUFACTURER. MULCH SHALL BE APPLIED TO ALL SEEDED AREAS IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION T-908 – MULCHING OF THE SPECIFICATIONS.

MAINTENANCE OF SEEDED AREAS: THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A GOOD STAND OF GRASS OF UNIFORM COLOR AND DENSITY. THE CONTRACTOR SHALL WATER THE SEEDED AREAS AS REQUIRED FOR SEED GERMINATION AND AS REQUIRED TO MAINTAIN AREAS OF ESTABLISHED GRASS. THE CONTRACTOR SHALL MOW GRASS AREAS AND CONTROL THE PRESENCE OF INVASIVE SPECIES AS REQUIRED. CONTRACTOR WILL BE REQUIRED TO RESEED AND MULCH ALL AREAS WHERE SEEDING EMERGENCE IS POOR. ALL AREAS OF EROSION SHALL BE REPAIRED AND RESEEDED AS SOON AS POSSIBLE. CONTRACTOR SHALL PROTECT SEEDED AREAS FROM TRAFFIC AS MUCH AS POSSIBLE.

PERMANENT SEEDING

Seed Mixture	Rate of Application	Planting Dates
Common Bermudagrass (Hulled)	50	March 1 - August 31
Common Bermudagrass (Unhulled)	70	September 1 - February 28

TEMPORARY SEEDING

Rye (Grain) Kobe Lespedeza	120 50	December 1 – April 15
Rye (Grain)	120	August 15 - December 30
Common Bermudagrass (Hulled)	50	March 1 – August 31

TEMPORARY AND PERMANENT SEEDING OPERATIONS



COIR FABRIC BAFFLE INSTALLATION
NOT TO SCALE

NOTES:

1. DRIVE STEEL POST AT LEAST 24" INTO SOLID GROUND.
2. USE STAPLES OR WIRE 1' APART HORIZONTALLY TO SECURELY ATTACH THE COIR FABRIC TO THE TOP WIRE.
3. SPACE THE BAFFLES ACCORDING TO THE APPROVED PLAN.
4. THE FLOOR OF THE BASIN IN THE OUTLET ZONE AND BERMS SHOULD BE SEEDED IMMEDIATELY AFTER THE BASIN IS CONSTRUCTED

MAINTENANCE REQUIREMENTS:

1. INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIREDREPAIRS IMMEDIATELY.
2. BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE,TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
3. REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL, TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES.TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEANOUT, AND REPLACE IF DAMAGED DURING CLEANOUT OPERATIONS. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH.
4. AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED, REMOVE ALL BAFFLE MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, BRING THE AREA TO GRADE, AND STABILIZE IT.

1



MAINTENANCE REQUIREMENTS:

1. INSPECT COIR WATTLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS.
2. REMOVE SEDIMENT AT LEAST WEEKLY AND AFTER EACH RAINFALL OF 1 INCH OR GREATER.
3. MAINTAIN GOOD CONTACT WITH THE GROUND AND PREVENT EROSION FROM OCCURRING BENEATH THE LOGS.
4. REPAIR ANY DAMAGED AREAS OR AREAS NOT IN CLOSE CONTACT WITH THE GROUND.CLEAR DEPOSITS WHEN THEY REACH HALF THE DESIGNED STORAGE DEPTH.

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REWSED PER DEQ COMMENT	7/17/25

SAMET HARNETT COUNTY 1

EROSION AND SEDIMENT CONTROL DETAILS

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
EC2.0

DATE:

PAGE:





Notes:

1. Clear the areas under the embankment and strip of roots and other objectionable material. Delay cleaning the reservoir area until the dam is in place.
2. Cover the foundation area, including the abutments with extra-strength filter fabric before backfilling with rock.
3. If a cutoff trench is required, excavate at center line of dam, extending all the way up the earth abutments. Apply filter fabric under the rockfill embankment from the upstream edge of the dam to the downstream edge of the apron. Overlap fill material a minimum of 1 foot at all joints, with the upstream strip laid over the downstream strip.
4. Construct the embankment with well-graded rock and gravel to the size and dimensions shown on the drawings. It is important that rock abutments be at least 2 feet higher than the spillway crest and at least 1 foot higher than the dam, all the way to the downstream toe, to prevent scour and erosion at the abutments.
5. Sediment-laden water from the construction site should be diverted into the basin reservoir at the furthest area from the dam.
6. Construct the rock dam before the basin area is cleared to minimize sediment yield from construction of the basin.
7. Immediately stabilize all areas disturbed during the construction of the dam except the sediment pool.
8. **Safety- Sediment basins should be considered dangerous because they attract children. Steep side slopes should be avoided. Fences with warning signs may be needed if trespassing is likely. All state and local requirements must be followed.**

Maintenance:

1. Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater.
2. Remove sediment and restore original volume when sediment accumulates to about one-half the design volume.
3. Sediment removed should be placed above the basin and adequately stabilized.
4. Check the structure for erosion, piping, and rock displacement and repair immediately.
5. Remove the structure and any unstable sediment immediately after the construction site has been permanently stabilized.
6. Smooth the basin site to blend with the surrounding area and stabilize.
7. All water and sediment should be removed from the basin prior to dam removal. Sediment should be placed in designated disposal areas and not allowed to flow into streams or drainage ways during structure removal.

NORTH CAROLINA Environmental Quality

SEDIMENT BASIN WITH ROCK DAM

Effective Date: 9/1/2023
in accordance with the 2013 Design Manual Updates

Date:

Page:



NOTE:

1. Other materials providing equivalent protection against erosive velocities may be substituted for use in silt socks or wattles.
2. Fill silt sock/wattle netting uniformly to the desired length such that logs do not deform.
3. Silt sock/ Wattle should be installed parallel to and a minimum of 10 feet beyond the toe of a graded slope. Silt sock/Wattles located below flat areas should be located at the edge of the land disturbance. The ends of the silt sock/wattles should be turned slightly upslope to prevent runoff from going around the ends of the silt sock/wattles.
4. Oak or other durable hardwood stakes with a 2 inch x 2 inch cross section should be driven vertically plumb, through the center of the silt sock/wattle. Stakes should be placed at a maximum interval of 4 feet or a maximum interval of 8 feet if the silt sock/wattle is placed in a 4 inch trench.
5. In the event staking is not possible (ie. when silt socks/wattles are used on pavement) heavy concrete blocks shall be used behind the silt sock/wattle to hold it in place during runoff events.

*THIS APPLICATION MAY NOT BE USED WITH COMPOST SOCKS SMALLER THAN 12".

COMPOST SOCK INITIAL FLOW RATES						
Compost Sock Design Diameter	8 Inch (200 mm)	12 Inch (300 mm)	18 Inch (450 mm)	24 Inch (600 mm)	32 Inch (750 mm)
Maximum Slope Length (<2%)	600 Feet (183 m)	750 Feet (229 m)	1,00 Feet (305 m)	1,300 Feet (305 m)	1,650 Feet (500 m)
Hydraulic Flow Through Rate	7.5 gpm/ft (941 l/min/)	11.3 gpm/ft (141 l/min)	15.0 gpm/ft (188 l/min)	22.5 gpm/ft (281 l/min)	30.0 gpm/ft (374 l/min)

MAINTENANCE:

1. Inspect Silt sock/wattle weekly and after each rain of 1 inch or greater. Remove accumulated sediment and any debris as needed to allow for adequate flow.
2. Silt sock/Wattle must be replaced if clogged or torn.
3. If ponding becomes excessive, the silt sock/wattle may need to be replaced with a larger diameter or a different measure.
4. Reinstall if damaged or dislodged.
5. Silt socks/Wattles shall be inspected until land disturbance is compete and the area above the measure has been permanently stabilized.

NORTH CAROLINA Environmental Quality

EFFECTIVE DATE: 11/12/2020

SILT SOCK / WATTLE FOR PERIMETER AND INLET PROTECTION

NOTE: MINIMUM H=2/3 PIPE DIAMETER

SECTION B-B

RIP RAP OUTLET PROTECTION

NOTES:

1. 5' W X 6' L, 9" THICK CLASS B RIP RAP.
2. RIPRAP SHOULD EXTEND UP BOTH SIDES OF THE APRON AND AROUND THE END OF THE PIPE OR CULVERT AT THE DISCHARGE OUTLET AT A MAXIMUM SLOPE OF 2:1 AND A HEIGHT NOT LESS THAN TWO THIRDS THE PIPE DIAMETER OR CULVERT HEIGHT.
3. THERE SHALL BE NO OVERFLOW FROM THE END OF THE APRON TO THE SURFACE OF THE RECEIVING CHANNEL. THE AREA TO BE PAVED OR RIPRAPPED SHALL BE UNDERCUT SO THAT THE INVERT OF THE APRON SHALL BE AT THE SAME GRADE (FLUSH) WITH THE SURFACE OF THE RECEIVING CHANNEL. THE APRON SHALL HAVE A CUTOFF OR TOE WALL AT THE DOWNSTREAM END.
4. THE WIDTH OF THE END OF THE APRON SHALL BE EQUAL TO THE BOTTOM WIDTH OF THE RECEIVING CHANNEL. MAXIMUM TAPER TO RECEIVING CHANNEL 5:1
5. ALL SUBGRADE FOR STRUCTURE TO BE COMPACTED TO 95% OR GREATER.
6. THE PLACING OF FILL, EITHER LOOSE OR COMPACTED IN THE RECEIVING CHANNEL SHALL NOT BE ALLOWED.
7. NO BENDS OR CURVES IN THE HORIZONTAL ALIGNMENT OF THE APRON WILL BE PERMITTED.
8. RIP RAP APRON SHALL BE EXTENDED AS POND EXCAVATION CONTINUES AND DEPTH INCREASES.

RIPRAP PIPE OUTLET PROTECTION

NOT TO SCALE

1

Temporary Diversion Calculations

Drain Area	C	i	A	Flow (cfs)
A	0.45	7.94	2.75	9.82575
B	0.45	7.94	0.9	3.2157
C	0.45	7.94	5.82	20.79486

Temporary Diversion	Length(ft)	Depth(ft)	Slope	V(ft/s)	Vp(ft/s) Bare Soil	Liner Required
A	703	1.5	0.007	6.198	2.000	Y; V>Vp
B	514	1.5	0.010	7.249	2.000	Y; V>Vp
C	737	1.5	0.007	6.054	2.000	Y; V>Vp

Design Check

Temporary Diversion	Length(ft)	Depth(ft)	Slope	V(ft/s)	Tc(lb/ft^2)	Liner Used
A	703	1.5	0.007	5.635	0.666	RECP
B	514	1.5	0.010	6.590	0.911	RECP
C	737	1.5	0.007	6.054	0.635	RECP

Permissible Unit Shear Stress Double Coconut RECP-2.0 (lb/ft2)

max. Shear Stress Allowed	
2	TRUE
2	TRUE
2	TRUE

Equations

$V(ft/s) = \frac{(1.49/n)xR_h^{.67}xS^{.5}}{}$

$T_c = Y_XDxS$

n= 0.02; .033

Diversion Dimensions (Minimum)

Depth	Bottom Width	Side Slope
1.5	2	2:1

1

Attachment 1
Samet - Harnett Ph1
Skimmer Basin Calculations
10y SMIN storm

Sedimentation and Erosion Control
Peak Flow (10yr, 5min)

Q10=CiA	36.8019	
i	7.94	10yr 5min storm
Acreage	10.3	
Mannings	0.45	

Requirements:		
Min. Volume (1,800 cf/Ac.)	18,540	cf
Min. Surface Area (325sf/cfs)	11,961	sf

ELEV	AREA (sq. ft.)	DEPTH (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)	
166	12,910	0			
167	14,977	1	13,944	13,944	
168	17,189	1	16,083	30,028	
169	19,543	1	18,366	48,394	
170	22,041	1	20,793	69,184	
171	24,683	1	23,363	92,549	
172	27,469	1	26,077	118,626	
173	30,398	1	28,934	147,560	
174	33,470	1	31,935	179,495	
175	36,639	1	35,055	214,550	
176	39,864	1	38,252	252,802	
177	43,146	1	41,506	294,308	
178	46,484	1	44,816	339,123	Skimmer Discharge Elevation
179	49,879	1	48,182	387,306	
180	53,331	1	51,605	438,911	Primary Spillway Elevation
181	60,403	1	56,867	495,778	
182	64,024	1	62,214	557,992	
183	67,702	1	65,863	623,856	

Spillway Information

Skimmer Elevation:	178.00	
Primary Spillway	182.00	
Proposed Sediment Storage Elevation:	170.00	
Volume at Proposed Elevation:	69,184	cf
Surface Area at Proposed Elevation:	22,041	sf

Skimmer Design:

Volume:	18,540	cf
Days to Drain:	3	
Skimmer Size(faircloth guidelines):	2	in
Orifice Size (Dia.):	2.4	in

Spillway Check

Weir Flow	Qprovided (cfs)	Q10 (cfs)
Q=CLH^1.5	122.3520127	>19.51
C	3.33	
L	20	ft
H	1.5	ft

Date:

Page:



NOTES:

1. Hardware cloth and gravel should overlay the silt fence at least 12 inches.
2. Stone outlets should be placed on low elevation areas of silt fence and based on field conditions.

MAINTENANCE:

1. Per NCG-01, inspect outlet at lest once a week and after each 1 inch or greater rainfall event. Complete any required repairs immediately. Freshen stone when sediment accumulation exceeds 6 inches. Keep mesh free of debris to provide adequate flow.
2. Remove sediment when half of stone outlet is covered.
3. Replace stone as needed to facilitate de-watering.

NORTH CAROLINA Environmental Quality

EFFECTIVE DATE: 11/12/2020

SILT FENCE OUTLET

Date:

Page:



NOTES:

1. Lime, fertilize and seed before installation. Planting of shrubs, trees, etc. should occur after installation.
2. Slope surface shall be smooth before placement for proper soil contact.
3. Design velocities exceeding 2 feet/second require temporary blankets, mats or similar liners to protect seed and soil until vegetation becomes established.
4. Terminal anchor trenches are required at RECP ends and intermittent check slots must be constructed across channels at 25 foot intervals.
5. Terminal anchor trenches should be a minimum of 12 inches in depth and 6 inches in width. Intermittent check slots should be 6 inches deep and 6 inches wide.
6. For installation on a slope, place RECP 2-3 feet over the top of the slope and into an excavated end trench measuring approximately 12 inches deep by 6 inches wide. Pin the RECP at 1 foot intervals along the bottom of the trench, backfill and compact. Unroll the RECP down the slope maintaining direct contact between the soil and RECP. Pin using staples or pins in a 3 feet center-to-center pattern.
7. 11 gauge, at least 6 inch by 1 inch staples or 12 inch minimum length wooden stakes are recommended for anchoring.
8. Grass-lined channels with design velocities exceeding 6 feet/second should include turf reinforcement mats
9. Check slots to be constructed per manufacturers specifications.
10. Staking or stapling layout per manufacturers specification.
11. If there is a berm at the top of slope, anchor upslope of the berm.
12. Do not stretch blankets/matting tight, allow the rolls to conform to any irregularities.
13. For slopes less than 3H:1V, rolls may be placed in horizontal strips.

MAINTENANCE:

1. Inspect Rolled Erosion Control Products at least weekly and after each rain of 1 inch or greater; repair immediately.
2. Good contact with the ground must be maintained, and erosion must not occur beneath the RECP.
3. Any areas of the RECP that are damaged or not in close contact with the ground shall be repaired and stapled.
4. If erosion occurs due to poorly controlled drainage, the problem shall be fixed and the eroded area protected.
5. Monitor and repair the RECP as necessary until ground cover is established.

NORTH CAROLINA Environmental Quality

EFFECTIVE DATE: 11/12/2020

ROLLED EROSION CONTROL PRODUCTS (RECP)

EAST COAST erosion control

Proud Member and Participant of:
www.eastcoasterosion.com
443 Bricker Road, Bernville, PA 19506
1.800.582.4005 +1.610.488.8496 Fax +1.610.488.8494

Material and Performance Specification

ECC-2™ Double Net Coconut Rolled Erosion Control Product

Description:
The ECC-2™ is made with uniformly distributed 100% coconut fiber and two polypropylene nets securely sewn together with UV stabilized thread. The lightly compressed blankets are wrapped and include a product label, code and installation guide. The blankets are palletized for easy transportation.
The ECC-2™ has functional longevity of approximately 36 months, but will vary depending on soil and climatic conditions, and is suitable for slopes 1:1 and medium to high flow channels. The ECC-2™ meets Type 4.B specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) RP-03 Section 713.17.

Matrix:	1	2
	100% Coconut	N/A

Netting:	Type	Net Color
	Top: Medium weight UV Stabilized Polypropylene	Black
	Middle: None	
	Bottom: Medium weight UV Stabilized Polypropylene	

Net Opening:	Top	Middle	Bottom
	0.75" x 0.75"	N/A	0.75" x 0.75"

Thread:	Type	Color
	UV Stabilized Thread	Black

Roll Sizes:	Standard		"A" Size		Mega	
Width:	8 ft	2.4 m	4.00 ft	1.2 m	16 ft	4.9 m
Length:	112.5 ft	34.3 m	225 ft	68.6 m	112.5 ft	34.3 m
Weight*:	57 lbs	25.9 kg	57 lbs	25.9 kg	114 lbs	51.7 kg
Area:	100 yd^2	83.6 m^2	100 yd^2	83.6 m^2	200 yd^2	167.2 m^2
Rolls/Pallet:	25		9		25	

*Weight at time of manufacturing.

Index Value Properties*:

Property	Test Method	Typical
Mass/Unit Area	ASTM D6475	8.30 oz/yd^2 281.4 g/m2
Thickness	ASTM D6525	0.26 in 6.60 mm
Tensile Strength-MD	ASTM D6818	265.00 lb/ft 3.79 kN/m
Elongation-MD	ASTM D6818	20 %
Tensile Strength-TD	ASTM D6818	175.00 lb/ft 2.55 kN/m
Elongation-TD	ASTM D6818	23.0 %
Light Penetration	ASTM D6567	16 %
Density (Specific Gravity	ASTM D792	N/A g/cm^3
Water Absorption	ASTM D1117	382 %

*May differ depending upon raw material variations

Slope Performance Design Values*:

Property	Test Method	Value	
C-Factors	ASTM D6459		0.01
Slope Length (L)	≤ 3:1	3:1-2:1	≥ 2:1
< 50 ft (15 m)	0.005	0.015	0.065
50 ft – 100 ft	0.013	0.030	0.078
>100 ft (30 m)	0.022	0.045	0.082

*Large-Scale Results obtained by 3rd Party GAI Accredited Independent Laboratory

Bench-Scale Testing* (NTPEP**):**

Test Method	Parameters	Results
ECTC Method 2 Rainfall	50mm (2in) / hr-30 min	SLR**=0.45
	100mm (4in) / hr-30 min	SLR**=10.43
	150mm (6in) / hr-30 min	SLR**=12.30
ECTC Method 3 Shear Resistance	Shear at .50 in soil loss	2.59lb/ft^2
ECTC Method 4 Germination	Top soil, Fescue; 21 day incubation	772 %

*Bench scale tests should not be used for design purposes.
**Soil Loss Ratio=Soil Loss Bare Soil/Soil Loss with RECP=1/C-Factor
***The preceding test data excerpts were reproduced with the permission of AASHTO, however, this does not constitute endorsement or approval of the product, material or device by AASHTO

Channel Performance Design Values*:

Property	Test Method	Value		
Unvegetated Shear Stress	ASTM D 6460	2.50	lbs/ft^2	119.70 Pa
Unvegetated Velocity	ASTM D 6460	13.0	ft/s	3.05 m/s
Vegetated Shear Stress	NA	N/A	lbs/ft^2	N/A Pa
Vegetated Velocity	NA	N/A	ft/s	N/A m/s
Manning's n (Value Represents a Range)		0.025		

*Large-Scale Results obtained by 3rd Party GAI Accredited Independent Laboratory

The values presented are for guidance purposes and do not constitute the practice of engineering. East Coast Erosion Blankets LLC (ECEB) guarantees that at the time of manufacture, our materials meet published specifications and are free from defects in material and workmanship. ECEB's responsibility for any product found to be defective in material or workmanship prior to installation, shall be limited to, at its option, replacement or credit for the purchase price. ECEB will not be held liable for any type of damage or losses, directly or indirectly for failure of the product. Correct erosion control practices are always the responsibility of the user.

Revised 10/01/2020

TC2
ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE
1	REWSED PER DEQ COMMENT	7/17/25

SAMET HARNETT COUNTY 1

EROSION AND SEDIMENT CONTROL DETAILS

ORIGINAL MAP SIZE
24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

EC2.1

PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un-attended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

(a) This General Permit as well as the Certificate of Coverage, after it is received.

(b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that Must be Reported

Permittees shall report the following occurrences:

(a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if:

- They are 25 gallons or more,
- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or
- They are within 100 feet of surface waters (regardless of volume).

(c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

(e) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	• ***Within 24 hours***, an oral or electronic notification. • ***Within 7 calendar days***, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	• ***Within 24 hours***, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	• ***A report at least ten days before the date of the bypass, if possible***. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	• ***Within 24 hours***, an oral or electronic notification. • ***Within 7 calendar days,*** a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41(l)(7)]	• ***Within 24 hours***, an oral or electronic notification. • ***Within 7 calendar days***, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)(6). • Division staff may waive the requirement for a written report on a case-by-case basis.

PART II, SECTION G, ITEM (4)
DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

(a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
(b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
(c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
(d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
(e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
(f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

DATE | REVISION | NO.

SAMET HARNETT COUNTY 1

EROSION AND SEDIMENT CONTROL DETAILS

PRELIMINARY

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:

EC2.2

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes

Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
• Temporary grass seed covered with straw or other mulches and tackifiers • Hydroseeding • Rolled erosion control products with or without temporary grass seed • Appropriately applied straw or other mulch • Plastic sheeting	• Permanent grass seed covered with straw or other mulches and tackifiers • Geotextile fabrics such as permanent soil reinforcement matting • Hydroseeding • Shrubs or other permanent plantings covered with mulch • Uniform and evenly distributed ground cover sufficient to restrain erosion • Structural methods such as concrete, asphalt or retaining walls • Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

1. Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
3. Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
4. Provide ponding area for containment of treated Stormwater before discharging offsite.
5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

1. Maintain vehicles and equipment to prevent discharge of fluids.
2. Provide drip pans under any stored equipment.
3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

1. Never bury or burn waste. Place litter and debris in approved waste containers.
2. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
4. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
5. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
6. Anchor all lightweight items in waste containers during times of high winds.
7. Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
8. Dispose waste off-site at an approved disposal facility.
9. On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
3. Contain liquid wastes in a controlled area.
4. Containment must be labeled, sized and placed appropriately for the needs of site.
5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

1. Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
2. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
3. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
2. Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
3. Provide stable stone access point when feasible.
4. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS

1. Do not discharge concrete or cement slurry from the site.
2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
3. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
4. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
6. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
7. Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
9. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

1. Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
2. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
3. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
4. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

1. Create designated hazardous waste collection areas on-site.
2. Place hazardous waste containers under cover or in secondary containment.
3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

TC2 ENGINEERING, PLLC
201 N. Front Street
Suite M-108
Wilmington, NC 28401
910-547-5856

NO.	REVISION	DATE

SAMET HARNETT COUNTY 1

EROSION AND SEDIMENT CONTROL DETAILS

PRELIMINARY

ORIGINAL MAP SIZE 24" X 36"
DRAWN: BPE
CHECKED: WPC
PROJECT NO.:

SHEET:
EC2.3

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

EXTERIOR FINISH SCHEDULE

MARK	FINISH	MANUFACTURER / COLOR
F1	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / SIMPLE WHITE SW 7021
F2	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / ANEW GRAY SW 7030
F3	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F4	STOREFRONT	TBD
F5	HOLLOW METAL DOORS & FRAMES PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F6	CANOPY	TBD
F7	COPING/GUTTERS/DOWNSPOUTS	FACTORY FINISH
F8	STEEL PIPE BOLLARD PRO INDUSTRIAL WATERBASED ALKYD (SEMI-GLOSS)	SHERWIN WILLIAMS / OSHA YELLOW
F9	LADDERS / STAIRS / PIPE AND TUBE RAILING	NO PAINT
F10	DOCK DOORS	PREFINISHED - TBD
F11	DOCK LEVELERS	NO PAINT - LABEL AS REQUIRED
F12	EXTERIOR EXPOSED GAS PIPING	PAINT

NOTES:
1. ALL REVEALS TO BE PAINTED SAME AS ADJACENT FIELD COLOR (ABOVE OR BELOW) - MAINTAIN CONSISTENCY AROUND BUILDING.

PAINT SPECIFICATIONS

INTERIOR

PROVIDE SHERWIN WILLIAMS OR APPROVED EQUAL

WALLS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

WALLS - CMU:
1 COAT: SHERWIN WILLIAMS: PREPRITE INTERIOR / EXTERIOR BLOCK FILLER
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

CEILIINGS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (FLAT)

HM DOORS / HM FRAMES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

EXTERIOR

PRE-CAST PANELS:
1 COAT: SHERWIN WILLIAMS: LOXON CONCRETE & MASONRY PRIMER
2 COATS: SHERWIN WILLIAMS: MEDIUM TEXTURE

ACCENTS:
2 COATS: SHERWIN WILLIAMS: A-100 EXTERIOR ACRYLIC LATEX (SATIN)

BOLLARDS / DOWNSPOUT PROTECTOR PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

DOCK SILLS & DRIVE-IN DOOR ANGLE PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC PRIMER / FINISH (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC (SEMI-GLOSS)

MECHANICAL EDGE OF DOCK LEVELER:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

REVEAL PROFILE

TYPE	DESCRIPTION	GRAPHIC
VERTICAL	1-1/2" X 3/4"	
HORIZONTAL	3-1/2" X 3/4"	



KEY PLAN

PAINT SCHEDULE

EXTERIOR

EXTERIOR STRUCTURAL / MISCELLANEOUS STEEL/ HOLLOW METAL ITEMS (HOLLOW METAL DOOR AND WINDOW FRAMES, BOLLARDS, LINTELS, EXPOSED GAS PIPING, WELD CONNECTIONS, STEEL EMBEDS, ETC.)
ALKYD SYSTEM
CLEAN/ SPOT PRIME, WHERE REQUIRED: UNIVERSAL METAL PRIMER
FIRST COAT: INDUSTRIAL ALKYD ENAMEL
FINAL COAT: INSUSTRIAL ALKYD ENAMEL (GLOSS)

EXTERIOR CONCRETE WALL PANELS:
"ULTRA-CRETE" OR "ELASTOMERIC" SYSTEM
PRESSURE WASH: COMPLETE EXTERIOR OF BUILDING TO BE PRESSURE WASHED PRIOR TO APPLICATION OF PRIMER.
PRIME COAT: COMPATIBLE WITH FINAL FINISH COAT (LOXON PRIMER)
FINAL COAT: MEDIUM TEXTURE

INTERIOR

STRUCTURAL / MISCELLANEOUS/ HOLLOW METAL STEEL ITEMS: (HOLLOW METAL DOOR AND WINDOW FRAMES, BOLLARDS, WELD CONNECTIONS AND EMBEDS, ETC.)

GALVANIZED - METAL SUBSTRATES: (INCLUDES GALVANIZED STEEL ITEMS AND EXPOSED GALVANIZED METAL DUCT)
LATEX SYSTEM
CLEAN: DEGREASE SUBSTRATE PRIOR TO PRIMER APPLICATION
PRIME COAT: DTM ACRYLIC PRIMER / FINISH
INTERMEDIATE COAT: DTM ACRYLIC COATING (GLOSS)
FINAL COAT: DTM ACRYLIC COATING (GLOSS)

CONCRETE BLOCK:
LATEX SYSTEM
PRIME COAT: HEAVY DITY BLOCK FILLER
INTERMEDIATE COAT: INTERIOR ALKYD MATCING FINALCOAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

WOOD SUBSTRATES: (PLYWOOD, TRIM, WOOD / COMPOSITE PANELED DOORS, WHERE SCHEDULED, SHELVING, ETC.)
ALKYD SYSTEM
PRIME COAT: INTERIOR ALKYD PRIMER / SEALER
INTERMEDIATE COAT: INTERIOR ALKYD MATCHING FINAL COAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

GYPSUM BOARD SUBSTRATES:
LATEX SYSTEM
PRIME COAT: INTERIOR LATEX PRIMER/ SEALER
INTERMEDIATE COAT: INTERIOR LATEX MATCHING FINAL COAT
FINAL COAT: INTERIOR LATEX (FLAT) FOR CEILINGS, SOFFITS OR BULKHEADS, EGGSHELL FOR VERITCAL SURFACES.

ELEVATION KEYNOTES

1. TILT-UP CONCRETE WALL PANEL (PAINT)
2. ALUMINUM ENTRY WITH INSULATED GLASS - SEE SHEET A600
3. ALUMINUM STOREFRONT WITH INSULATED GLASS - SEE SHEET A600
4. PRE-ENGINEERED AND PREFINISHED METAL CANOPY
5. 6'-0" x 5'-0" HIGH ALUM. FRAME CLEARSTORY WINDOW @ 21'-0" A.F.F.
6. 6'-0" x 5'-0" KNOCK-OUT PANEL @ 21'-0" A.F.F.
7. 6'-0" x 7'-0" HIGH KNOCK-OUT PANEL
8. 6'-0" x 8'-11" HIGH KNOCK-OUT PANEL
10. HOLLOW METAL DOOR AND FRAME (PAINT)
11. 24 GA. PREFINISHED METAL COPING
12. PREFINISHED 8" W. x 6" H. METAL GUTTER"
13. PREFINISHED 5" x 5" METAL DOWNSPOUT"
14. DOWNSPOUT GUARD - SEE A1/A501 & B1/A501 NO PAINT IF GALVANIZED, IF NOT, MATCH ADJACENT WALL FINISH.
15. GALVANIZED STEEL STAIR
16. GALVANIZED STEEL STAIR WITH AREA OF ASSISTED RESCUE
18. STEEL PIPE BOLLARD (PAINT)
19. 9'-0" x 10'-0" INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
20. PIT LEVELER (REFER TO SAMET STANDARDS)
21. 9'-0" x 12'-2" HIGH KNOCK-OUT PANEL
22. 14' x 16' INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
23. 14'-0" x 16'-0" HIGH KNOCK-OUT PANEL
24. GALVANIZED METAL ROOF ACCESS LADDER TO COMPLY WITH 2018 NCBC, OSHA # 1910.28 & IMC SEC. 306.5 (SEE DET. C1/A500)
25. EDGE OF DOCK LEVELER (REFER TO SAMET STANDARDS)
26. 6'-0" x 5'-0" HIGH ALUM. FRAME CLERESTORY WINDOW @ 25'-10" A.F.F.
27. 6'-0" x 5'-0" LOUVER. SEE MECH DWG'S FOR MORE INFORMATION



B1 EAST ELEVATION
1" = 20'-0"



B3 WEST ELEVATION
1" = 20'-0"



C1 SOUTH ELEVATION
1" = 20'-0"



A1 NORTH ELEVATION
1" = 20'-0"

triaddesigngroup
Architecture | Engineering | Interior Design

4807 Koger Boulevard Suite C
Greensboro, NC 27407
Telephone 336-218-8282

8430 University Executive
Park Drive Suite 650
Charlotte, NC 28262
Telephone 704-312-0140
www.triad-designgroup.com

NC Architecture Reg. 50709
NC Engineering Lic. C-1108

TRIAD DESIGN GROUP CORPORATE P.C. SEAL NORTH CAROLINA 1994

PRELIMINARY

NOT ISSUED FOR CONSTRUCTION

This drawing, and the details herein, as an instrument of service, is the property of Triad Design Group, PC. It may be used only for this specific project, and shall not be loaned, copied, or reproduced in any form without expressed written consent from Triad Design Group, PC. Copyright 2025. Triad Design Group, PC, All rights reserved.

Triad Design Group, PC, shall not be responsible for construction means, methods, techniques, or procedures utilized by the contractor, nor for the safety of public or contractors' employees; nor for the failure of the contractor to carry out the work in accordance with the contract documents.

SAMET

Harnett 95 Industrial Center

SPEC BUILDING 1

US 301 S.
Dunn, North Carolina

SUBMITTALS:

DATE	DESCRIPTION
2025-05-23	90% REVIEW

REVISIONS:

NO	DATE	DESCRIPTION

SHEET TITLE:

EXTERIOR ELEVATIONS

DATE: DATE
DRAWN: LWM | CHECKED: MTM
JOB NUMBER: 25-009
SHEET:

A200

5/23/2025 2:57:04 PM

PAINT SCHEDULE

EXTERIOR

EXTERIOR GALVANIZED - METAL SUBSTRATES:
LATEX SYSTEM,
CLEAN: DEGREASE SUBSTRATE PRIOR TO PRIMER APPLICATION
PRIME COAT: DTM ACRYLIC PRIMER / FINISH
INTERMEDIATE COAT: DTM ACRYLIC COATING (GLOSS)
FINAL COAT: DTM ACRYLIC COATING (GLOSS)

EXTERIOR STRUCTURAL / MISCELLANEOUS STEEL/ HOLLOW METAL ITEMS (HOLLOW METAL DOOR AND WINDOW FRAMES, BOLLARDS, LINTELS, LADDERS, EXPOSED GAS PIPING, WELD CONNECTIONS, STEEL EMBEDS, ETC.)
ALKYD SYSTEM
CLEAN/ SPOT PRIME: WHERE REQUIRED: UNIVERSAL METAL PRIMER
FIRST COAT: INDUSTRIAL ALKYD ENAMEL
FINAL COAT: INSUSTRIAL ALKYD ENAMEL (GLOSS)

EXTERIOR CONCRETE WALL PANELS:
"ULTRA-CRETE" OR "ELASTOMERIC" SYSTEM
PRESSURE WASH: COMPLETE EXTERIOR OF BUILDING TO BE PRESSURE WASHED PRIOR TO APPLICATION OF PRIMER.
PRIME COAT: COMPATIBLE WITH FINAL FINISH COAT (LOXON PRIMER)
FINAL COAT: MEDIUM TEXTURE

INTERIOR

STRUCTURAL / MISCELLANEOUS/ HOLLOW METAL STEEL ITEMS: (HOLLOW METAL DOOR AND WINDOW FRAMES, COLUMNS, BOLLARDS, RAILINGS, LINTELS, LADDERS, STAIRS, DOCK LEVELERS, WELD CONNECTIONS AND EMBEDS, ETC.)

GALVANIZED - METAL SUBSTRATES: (INCLUDES GALVANIZED STEEL ITEMS AND EXPOSED GALVANIZED METAL DUCT)
LATEX SYSTEM
CLEAN: DEGREASE SUBSTRATE PRIOR TO PRIMER APPLICATION
PRIME COAT: DTM ACRYLIC PRIMER / FINISH
INTERMEDIATE COAT: DTM ACRYLIC COATING (GLOSS)
FINAL COAT: DTM ACRYLIC COATING (GLOSS)

CONCRETE BLOCK:
LATEX SYSTEM
PRIME COAT: HEAVY DITY BLOCK FILLER
INTERMEDIATE COAT: INTERIOR ALKYD MATCING FINALCOAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

WOOD SUBSTRATES: (PLYWOOD, TRIM, WOOD / COMPOSITE PANELED DOORS, WHERE SCHEDULED, SHELVING, ETC.)
ALKYD SYSTEM
PRIME COAT: INTERIOR ALKYD PRIMER / SEALER
INTERMEDIATE COAT: INTERIOR ALKYD MATCHING FINAL COAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

GYPSUM BOARD SUBSTRATES:
LATEX SYSTEM
PRIME COAT: INTERIOR LATEX PRIMER/ SEALER
INTERMEDIATE COAT: INTERIOR LATEX MATCHING FINAL COAT
FINAL COAT: INTERIOR LATEX (FLAT) FOR CEILINGS, SOFFITS OR BULKHEADS, EGGSHELL FOR VERITCAL SURFACES.

REVEAL PROFILE

TYPE	DESCRIPTION	GRAPHIC
VERTICAL	1-1/2" X 3/4"	
HORIZONTAL	3-1/2" X 3/4"	

ELEVATION KEYNOTES

1. TILT-UP CONCRETE WALL PANEL (PAINT)
2. ALUMINUM ENTRY WITH INSULATED GLASS - SEE SHEET A600
3. ALUMINUM STOREFRONT WITH INSULATED GLASS - SEE SHEET A600
4. PRE-ENGINEERED AND PREFINISHED METAL CANOPY
5. 6'-0" x 5'-0" HIGH ALUM. FRAME CLEARSTORY WINDOW @ 21'-0" A.F.F.
6. 6'-0" x 5'-0" KNOCK-OUT PANEL @ 21'-0" A.F.F.
7. 6'-0" x 7'-0" HIGH KNOCK-OUT PANEL
8. 6'-0" x 8'-11" HIGH KNOCK-OUT PANEL
10. HOLLOW METAL DOOR AND FRAME (PAINT)
11. 24 GA. PREFINISHED METAL COPING
12. PREFINISHED 8" W. x 6" H. METAL GUTTER"
13. PREFINISHED 5" x 5" METAL DOWNSPOUT"
14. DOWNSPOUT GUARD - SEE A1/A501 & B1/A501 NO PAINT IF GALVANIZED, IF NOT, MATCH ADJACENT WALL FINISH.
15. GALVANIZED STEEL STAIR
16. GALVANIZED STEEL STAIR WITH AREA OF ASSISTED RESCUE
18. STEEL PIPE BOLLARD (PAINT)
17. 9'-0" x 10'-0" INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
20. PIT LEVELER (REFER TO SAMET STANDARDS)
21. 9'-0" x 12'-2" HIGH KNOCK-OUT PANEL
22. 14' x 16' INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
23. 14'-0" x 16'-0" HIGH KNOCK-OUT PANEL
24. GALVANIZED METAL ROOF ACCESS LADDER TO COMPLY WITH 2018 NCBC, OSHA # 1910.28 & IMC SEC. 306.5 (SEE DET. C1/A500)
25. EDGE OF DOCK LEVELER (REFER TO SAMET STANDARDS)
26. 6'-0" x 5'-0" HIGH ALUM. FRAME CLERESTORY WINDOW @ 25'-10" A.F.F.
27. 6'-0" x 5'-0" LOUVER. SEE MECH DWG'S FOR MORE INFORMATION



D1 NORTH ELEVATION AREA 'A'
1/16" = 1'-0"



C1 NORTH ELEVATION AREA 'B'
1/16" = 1'-0"



B1 SOUTH ELEVATION AREA 'A'
1/16" = 1'-0"



A1 SOUTH ELEVATION AREA 'B'
1/16" = 1'-0"

PAINT SPECIFICATIONS

INTERIOR — PROVIDE SHERWIN WILLIAMS OR APPROVED EQUAL

WALLS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

WALLS - CMU:
1 COAT: SHERWIN WILLIAMS: PREPRITE INTERIOR / EXTERIOR BLOCK FILLER
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

CEILINGS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (FLAT)

HM DOORS / HM FRAMES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

EXTERIOR

PRE-CAST PANELS:
1 COAT: SHERWIN WILLIAMS: LOXON CONCRETE & MASONRY PRIMER
2 COATS: SHERWIN WILLIAMS: MEDIUM TEXTURE

ACCENTS:
2 COATS: SHERWIN WILLIAMS: A-100 EXTERIOR ACRYLIC LATEX (SATIN)

BOLLARDS / DOWNSPOUT PROTECTOR PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

DOCK SILLS & DRIVE-IN DOOR ANGLE PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC PRIMER / FINISH (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC (SEMI-GLOSS)

MECHANICAL EDGE OF DOCK LEVELER:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

EXTERIOR FINISH SCHEDULE

MARK	FINISH	MANUFACTURER / COLOR
F1	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / SIMPLE WHITE SW 7021
F2	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / ANEW GRAY SW 7030
F3	CONCRETE WALL PANELS ELASTOMETRIC PAINT (TEXTURE)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F4	STOREFRONT	TBD
F5	HOLLOW METAL DOORS & FRAMES PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F6	CANOPY	TBD
F7	COPING/GUTTERS/DOWNSPOUTS	FACTORY FINISH
F8	STEEL PIPE BOLLARD PRO INDUSTRIAL WATERBASED ALKYD (SEMI-GLOSS)	SHERWIN WILLIAMS / OSHA YELLOW
F9	LADDERS / STAIRS / PIPE AND TUBE RAILING	NO PAINT
F10	DOCK DOORS	PREFINISHED - TBD
F11	DOCK LEVELERS	NO PAINT - LABEL AS REQUIRED
F12	EXTERIOR EXPOSED GAS PIPING	PAINT

NOTES:
1. ALL REVEALS TO BE PAINTED SAME AS ADJACENT FIELD COLOR (ABOVE OR BELOW) - MAINTAIN CONSISTENCY AROUND BUILDING.

triaddesigngroup
Architecture | Engineering | Interior Design

4807 Koger Boulevard Suite C
Greensboro, NC 27407
Telephone 336-218-8282

8430 University Executive
Park Drive Suite 650
Charlotte, NC 28262
Telephone 704-312-0140
www.triad-designgroup.com

NC Architecture Reg. 50709
NC Engineering Lic. C-1108

TRIAD DESIGN GROUP CORPORATE P.C. SEAL NORTH CAROLINA 1994

PRELIMINARY

NOT ISSUED FOR CONSTRUCTION

This drawing, and the details herein, as an instrument of service, is the property of Triad Design Group, PC. It may be used only for this specific project, and shall not be loaned, copied, or reproduced in any form without expressed written consent from Triad Design Group, PC. Copyright 2025. Triad Design Group, PC, All rights reserved.

Triad Design Group, PC, shall not be responsible for construction means, methods, techniques, or procedures utilized by the contractor, nor for the safety of public or contractors' employees; nor for the failure of the contractor to carry out the work in accordance with the contract documents.

SAMET

Harnett 95 Industrial Center
SPEC BUILDING 1
US 301 S.
Dunn, North Carolina

SUBMITTALS:

DATE	DESCRIPTION
2025-05-23	90% REVIEW

REVISIONS:

NO	DATE	DESCRIPTION

SHEET TITLE:
PARTIAL ELEVATIONS

DATE: DATE
DRAWN: LWM | CHECKED: MTM
JOB NUMBER: 25-009
SHEET:
A201

5/23/2025 2:57:10 PM



D2 ENLARGED ELEVATION CENTER ENTRANCE
1/8" = 1'-0"



B2 ENLARGED ELEVATION @ CORNER ENTRY
1/8" = 1'-0"



B4 ENLARGED ELEVATION @ SIDE WALL
1/8" = 1'-0"



A1 ENLARGED ELEVATION @ PERSONNEL DOOR
1/8" = 1'-0"



A3 ENLARGED ELEVATION @ DOCK WALL
1/8" = 1'-0"

PAINT SCHEDULE

EXTERIOR

EXTERIOR GALVANIZED - METAL SUBSTRATES:
LATEX SYSTEM,
CLEAN: DEGREASE SUBSTRATE PRIOR TO PRIMER APPLICATION
PRIME COAT: DTM ACRYLIC PRIMER / FINISH
INTERMEDIATE COAT: DTM ACRYLIC COATING (GLOSS)
FINAL COAT: DTM ACRYLIC COATING (GLOSS)

EXTERIOR STRUCTURAL / MISCELLANEOUS STEEL/ HOLLOW METAL ITEMS (HOLLOW METAL DOOR AND WINDOW FRAMES, BOLLARDS, RAILINGS, LINTELS, LADDERS, STAIRS, DOCK LEVELERS, EXPOSEDE GAS PIPING, WELD CONNECTIONS, STEEL EMBEDS, ETC.)
ALKYD SYSTEM
CLEAN/ SPOT PRIME, WHERE REQUIRED: UNIVERSAL METAL PRIMER
FIRST COAT: INDUSTRIAL ALKYD ENAMEL
FINAL COAT: INSUSTRIAL ALKYD ENAMEL (GLOSS)

EXTERIOR CONCRETE WALL PANELS:
"ULTRA-CRETE" OR "ELASTOMERIC" SYSTEM
PRESSURE WASH: COMPLETE EXTERIOR OF BUILDING TO BE PRESSURE WASHED PRIO TO APPLICATION OF PRIMER
PRIME COAT: COMPATIBLE WITH FINAL FINISH COAT (LOXON PRIMER)
FINAL COAT: MEDIUM TEXTURE

INTERIOR

STRUCTURAL / MISCELLANEOUS/ HOLLOW METAL STEEL ITEMS: (HOLLOW METAL DOOR AND WINDOW FRAMES, COLUMNS, BOLLARDS, RAILINGS, LINTELS, LADDERS, STAIRS, DOCK LEVELERS, WELD CONNECTIONS AND EMBEDS, ETC.)

GALVANIZED - METAL SUBSTRATES: (INCLUDES GALVANIZED STEEL ITEMS AND EXPOSED GALVANIZED METAL DUCT)
LATEX SYSTEM
CLEAN: DEGREASE SUBSTRATE PRIOR TO PRIMER APPLICATION
PRIME COAT: DTM ACRYLIC PRIMER / FINISH
INTERMEDIATE COAT: DTM ACRYLIC COATING (GLOSS)
FINAL COAT: DTM ACRYLIC COATING (GLOSS)

CONCRETE BLOCK:
LATEX SYSTEM
PRIME COAT: HEAVY DITY BLOCK FILLER
INTERMEDIATE COAT: INTERIOR ALKYD MATCING FINALCOAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

WOOD SUBSTRATES: (PLYWOOD, TRIM, WOOD / COMPOSITE PANELED DOORS, WHERE SCHEDULED, SHELVING, ETC.)
ALKYD SYSTEM
PRIME COAT: INTERIOR ALKYD PRIMER / SEALER
INTERMEDIATE COAT: INTERIOR ALKYD MATCHING FINAL COAT
FINAL COAT: INTERIOR ALKYD (SEMI-GLOSS)

GYPSUM BOARD SUBSTRATES:
LATEX SYSTEM
PRIME COAT: INTERIOR LATEX PRIMER/ SEALER
INTERMEDIATE COAT: INTERIOR LATEX MATCHING FINAL COAT
FINAL COAT: INTERIOR LATEX (FLAT) FOR CEILINGS, SOFFITS OR BULKHEADS, EGGSHELL FOR VERITCAL SURFACES.

PAINT SPECIFICATIONS

INTERIOR — PROVIDE SHERWIN WILLIAMS OR APPROVED EQUAL

WALLS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

WALLS - CMU:
1 COAT: SHERWIN WILLIAMS: PREPRITE INTERIOR / EXTERIOR BLOCK FILLER
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (EGGSHELL)

CEILIINGS - GWB:
1 COAT: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX PRIMER (WHITE)
2 COATS: SHERWIN WILLIAMS: PRO MAR 200 ZERO VOC INTERIOR LATEX (FLAT)

HM DOORS / HM FRAMES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

EXTERIOR

PRE-CAST PANELS:
1 COAT: SHERWIN WILLIAMS: LOXON CONCRETE & MASONRY PRIMER
2 COATS: SHERWIN WILLIAMS: MEDIUM TEXTURE

ACCENTS:
2 COATS: SHERWIN WILLIAMS: A-100 EXTERIOR ACRYLIC LATEX (SATIN)

BOLLARDS / DOWNSPOUT PROTECTOR PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

DOCK SILLS & DRIVE-IN DOOR ANGLE PLATES:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC PRIMER / FINISH (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL DTM ACRYLIC (SEMI-GLOSS)

MECHANICAL EDGE OF DOCK LEVELER:
PRIMER: SHERWIN WILLIAMS: PRO INDUSTRIAL PRO-CRYL UNIVERSAL PRIMER (PRIME AS NEEDED)
2 COATS: SHERWIN WILLIAMS: PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)

ELEVATION KEYNOTES

1. TILT-UP CONCRETE WALL PANEL (PAINT)
2. ALUMINUM ENTRY WITH INSULATED GLASS - SEE SHEET A600
3. ALUMINUM STOREFRONT WITH INSULATED GLASS - SEE SHEET A600
4. PRE-ENGINEERED AND PREFINISHED METAL CANOPY
5. 6'-0" x 5'-0" HIGH ALUM. FRAME CLEARSTORY WINDOW @ 21'-0" A.F.F.
6. 6'-0" x 5'-0" KNOCK-OUT PANEL @ 21'-0" A.F.F.
7. 6'-0" x 7'-0" HIGH KNOCK-OUT PANEL
8. 6'-0" x 8'-11" HIGH KNOCK-OUT PANEL
10. HOLLOW METAL DOOR AND FRAME (PAINT)
11. 24 GA. PREFINISHED METAL COPING
12. PREFINISHED 8" W. x 6" H. METAL GUTTER"
13. PREFINISHED 5" x 5" METAL DOWNSPOUT"
14. DOWNSPOUT GUARD - SEE A1/A501 & B1/A501 NO PAINT IF GALVANIZED, IF NOT, MATCH ADJACENT WALL FINISH.
15. GALVANIZED STEEL STAIR
16. GALVANIZED STEEL STAIR WITH AREA OF ASSISTED RESCUE
18. STEEL PIPE BOLLARD (PAINT)
17. ~~NOT USED~~ INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
20. PIT LEVELER (REFER TO SAMET STANDARDS)
21. 9'-0" x 12'-2" HIGH KNOCK-OUT PANEL
22. 14' x 16' INSULATED OVERHEAD SECTIONAL DOOR (FACTORY FINISH). SEE DOOR SCHEDULE
23. 14'-0" x 16'-0" HIGH KNOCK-OUT PANEL
24. GALVANIZED METAL ROOF ACCESS LADDER TO COMPLY WITH 2018 NCBC, OSHA # 1910.28 & IMC SEC. 306.5 (SEE DET. C1/A500)
25. EDGE OF DOCK LEVELER (REFER TO SAMET STANDARDS)
26. 6'-0" x 5'-0" HIGH ALUM. FRAME CLERESTORY WINDOW @ 25'-10" A.F.F.
27. 6'-0" x 5'-0" LOUVER. SEE MECH DWG'S FOR MORE INFORMATION

EXTERIOR FINISH SCHEDULE

MARK	FINISH	MANUFACTURER / COLOR
F1	CONCRETE WALL PANELS ELASTOMERIC PAINT (TEXTURE)	SHERWIN WILLIAMS / SIMPLE WHITE SW 7021
F2	CONCRETE WALL PANELS ELASTOMERIC PAINT (TEXTURE)	SHERWIN WILLIAMS / ANEW GRAY SW 7030
F3	CONCRETE WALL PANELS ELASTOMERIC PAINT (TEXTURE)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F4	STOREFRONT	TBD
F5	HOLLOW METAL DOORS & FRAMES PRO INDUSTRIAL WATERBASED ALKYD URETHANE (SEMI-GLOSS)	SHERWIN WILLIAMS / KEYSTONE GRAY SW 7504
F6	CANOPY	TBD
F7	COPING/GUTTERS/DOWNSPOUTS	FACTORY FINISH
F8	STEEL PIPE BOLLARD PRO INDUSTRIAL WATERBASED ALKYD (SEMI-GLOSS)	SHERWIN WILLIAMS / OSHA YELLOW
F9	LADDERS / STAIRS / PIPE AND TUBE RAILING	NO PAINT
F10	DOCK DOORS	PREFINISHED - TBD
F11	DOCK LEVELERS	NO PAINT - LABEL AS REQUIRED
F12	EXTERIOR EXPOSED GAS PIPING	PAINT

NOTES:
1. ALL REVEALS TO BE PAINTED SAME AS ADJACENT FIELD COLOR (ABOVE OR BELOW) - MAINTAIN CONSISTENCY AROUND BUILDING.

REVEAL PROFILE

TYPE	DESCRIPTION	GRAPHIC
VERTICAL	1-1/2" X 3/4	
HORIZONTAL	3-1/2" X 3/4"	

triadDESIGNgroup
Architecture | Engineering | Interior Design

4807 Koger Boulevard Suite C
Greensboro, NC 27407
Telephone 336-218-8282

8430 University Executive
Park Drive Suite 650
Charlotte, NC 28262
Telephone 704-312-0140
www.triad-designgroup.com

NC Architecture Reg. 50709
NC Engineering Lic. C-1108

TRIAD DESIGN GROUP CORPORATE P.C. SEAL NORTH CAROLINA 1994

PRELIMINARY

NOT ISSUED FOR CONSTRUCTION

This drawing, and the details herein, as an instrument of service, is the property of Triad Design Group, PC. It may be used only for this specific project, and shall not be loaned, copied, or reproduced in any form without expressed written consent from Triad Design Group, PC. Copyright 2025. Triad Design Group, PC, All rights reserved.

Triad Design Group, PC, shall not be responsible for construction means, methods, techniques, or procedures utilized by the contractor, nor for the safety of public or contractors' employees; nor for the failure of the contractor to carry out the work in accordance with the contract documents.

SAMET

Harnett 95 Industrial Center

SPEC BUILDING 1

US 301 S.
Dunn, North Carolina

SUBMITTALS:

DATE	DESCRIPTION
2025-05-23	90% REVIEW

REVISIONS:

NO	DATE	DESCRIPTION

SHEET TITLE:
ENLARGED ELEVATIONS

DATE: DATE
DRAWN: LWM | CHECKED: MTM
JOB NUMBER: 25-009
SHEET:

A202

5/23/2025 2:57:12 PM