

# OPERATIONS PERMIT

Name: (owner) Gary Sullivan

New Installation  Septic Tank

Property Location: SR# 1561 Bailey Road

Repairs  Nitrification Line

Subdivision \_\_\_\_\_ Lot # \_\_\_\_\_

TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: Harold Chappell Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 18-20 in.

French Drain: \_\_\_\_\_ Linear feet

Date: 5-25-00

PERMIT NO. 13693

Inspected by: James E. Marshall, M.S.  
Environmental Health Specialist

