

OPERATIONS PERMIT

Name: (owner) Deleis Berryman / Res Prop New Installation Septic Tank
 Property Location: SR# NC 27 Repairs Nitrification Line
 Subdivision Longleaf Lot # 21
 TAX ID# _____ Quadrant # _____
 Contractor: J. F. Arecloth Registration # _____

Basement with Plumbing: Garage: SYSTEM INSTALLED
 Water Supply: Well Public Community during wet soil conditions
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 160 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain: _____ Linear feet

Date: 3-22-01

PERMIT NO. 17704

Inspected by: Joe Waters
Environmental Health Specialist

