

00-40000443

OPERATIONS PERMIT

Name: (owner) Robert & Tami Cieri New Installation Septic Tank
 Property Location: SR# NC 24/27 Repairs Nitrification Line
 Subdivision Highland Glenwood Lot # 72
 TAX ID# _____ Quadrant # _____
 Contractor: Wayne Sharpe Registration # _____
 Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
 Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
 Subsurface Drainage Field: No. of ditches 3 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 18 in.
 French Drain: _____ Linear feet

PERMIT NO. 17730

Date: 24 August 2009
 Inspected by: Verne Day
 Environmental Health Specialist

