

OPERATIONS PERMIT

00-40000553

Name: (owner) Weaver Dev. Corp

New Installation Septic Tank

Property Location: SR# 1141

Repairs Nitrification Line

Subdivision Sunset Ridge

Lot # 60

TAX ID# _____

Quadrant # _____

Contractor: W. Sharp

Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-30 in.

French Drain: _____ Linear feet

Date: 10-13-2000

PERMIT NO. 17917

Inspected by: J. L. Waters
Environmental Health Specialist

