

# OPERATIONS PERMIT

00-40000689

Name: (owner) Robert & Terri Ciceci  New Installation  Septic Tank  
 Property Location: SR# NC24/27  Repairs  Nitrification Line  
 Subdivision The Highland @ Sherwood Forest Lot # 16  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: W. Sharpe Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_  
 Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons  
 Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 210 ft. width of ditches 3 ft. depth of ditches 18-24 in.  
 French Drain: \_\_\_\_\_ Linear feet

Date: 11-22-00

PERMIT NO. 17351

Inspected by: J. W. [Signature]  
Environmental Health Specialist

