

OPERATIONS PERMIT

Name: (owner) Honeycutt Custom Homes New Installation Septic Tank
 Property Location: SR# Hwy 55 Repairs Nitrification Line
 Subdivision Tuxington Lot # 3
 TAX ID# _____ Quadrant # _____
 Contractor: Barefoot Septic Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain: — Linear feet

Date: 8-24-00

PERMIT NO. 17466

Inspected by: James E. Marshall
Environmental Health Specialist

