

# OPERATIONS PERMIT

40000768

Name: (owner) Robert + Terri Cieri  New Installation  Septic Tank  
 Property Location: SR# H 2427  Repairs  Nitrification Line  
 Subdivision The Highlands at Skerwood Forest Lot # 58  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: Wayne Sharp Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.  $\checkmark$

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 110 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain: \_\_\_\_\_ Linear feet

Date: 11-17-00

PERMIT NO. 16772

Inspected by: Art H. Boyd P.S.  
Environmental Health Specialist

