

## Harnett County

Inspections  
420 McKinney Pkwy  
Lillington , NC 27546

Phone: 910-893-7525  
Fax: 910-893-2793

### Inspection Report

**Permit:** MCOM2503-0003

**OWNER:** TORTILLERIA Y TAQUERIA LION INC

**Site Address:** 105 E H ST ERWIN, NC 28339

Harnett County Inspections Department

Inspection Type: ROUGH IN

Inspection Date: 03/31/2025

Result: DISAPPROVED

Remarks:

Notes: Exhaust fan will need to be interlocked to gas supply. Will need listed duct for unit, single wall piping cannot pass through concealed spaces or be less than 18 inches from combustibles. Gas piping will need an equipment connector and unit will need a restraint device. Will need make up air. Will need co/mo detector.

All violations are subject to reinspection fees at the inspectors discretion.

**Steven Gazlay**  
Inspector