

OPERATIONS PERMIT

Name: (owner) Weaver Dev. New Installation Septic Tank
 Property Location: SR# 1141 Repairs Nitrification Line
 Subdivision Sweet Ridge Lot # 38
 TAX ID# _____ Quadrant # _____
 Contractor: Wayne Sharp Registration # _____
 Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
 Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
 Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 160 ft. width of ditches 3 ft. depth of ditches 24 in.
 French Drain: _____ Linear feet

PERMIT NO. 16602

Date: 22 March 2009
 Inspected by: Vernon R. [Signature]
 Environmental Health Specialist

Tank Info
 BTS-1000
 STB-103
 2/13/00
 Zink filter

