

7th Mar 2024

Subject: Precast Baffle Wall in 1,600 Gal. GT

To whom it my concerns,

Our submittal for the 1,600 gallons grease trap shows 6'-7.25" baffle wall that is designed to the same standard as the main structure. Baffle wall should be carefully inserted in the provided slot and placed centered in slot. Groves around the baffle wall should be cleaned before grouting the voids in place to prevent movement when the system is in used. Please note that after placing the backfill around the structure, both chambers need to be filled with clean water simultaneously up to operation level before putting system in use.

Baffle wall if installed correctly and system is filled according to the method prescribed herein and, on the submittal, should perform equal to or better than CIP alternative.

Please do not hesitate to reach out if you have any questions or concerns.

Regards,

Hussam Al Tahan, P.E.
Engineering Manager-Carolinas
Oldcastle Infrastructure, Inc.