

HTE 03-5-6739A

16535

# OPERATIONS PERMIT

Name: (owner) Robert & Terri Cressi

New Installation  Septic Tank

Property Location: SR# NC24127

Repairs  Nitrification Line

Subdivision The Highlands @ Sherwood Forest

Lot # 59

Tax ID # \_\_\_\_\_

Quadrant # \_\_\_\_\_

Contractor: Larry Sharpe

Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 55 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other Tree Chips

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 240 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 12-23-03

PERMIT NO. 19291

Inspected by: J. L. Lewis  
Environmental Health Specialist

