

HTE 03-56933

16220

# OPERATIONS PERMIT

Name: (owner) Pine Grove Dev.  New Installation  Septic Tank  
 Property Location: SR# NC24127  Repairs  Nitrification Line  
 Subdivision Wood Bridge Lot # 14  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Ted Brown Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: \_\_\_\_\_ ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other Pump to Chamber

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 7-29-03

Inspected by: Ju Lopez  
Environmental Health Specialist

PERMIT NO. 19402

