

HTE 03-5-8493
Site A

16374

OPERATIONS PERMIT

Name: (owner) Randall O Quinn New Installation Septic Tank
Property Location: SR# 1215 Repairs Nitrification Line
Subdivision Curtis Randall O Quinn Lot # Lot 1 site A
Tax ID # _____ Quadrant # _____
Contractor: LARRY SHARPE Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Tine Chips

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: _____ Linear feet

Date: 01-22-04

Inspected by: Joe Walters
Environmental Health Specialist

PERMIT NO. 21053

