

HTE # 06-500-14997

HARRIS COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH SECTION

18489

OPERATIONS PERMIT

Name: (owner) Pine Grove Dev. New Installation Septic Tank Repair

Property Location: SR# N127 Nitrification Line Expansion
Subdivision Northway Cross Keys Lot # 42 Tax ID # _____ Quadrant # _____

Contractor: Ted Beaman Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community
Distance From Well: _____ ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other 25% reduction system - 2nd chamber a-t-v

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 300 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: _____ Linear feet 1 chamber Date: 7-27-06

PERMIT NO. 27026 Inspected by: [Signature]

Handwritten notes:
M-1-1200
578-814
5-27-06

