

HTE# 06-50015808

Harrick County Department of Public Health

23229

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Highland Home Builders

PROPERTY LOCATION: NC 24/27

SUBDIVISION: The Highland e Shalwood Forest LOT # 34

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: MH (68x40) 3BR

Proposed Wastewater System Type: Pumps Conventional

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years No expiration

Permit conditions: Meet onsite - M-17 maintain All set Backs &c

Attached sheet for details

Authorized State Agent: J. W. [Signature]

Date: 10-02-06

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout

ISSUED TO: Highland Home Builders

PROPERTY LOCATION: NC 24/27

SUBDIVISION _____ LOT # _____

Facility Type: MH (68x40) 3BR New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pumps Conventional (Initial)

Wastewater Flow: 360 GPD

(See note below, if applicable)

LPP Repair 360 LF (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Exact length of each trench 1x300 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size 1000 gallons

Trenches shall be installed on contour at a

Soil Cover: 6 inches

To Be Determined At Later Date

Maximum Trench Depth of: 18 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/- 1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

6 inches below pipe

Conditions: Meet onsite - maintain All set Backs &c Attached sheet for details

Aggregate Depth: 2 inches above pipe

12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: J. W. [Signature]

Date: 10-2-06

SEE ATTACHED SITE SKETCH

Construction Authorization Expiration Date: 10-2-2011

HTE# 06-50015808

Permit # 23229

Pass

Harnett County Department of Public Health Site Sketch

ISSUED TO: Highland Home Builders PROPERTY LOCATOR: NC24/27
SUBDIVISION: The Highlands at Sherwood LOT # 34

Authorized State Agent: Jan [Signature] Date: 10-2-03

MUST meet onsite for Final septic system layout
Pump supply ^(optic) line must cross under the water line (main line) There must be 18" of separation between water line & septic pump supply line. There shall be no pipe joints within 10' of the crossing, either in supply line or water line. Please note that Harnett Co. Environmental Health must have approval (in writing) from Harnett Co. Dept. of Public Utilities that the crossing meets their standards. Before operations permit can be issued. SEE ~~attached~~ attached for our Rules -

Drain lines to be installed at 18" max ditch depth
Follow contours
Maintain 10' set back
Do not Drive or Park on septic system

Line 1 = 75'
Line 2 = 75'
Line 3 = 75'
Line 4 = 75'
Total = 300'

