

HTE # 0650015808

# OPERATIONS PERMIT

Name: (owner) Highland Home Builders  New Installation  Septic Tank  Repair

Property Location: SR# NC24/27  Nitrification Line  Expansion  
Subdivision The High Land & Shallow Ford Lot # 34 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: L. Shaper Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community  
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other Pump to Conventional

Size of tank: Septic Tank: 1000 gallons Pump Tank: 000 gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 300 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: \_\_\_\_\_ Linear feet Date: 11-3-06

PERMIT NO. 23229 Inspected by: Joe Waters

