

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Albert Mullings PROPERTY LOCATION: NC 24/27 (Lizzie Jeter Lane)
 NEW REPAIR EXPANSION SUBDIVISION: Lost Valley LOT # 7
 Type of Structure: SWMH 14x76 3BR Site Improvements required prior to Construction Authorization Issuance: Due To The Woods/Vegetation I
 Proposed Wastewater System Type: Pump to Conventional
 Projected Daily Flow: 360 GPD could not tell if pump will be needed or
 Number of bedrooms: 3 Number of Occupants: 6 max not once area marked by my Blue Flags is
 Basement Yes No cleared I can determine
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet Permit valid for: Five years
 Permit conditions: Meet on site for final layout. Clear area marked by my Blue Flags do remove my Flags. Stub out plumbing at ground level or higher where shown & if 18x24" ditch depths can be maintained then pump may not be required No expiration

Authorized State Agent: J. W. [Signature] Date: 5-28-07 ~~5-23-07~~ SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Albert Mullings PROPERTY LOCATION: NC 24/27 (Lizzie Jeter Lane)
 Facility Type: SWMH 14x76 3BR New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to Conventional (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable) 290 LF of LPP (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 1x240 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
ZF needed Maximum Trench Depth of: 18-24 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
 Conditions: _____ 2 inches above pipe
 _____ 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: J. W. [Signature] Date: 5-28-07 ~~5-23-07~~ SEE ATTACHED SITE SKETCH
 Construction Authorization Expiration Date: 5-28-2012 ~~5-23-07~~

