

HTE# ~~100~~
07-5-176592R2

Harnett County Department of Public Health

Improvement Permit

26230

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: HWY 24

ISSUED TO: PINE GROVE DEVELOPMENT SUBDIVISION NATURES CROSSROADS LOT # 46

NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: MAN HOME (31x76')

Proposed Wastewater System Type: PUMP TO 25% REDUCTION

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature] REHS Date: 8/11/10 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: PINE GROVE DEVELOPMENT PROPERTY LOCATION: HWY 24

SUBDIVISION NATURES CROSSROADS LOT # 46

Facility Type: MAN. HOME (31x76') New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable)
Pump To 25% REDUCTION (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Number of trenches 1

Pump Tank Size 1000 gallons Exact length of each trench 235 feet Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

Maximum Trench Depth of: 12 inches (Maximum soil cover shall not exceed 36" above the trench bottom)

(Trench bottoms shall be level to +/-1/4" in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: MINIMUM OF 6" OF COVER NEEDED OVER DRAINFIELD. THIS PERMIT BASED ON A PROPOSAL FROM APPLICANTS SOIL SCIENTIST _____ inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] REHS Date: 8/11/10

Construction Authorization Expiration Date: 8/11/15

HTE# 07-5-17659 RR2

Permit # 26230

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: Hwy 24

ISSUED TO: PINE GROVE DEVELOPMENT

SUBDIVISION NATURES CAVE ROADS

LOT # 46

Authorized State Agent:

~~RENS (OLIVER TOLKSDORF)~~

Date: 8/11/10

