

HTE# 08-5-19451

Harrison County Department of Public Health

24540

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: JUNE McDONALD
PROPERTY LOCATION: STOCKYARD RD
SUBDIVISION: STOCKYARD RD EST. LOT # 25
Type of Structure: MAN. HOME (28x80)
Proposed Wastewater System Type: CONVENTIONAL
Projected Daily Flow: 480 GPD
Number of bedrooms: 4 Number of Occupants: 8 max
Basement: No
Pump Required: No
Type of Water Supply: Public
Distance from well: 100 feet
Permit valid for: Five years

Authorized State Agent: [Signature] Date: 3/5/08 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: JUNE McDONALD
PROPERTY LOCATION: STOCKYARD RD
SUBDIVISION: STOCKYARD RD EST LOT # 25
Facility Type: MAN. HOME (28x80) New
Basement? No
Type of Wastewater System: CONVENTIONAL (Initial)
Wastewater Flow: 480 GPD
CONVENTIONAL (Repair)

Installation Requirements/Conditions

5 TRENCHES
Septic Tank Size 1000 gallons
Exact length of each trench 80 feet
Trench Spacing: 9 Feet on Center
Pump Tank Size [blank] gallons
Trenches shall be installed on contour at a
Maximum Trench Depth of: 18-24 inches
(Pump Requirements: [blank] ft. TDH vs. [blank] GPM)
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: [Signature] Date: [blank]

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: [Signature] Date: 3/5/08
SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 3/5/13

HTE# 08-5-19451

Permit # 24540

# Harnett County Department of Public Health Site Sketch

ISSUED TO: JUNE McDONALD PROPERTY LOCATOR: STOCKYARD RD  
SUBDIVISION STOCKYARD RD EST LOT # 25

Authorized State Agent: ~~\_\_\_\_\_~~ ES (OLIVER TOLKSDORF) Date: 3/5/08

