

HTE# 08-5-20702

Harnett County Department of Public Health 24582

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Farrell R. Dees PROPERTY LOCATION: SR 1232 Cameron Rd.
 NEW REPAIR EXPANSION SUBDIVISION: Neill Cummings LOT # 2
 Type of Structure: MH 14x70' Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: Conventional
 Projected Daily Flow: 240 GPD
 Number of bedrooms: 2 Number of Occupants: 4 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: Bryan McSwain, R.S. Date: 8/19/2008 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Farrell R. Dees PROPERTY LOCATION: SR 1232
 Facility Type: MH 14x70' New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** conventional (Initial) Wastewater Flow: 240 GPD
 (See note below, if applicable conventional (Repair))

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4x50 ~~3x70~~ feet Trench Spacing: 9 Feet on Center
 Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 20 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/- 1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total
 Conditions: Drain lines to be run on contour & NO DEEPER than 20 inches
All parts of septic system to be 100ft away from well

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: Bryan McSwain, R.S. Date: 8/19/2008 SEE ATTACHED SITE SKETCH
 Construction Authorization Expiration Date: 8/19/2013

HTE# OF-5-20702

Permit # 24582

Harnett County Department of Public Health Site Sketch

ISSUED TO: Farrell R. Daer PROPERTY LOCATOR: 52/232 Cameron Rd.
SUBDIVISION: Neill Cummings LOT # 2

Authorized State Agent: Ben McLean, R.S. Date: 8/19/2008

