

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Jeffrey Hyde
NEW [x] REPAIR [] EXPANSION []
Type of Structure: MH 14'x80'
Proposed Wastewater System Type: conventional
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [x] No
Pump Required: [] Yes [x] No
Type of Water Supply: [] Community [] Public [x] Well
Permit conditions:

PROPERTY LOCATION: SR 1105 McKoy Town Rd
SUBDIVISION: MCK TR# LOT # 2
Site Improvements required prior to Construction Authorization Issuance:
Permit valid for: [x] Five years [] No expiration

Authorized State Agent: Bryan McLean, R.S. Date: 4/17/2009 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Jeffrey Hyde
Facility Type: MH 14'x80' [x] New [] Expansion [] Repair
Basement? [] Yes [x] No Basement Fixtures? [] Yes [] No
Type of Wastewater System** conventional (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable []) conventional (Repair)

PROPERTY LOCATION: SR 1105
SUBDIVISION: MCK LOT # 2

Installation Requirements/Conditions
Septic Tank Size 1000 gallons Exact length of each trench 80 feet Trench Spacing: 9 Feet on Center
Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 8 inches
Maximum Trench Depth of: 20 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: ft. TDH vs. GPM Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total
Conditions: Run drain lines on contour & NO DEEPER than 20 inches
All parts of septic system to be 100ft from well

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McLean, R.S. Date: 4/17/2009
Construction Authorization Expiration Date: 4/17/2014

HTE# 09-5-21794

Permit # 25263

Harnett County Department of Public Health Site Sketch

ISSUED TO: Jeffrey Hyde

PROPERTY LOCATOR: SR 1105 McKoy Town Rd.

SUBDIVISION MCK

LOT # 2

Authorized State Agent: Dana McSwain P.S.

Date: 4/17/2009

