

Application # 09 500 22434

Harnett County Central Permitting

PO Box 65 Lillington, NC 27546

Telephone Number: 910-893-7525 Fax 910-893-2793 www.harnett.org/permits

Application for Manufactured Home Set-Up Permit
(Please fill out each part completely)

SCANNED
7/29/09
DATE

Part I - Owner Information:

Home Owner Information (To be completed by owner of the manufactured home)

Name: Kari-Lynn Monte Address: 218 Sierra Trail

City: Spring Lake State: NC Zip: 28390 Daytime Phone: (910) 303-3861

Landowner Information (To be completed by landowner, if different than above)

Name: _____ Address: _____

City: _____ State: _____ Zip: _____ Daytime Phone: () _____

Part II - Contractor Information (To be completed by Contractors or Homeowner, if applicable.)

Name, address, & phone must match information on license)

A. **Set-Up Contractor** Company Name: Choo-Choo Homes, Transit

Phone: (910) 860-8787 Address: 4209 Bragg Blvd, PO Box 35595

City: Fayetteville State: NC Zip: 28303

Setup Signature: [Signature] State Lic# 3539

B. **Electrical Contractor** Company Name: South River Electric Membership R.A. Gregory Electric

Phone: (910) 854-6937 Address: 1948 NC 27 W

City: Spring Lake Lillington State: NC Zip: 28390 2754

Electrician's Signature: [Signature] State Lic# 21717

C. **Mechanical Contractor** Company Name: Total Systems Heating & Cooling, Inc

Phone: (910) 436-3450 Address: 13341 Hwy 210 South

City: Spring Lake State: NC Zip: 28390

HVAC Signature: [Signature] State Lic# 28846

D. **Plumbing Contractor** Company Name: James Blue Jamie Johnson

Phone: (910) 494-3674 Address: (910) 814-7705

City: Fayetteville Lillington State: NC Zip: _____

Plumber's Signature: _____ State Lic# _____

JUL 28 2009

Part III - Manufactured Home Information

Model Year: 1998 Size: 28 X 76 **Complete & follow zoning criteria sheet**

Park Name: _____ Lot Number: _____

I hereby certify that I have the authority to apply for this permit, that the application is correct including the contractor information and signatures, and that the construction or installation will conform to the applicable manufactured home set-up requirements, and the Harnett County Zoning Ordinance. I understand that if any item is incorrect or false information has been provided that this permit could be revoked.

[Signature]
Signature of Home Owner or Agent

July 28, 2009
Date

*Effective July 1, 2004, a County Tax Department Moving Permit must be provided before a Set Up Permit will be issued. It is purchased from the tax office of the county that the home is moved from. If the home is from a dealer, we need proof of year on the Form 500 and if available, the serial number.
List of inspections and Egress requirements available upon request. Progress Energy customers must provide Premise Number.

Appl. # 09 500 22434



4209 Bragg Blvd.
Fayetteville, NC 28303
Phone (910) 860-8787 Fax (910) 860-1938

The undersigned Purchaser(s) has agreed to purchase from Choo Choo Homes Inc (the "Seller") the manufactured home described on page 1 (the "Home"). In that connection, Purchaser(s) submits herewith a (circle appropriate choice)

Manufactured Home Credit Application and/or Non-Refundable Deposit of \$ _____

Once the Home is delivered on the Purchaser(s) home site and/or the site the Purchaser(s) has specified the contract then becomes due in full. Failure to pay the contract can and will result in the Seller exercising it's right to collect the amount owed in full through legal action such as Judgments, liens and any means within their legal right.

Purchaser(s) acknowledges and agrees that any and all wheels, axles, and related apparatus and equipment used to transport the Home for delivery to Purchaser are and shall remain at all times the sole property of manufacturer and are not sold to Purchaser.

Purchaser(s) represents to Seller that, to the best of Purchaser's knowledge, the lot upon which the home is to be located _____ is _____ is not located in a Special Flood Hazard Area as shown on maps prepared by the U.S. Department of Housing and Urban Development, or in a flood prone area, the cost to set up the Home upon delivery may exceed those provided for in this Contract or contemplated by the parties. Purchaser(s) hereby agrees to pay such excess cost in addition to all other amounts provided for herein.

Purchaser(s) acknowledges and agrees that he/she is of statutory age or has been legally emancipated; that he/she is purchasing the insurance described on page 1 voluntarily; that the trade-in described on page 1, if any, is free from all claims, liens and encumbrances, except as noted; and that if any provision of this Agreement is unenforceable, the remaining provisions will be valid.

Not valid unless signed by an authorized representative of Seller. Approval by Seller is subject to acceptance by a bank or finance Company, if applicable.

(Seller) Choo Choo Homes Inc
4209 Bragg Blvd
Fayetteville, NC 28303


By: [Signature]
Purchaser(s) acknowledges receipt of a true copy of this Agreement and that he/she has read and understands its terms

Keri-Lyn Monte
Purchaser
Social Security No. 576-68-0922

Purchaser
Social Security No. _____

I UNDERSTAND THAT I HAVE THE RIGHT TO CANCEL THIS PURCHASE BEFORE MIDNIGHT ON THE THIRD BUSINESS DAY AFTER THE DATE THAT I HAVE SIGNED THIS AGREEMENT. I UNDERSTAND THAT THIS CANCELLATION MUST BE WRITTEN. IF I CANCEL THIS PURCHASE AFTER THE THREE-DAY PERIOD, I UNDERSTAND THAT THE DEALER MAY NOT HAVE ANY OBLIGATION TO GIVE ME BACK THE MONEY THAT I PAID THE DEALER.

North Carolina DOT Division of Highways
Single Trip Permit #907272H0031



Valid From: 7/27/2009 to 8/5/2009

Issued to:
CHOO CHOO HOMES INC
4209 BRAGG BLVD
FAYETTEVILLE, NC 28303-3858

Phone: 910.860.8787 State Fee: \$24.00
Sent by: Email-
CHOOCHOOHOMES@NC.RR.COM

Load Description: **MOBILE HOME - (2622B)** Escorts: 1
Power Unit: **MH TOTER** License: **ID012893(NC)** Registered weight: **LEGAL** VIN: **16977** Axles: 2
Dimensions - Length: **105'0"** Width: **14'0"** Height: **13'6"** Trailer: **80'0"** Overhang - Front: **NONE** Rear: **NONE**

ALL AXLE, AXLE GROUP, AND GROSS VEHICLE WEIGHTS ARE LEGAL

From: **CUMBERLAND CO** To: **HARNETT CO**

Permit does not authorize travel on routes beyond "From", point of origin or "To", destination specified.

Via Routes: **FROM A POINT ON NC24/87 TO NC210 TO HARNETT CO SR2048/BETHEL BAPTIST RD TO A DESTINATION ON SR2048**

The route from a specific origin to a specific destination must be included within a single permitted route of travel.

Permits issued by the Department of Transportation do not authorize travel on city streets, such authority must be obtained from the city/municipality prior to movement of permitted load.

Issuance of a permit by the NCDOT does not imply nor guarantee the clearance of width or height along permitted route of travel. It is the responsibility of permit holder to check route prior to travel thereon.

Permittee to follow all detours authorized by DOT or law enforcement. Use extreme safety precautions and obey posted speed limits while traveling into or through all DOT authorized construction workzones.

Permit not valid when: visibility is less than 500 feet; highway covered with ice or snow; wind gusts exceed 25 MPH or travel conditions are considered unsafe by the Division of Highways or law enforcement having jurisdiction.

Dimensions and/or weights different from those stated on the permit shall not eliminate the escort requirement indicated on this document. Escort vehicle(s) shall be equipped with: flashing amber lights, rotating sealed beam or strobe, minimum 5 inch diameter base and a minimum 4 inch lens height to be mounted on top of escort vehicle, display a banner, yellow in color, mounted on bumper or roof bearing the legend "WIDE LOAD" or "OVERSIZED LOAD" in black (10 inch X 1 1/2 inch) brush stroke lettering visible from front or rear as required by location of escort.

The driver of the escort vehicle is required to be certified in accordance with the North Carolina Escort Vehicle Operator Certification Program.

Power unit and escort vehicle must maintain radio contact and burn headlamps during movement.

Escort vehicle/transporters shall monitor trailing traffic build up and pull to the roadside periodically as the opportunity arises to allow line of traffic to clear.

Escort must be a truck (single vehicle) of not less than 1/4 ton rated load capacity but not more than 17,000 lbs GVWR or a single vehicle passenger vehicle of not less than 2,000 lbs gross weight.

Escort vehicle shall display on both sides of vehicle placards/identification signs measuring 8" by 12" providing escort company's or individual's name and telephone number.

Escort vehicle is not authorized to tow a trailer.

Convoy travel is NOT authorized. Permitted vehicles owned or leased by the same company or permitted vehicles originating at the same location shall travel at a distance of not less than two miles apart.

No driver or passenger other than a certified escort vehicle operator will be allowed to travel in the escort vehicle.

Special Restrictions

A BANNER MEASURING 7ft x 18in HIGH, YELLOW IN COLOR, BEARING THE LEGEND 'WIDE 14 FT LOAD' OR 'OVERSIZE 14 FT LOAD' IN BLACK 10in x 1 1/2in BRUSH STROKE LETTERING TO BE DISPLAYED ON FRONT AND REAR OF MOBILE/MODULAR HOME COMBINATION.

FLASHING AMBER LIGHTS, ROTATING SEALED BEAM OR STROBE, MINIMUM 5 IN. DIAMETER BASE AND MINIMUM 4 IN. LENS HEIGHT ARE REQUIRED TO BE DISPLAYED 72 IN. FROM THE ROAD SURFACE ON ALL FOUR CORNERS OF THE MOBILE/MODULAR UNIT WITH THE OPTION OF MOUNTING THE 2 REQUIRED FRONT LIGHTS ON THE MIRROR BAR NO LESS THAN THE EXTREME WIDTH OF THE TOTER.

RED OR ORANGE FLAGS (18"x18") TO BE DISPLAYED ON ALL FOUR CORNERS OF THE MOBILE/MODULAR UNIT 50 IN. FROM THE ROAD SURFACE.

POWER UNIT(TOTER) SHALL BE A VEHICLE DESIGNED AND EQUIPPED FOR THE SOLE PURPOSE OF TRANSPORTING MOBILE/MODULAR HOMES WITH A MINIMUM LENGTH OF 15 FT AND MUST BE RATED AT NO LESS THAN 2 TONS AND MINIMUM REQUIREMENT OF 4 SPEED TRANSMISSION.

MAXIMUM WIDTH SHALL BE A 14 FOOT WIDE UNIT WITH ROOF OVERHANG NOT TO EXCEED A TOTAL OF 12 INCHES. BAY WINDOWS, PORCH EXTENSIONS OR ROOM EXTENSIONS MAY BE TRANSPORTED PROVIDING THE PROTRUSION DOES NOT EXTEND BEYOND THE MAXIMUM OF 12 INCHES OF ROOF OVERHANG OR THE TOTAL WIDTH OF OVERHANG ON THE APPROPRIATE SIDE OF THE UNIT. REFLECTIVE EXTENDERS EQUAL TO THE WIDTH OF THE ROOF OVERHANG OR PROTRUSION SHALL BE ATTACHED TO THE FRONT AND REAR OF THE UNIT TO CLEARLY IDENTIFY THE TOTAL WIDTH OF THE UNIT. AN EXTENDER SHALL BE PLACED ON THE FRONT AND REAR OF THE MOBILE HOME WITH A LENGTH TO EXTEND HORIZONTALLY EQUAL TO BUT NOT BEYOND THE EXTREME OUTERMOST EDGE OF THE HOME'S EXTENSION. THE EXTENDERS SHALL HAVE RETRO-REFLECTIVE SHEETING, A MINIMUM OF 4", WHICH IS REQUIRED TO BE TYPE III HIGH INTENSITY (ENCAPSULATED LENS) OR TYPE IV HIGH PERFORMANCE (PRISMATIC) WITH ALTERNATING FLUORESCENT YELLOW AND BLACK DIAGONAL STRIPES SLOPING TOWARDS THE OUTSIDE OF THE HOME WITH A MINIMUM AREA OF 288 SQUARE INCHES. THE BOTTOM OF THE EXTENDERS SHALL BE 6' TO 8' ABOVE THE ROAD SURFACE WITH A 5" AMBER FLASHING BEACON MOUNTED ON THE TOP OF EACH EXTENDER.

MOVER IS REQUIRED TO HAVE ONE REAR ESCORT ON ALL MULTI-LANE HIGHWAYS, ONE FRONT ESCORT ON ALL 2 LANE HIGHWAYS FROM A MANUFACTURER TO A STATE LICENSED RETAIL SALES LOT, AND FRONT AND REAR ESCORTS ARE REQUIRED FOR ALL OTHER MOVEMENT ON ALL TWO LANE HIGHWAYS.

A MINIMUM OF 3 AXLES ARE REQUIRED FOR UNITS GREATER THAN 52 FEET IN LENGTH TO INCLUDE THE TONGUE MEASUREMENT.

THE TOTAL LENGTH OF THE COMBINATION MUST NOT EXCEED 105 FEET WITH A MAXIMUM OF 80 FEET UNIT/ TONGUE.

TAIL LIGHTS AND TURN SIGNALS IN GOOD WORKING CONDITION INSTALLED ON THE REAR OF THE MOBILE/ MODULAR UNIT.

COMBINATION IS TO BE EQUIPPED WITH 7x14.5 OR LARGER, 8PLY, 10 PLY OR 12 PLY RATED TIRES-TREAD DEPTH NOT LESS THAN 2/32".

MOBILE/MODULAR UNIT SHALL BE EQUIPPED WITH A MINIMUM OF 2 BRAKING AXLES IN GOOD WORKING CONDITION CONTROLLED AND OPERATED FROM THE TOWING UNIT; ALL WHEELS ON THE BRAKING AXLES SHALL BE EQUIPPED WITH OPERABLE BRAKES. AUTHORIZATION OF SPECIAL AXLE EXEMPTION FOR THE SPECIFIC HOME IS REQUIRED TO BE CARRIED IN THE PULLING UNIT WHILE TRAVELING ON ALL NORTH CAROLINA HIGHWAYS.

MOBILE HOME TO DISPLAY PROPER LICENSE TAG.

TOWING VEHICLE MUST BE PROPERLY LICENSED FOR GROSS WEIGHT OF THE TOWING UNIT AND TONGUE WEIGHT OF THE MOBILE HOME.

TRAVEL AUTHORIZED MONDAY THROUGH SATURDAY SUNRISE TO SUNSET.

TRAVEL PROHIBITED WITHIN A 10 MILE RADIUS OF THE CITY LIMITS OF CHARLOTTE, RALEIGH, DURHAM AND CHAPEL HILL BETWEEN 7AM - 9AM AND 4PM - 6PM

MAY TRAVEL POSTED SPEED LIMIT, NOT TO EXCEED A MAXIMUM SPEED OF 60 MPH

Permittee is responsible for any/all damages to persons/property. Civil penalties will be assessed if: operating off route, transporting improper load, in violation of escort requirements, operating with improper safety equipment or license, failure to comply with dimensions and/or weights of permit, failure to comply with travel restrictions or falsification of a permit application.

PERMIT SHALL BE SIGNED AND CARRIED IN TOWING VEHICLE DURING MOVEMENT.

I CERTIFY THAT I AM FAMILIAR WITH ALL LAWS/ REQUIREMENTS GOVERNING THIS MOVE AND WILL BE IN FULL COMPLIANCE DURING MOVEMENT. ANY ALTERATION(S) WILL RESULT IN VOIDING PERMIT AND SUSPENSION OF NC PERMIT PRIVILEGES. REPEATED PERMIT VIOLATIONS MAY RESULT IN SUSPENSION AND/ OR DENIAL OF NC PERMIT PRIVILEGES.

[Signature]
Permittee Signature

7-27-09
Date

1600485

BSJ

[Signature]
Director of Permits

Authorized: 7/27/09 7:47 am