

HTE# 09-522613

Harrell County Department of Public Health

25655

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Thomas E Lamm PROPERTY LOCATION: BBQ CHURCH RD SUBDIVISION _____ LOT # _____
NEW ☒ REPAIR ☐ EXPANSION ☐
Type of Structure: MAN HOME Site Improvements required prior to Construction Authorization Issuance: WELL MUST BE PROPERLY ABANDONED.
Proposed Wastewater System Type: CONVENTIONAL
Projected Daily Flow: 240 GPD
Number of bedrooms: 2 Number of Occupants: 4 max
Basement ☐ Yes ☒ No
Pump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilities
Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feet Permit valid for: ☒ Five years
Permit conditions: _____ ☐ No expiration

Authorized State Agent: [Signature] Date: 8/28/09 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Thomas Lamm PROPERTY LOCATION: BBQ CHURCH RD SUBDIVISION _____ LOT # _____
Facility Type: MAN. HOME ☒ New ☐ Expansion ☐ Repair
Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 240 GPD
(See note below, if applicable ☐)
CONVENTIONAL (Repair)
Installation Requirements/Conditions
Septic Tank Size 1000 gallons Number of trenches 2
Pump Tank Size _____ gallons Exact length of each trench 60 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a Soil Cover: 12 inches
Maximum Trench Depth of: 24 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
(Trench bottoms shall be level to +/- 1/4" in all directions)
Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: 6 inches below pipe
2 inches above pipe
Conditions: _____ 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9/18/09
Construction Authorization Expiration Date: 9/18/14

HTE# 09-5-22613

Permit # 25655

Harnett County Department of Public Health Site Sketch

ISSUED TO: Thomas E. Lamm PROPERTY LOCATOR: BBQ Church Rd
SUBDIVISION _____ LOT # _____

Authorized State Agent: [Signature] Date: 9/18/09

