

HTE# 10-5-23789

Harnett County Department of Public Health

25912

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: LLOYD JUNIOR BOGERTPROPERTY LOCATION: DOGS RD (MURPHY LN)NEW ☒ REPAIR ☐ EXPANSION ☐SUBDIVISION NEWKIRKLOT # 15Type of Structure: MAN. HOME (16'x72')

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: CONVENTIONALProjected Daily Flow: 360 GPDNumber of bedrooms: 3 Number of Occupants: 6 maxBasement ☐ Yes ☒ NoPump Required: ☐ Yes ☒ No ☐ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feetPermit valid for: ☒ Five years
☐ No expiration

Permit conditions:

Authorized State Agent:

REHSDate: 3/4/10

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: LLOYD JUNIOR BOGERTPROPERTY LOCATION: DOGS RD (MURPHY LN)SUBDIVISION NEWKIRKLOT # 15Facility Type: MAN. HOME (16'x72') ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ NoType of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 360 GPD(See note below, if applicable ☐)CONVENTIONAL (Repair)Installation Requirements/ConditionsSeptic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 3Exact length of each trench 50 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24 inches(Trench bottoms shall be level to $\pm 1/4"$

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 12 inches(Maximum soil cover shall not exceed
36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe2 inches above pipeConditions: WATER LINE MUST BE 10' FROM SEPTIC SYSTEM. NO12 inches totalUTILITIES MAY ENCRANCH ON INITIAL OR REPAIR AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:

REHSDate: 3/4/10Construction Authorization Expiration Date: 3/4/15

HTE# 10-5-23789

Permit # 25912

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: Does Rd (MURPHY LN)

ISSUED TO: LLOYD JUNIOR BOGERT SUBDIVISION NEWKIRK LOT # 15

Authorized State Agent: ~~REHS (OLIVER TOLKSDORF)~~ Date: 3/4/10

