

HTE# 12-5-29514

Harnett County Department of Public Health

Improvement Permit

27090

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: FLOYD KOERNER PROPERTY LOCATION: BYRD POND RD LOT # _____
NEW ☒ REPAIR ☐ EXPANSION ☐
Type of Structure: MAN HOME (28x56) Site Improvements required prior to Construction Authorization Issuance: _____
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 240 GPD
Number of bedrooms: 2 Number of Occupants: 4 max
Basement ☐ Yes ☒ No
Pump Required: ☐ Yes ☒ No ☐ May be required based on final location and elevations of facilities
Type of Water Supply: ☐ Community ☐ Public ☒ Well Distance from well 100 feet *
Permit conditions: _____ Permit valid for: ☒ Five years ☐ No expiration

Authorized State Agent: [Signature] Date: 8/15/12 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: FLOYD KOERNER PROPERTY LOCATION: _____
SUBDIVISION _____ LOT # _____
Facility Type: MAN HOME (28x56) ☒ New ☐ Expansion ☐ Repair
Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 240 GPD
(See note below, if applicable ☐ 25% REDUCTION SYSTEM (Repair))
Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size _____ gallons
Number of trenches 1
Exact length of each trench 200 feet
Trenches shall be installed on contour at a
Maximum Trench Depth of: 18 inches
(Trench bottoms shall be level to +/-1/4" in all directions)
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: _____ inches below pipe
_____ inches above pipe
_____ inches total
Conditions: _____

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 8/15/12
Construction Authorization Expiration Date: 8/15/17

HTE# 12-5-29514

Permit # 27090

Harnett County Department of Public Health Site Sketch

ISSUED TO: FLOYD ROSENER PROPERTY LOCATOR: BYRD POND RD
SUBDIVISION _____ LOT # _____

Authorized State Agent: RENS (OLIVER TOLKSDORF) Date: 9/15/12

