

HTE# 13-5-32184

Harnett County Department of Public Health

27587

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Jesus Figueroa PROPERTY LOCATION: SR 156 FERTUS RD
 NEW ☒ REPAIR ☐ EXPANSION ☐ SUBDIVISION _____ LOT # 16
 Type of Structure: 3 BR M/H Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% REDUCTION
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement ☐ Yes ☒ No
 Pump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilities
 Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well _____ feet Permit valid for: ☒ Five years
 Permit conditions: All property TOWN TO BE Demol for final ☐ No expiration

Authorized State Agent: James E. Markant Date: 10-4-13 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Jesus Figueroa PROPERTY LOCATION: SR 156 FERTUS RD
 SUBDIVISION _____ LOT # 16
 Facility Type: M/H ☒ New ☐ Expansion ☐ Repair
 Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
 Type of Wastewater System** 25% REDUCTION (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable ☐ 25% REDUCTION (Repair))
 Installation Requirements/Conditions
 Septic Tank Size 1200 gallons Number of trenches 4
 Pump Tank Size _____ gallons Exact length of each trench 100 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 22-18 max inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/-1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 4 inches below pipe
 Conditions: All Property TOWNS TO BE Demol for final 2 inches above pipe
12 inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markant Date: 10-4-13
 Construction Authorization Expiration Date: 10-4-18

HTE# 13-5-32184

Permit # 27587

Harnett County Department of Public Health Site Sketch

ISSUED TO: Jesus Cano Figueroa PROPERTY LOCATOR: SL 156 Festus RD SUBDIVISION _____ LOT # 16

Authorized State Agent: James E. Mahoney Date: 10-4-13

