

HTE# 15-5-35498

Hamilton County Department of Public Health

28301

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: PAUL NORMANDIN
PROPERTY LOCATION: HILLMAN GROVE RD
SUBDIVISION: -
LOT # 7A
NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: MAN. HOME (14x70)
Proposed Wastewater System Type: 25% REDUCTION
Projected Daily Flow: 240 GPD
Number of bedrooms: 2 Number of Occupants: 4 max
Basement [ ] Yes [X] No
Pump Required: [ ] Yes [X] No
Type of Water Supply: [ ] Community [ ] Public [X] Well
Distance from well: 100 feet
Permit valid for: [X] Five years [ ] No expiration

Authorized State Agent: [Signature] Date: 3/11/15 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: PAUL NORMANDIN
PROPERTY LOCATION: HILLMAN GROVE RD
SUBDIVISION: -
LOT # 7A
Facility Type: MAN HOME (14x70) [X] New [ ] Expansion [ ] Repair
Basement? [ ] Yes [X] No Basement Fixtures? [ ] Yes [X] No
Type of Wastewater System: 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 240 GPD
(See note below, if applicable [ ]) 25% REDUCTION (Repair)

Installation Requirements/Conditions
Septic Tank Size: 1000 gallons
Pump Tank Size: \_\_\_\_\_ gallons
Number of trenches: 2
Exact length of each trench: 50 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a Maximum Trench Depth of: 2430 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM
Aggregate Depth: \_\_\_\_\_ inches below pipe \_\_\_\_\_ inches above pipe \_\_\_\_\_ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 3/11/15
Construction Authorization Expiration Date: 3/11/20

HTE# 15-5-35498

Permit # 28301

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Paul Norman PROPERTY LOCATOR: HILLMAN GROVE RD  
SUBDIVISION - LOT # 7A

Authorized State Agent: ~~XXXXXXXXXXXXXXXXXXXX~~ REHS (OLIVER TOLKSDORF) Date: 3/11/15

